Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S25 A1
Client Sample No. TPG-L2-1CH-100404
Description
Analysis Date 10/10/2004
Analyst KM

Volume (L) 291.6
No. of Grid Openings 91
Filter Area (mm2) 385
Area Analyzed (mm2) 1.32
Analytical Sens. (struc/cc) 0.00100
Dectection Limit. (struc/cc) 0.00299

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	19.7	0.0260	0.0170 - 0.0381	26
Total Asbestos Structures	19.7	0.0260	0.0170 - 0.0381	26
Asbestos Structures > 5um	9.9	0.0130	0.00693 - 0.0223	13
Asbestos Fibers and Bundles > 5um	6.8	0.00901	0.00412 - 0.0171	9
PCM Equivalent Fibers-US	6.1	0.00801	0.00346 - 0.0158	8
PCM Equivalent Structures-US	5.3	0.00701	0.00282 - 0.0144	7
PROTOCOL ASB STRUCS 5-10	2.3	0.00300	0.00 - 0.00776	3
PROTOCOL ASB STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS TOTAL	2.3	0.00300	0.00 - 0.00776	3
PROTOCOL CHRYS STRUCS 5-10	0.8	0.00100	0.00 - 0.00475	1
PROTOCOL CHRYS STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS TOTAL	0.8	0.00100	0.00 - 0.00475	1
PROTOCOL AMPH STRUCS 5-10	1.5	0.00200	0.00 - 0.00631	2
PROTOCOL AMPH STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS TOTAL	1.5	0.00200	0.00 - 0.00631	2
AHERA-like Total Structures 3:1	19.7	0.0260	0.0170 - 0.0381	26
AHERA-like Asb Strucs >5 and 3:1	9.9	0.0130	0.00693 - 0.0223	13
AHERA-like Asb Strucs 5 - 10 and 3:1	6.8	0.00901	0.00412 - 0.0171	9
AHERA-like Asb Strucs >10 and 3:1	3.0	0.00401	0.00109 - 0.0103	4
Total Other Amphibole Strucs 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S24 A1
Client Sample No. TPG-L2-11CH-100404
Description
Analysis Date 10/10/2004
Analyst DW

Volume (L) 288.72
No. of Grid Openings 92
Filter Area (mm2) 385
Area Analyzed (mm2) 1.33
Analytical Sens. (struc/cc) 0.00100
Dectection Limit. (struc/cc) 0.00299

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	10.5	0.0140	0.00766 - 0.0235	14
Total Asbestos Structures	10.5	0.0140	0.00766 - 0.0235	14
Asbestos Structures > 5um	6.8	0.00900	0.00412 - 0.0171	9
Asbestos Fibers and Bundles > 5um	6.0	0.00800	0.00346 - 0.0158	8
PCM Equivalent Fibers-US	5.3	0.00700	0.00281 - 0.0144	7
PCM Equivalent Structures-US	3.0	0.00400	0.00109 - 0.0102	4
PROTOCOL ASB STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS >10	1.5	0.00200	0.00 - 0.00630	2
PROTOCOL ASB STRUCS TOTAL	1.5	0.00200	0.00 - 0.00630	2
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS >10	0.8	0.00100	0.00 - 0.00474	1
PROTOCOL CHRYS STRUCS TOTAL	0.8	0.00100	0.00 - 0.00474	1
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS >10	0.8	0.00100	0.00 - 0.00474	1
PROTOCOL AMPH STRUCS TOTAL	0.8	0.00100	0.00 - 0.00474	1
AHERA-like Total Structures 3:1	10.5	0.0140	0.00766 - 0.0235	14
AHERA-like Asb Strucs >5 and 3:1	6.8	0.00900	0.00412 - 0.0171	9
AHERA-like Asb Strucs 5 - 10 and 3:1	2.3	0.00300	0.00 - 0.00775	3
AHERA-like Asb Strucs >10 and 3:1	4.5	0.00600	0.00220 - 0.0131	6
Total Other Amphibole Strucs 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S27 A1
Client Sample No. TPG-L2-2CH-100404
Description
Analysis Date 10/11/2004
Analyst JH

Volume (L) 290.4
No. of Grid Openings 44
Filter Area (mm2) 385
Area Analyzed (mm2) 0.638
Analytical Sens. (struc/cc) 0.00208
Dectection Limit. (struc/cc) 0.00622

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	83.1	0.110	0.0826 - 0.144 (Poisson)	53
Total Asbestos Structures	87.8	0.116	0.0880 - 0.151 (Poisson)	56
Asbestos Structures > 5um	17.3	0.0229	0.0114 - 0.0409	11
Asbestos Fibers and Bundles > 5um	7.8	0.0104	0.00338 - 0.0243	5
PCM Equivalent Fibers-US	6.3	0.00832	0.00227 - 0.0213	4
PCM Equivalent Structures-US	4.7	0.00624	0.00 - 0.0161	3
PROTOCOL ASB STRUCS 5-10	1.6	0.00208	0.00 - 0.00986	1
PROTOCOL ASB STRUCS >10	0.0	<0.00622	0.00 - 0.00622	0
PROTOCOL ASB STRUCS TOTAL	1.6	0.00208	0.00 - 0.00986	1
PROTOCOL CHRYS STRUCS 5-10	1.6	0.00208	0.00 - 0.00986	1
PROTOCOL CHRYS STRUCS >10	0.0	<0.00622	0.00 - 0.00622	0
PROTOCOL CHRYS STRUCS TOTAL	1.6	0.00208	0.00 - 0.00986	1
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00622	0.00 - 0.00622	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00622	0.00 - 0.00622	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00622	0.00 - 0.00622	0
AHERA-like Total Structures 3:1	81.6	0.108	0.0808 - 0.142 (Poisson)	52
AHERA-like Asb Strucs >5 and 3:1	17.3	0.0229	0.0114 - 0.0409	11
AHERA-like Asb Strucs 5 - 10 and 3:1	9.4	0.0125	0.00458 - 0.0272	6
AHERA-like Asb Strucs >10 and 3:1	7.8	0.0104	0.00338 - 0.0243	5
Total Other Amphibole Strucs 3:1	0.0	<0.00622	0.00 - 0.00622	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00622	0.00 - 0.00622	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00622	0.00 - 0.00622	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00622	0.00 - 0.00622	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S28 A1
Client Sample No. TPG-L2-3CH-100404
Description
Analysis Date 10/11/2004
Analyst KM

Volume (L) 299.16
No. of Grid Openings 89
Filter Area (mm2) 385
Area Analyzed (mm2) 1.29
Analytical Sens. (struc/cc) 0.000998
Dectection Limit. (struc/cc) 0.00298

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	17.1	0.0220	0.0138 - 0.0332	22
Total Asbestos Structures	17.1	0.0220	0.0138 - 0.0332	22
Asbestos Structures > 5um	4.7	0.00599	0.00220 - 0.0130	6
Asbestos Fibers and Bundles > 5um	1.6	0.00200	0.00 - 0.00629	2
PCM Equivalent Fibers-US	0.8	0.000998	0.00 - 0.00473	1
PCM Equivalent Structures-US	0.8	0.000998	0.00 - 0.00473	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
AHERA-like Total Structures 3:1	17.1	0.0220	0.0138 - 0.0332	22
AHERA-like Asb Strucs >5 and 3:1	4.7	0.00599	0.00220 - 0.0130	6
AHERA-like Asb Strucs 5 - 10 and 3:1	3.9	0.00499	0.00162 - 0.0116	5
AHERA-like Asb Strucs >10 and 3:1	0.8	0.000998	0.00 - 0.00473	1
Total Other Amphibole Strucs 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S29 A1
Client Sample No. TPG-L2-4CH-100404
Description
Analysis Date 10/12/2004
Analyst DW

Volume (L) 290
No. of Grid Openings 17
Filter Area (mm2) 385
Area Analyzed (mm2) 0.246
Analytical Sens. (struc/cc) 0.00539
Dectection Limit. (struc/cc) 0.0161

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	198.9	0.264	0.195 - 0.349 (Poisson)	49
Total Asbestos Structures	215.2	0.286	0.214 - 0.374 (Poisson)	53
Asbestos Structures > 5um	60.9	0.0808	0.0452 - 0.133	15
Asbestos Fibers and Bundles > 5um	8.1	0.0108	0.00 - 0.0340	2
PCM Equivalent Fibers-US	8.1	0.0108	0.00 - 0.0340	2
PCM Equivalent Structures-US	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL ASB STRUCS >10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL AMPH STRUCS >10	0.0	<0.0161	0.00 - 0.0161	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.0161	0.00 - 0.0161	0
AHERA-like Total Structures 3:1	198.9	0.264	0.195 - 0.349 (Poisson)	49
AHERA-like Asb Strucs >5 and 3:1	60.9	0.0808	0.0452 - 0.133	15
AHERA-like Asb Strucs 5 - 10 and 3:1	32.5	0.0431	0.0186 - 0.0850	8
AHERA-like Asb Strucs >10 and 3:1	28.4	0.0377	0.0152 - 0.0777	7
Total Other Amphibole Strucs 3:1	0.0	<0.0161	0.00 - 0.0161	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.0161	0.00 - 0.0161	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.0161	0.00 - 0.0161	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.0161	0.00 - 0.0161	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S30 A1
Client Sample No. TPG-L2-5CH-100404
Description
Analysis Date 10/12/2004
Analyst JH

Volume (L) 288.84
No. of Grid Openings 71
Filter Area (mm2) 385
Area Analyzed (mm2) 1.03
Analytical Sens. (struc/cc) 0.00130
Dectection Limit. (struc/cc) 0.00387

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	41.8	0.0557	0.0403 - 0.0750 (Poisson)	43
Total Asbestos Structures	48.6	0.0648	0.0481 - 0.0854 (Poisson)	50
Asbestos Structures > 5um	9.7	0.0130	0.00621 - 0.0238	10
Asbestos Fibers and Bundles > 5um	4.9	0.00648	0.00210 - 0.0151	5
PCM Equivalent Fibers-US	3.9	0.00518	0.00141 - 0.0133	4
PCM Equivalent Structures-US	2.9	0.00389	0.00 - 0.0100	3
PROTOCOL ASB STRUCS 5-10	1.9	0.00259	0.00 - 0.00816	2
PROTOCOL ASB STRUCS >10	0.0	<0.00387	0.00 - 0.00387	0
PROTOCOL ASB STRUCS TOTAL	1.9	0.00259	0.00 - 0.00816	2
PROTOCOL CHRYS STRUCS 5-10	1.0	0.00130	0.00 - 0.00614	1
PROTOCOL CHRYS STRUCS >10	0.0	<0.00387	0.00 - 0.00387	0
PROTOCOL CHRYS STRUCS TOTAL	1.0	0.00130	0.00 - 0.00614	1
PROTOCOL AMPH STRUCS 5-10	1.0	0.00130	0.00 - 0.00614	1
PROTOCOL AMPH STRUCS >10	0.0	<0.00387	0.00 - 0.00387	0
PROTOCOL AMPH STRUCS TOTAL	1.0	0.00130	0.00 - 0.00614	1
AHERA-like Total Structures 3:1	41.8	0.0557	0.0403 - 0.0750 (Poisson)	43
AHERA-like Asb Strucs >5 and 3:1	9.7	0.0130	0.00621 - 0.0238	10
AHERA-like Asb Strucs 5 - 10 and 3:1	8.7	0.0117	0.00533 - 0.0221	9
AHERA-like Asb Strucs >10 and 3:1	1.0	0.00130	0.00 - 0.00614	1
Total Other Amphibole Strucs 3:1	0.0	<0.00387	0.00 - 0.00387	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00387	0.00 - 0.00387	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00387	0.00 - 0.00387	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00387	0.00 - 0.00387	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S26 A1
Client Sample No. TPG-L2-1ZB-100404
Description
Analysis Date 10/11/2004
Analyst JH

Volume (L) 303.6
No. of Grid Openings 88
Filter Area (mm2) 385
Area Analyzed (mm2) 1.28
Analytical Sens. (struc/cc) 0.000995
Dectection Limit. (struc/cc) 0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.00297	0.00 - 0.00297	0
Total Asbestos Structures	0.0	<0.00297	0.00 - 0.00297	0
Asbestos Structures > 5um	0.0	<0.00297	0.00 - 0.00297	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00297	0.00 - 0.00297	0
PCM Equivalent Fibers-US	0.0	<0.00297	0.00 - 0.00297	0
PCM Equivalent Structures-US	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Total Structures 3:1	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Total Other Amphibole Strucs 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4760 S95 A1	**Volume (L)**	0
Client Sample No.	TPG-L2-FB-100404	**No. of Grid Openings**	10
Description	FILTER BLANK	**Filter Area (mm2)**	385
Analysis Date	12/27/2004	**Area Analyzed (mm2)**	0.145
Analyst	JH	**Analytical Sens. (struc/cc)**	NA
		Dectection Limit. (struc/cc)	NA

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	NA	NA	0
Total Asbestos Structures	0.0	NA	NA	0
Asbestos Structures > 5um	0.0	NA	NA	0
Asbestos Fibers and Bundles > 5um	0.0	NA	NA	0
PCM Equivalent Fibers-US	0.0	NA	NA	0
PCM Equivalent Structures-US	0.0	NA	NA	0
PROTOCOL ASB STRUCS 5-10	0.0	NA	NA	0
PROTOCOL ASB STRUCS >10	0.0	NA	NA	0
PROTOCOL ASB STRUCS TOTAL	0.0	NA	NA	0
PROTOCOL CHRYS STRUCS 5-10	0.0	NA	NA	0
PROTOCOL CHRYS STRUCS >10	0.0	NA	NA	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	NA	NA	0
PROTOCOL AMPH STRUCS 5-10	0.0	NA	NA	0
PROTOCOL AMPH STRUCS >10	0.0	NA	NA	0
PROTOCOL AMPH STRUCS TOTAL	0.0	NA	NA	0
AHERA-like Total Structures 3:1	0.0	NA	NA	0
AHERA-like Asb Strucs >5 and 3:1	0.0	NA	NA	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	NA	NA	0
AHERA-like Asb Strucs >10 and 3:1	0.0	NA	NA	0
Total Other Amphibole Strucs 3:1	0.0	NA	NA	0
Other Amphibole Strucs >5 and 3:1	0.0	NA	NA	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	NA	NA	0
Other Amphibole Strucs >10 and 3:1	0.0	NA	NA	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1CH-100404 *Lab/Cor Sample No.:* B4760 S25 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B34		NSD									
A	2	B14		NSD									
A	3	C24	AZQ	1	1	F	5.5	0.4	14	5262	15181	Mg, Si, Fe Amosite Zone Axis [7 1 20] - JH	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	C24	ADQ	2	2	F	18	4	4.5			Mg, Si, Ca,Fe Actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	4	C4		NSD									
A	5	C44		NSD									
A	6	B43		NSD									
A	7	B33	AZQ	3		MD1-0	2.5	2	1.2			Actinolite	TAS_AHRA
A	7	B33	AZQ		3	MF	1.7	0.2	8.5	5263	15502	Mg, Si, Ca,Fe Actinolite Zone Axis [3 -1 2] - KM	
A	8	B3	AX	4	4	F	15	2.5	6.0			Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	8	B3	CDQ	5		MD1-0	10	8	1.2			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	8	B3	CDQ		5	MB	1.8	0.15	12	5264	15183	Mg, Si Chrysotile Confirmed - KM	
A	9	C13		NSD									
A	10	C33	ADQ	6	6	F	6.8	1.5	4.5			Mg, Si, Ca,Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	11	B32	CM	7		MD1-0	15	10	1.5			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	11	B32	CM		7	MF	1.2	0.1	12			Chrysotile	
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12	CMQ	8	8	F	1.2	0.1	12			Mg, Si Chrysotile	TAS_AHRA
A	15	C32		NSD									
A	16	B31		NSD									
A	17	B21	CM	9	9	F	1	0.08	12			Chrysotile	TAS_AHRA
A	18	B1		NSD									
A	19	C11	CD	10	10	F	0.8	0.08	10			Chrysotile	TAS_AHRA
A	20	C31		NSD									
A	21	A31	CDQ	11		MD1-0	6.5	6	1.1			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1CH-100404 *Lab/Cor Sample No.:* B4760 S25 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	21	A31	CDQ		11	MF	1.1	0.1	11			Chrysotile	
A	22	A11	ADQ	12		MD1-1	15	10	1.5			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	22	A11	ADQ		12	MF	10	0.4	25			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT
A	23	D1	CD	13		MD1-0	3	2	1.5			Chrysotile	TAS_AHRA
A	23	D1	CD		13	MF	0.7	0.08	8.8			Chrysotile	
A	24	D21	CDQ	14	14	B	8.5	0.4	21			Mg, Si Chrysotile	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	25	D41		NSD									
A	26	A32		NSD									
A	27	A12		NSD									
A	28	D2		NSD									
A	29	D22		NSD									
A	30	D42		NSD									
A	31	D10		NSD									
B	32	B44		NSD									
B	33	B24		NSD									
B	34	B4		NSD									
B	35	C14		NSD									
B	36	C34		NSD									
B	37	B33	CD	15	15	F	0.9	0.11	8.2			Chrysotile	TAS_AHRA
B	38	B13	ADQ	16	16	F	3.8	0.5	7.6			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	39	C3		NSD									
B	40	C23		NSD									
B	41	C43		NSD									
B	42	B42	CD	17	17	F	1	0.1	10			Chrysotile	TAS_AHRA
B	43	B22		NSD									
B	44	B2	CD	18		MD1-0	5.9	4	1.5			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	44	B2	CD		18	MF	1.5	0.11	14			Chrysotile	
B	45	C12		NSD									
B	46	C32		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1CH-100404 *Lab/Cor Sample No.:* B4760 S25 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	47	B41		NSD									
B	48	B21		NSD									
B	49	B1		NSD									
B	50	C11		NSD									
B	51	C31		NSD									
B	52	A41		NSD									
B	53	A21		NSD									
B	54	A1		NSD									
B	55	D11		NSD									
B	56	D31		NSD									
B	57	A32	ADQ	19	19	F	5.5	1	5.5			Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	58	A12	CD	20	20	F	0.8	0.11	7.3			Chrysotile	TAS_AHRA
B	59	D2		NSD									
B	60	D22		NSD									
B	61	D42		NSD									
B	62	C10		NSD									
C	63	B34		NSD									
C	64	B14		NSD									
C	65	C4		NSD									
C	66	C24		NSD									
C	67	C44	ADQ	21	21	F	1.8	0.5	3.6			Mg, Si, Ca,Fe Actinolite	TAS_AHRA
C	68	B43		NSD									
C	69	B23	ADQ	22	22	F	10	1.5	6.7			Mg, Si, Ca,Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	70	B3		NSD									
C	71	C13		NSD									
C	72	C33		NSD									
C	73	B32		NSD									
C	74	B12		NSD									
C	74	C2	ADQ	23	23	F	9	3	3.0			Mg, Si, Ca,Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	75	C22		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1CH-100404 *Lab/Cor Sample No.:* B4760 S25 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	76	C42		NSD									
C	77	B41		NSD									
C	78	B21		NSD									
C	79	B2		NSD									
C	80	C12		NSD									
C	81	C32		NSD									
C	82	A31	CD	24		MD1-0	4.5	3.5	1.3			Chrysotile	TAS_AHRA
C	82	A31	CD		24	MF	0.5	0.08	6.2			Chrysotile	
C	82	A31	ADQ	25	25	F	4.5	1.35	3.3			Mg, Si, Ca,Fe Actinolite	TAS_AHRA
C	83	A11		NSD									
C	84	D1		NSD									
C	85	D21	CD	26	26	F	1	0.12	8.3			Chrysotile	TAS_AHRA
C	86	D41		NSD									
C	87	A42		NSD									
C	88	A22		NSD									
C	89	A2		NSD									
C	90	D12		NSD									
C	91	D32		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-11CH-100404 *Lab/Cor Sample No.:* B4760 S24 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34	ADQ	1	1	F	5	1.5	3.3			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	6	C43		NSD									
A	7	C23		NSD									
A	8	C3	ADQ	2	2	F	10	2.5	4.0			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	8	C3	ADQ	3	3	F	1.5	0.5	3.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	9	B13	ADQ	4	4	F	14	1.5	9.3			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	10	B33		NSD									
A	11	B42		NSD									
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C32		NSD									
A	16	C41		NSD									
A	17	B1		NSD									
A	18	B21		NSD									
A	19	B41		NSD									
A	20	B40		NSD									
A	21	B30		NSD									
A	22	B20		NSD									
A	23	B10		NSD									
A	24	A1		NSD									
A	25	A21		NSD									
A	26	A41		NSD									
A	27	A32		NSD									
A	28	A22		NSD									
A	29	A12		NSD									
A	30	A2		NSD									
A	31	D12		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-11CH-100404 *Lab/Cor Sample No.:* B4760 S24 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	32	D32		NSD									
B	33	B44	AZQ	5	5	F	2.75	0.4	6.9	5281	570	Mg, Si, Ca, Fe Actinolite Zone Axis [3 0 1] - KM	TAS_AHRA
B	34	B24		NSD									
B	35	B4	ADQ	6		MD	5.5	5	1.1			Mg, Si, Ca, Fe Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	35	B4	ADQ		6	MF	5.5	1.5	3.7			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	36	C14		NSD									
B	37	C34		NSD									
B	38	C43		NSD									
B	39	C31		NSD									
B	40	C11	ADQ	7		MD1-1	12	6	2.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	40	C11	ADQ		7	MF	8	0.7	11			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	41	B21		NSD									
B	42	B41		NSD									
B	43	A40		NSD									
B	44	A20		NSD									
B	45	A10		NSD									
B	46	D10		NSD									
B	47	D30		NSD									
B	48	D22		NSD									
B	49	D2		NSD									
B	50	A12		NSD									
B	51	A32	AZQ	8	8	F	4.5	0.7	6.4	825	571	Na, Mg, Al, Si, Ca, Fe Actinolite Ferrian-actinolite - Zone Axis [2 0 1] - KM	TAS_AHRA
B	52	A44		NSD									
B	53	A24		NSD									
B	54	A4		NSD									
B	55	D14		NSD									
B	56	D24		NSD									
B	57	A13		NSD									
B	58	A11	CDQ	9		MD1-1	18	15	1.2			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	58	A11	CDQ		9	MF	15	0.05	300	826	572	Mg, Si Chrysotile Confirmed - KM	AFB>5, PSAS >10, PSAS TOT, PCAS >10, PCAS TOT

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-11CH-100404 *Lab/Cor Sample No.:* B4760 S24 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	59	B10		NSD									
B	60	B12		NSD									
B	61	B14		NSD									
B	62	B34		NSD									
B	63	B32		NSD									
B	64	B30		NSD									
C	65	A1	CDQ	10	10	B	4	0.6	6.7			Mg, Si Chrysotile	TAS_AHRA
C	66	A21		NSD									
C	67	A41		NSD									
C	68	B40		NSD									
C	69	B20		NSD									
C	70	B10		NSD									
C	71	C20		NSD									
C	72	C40		NSD									
C	73	D41		NSD									
C	74	D21		NSD									
C	75	D1		NSD									
C	76	A11		NSD									
C	77	A31		NSD									
C	78	A43	ADQ	11	11	F	8	1	8.0			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	79	A23		NSD									
C	80	A3		NSD									
C	81	D3		NSD									
C	82	D23		NSD									
C	83	D43		NSD									
C	84	D44		NSD									
C	85	D34	ADQ	12	12	F	10.5	2.5	4.2			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	86	D4		NSD									
C	87	A14		NSD									
C	88	A24	ADQ	13		MD1-0	12	5	2.4			Tremolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	88	A24	AZQ		13	MF	4	0.25	16	827	573	Mg, Si, Ca, Fe Tremolite Zone Axis [5 1 6] - KM	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-11CH-100404 *Lab/Cor Sample No.:* B4760 S24 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	89	A44	ADQ	14		MD1-1	13	7	1.9			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	89	A44	ADQ		14	MF	13	0.5	26			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US, PSAS >10, PSAS TOT, PSAM >10, PSAM TOT
C	90	B11		NSD									
C	91	B12		NSD									
C	92	B13		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S27 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A1	CDQ	1		MD1-0	4.9	3	1.6			Chrysotile	TAS_AHRA
A	1	A1	CDQ		1	MB	4.9	0.3	16	828	574	Mg, Si Chrysotile Confirmed - KM	
A	1	A1	CDQ	2	2	B	0.7	0.2	3.5			Chrysotile	TAS_AHRA
A	1	A1	CDQ	3	3	B	1	0.08	12			Chrysotile	TAS_AHRA
A	1	A1	CDQ	4	4	F	0.6	0.04	15			Chrysotile	TAS_AHRA
A	1	A1	CDQ	5	5	F	0.6	0.04	15			Chrysotile	TAS_AHRA
A	2	A21	CDQ	6		MD2-0	6	2.3	2.6			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	A21	CDQ		6	MF	1.5	0.05	30			Chrysotile	
A	2	A21	CDQ		7	MF	2.5	0.05	50			Chrysotile	
A	3	A41		NSD									
A	4	A43	AZQ	7	8	F	4	0.7	5.7	829	575	Na, Mg, Al, Si, Ca, Fe Actinolite Zone Axis [7 1 0] - KM	TAS_AHRA
A	5	A23	CD	8	9	F	0.6	0.05	12			Chrysotile	TAS_AHRA
A	6	A3	CD	9	10	F	0.7	0.05	14			Chrysotile	TAS_AHRA
A	7	D13		NSD									
A	8	D30	CD	10	11	F	1	0.07	14			Chrysotile	TAS_AHRA
A	8	D30	CD	11	12	B	2.3	0.5	4.6			Chrysotile	TAS_AHRA
A	9	D41	CD	12	13	F	0.7	0.05	14			Chrysotile	TAS_AHRA
A	9	D41	CD	13	14	B	17	7	2.4			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	10	C40	ADQ	14	15	F	4.5	0.9	5.0			Mg, Si, Ca,Fe Actinolite	TAS_AHRA
A	11	C20		NSD									
A	12	C10		NSD									
A	13	C42	CD	15		MD2-0	2.6	2.3	1.1			Chrysotile	TAS_AHRA
A	13	C42	CD		16	MF	2.5	0.04	62			Chrysotile	
A	13	C42	CD		17	MF	0.7	0.08	8.8			Chrysotile	
A	14	C22	CD	16		MD1-0	8	5	1.6			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	14	C22	CD		18	MB	2.4	0.2	12			Chrysotile	
A	14	C22	CD	17	19	F	1.1	0.04	28			Chrysotile	TAS_AHRA
A	14	C22	CD	18	20	F	1	0.04	25			Chrysotile	TAS_AHRA
A	15	C2		NSD									
A	16	B12	CD	19	21	F	0.55	0.05	11			Chrysotile	TAS_AHRA
A	17	B22	CD	20	22	B	2.3	0.2	12			Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S27 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	18	B42		NSD									
A	19	B44		NSD									
A	20	B24	CD	21		MD1-0	4	2.3	1.7			Chrysotile	TAS_AHRA
A	20	B24	CD		23	MF	4	0.06	67			Chrysotile	
A	20	B24	ADQ	22	24	F	15	5	3.0			Mg, Si, Ca,Fe Actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	21	C4	CD	23	25	CC6-0	2.3	0.4	5.8			Chrysotile	
A	22	C24	CDQ	24	26	F	1.7	0.05	34			Mg, Si Chrysotile	TAS_AHRA
A	22	C24	CD	25	27	F	2.5	0.06	42			Chrysotile	TAS_AHRA
B	23	A10		NSD									
B	24	B40		NSD									
B	25	B41		NSD									
B	26	A41	CD	26	28	F	1	0.1	10			Chrysotile	TAS_AHRA
B	27	A21	CD	27	29	F	0.75	0.05	15			Chrysotile	TAS_AHRA
B	27	A21	ADQ	28		MD1-1	11	10	1.1			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	27	A21	ADQ		30	MF	5.1	1.3	3.9			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	28	A1	CDQ	29		MD1-0	5	3.5	1.4			Chrysotile	TAS_AHRA
B	28	A1	CDQ		31	MB	2	0.3	6.7			Mg, Si Chrysotile	
B	28	A1	CD	30		MD1-0	4	2	2.0			Chrysotile	TAS_AHRA
B	28	A1	CD		32	MF	0.6	0.05	12			Chrysotile	
B	29	D11		NSD									
B	30	D31		NSD									
B	31	D41	CMQ	31	33	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	31	D41	CMQ	32	34	F	1.2	0.05	24			Mg, Si Chrysotile	TAS_AHRA
B	31	D41	CMQ	33	35	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	31	D41	ADQ	34	36	F	8.5	0.85	10			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	31	D41	CMQ	35	37	B	9	2.5	3.6			Mg, Si Chrysotile	AS>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	32	D21		NSD									
B	32	A1	CMQ	36	38	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
B	33	A1	CMQ	37	39	F	0.75	0.05	15			Mg, Si Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S27 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	33	A1	ADQ	38	40	F	9	2	4.5			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	34	A21	CD	39		MD1-0	20	20	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	34	A21	CD		41	MF	1	0.05	20			Chrysotile	
B	34	A21	CMQ	40	42	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	34	A21	CMQ	41	43	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
B	34	A21	CMQ	42	44	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	34	A21	CMQ	43	45	F	0.5	0.05	10			Mg, Si Chrysotile	TAS_AHRA
B	35	A41	CMQ	44		MD1-1	40	15	2.7			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	35	A41	CMQ		46	MF	5.1	0.05	100			Mg, Si Chrysotile	AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
B	36	A32	CMQ	45		MD1-0	5	5	1.0			Chrysotile	TAS_AHRA
B	36	A32	CMQ		47	MF	0.6	0.05	12			Mg, Si Chrysotile	
B	37	A12	CDQ	46	48	F	1.75	0.05	35			Mg, Si Chrysotile	TAS_AHRA
B	38	D2		NSD									
B	39	D22		NSD									
B	40	D42		NSD									
B	41	C44	CMQ	47	49	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
B	42	C24	AQ	48	50	F	4	0.5	8.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	42	C24	CMQ	49	51	F	2.75	0.05	55			Mg, Si Chrysotile	TAS_AHRA
B	43	C4	CMQ	50	52	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	43	C4	CMQ	51	53	F	1	0.025	40			Mg, Si Chrysotile	TAS_AHRA
B	44	B14	CMQ	52		MD1-0	10	8	1.2			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	44	B14	CMQ		54	MF	0.85	0.1	8.5			Mg, Si Chrysotile	
B	44	B14	CMQ	53		MD2-0	3	2	1.5			Chrysotile	TAS_AHRA
B	44	B14	CMQ		55	MF	1.25	0.15	8.3			Mg, Si Chrysotile	
B	44	B14	CMQ		56	MF	1	0.15	6.7			Mg, Si Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S28 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	B33		NSD									
A	7	B13		NSD									
A	8	C3		NSD									
A	9	C23		NSD									
A	10	C43		NSD									
A	11	B42		NSD									
A	12	B22	CDQ	1		MD1-0	8	6	1.3			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	12	B22	CDQ		1	MB	1.5	0.38	3.9	5265	15184	Mg, Si Chrysotile Confirmed - KM	
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C32		NSD									
A	16	B41		NSD									
A	17	B21		NSD									
A	18	B1	CMQ	2	2	B	3.7	0.5	7.4			Mg, Si Chrysotile	TAS_AHRA
A	19	C11		NSD									
A	20	C31	CMQ	3		MD1-0	5.5	3.8	1.4			Mg, Si Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	20	C31	CMQ		3	MF	0.5	0.1	5.0			Mg, Si Chrysotile	
A	21	A41	ADQ	4	4	F	3.7	1.1	3.4			Mg, Si, Ca,Fe Actinolite	TAS_AHRA
A	22	A21		NSD									
A	23	A1		NSD									
A	24	D11		NSD									
A	25	D31		NSD									
A	26	A32		NSD									
A	27	A12		NSD									
A	28	D2		NSD									
A	29	D22		NSD									
A	30	D42		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S28 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	31	B44		NSD									
B	32	B24		NSD									
B	33	B4		NSD									
B	34	C14		NSD									
B	35	C34	AZQ	5		MD1-0	10	6	1.7			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	35	C34	AZQ		5	MF	1.7	0.45	3.8	5285	15185	Mg, Si, Ca,Fe Actinolite Zone Axis [1 0 0] - KM	
B	36	B33		NSD									
B	37	B13		NSD									
B	38	C13		NSD									
B	39	C23		NSD									
B	40	C43		NSD									
B	41	B42		NSD									
B	42	B22		NSD									
B	43	B2		NSD									
B	44	C12		NSD									
B	45	C32	CQ	6		MD1-0	8	6	1.3			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	45	C32	CQ		6	MF	0.7	0.1	7.0			Mg, Si Chrysotile	
B	46	B41		NSD									
B	47	B11		NSD									
B	48	C1		NSD									
B	49	C21		NSD									
B	50	C41		NSD									
B	51	A31		NSD									
B	52	A11	CM	7	7	B	2.2	0.35	6.3			Chrysotile	TAS_AHRA
B	53	D1		NSD									
B	54	D21		NSD									
B	55	D41		NSD									
B	56	A42		NSD									
B	57	A22		NSD									
B	58	A2		NSD									
B	59	D12		NSD									
B	60	D32		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S28 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	61	A12		NSD									
C	61	A32	CMQ	8	8	F	1.7	0.05	34			Mg, Si Chrysotile	TAS_AHRA
C	61	A32	CMQ	9	9	F	1.05	0.05	21			Mg, Si Chrysotile	TAS_AHRA
C	61	A32	CMQ	10	10	F	0.5	0.07	7.1			Mg, Si Chrysotile	TAS_AHRA
C	62	A42	CMQ	11	11	F	0.65	0.05	13			Mg, Si Chrysotile	TAS_AHRA
C	63	A41		NSD									
C	64	A31	CDQ	12	12	B5-0	1.75	0.25	7.0			Mg, Si Chrysotile	TAS_AHRA
C	65	A40		NSD									
C	66	B31	AQ	13	13	F	5	1	5.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
C	67	B32		NSD									
C	68	B33	CMQ	14	14	F	0.5	0.05	10			Mg, Si Chrysotile	TAS_AHRA
C	68	B33	CMQ	15	15	F	1	0.07	14			Mg, Si Chrysotile	TAS_AHRA
C	69	B43		NSD									
C	70	B44	CMQ	16	16	F	1.4	0.05	28			Mg, Si Chrysotile	TAS_AHRA
C	70	B44	CMQ	17	17	F	1.1	0.05	22			Mg, Si Chrysotile	TAS_AHRA
C	71	B34		NSD									
C	72	C31		NSD									
C	73	C42		NSD									
C	74	D20		NSD									
C	75	D30	CDQ	18	18	B6-0	0.75	0.3	2.5			Mg, Si Chrysotile	TAS_AHRA
C	76	D40		NSD									
C	77	D22		NSD									
C	78	D32		NSD									
C	79	D42		NSD									
D	80	D22		NSD									
D	81	D32	CDQ	19	19	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
D	82	D41	CMQ	20	20	F	0.75	0.05	15			Mg, Si Chrysotile	TAS_AHRA
D	82	D41	AQ	21	21	F	15	5	3.0			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
D	83	D40		NSD									
D	84	D31		NSD									
D	85	D30	AQ	22	22	F	5.5	1.3	4.2			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
D	86	C20		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S28 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
D	87	C30		NSD									
D	88	C40		NSD									
D	89	C31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report #: 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S29 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	CDQ	1		MD1-0	11	9	1.2			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	1	B44	CDQ		1	MF	1.25	0.15	8.3			Mg, Si Chrysotile	
A	1	B44	CQ	2		MD2-0	10	7	1.4			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B44	CQ		2	MF	0.6	0.05	12			Mg, Si Chrysotile	
A	1	B44	CQ		3	MF	0.7	0.05	14			Mg, Si Chrysotile	
A	1	B44	CQ	3		MD1-0	1	1	1.0			Chrysotile	TAS_AHRA
A	1	B44	CQ		4	MF	0.75	0.15	5.0			Mg, Si Chrysotile	
A	2	B14	CQ	4		MD1-0	4	2	2.0			Chrysotile	TAS_AHRA
A	2	B14	CQ		5	MF	1.25	0.15	8.3			Mg, Si Chrysotile	
A	3	C4	CDQ	5	6	F	1.5	0.05	30			Mg, Si Chrysotile	TAS_AHRA
A	3	C4	CDQ	6	7	F	1.3	0.05	26			Mg, Si Chrysotile	TAS_AHRA
A	3	C4	CQ	7	8	F	0.6	0.01	60			Mg, Si Chrysotile	TAS_AHRA
A	3	C4	CDQ	8		MD2-0	5	5	1.0			Chrysotile	TAS_AHRA
A	3	C4	CDQ		9	MF	2.5	0.05	50			Mg, Si Chrysotile	
A	3	C4	CDQ		10	MF	2	0.05	40	831	577	Mg, Si Chrysotile Confirmed - KM	
A	3	C4	CQ	9	11	F	0.65	0.15	4.3			Mg, Si Chrysotile	TAS_AHRA
A	3	C4	CQ	10	12	F	0.75	0.01	75			Mg, Si Chrysotile	TAS_AHRA
A	4	C24	CM	11		MD2-0	10	7	1.4			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	4	C24	CM		13	MF	1.5	0.05	30			Chrysotile	
A	4	C24	CM		14	MF	0.75	0.05	15			Chrysotile	
A	4	C24	CM	12	15	F	0.5	0.05	10			Chrysotile	TAS_AHRA
A	4	C24	CD	13	16	F	0.5	0.01	50			Chrysotile	TAS_AHRA
A	5	C44	CM	14		MD1-0	1.2	1.2	1.0			Chrysotile	TAS_AHRA
A	5	C44	CM		17	MF	1	0.05	20			Chrysotile	
A	5	C44	CM	15	18	F	0.5	0.05	10			Chrysotile	TAS_AHRA
A	5	C44	CM	16	19	F	1.2	0.05	24			Chrysotile	TAS_AHRA
A	5	C44	CM	17		MD1-0	1.5	0.75	2.0			Chrysotile	TAS_AHRA
A	5	C44	CM		20	MF	1.2	0.05	24			Chrysotile	
A	5	C44	CM	18	21	F	1.5	0.05	30			Chrysotile	TAS_AHRA
A	5	C44	AZQ	19		MD1-0	20	15	1.3			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	5	C44	AZQ		22	MF	4	0.65	6.2	5286	15503	Mg,Al,Si,Ca,Fe Actinolite Zone Axis [1 -1 1] - KM	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S29 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	6	C43		NSD									
A	7	C33	CM	20		MD1-0	5.5	5	1.1			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	7	C33	CM		23	MF	1	0.05	20			Chrysotile	
A	7	C33	CM	21		MD1-0	20	15	1.3			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	7	C33	CM		24	MF	0.6	0.05	12			Chrysotile	
A	7	C33	CM	22	25	F	0.6	0.01	60			Chrysotile	TAS_AHRA
A	7	C33	CM	23	26	F	0.5	0.05	10			Chrysotile	TAS_AHRA
A	7	C33	CM	24	27	F	1	0.05	20			Chrysotile	TAS_AHRA
A	7	C33	CM	25	28	F	0.75	0.05	15			Chrysotile	TAS_AHRA
A	7	C33	CM	26		MD1-0	15	15	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	7	C33	CM		29	MF	1.2	0.1	12			Chrysotile	
A	7	C33	CM	27		MD1-1	30	15	2.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	7	C33	CM		30	MB	8	1.2	6.7			Chrysotile	AFB>5, PCMEF-US
A	8	C13	CM	28		MD1-0	10	10	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	8	C13	CM		31	MF	0.6	0.05	12			Chrysotile	
A	9	B3	CM	29		MD1-0	20	15	1.3			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	9	B3	CM		32	MF	1	0.05	20			Chrysotile	
A	9	B3	CM	30	33	F	0.65	0.05	13			Chrysotile	TAS_AHRA
A	9	B3	CM	31	34	F	0.65	0.05	13			Chrysotile	TAS_AHRA
A	9	B3	CM	32		MD1-0	7.5	7.5	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	9	B3	CM		35	MF	0.75	0.05	15			Chrysotile	
A	10	B23		NSD									
A	11	B43	CD	33	36	B	2	2	1.0			Chrysotile	TAS_AHRA
A	11	B43	ADQ	34		MD1-1	20	15	1.3			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	11	B43	AQ		37	MF	9	0.75	12			Mg, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
A	11	B43	CM	35	38	F	0.75	0.05	15			Chrysotile	TAS_AHRA
A	11	B43	CM	36	39	F	0.75	0.05	15			Chrysotile	TAS_AHRA
A	11	B43	CM	37	40	F	1	0.15	6.7			Chrysotile	TAS_AHRA
A	12	B32	CM	38	41	F	0.6	0.05	12			Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S29 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	12	B32	CM	39		MD2-0	3.5	3	1.2			Chrysotile	TAS_AHRA
A	12	B32	CM		42	MF	0.75	0.05	15			Chrysotile	
A	12	B32	CM		43	MF	0.75	0.05	15			Chrysotile	
A	12	B32	CM	40	44	F	0.5	0.05	10			Chrysotile	TAS_AHRA
A	12	B32	CM	41		MD1-0	6	5	1.2			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	12	B32	CM		45	MF	3.5	0.15	23			Chrysotile	
A	12	B32	CM	42		MD1-0	10	10	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	12	B32	CM		46	MF	1	0.05	20			Chrysotile	
B	13	B31		NSD									
B	14	B11	CM	43	47	F	0.5	0.01	50			Chrysotile	TAS_AHRA
B	15	C1	CM	44	48	F	0.5	0.05	10			Chrysotile	TAS_AHRA
B	16	C21	CM	45		MD1-0	4	2.5	1.6			Chrysotile	TAS_AHRA
B	16	C21	CM		49	MF	1	0.01	100			Chrysotile	
B	16	C21	CM	46	50	F	1.2	0.01	120			Chrysotile	TAS_AHRA
B	16	C21	CM	47	51	F	1	0.01	100			Chrysotile	TAS_AHRA
B	17	C41	CD	48		MD1-0	4	3	1.3			Chrysotile	TAS_AHRA
B	17	C41	CD		52	MF	2.5	0.01	250			Chrysotile	
B	17	C41	CM	49		MD1-0	7.5	7.5	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	17	C41	CM		53	MF	1	0.05	20			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S30 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A10		NSD									
A	2	A30		NSD									
A	3	A40	CD	1		MD1-0	3	1.8	1.7			Chrysotile	TAS_AHRA
A	3	A40	CD		1	MB	3	0.1	30	833		Chrysotile Fiber tilts into grid bar. Confirmed - KM	
A	3	A40	CDQ	2	2	B	1.1	0.2	5.5	834	579	Mg, Si Chrysotile Confirmed - KM	TAS_AHRA
A	4	B41	AZQ	3	3	F	4.5	0.3	15	835	580	Mg, Si, Ca, Fe Tremolite Zone Axis [3 0 1] - KM	TAS_AHRA
A	5	B21	CDQ	4	4	F	1.2	0.1	12			Chrysotile	TAS_AHRA
A	6	B1		NSD									
A	7	C11		NSD									
A	8	C31	CDQ	5	5	F	5.2	0.05	100			Chrysotile	AS>5, AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	9	C43		NSD									
A	10	C23	CDQ	6	6	F	0.7	0.1	7.0			Chrysotile	TAS_AHRA
A	11	C3		NSD									
A	12	B13		NSD									
A	13	B33		NSD									
A	14	A41		NSD									
A	15	A21		NSD									
A	16	D1		NSD									
A	17	D3		NSD									
A	17	D13	CD	7	7	F	1.2	0.08	15			Chrysotile	TAS_AHRA
A	18	D43		NSD									
B	19	A1		NSD									
B	20	A3	CD	8	8	F	1.2	0.06	20			Chrysotile	TAS_AHRA
B	20	A3	ADQ	9	9	F	2.7	0.3	9.0			Tremolite	TAS_AHRA
B	21	A4		NSD									
B	22	A24		NSD									
B	23	A44	CD	10		CD3-0	3	2	1.5			Chrysotile	TAS_AHRA
B	23	A44	CD		10	CB	3	0.5	6.0			Chrysotile	
B	23	A44	CD		11	CF	2.5	0.05	50			Chrysotile	
B	23	A44	CD		12	CB	2.2	0.6	3.7			Chrysotile	
B	24	A24		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S30 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	25	A22		NSD									
B	26	A2	CD	11	13	F	1.1	0.07	16			Chrysotile	TAS_AHRA
B	27	D12		NSD									
B	28	D32	CD	12	14	B	3.5	0.25	14			Chrysotile	TAS_AHRA
B	29	D40	CD	13	15	F	1.2	0.05	24			Chrysotile	TAS_AHRA
B	30	D20		NSD									
B	31	D10		NSD									
B	32	C20		NSD									
B	33	C40		NSD									
B	34	C42	CD	14	16	F	0.7	0.05	14			Chrysotile	TAS_AHRA
B	35	C22		NSD									
B	36	C2		NSD									
B	37	B12	CD	15	17	F	0.5	0.05	10			Chrysotile	TAS_AHRA
B	38	B32		NSD									
B	39	B44		NSD									
B	40	B24		NSD									
B	41	B4		NSD									
B	42	C14		NSD									
B	43	B1	AZQ	16	18	F	5.1	1	5.1	838	582	Mg, Si, Ca, Fe Actinolite Zone Axis [4 0 3] - KM	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	44	B3		NSD									
B	45	B14		NSD									
B	46	B12	CD	17		MD3-0	3	3	1.0			Chrysotile	TAS_AHRA
B	46	B12	CD		19	MB	3	0.2	15			Chrysotile	
B	46	B12	CD		20	MF	2.8	0.05	56			Chrysotile	
B	46	B12	CD		21	MB	2.4	0.15	16			Chrysotile	
B	47	B10		NSD									
B	48	A11		NSD									
B	49	A13		NSD									
B	50	A34	ADQ	18	22	F	7	1	7.0			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	51	A32		NSD									
B	52	A30		NSD									
B	53	B31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S30 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	54	B33	ADQ	19	23	F	1.5	0.3	5.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	54	B33	CD	20	24	B	1	0.2	5.0			Chrysotile	TAS_AHRA
B	55	C13	CD	21	25	F	1.2	0.06	20			Chrysotile	TAS_AHRA
B	56	C11	CD	22		MD1-0	5.3	4.8	1.1			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	56	C11	CD		26	MB	2	0.2	10			Chrysotile	
B	56	C11	CD	23	27	F	2.3	0.06	38			Chrysotile	TAS_AHRA
B	56	C11	CD	24		CD3-0	2.8	1	2.8			Chrysotile	TAS_AHRA
B	56	C11	CD		28	CR15-0	2.8	0.6	4.7			Chrysotile	
B	56	C11	CD		29	CF	1.2	0.05	24			Chrysotile	
B	56	C11	CD		30	CF	1	0.04	25			Chrysotile	
B	56	C11	CD	25	31	B	1.5	0.5	3.0			Chrysotile	TAS_AHRA
B	57	D11		NSD									
B	58	D13		NSD									
B	59	D34	ADQ	26	32	F	2.3	0.3	7.7			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	59	D34	ADQ	27		MD1-1	5.2	3	1.7			Tremolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	59	D34	ADQ		33	MF	5.2	0.4	13			Mg, Si, Ca, Fe Tremolite	AFB>5, PCMEF-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT
C	60	B44	CM	28		MD1-0	3.5	3.5	1.0			Chrysotile	TAS_AHRA
C	60	B44	CM		34	MF	2	0.05	40			Chrysotile	
C	61	B24	CM	29	35	F	0.6	0.05	12			Chrysotile	TAS_AHRA
C	61	B24	CM	30	36	F	0.5	0.01	50			Chrysotile	TAS_AHRA
C	61	B24	CM	31		MD1-0	5.5	5.5	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	61	B24	CM		37	MB	2.5	0.3	8.3			Chrysotile	
C	62	B4		NSD									
C	63	C14	CD	32		MD1-0	6.5	6.5	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	63	C14	CM		38	MF	1.5	0.1	15			Chrysotile	
C	63	C14	CM	33	39	F	0.6	0.05	12			Chrysotile	TAS_AHRA
C	63	C14	CM	34	40	F	0.6	0.05	12			Chrysotile	TAS_AHRA
C	64	B33		NSD									
C	65	B13	CM	35	41	F	0.75	0.15	5.0			Chrysotile	TAS_AHRA
C	65	B13	CM	36		MD1-0	4	2.5	1.6			Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S30 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#.	Comment	Count Categories
C	65	B13	CM		42	MB	4.5	0.85	5.3			Chrysotile	
C	65	B13	CM	37	43	F	1	0.05	20			Chrysotile	TAS_AHRA
C	66	C3		NSD									
C	67	C23	CM	38		MD1-0	1	1	1.0			Chrysotile	TAS_AHRA
C	67	C23	CM		44	MF	1	0.05	20			Chrysotile	
C	68	C43	CM	39		MD1-1	15	15	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	68	C43	CM		45	MB	9	1.2	7.5			Chrysotile	AFB>5, PCMEF-US
C	69	C32	CM	40	46	F	0.5	0.05	10			Chrysotile	TAS_AHRA
C	70	C12		NSD									
C	71	B2	CM	41	47	F	0.6	0.01	60			Chrysotile	TAS_AHRA
C	71	B2	CM	42		MD2-0	10	10	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	71	B2	CM		48	MB	1.2	0.25	4.8			Chrysotile	
C	71	B2	CM		49	MF	1	0.05	20			Chrysotile	
C	71	B2	CM	43		MD1-0	8	2	4.0			Chrysotile	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	71	B2	CM		50	MF	0.6	0.05	12			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S26 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A1		NSD									
A	2	A21		NSD									
A	3	A41		NSD									
A	4	A43		NSD									
A	5	A23		NSD									
A	6	A3		NSD									
A	7	D13		NSD									
A	8	D33		NSD									
A	9	D40		NSD									
A	10	D20		NSD									
A	11	D10		NSD									
A	12	C10		NSD									
A	13	C20		NSD									
A	14	C40		NSD									
A	15	C42		NSD									
A	16	C22		NSD									
A	17	C2		NSD									
A	18	A12		NSD									
A	19	A32		NSD									
A	20	B44		NSD									
A	21	B24		NSD									
A	22	B4		NSD									
A	23	C14		NSD									
A	24	C34		NSD									
A	25	C44		NSD									
A	26	C33		NSD									
A	27	C13		NSD									
A	28	B3		NSD									
A	29	B23		NSD									
A	30	B43		NSD									
B	31	A10		NSD									
B	32	A42		NSD									
B	33	A22		NSD									
B	34	A2		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S26 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	35	D12		NSD									
B	36	D32		NSD									
B	37	D44		NSD									
B	38	D24		NSD									
B	39	D4		NSD									
B	40	A14		NSD									
B	41	A34		NSD									
B	42	B40		NSD									
B	43	B20		NSD									
B	44	B10		NSD									
B	45	B42		NSD									
B	46	B22		NSD									
B	47	B2		NSD									
B	48	C12		NSD									
B	49	C32		NSD									
B	50	C44		NSD									
B	51	C24		NSD									
B	52	B4		NSD									
B	53	B24		NSD									
B	54	B44		NSD									
B	55	D1		NSD									
B	56	A1		NSD									
B	57	A11		NSD									
B	58	A21		NSD									
B	59	A31		NSD									
B	60	A41		NSD									
C	61	A4		NSD									
C	62	A2		NSD									
C	63	A11		NSD									
C	64	A13		NSD									
C	65	B10		NSD									
C	66	B12		NSD									
C	67	B14		NSD									
C	68	B24		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S26 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	69	B22		NSD									
C	70	B20		NSD									
C	71	A21		NSD									
C	72	A23		NSD									
C	73	A33		NSD									
C	74	A43		NSD									
C	75	A42		NSD									
C	76	A40		NSD									
C	77	B41		NSD									
C	78	B43		NSD									
C	79	B44		NSD									
C	80	B1		NSD									
C	81	B3		NSD									
C	82	C14		NSD									
C	83	C12		NSD									
C	84	C10		NSD									
C	85	D11		NSD									
C	86	D13		NSD									
C	87	D34		NSD									
C	88	D32		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TPG-L2-FB-100404 *Lab/Cor Sample No.:* B4760 S95 A1

Descripiton: FILTER BLANK

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A2		NSD									
A	2	C3		NSD									
A	3	B30		NSD									
A	4	D22		NSD									
A	5	C10		NSD									
B	6	A20		NSD									
B	7	A3		NSD									
B	8	D11		NSD									
B	9	C32		NSD									
B	10	B2		NSD									

NSD = No Structures Detected
PAS = Primary Asbestos Structures
TAS = Total Asbestos Structures
AS>5 = Asbestos Structures > 5um
AFB>5 = Asbestos Fibers and Bundles > 5um
PCMEF-US = PCM Equivalent Fibers-US
PCMES-US = PCM Equivalent Structures-US
PCMEF-ISO = PCM Equivalent Fibers-ISO
PCMES-ISO = PCM Equivalent Structures-ISO

CF = Cleavage Fragments
TS = Transitional Structures

PSAS 5-10 = PROTOCOL ASB STRUCS 5-10
PSAS >10 = PROTOCOL ASB STRUCS >10
PSAS TOT = PROTOCOL ASB STRUCS TOTAL
PSCH 5-10 = PROTOCOL CHRYS STRUCS 5-10
PSCH >10 = PROTOCOL CHRYS STRUCS >10
PSCH TOT = PROTOCOL CHRYS STRUCS TOTAL
PSAM 5-10 = PROTOCOL AMPH STRUCS 5-10
PSAM >10 = PROTOCOL AMPH STRUCS >10
PSAM TOT = PROTOCOL AMPH STRUCS TOTAL

PChS = Primary Chrysotile Structures
PAmS = Primary Amphibole Structures

TAS_AHRA = AHERA-like Total Strucs 3:1
AS>5_AHRA = AHERA-like Asb Strucs >5 and 3:1
AS5-10_AHRA = AHERA-like Asb Strucs 5 - 10 and 3:1
AS>10_AHRA = AHERA-like Asb Strucs >10 and 3:1
TOS_AHRA = Total Other Amphibole Strucs 3:1
OS>5_AHRA = Other Amphibole Struc >5 and 3:1
OS5-10_AHRA = Other Amphibole Struc 5 - 10 and 3:1
OS>10_AHRA = Other Amphibole Strucs >10 and 3:1

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S4 A1
Client Sample No. APG-L2-2CH-100404
Description
Analysis Date 10/7/2004
Analyst KM

Volume (L) 289.2
No. of Grid Openings 92
Filter Area (mm2) 385
Area Analyzed (mm2) 1.33
Analytical Sens. (struc/cc) 0.000999
Dectection Limit. (struc/cc) 0.00299

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	14.3	0.0190	0.0114 - 0.0296	19
Total Asbestos Structures	14.3	0.0190	0.0114 - 0.0296	19
Asbestos Structures > 5um	7.5	0.00999	0.00479 - 0.0184	10
Asbestos Fibers and Bundles > 5um	6.8	0.00899	0.00411 - 0.0171	9
PCM Equivalent Fibers-US	6.8	0.00899	0.00411 - 0.0171	9
PCM Equivalent Structures-US	7.5	0.00999	0.00479 - 0.0184	10
PROTOCOL ASB STRUCS 5-10	1.5	0.00200	0.00 - 0.00629	2
PROTOCOL ASB STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS TOTAL	1.5	0.00200	0.00 - 0.00629	2
PROTOCOL CHRYS STRUCS 5-10	0.8	0.000999	0.00 - 0.00473	1
PROTOCOL CHRYS STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS TOTAL	0.8	0.000999	0.00 - 0.00473	1
PROTOCOL AMPH STRUCS 5-10	0.8	0.000999	0.00 - 0.00473	1
PROTOCOL AMPH STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS TOTAL	0.8	0.000999	0.00 - 0.00473	1
AHERA-like Total Structures 3:1	14.3	0.0190	0.0114 - 0.0296	19
AHERA-like Asb Strucs >5 and 3:1	7.5	0.00999	0.00479 - 0.0184	10
AHERA-like Asb Strucs 5 - 10 and 3:1	5.3	0.00699	0.00281 - 0.0144	7
AHERA-like Asb Strucs >10 and 3:1	2.3	0.00300	0.00 - 0.00774	3
Total Other Amphibole Strucs 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4760-S5 A1	**Volume (L)**	295.56
Client Sample No.	APG-L2-3CH-100404	**No. of Grid Openings**	91
Description		**Filter Area (mm2)**	385
Analysis Date	10/7/2004	**Area Analyzed (mm2)**	1.32
Analyst	KM	**Analytical Sens. (struc/cc)**	0.000988
		Dectection Limit. (struc/cc)	0.00295

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	6.8	0.00889	0.00407 - 0.0169	9
Total Asbestos Structures	6.8	0.00889	0.00407 - 0.0169	9
Asbestos Structures > 5um	1.5	0.00198	0.00 - 0.00622	2
Asbestos Fibers and Bundles > 5um	1.5	0.00198	0.00 - 0.00622	2
PCM Equivalent Fibers-US	1.5	0.00198	0.00 - 0.00622	2
PCM Equivalent Structures-US	0.8	0.000988	0.00 - 0.00468	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL ASB STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
AHERA-like Total Structures 3:1	6.8	0.00889	0.00407 - 0.0169	9
AHERA-like Asb Strucs >5 and 3:1	1.5	0.00198	0.00 - 0.00622	2
AHERA-like Asb Strucs 5 - 10 and 3:1	0.8	0.000988	0.00 - 0.00468	1
AHERA-like Asb Strucs >10 and 3:1	0.8	0.000988	0.00 - 0.00468	1
Total Other Amphibole Strucs 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S6 A1
Client Sample No. APG-L2-4CH-100404
Description
Analysis Date 10/8/2004
Analyst JH

Volume (L) 299.4
No. of Grid Openings 89
Filter Area (mm2) 385
Area Analyzed (mm2) 1.29
Analytical Sens. (struc/cc) 0.000997
Dectection Limit. (struc/cc) 0.00298

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	7.8	0.00997	0.00478 - 0.0183	10
Total Asbestos Structures	7.8	0.00997	0.00478 - 0.0183	10
Asbestos Structures > 5um	3.1	0.00399	0.00109 - 0.0102	4
Asbestos Fibers and Bundles > 5um	3.1	0.00399	0.00109 - 0.0102	4
PCM Equivalent Fibers-US	3.1	0.00399	0.00109 - 0.0102	4
PCM Equivalent Structures-US	3.1	0.00399	0.00109 - 0.0102	4
PROTOCOL ASB STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
AHERA-like Total Structures 3:1	7.8	0.00997	0.00478 - 0.0183	10
AHERA-like Asb Strucs >5 and 3:1	3.1	0.00399	0.00109 - 0.0102	4
AHERA-like Asb Strucs 5 - 10 and 3:1	3.1	0.00399	0.00109 - 0.0102	4
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Total Other Amphibole Strucs 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S7 A1
Client Sample No. APG-L2-5CH-100404
Description
Analysis Date 10/7/2004
Analyst DW

Volume (L) 290.64
No. of Grid Openings 91
Filter Area (mm2) 385
Area Analyzed (mm2) 1.32
Analytical Sens. (struc/cc) 0.00100
Dectection Limit. (struc/cc) 0.00300

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	4.6	0.00603	0.00221 - 0.0131	6
Total Asbestos Structures	4.6	0.00603	0.00221 - 0.0131	6
Asbestos Structures > 5um	0.8	0.00100	0.00 - 0.00476	1
Asbestos Fibers and Bundles > 5um	0.8	0.00100	0.00 - 0.00476	1
PCM Equivalent Fibers-US	0.8	0.00100	0.00 - 0.00476	1
PCM Equivalent Structures-US	0.8	0.00100	0.00 - 0.00476	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL ASB STRUCS >10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00300	0.00 - 0.00300	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00300	0.00 - 0.00300	0
AHERA-like Total Structures 3:1	4.6	0.00603	0.00221 - 0.0131	6
AHERA-like Asb Strucs >5 and 3:1	0.8	0.00100	0.00 - 0.00476	1
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00300	0.00 - 0.00300	0
AHERA-like Asb Strucs >10 and 3:1	0.8	0.00100	0.00 - 0.00476	1
Total Other Amphibole Strucs 3:1	0.0	<0.00300	0.00 - 0.00300	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00300	0.00 - 0.00300	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00300	0.00 - 0.00300	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00300	0.00 - 0.00300	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4760 S3 A1	**Volume (L)**	299.76
Client Sample No.	APG-L2-1ZB-100404	**No. of Grid Openings**	83
Description		**Filter Area (mm2)**	385
Analysis Date	10/7/2004	**Area Analyzed (mm2)**	1.20
Analyst	DW	**Analytical Sens. (struc/cc)**	0.00107
		Dectection Limit. (struc/cc)	0.00319

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.00319	0.00 - 0.00319	0
Total Asbestos Structures	0.0	<0.00319	0.00 - 0.00319	0
Asbestos Structures > 5um	0.0	<0.00319	0.00 - 0.00319	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00319	0.00 - 0.00319	0
PCM Equivalent Fibers-US	0.0	<0.00319	0.00 - 0.00319	0
PCM Equivalent Structures-US	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL ASB STRUCS >10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00319	0.00 - 0.00319	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00319	0.00 - 0.00319	0
AHERA-like Total Structures 3:1	0.0	<0.00319	0.00 - 0.00319	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00319	0.00 - 0.00319	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00319	0.00 - 0.00319	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00319	0.00 - 0.00319	0
Total Other Amphibole Strucs 3:1	0.0	<0.00319	0.00 - 0.00319	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00319	0.00 - 0.00319	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00319	0.00 - 0.00319	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00319	0.00 - 0.00319	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S4 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B34	ADQ	1	1	F	7.5	0.8	9.4			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	B14		NSD									
A	3	C14		NSD									
A	4	C44	ADQ	2	2	F	4.8	0.8	6.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	5	B23		NSD									
A	6	B3		NSD									
A	7	C13		NSD									
A	8	C43		NSD									
A	9	B42		NSD									
A	10	B22		NSD									
A	11	B2		NSD									
A	12	C12		NSD									
A	13	C32	AZQ	3	3	F	8	0.5	16	845	544	Mg, Si, Ca, Fe Actinolite Zone Axis [3 1 0] -- KM	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	14	B21		NSD									
A	15	B1		NSD									
A	16	C11		NSD									
A	17	C31		NSD									
A	18	B20		NSD									
A	19	B10		NSD									
A	20	A20		NSD									
A	21	A10		NSD									
A	22	D10	ADQ	4	4	F	2	0.38	5.3			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	23	D40		NSD									
A	24	A21		NSD									
A	25	A1		NSD									
A	26	D11		NSD									
A	27	D31		NSD									
A	28	A32	ADQ	5	5	F	5.5	0.8	6.9			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	29	A12		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S4 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	30	D2	CDQ	6	6	B	4.5	0.2	22	802	546	Mg, Si Chrysotile Confirmed - KM	TAS_AHRA
A	31	D22		NSD									
B	32	B24		NSD									
B	33	B14		NSD									
B	34	C14	ADQ	7	7	F	2.5	0.4	6.2			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	35	C24		NSD									
B	36	C34		NSD									
B	37	B33	CDQ	8	8	B	24	1	24			Mg, Si Chrysotile	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	38	B13	CDQ	9	9	B	5.3	0.4	13			Mg, Si Chrysotile	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	38	B13	CDQ	10	10	F	1.2	0.08	15			Mg, Si Chrysotile	TAS_AHRA
B	39	C3		NSD									
B	40	C23		NSD									
B	41	C43		NSD									
B	42	B12		NSD									
B	43	C2		NSD									
B	44	C22		NSD									
B	45	C42		NSD									
B	46	B11		NSD									
B	47	C1		NSD									
B	48	C21		NSD									
B	49	C41		NSD									
B	50	B40		NSD									
B	51	B20	ADQ	11	11	F	3.5	0.5	7.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	52	C20		NSD									
B	53	C40		NSD									
B	54	D10	ADQ	12	12	F	4	0.4	10			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	55	D40		NSD									
B	56	A30		NSD									
B	57	A10		NSD									
B	58	A31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S4 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	59	A1		NSD									
B	60	D1		NSD									
B	61	D21		NSD									
B	62	D41		NSD									
C	63	B44		NSD									
C	64	C34	CMQ	13	13	F	1.2	0.1	12			Mg, Si Chrysotile	TAS_AHRA
C	65	C44		NSD									
C	66	B33		NSD									
C	67	B13	ADQ	14	14	F	8.5	0.6	14			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	68	C23		NSD									
C	69	C33		NSD									
C	70	B22		NSD									
C	71	B12		NSD									
C	72	C12		NSD									
C	73	C32		NSD									
C	74	C42		NSD									
C	75	B1		NSD									
C	76	C1		NSD									
C	77	C11		NSD									
C	78	C31		NSD									
C	79	A30		NSD									
C	80	A10		NSD									
C	81	D20		NSD									
C	82	D40		NSD									
C	83	A11	ADQ	15	15	F	5.5	0.7	7.9			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	84	A31		NSD									
C	85	D1		NSD									
C	86	D21		NSD									
C	87	D41		NSD									
C	88	A33	ADQ	16		MD1-0	5.3	1.5	3.5			Actinolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-2CH-100404 *Lab/Cor Sample No.:* B4760 S4 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	88	A33	ADQ		16	MF	2.2	0.38	5.8			Mg, Al, Si, Ca, Fe Actinolite	
C	89	A13	ADQ	17	17	F	11	2.5	4.4			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	90	D3		NSD									
C	91	D33		NSD									
C	92	A24	CMQ	18	18	F	0.8	0.12	6.7			Mg, Al, Si, Ca, Fe Chrysotile	TAS_AHRA
C	92	A24	ADQ	19	19	F	10.5	1.5	7.0			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S5 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	AZQ	1	1	F	8	0.8	10	804	15501	Mg, Si, Ca, Fe Actinolite Zone Axis [5 1 2] - KM	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	B43		NSD									
A	7	B3		NSD									
A	8	B3		NSD									
A	9	C13		NSD									
A	10	C33		NSD									
A	11	B12	CDQ	2	2	B	0.7	0.2	3.5	805	548	Mg, Si Chrysotile Confirmed - KM	TAS_AHRA
A	12	C2		NSD									
A	13	C22		NSD									
A	14	C42		NSD									
A	15	B41		NSD									
A	16	B21	AZQ	3	3	F	1.5	0.25	6.0	806	549	Mg, Si, Ca, Fe Actinolite Zone Axis [1 0 1] - KM	TAS_AHRA
A	17	B1		NSD									
A	18	C11		NSD									
A	19	C31		NSD									
A	20	B30		NSD									
A	21	B10		NSD									
A	22	C10		NSD									
A	23	C40		NSD									
A	24	A40		NSD									
A	25	A20		NSD									
A	26	D10		NSD									
A	27	D30		NSD									
A	28	A31		NSD									
A	29	A11		NSD									
A	30	D1		NSD									
A	31	D21		NSD									
B	32	B4		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S5 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	33	C4		NSD									
B	34	C24		NSD									
B	35	A33		NSD									
B	36	D13		NSD									
B	37	D23		NSD									
B	38	D33		NSD									
B	39	D43		NSD									
B	40	A32		NSD									
B	41	D22		NSD									
B	42	D32		NSD									
B	43	D42		NSD									
B	44	A41		NSD									
B	45	A21		NSD									
B	46	D11		NSD									
B	47	D21		NSD									
B	48	D31		NSD									
B	49	D41		NSD									
B	50	D30	ADQ	4		MD1-1	13	4	3.2			Amosite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	50	D30	AZQ		4	MB	10	2	5.0	807	550	Mg, Si, Fe Amosite Zone Axis [1 0 0] - KM	AFB>5, PCMEF-US
B	51	D40		NSD									
B	52	A30	ADQ	5		MD1-0	4	2	2.0			Actinolite	TAS_AHRA
B	52	A30	ADQ		5	MF	1.2	0.22	5.5			Mg, Al, Si, Ca, Fe Actinolite	
B	52	A30	ADQ	6	6	F	5	1	5.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	53	A10		NSD									
B	54	C10		NSD									
B	55	C30		NSD									
B	56	B1	CM	7	7	F	1.2	0.11	11			Chrysotile	TAS_AHRA
B	57	C11		NSD									
B	58	C21		NSD									
B	59	C41		NSD									
B	60	B22		NSD									
B	61	B2		NSD									
C	62	B44		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-3CH-100404 *Lab/Cor Sample No.:* B4760 S5 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	63	B34		NSD									
C	64	B43		NSD									
C	65	B33		NSD									
C	66	B23		NSD									
C	67	B42		NSD									
C	68	B32	ADQ	8	8	F	1.8	0.12	15			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	69	B20		NSD									
C	70	B10		NSD									
C	71	A40		NSD									
C	72	A30		NSD									
C	73	D40	ADQ	9	9	F	1.8	0.3	6.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	74	A21		NSD									
C	75	A11		NSD									
C	76	A42		NSD									
C	77	A32		NSD									
C	78	A22		NSD									
C	79	A2		NSD									
D	80	C10		NSD									
D	81	C20		NSD									
D	82	C30		NSD									
D	83	C40		NSD									
D	84	A21		NSD									
D	85	A1		NSD									
D	86	D11		NSD									
D	87	D31		NSD									
D	88	A42		NSD									
D	89	A22		NSD									
D	90	A2		NSD									
D	91	D31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S6 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A10		NSD									
A	2	A30		NSD									
A	3	B40		NSD									
A	4	B42		NSD									
A	5	B22		NSD									
A	6	B24	AZQ	1	1	F	4.8	0.8	6.0	808	551	Mg, Si, Ca, Fe Actinolite Zone Axis [1 0 0] - KM	TAS_AHRA
A	7	B4		NSD									
A	8	B2		NSD									
A	9	A12		NSD									
A	10	A14	ADQ	2	2	F	4.5	0.6	7.5			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	11	A13		NSD									
A	12	D3		NSD									
A	13	D1		NSD									
A	14	C1		NSD									
A	15	C3	ADQ	3	3	F	5.3	1.2	4.4			Na, Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	16	C24		NSD									
A	17	C22		NSD									
A	18	C20		NSD									
A	19	D21		NSD									
A	20	D23	AZQ	4	4	F	2.3	0.4	5.8	810	553	Mg, Si, Ca, Fe Tremolite Zone Axis [4 1 3] - KM	TAS_AHRA
A	21	D43		NSD									
A	22	D41		NSD									
A	23	C40		NSD									
A	24	C42		NSD									
A	25	C33	ADQ	5	5	F	7.5	0.7	11		554	Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	26	C13		NSD									
A	27	B3		NSD									
A	28	B23	ADQ	6	6	F	4	0.5	8.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	29	B31		NSD									
B	30	A1		NSD									
B	31	A3		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S6 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	32	A23		NSD									
B	33	A43		NSD									
B	34	A41	ADQ	7	7	F	4.8	0.4	12			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	35	B40		NSD									
B	36	B42		NSD									
B	37	B24		NSD									
B	38	B22		NSD									
B	39	B20		NSD									
B	40	A21		NSD									
B	41	A23		NSD									
B	42	A3		NSD									
B	43	A1		NSD									
B	44	B1		NSD									
B	45	B3		NSD									
B	46	C14		NSD									
B	47	C12		NSD									
B	48	C10		NSD									
B	49	D11		NSD									
B	50	D12		NSD									
B	51	D34		NSD									
B	52	D32		NSD									
B	53	D30		NSD									
B	54	C31		NSD									
B	55	C33		NSD									
B	56	C13	ADQ	8	8	F	5.5	1.2	4.6			Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	56	C13	AZQ	9	9	F	5.1	1.5	3.4	843	557	Mg, Si, Ca, Fe Actinolite Ferri-actinolite - Zone Axis [4 0 -1] - KM	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	57	B3		NSD									
B	58	B23		NSD									
B	59	B21		NSD									
B	60	A10		NSD									
C	61	D1		NSD									
C	62	D3		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-4CH-100404 *Lab/Cor Sample No.:* B4760 S6 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	63	D24		NSD									
C	64	D22		NSD									
C	65	D20		NSD									
C	66	C23		NSD									
C	67	C44		NSD									
C	68	C42		NSD									
C	69	C40		NSD									
C	70	D43		NSD									
C	71	A1		NSD									
C	72	A22		NSD									
C	73	A20		NSD									
C	74	B21		NSD									
C	75	B13		NSD									
C	76	B4		NSD									
C	77	B2		NSD									
C	78	C1		NSD									
C	79	C3		NSD									
C	80	B10		NSD									
C	81	B20		NSD									
C	82	B22		NSD									
C	83	B12		NSD									
C	84	B3		NSD									
C	85	B1		NSD									
C	86	A2		NSD									
C	87	A12		NSD									
C	88	A32	ADQ	10	10	F	4	1	4.0			Actinolite	TAS_AHRA
C	89	A31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S7 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	C43		NSD									
A	7	C23		NSD									
A	8	C3		NSD									
A	9	B13		NSD									
A	10	B33		NSD									
A	11	B42		NSD									
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C32		NSD									
A	16	C41		NSD									
A	17	C21		NSD									
A	18	B11		NSD									
A	19	B31		NSD									
A	20	B41		NSD									
A	21	A31	AZQ	1	1	F	4.8	0.7	6.9	5229	15149	MG,AL,SI,CA,FE Actinolite Zone Axis [1 0 1] - KM	TAS_AHRA
A	22	A11		NSD									
A	23	D1		NSD									
A	24	D21		NSD									
A	25	D41		NSD									
A	26	D42		NSD									
A	27	D22		NSD									
A	28	D2		NSD									
A	29	A12		NSD									
A	30	A32		NSD									
A	31	A42	ADQ	2	2	F	2.5	0.5	5.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	32	A43		NSD									
A	33	A23		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S7 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	34	A3		NSD									
A	35	D13		NSD									
A	36	D33		NSD									
A	37	D44		NSD									
B	38	B44		NSD									
B	39	B24		NSD									
B	40	B4		NSD									
B	41	C14		NSD									
B	42	C34	ADQ	3	3	F	16.5	2.5	6.6			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	43	C44	ADQ	4	4	F	3.5	0.65	5.4			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	44	C43		NSD									
B	45	C23		NSD									
B	46	C3		NSD									
B	47	B13		NSD									
B	48	B23		NSD									
B	49	B43		NSD									
B	50	B42		NSD									
B	51	B22		NSD									
B	52	B2		NSD									
B	53	C12		NSD									
B	54	C32		NSD									
B	55	C41		NSD									
B	56	C11		NSD									
B	57	A41		NSD									
B	58	A21		NSD									
B	59	A1		NSD									
B	60	D11		NSD									
B	61	D31		NSD									
B	62	D41		NSD									
B	63	D21		NSD									
B	64	D1		NSD									
B	65	A11		NSD									
B	66	A31		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-5CH-100404 *Lab/Cor Sample No.:* B4760 S7 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	67	A41		NSD									
B	68	A43		NSD									
B	69	A33		NSD									
B	70	A23		NSD									
B	71	A13		NSD									
B	72	A3		NSD									
B	73	D3		NSD									
B	74	D13		NSD									
B	75	D23		NSD									
B	76	D33		NSD									
B	77	D43	CMQ	5	5	F	1	0.05	20	5230	15150	Mg, Si Chrysotile	TAS_AHRA
C	78	C42		NSD									
C	79	C32		NSD									
C	80	C12		NSD									
C	81	C2		NSD									
C	82	B12	CMQ	6	6	F	1.2	0.05	24	5283	15198	Mg, Si Chrysotile	TAS_AHRA
C	83	B4		NSD									
C	84	C4		NSD									
C	85	C14		NSD									
C	86	C24		NSD									
C	87	C34		NSD									
C	88	C44		NSD									
C	89	C43		NSD									
C	90	C33		NSD									
C	91	C23		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S3 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	C43		NSD									
A	7	C23		NSD									
A	8	C3		NSD									
A	9	B13		NSD									
A	10	B33		NSD									
A	11	B42		NSD									
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C32		NSD									
A	16	C41		NSD									
A	17	C21		NSD									
A	18	C1		NSD									
A	19	B11		NSD									
A	20	B31		NSD									
A	21	B40		NSD									
A	22	B20		NSD									
A	23	B10		NSD									
A	24	D41		NSD									
A	25	D21		NSD									
A	26	D1		NSD									
A	27	A11		NSD									
A	28	A31		NSD									
A	29	A42		NSD									
A	30	A22		NSD									
A	31	A2		NSD									
A	32	D12		NSD									
A	33	D32		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S3 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	34	D43		NSD									
B	35	B44		NSD									
B	36	B24		NSD									
B	37	B4		NSD									
B	38	C14		NSD									
B	39	C34		NSD									
B	40	C43		NSD									
B	41	C23		NSD									
B	42	C3		NSD									
B	43	B13		NSD									
B	44	B33		NSD									
B	45	B42		NSD									
B	46	B22		NSD									
B	47	B2		NSD									
B	48	C12		NSD									
B	49	C32		NSD									
B	50	C41		NSD									
B	51	C21		NSD									
B	52	C1		NSD									
B	53	B11		NSD									
B	54	B31		NSD									
B	55	B40		NSD									
B	56	B20		NSD									
B	57	B10		NSD									
B	58	A10		NSD									
B	59	A30		NSD									
B	60	A41		NSD									
B	61	A21		NSD									
C	62	B43		NSD									
C	63	B23		NSD									
C	64	B3		NSD									
C	65	C13		NSD									
C	66	C33		NSD									
C	67	C42		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R3

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: APG-L2-1ZB-100404 *Lab/Cor Sample No.:* B4760 S3 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	68	C22		NSD									
C	69	C2		NSD									
C	70	B12		NSD									
C	71	B32		NSD									
C	72	B41		NSD									
C	73	B21		NSD									
C	74	B1		NSD									
C	75	C11		NSD									
C	76	C31		NSD									
C	77	C41		NSD									
C	78	C40		NSD									
C	79	C20		NSD									
C	80	C10		NSD									
C	81	D11		NSD									
C	82	D31		NSD									
C	83	D41		NSD									