




CLOW WATER SYSTEMS COMPANY



2266 South Sixth Street
P.O. Box 6001
Coshocton, Ohio 43812-6001
(740) 622-6651
FAX (740) 622-8551

May 29, 2013

Director
Special Litigation and Projects Division
Office of Civil Enforcement
Bldg. Ariel Rios South
3rd Floor, Room 3118B
1200 Pennsylvania Ave. NW
Washington, D.C. 20004

Kimbra Reibold
Ohio EPA, SEDO-DAPC
2195 Front Street
Logan, Ohio 43138

Robert A. Kaplan
Regional Counsel
USEPA, Region 5
Mail Code C-14J
77 West Jackson Boulevard
Chicago, Illinois 60604

Compliance Tracker, AE-17J

Air Enforcement and Compliance Assurance Branch
USEPA, Region 5
77 West Jackson Boulevard
Chicago, Illinois 60604

Director
USEPA, Region V
Air and Radiation Division
77 West Jackson Blvd.
Chicago, IL 60604

James M. Proctor II
McWane, Inc.
JMProctor@mcwane.com

Jeet Radia
McWane, Inc.
jradia@mcwane.com

**Re: Consent Decree Civil Action No. [CV] 10-JEO-1902-S
NESHAP 40 CFR Part 63 Subpart ZZZZZ**

Dear Sir/Madam:

Clow Water Systems Company (Clow) conducted a stack test on May 2, 2013 of its Cupola Scrubber System (P901) to demonstrate compliance with the Emission Limit of 0.078 pounds of particulate matter per ton of metal melted as required by the Consent Decree (Appendix 3 (III)).

In addition, observations were made for opacity at the Cupola Shroud and Flange Fabrication central roof vent using Method 9 and Method 22 respectfully in accordance with NESHAP 40 CFR Part 63 Subpart ZZZZZ.

A copy of the stack test report is enclosed. The results of the stack test are summarized below. All values are averages of three 60-minute test runs.

Emission Rate (lb PM/ton metal melted):	0.046
Operating Rate (ton metal melted/hr):	76
Scrubber System Total Pressure Drop (in. H ₂ O):	76
Ring Jet Water Flow Rate (gpm):	752
Ring Jet Pump Pressure (psi):	34
Venturi Water Flow Rate (gpm):	359
Venturi Pump Pressure (psi):	13
Method 9 Cupola Shroud (max % VE):	15
Method 22 Flange Fabrication vent:	no VE observed

If you have any questions regarding the enclosed, please contact me at (740) 291-1087.

Sincerely,



Heather Rainwater
Environmental Manager
Clow Water Systems Company

**Superior Quality
Emission Testing.**

**Valid Results
Guaranteed.**

Air Compliance



Testing, Inc.

P.O. Box 41156 Cleveland, Ohio 44141

1-800-EPA-AIR1 www.aircomp.com

testing@aircomp.com

May 28, 2013

Heather Rainwater
Environmental Manager
Clow Water Systems Co.
PO Box 6001
Coshocton, Ohio 43812-6001


Dear Heather:

The following report provides the results of the compliance emission testing conducted on May 2, 2013. These results are a product of the application of the U.S. EPA Stationary Source Sampling Methods listed in 40 CFR Part 60 Appendix A that were in effect at the time of this test. To the best of my knowledge, this report has been checked for completeness, and the results presented are accurate, error-free, legible, and representative of the actual emissions measured during testing.

Please mail one copy of this report along with any other supportive process operating data collected during this test to your local EPA representative. You should also attach a cover letter (on company letterhead) stating the purpose and the outcome of this test. Additionally, you may address, preferably in a timetable format, any obligations or implications that might be necessary to achieve environmental compliance because of the result of this test.

Please do not hesitate to call if you have any questions or concerns about these test results. On behalf of Air Compliance Testing, I would also like to personally thank you for the opportunity to work with you on this testing project and would enjoy the opportunity to work with you again on any additional future testing projects.

Sincerely,



Robert J. Lisy, Jr.
Technical Manager

Table of Contents

	Page
1.0 INTRODUCTION	2
1.1 Summary of Test Program	2
1.2 Key Personnel	2
2.0 SUMMARY AND DISCUSSION OF TEST RESULTS	3 - 4
2.1 Objectives and Test Matrix	3
2.2 Field Test Changes and Problems	3
2.3 Presentation of Results	4
3.0 PLANT AND SAMPLING LOCATION DESCRIPTIONS	11
3.1 Process Description and Operation	11
3.2 Control Equipment Description	11
3.3 Flue Gas Sampling Locations	11
3.4 Process Sampling Location	11
4.0 SAMPLING AND ANALYTICAL PROCEDURES	14 - 15
4.1 Test Methods	14 - 15
4.2 Procedures for Obtaining Process Data	15
5.0 INTERNAL QA/QC ACTIVITIES	17
5.1 QA Audits	17
5.2 QA/QC Problems	17
6.0 APPENDIX	20
Production and Process Data	
Laboratory Results	
Field Data Sheets	
Calibrations and Certifications	

1.0 INTRODUCTION

1.1 Summary of Test Program

Clow Water Systems Co. (Facility ID: 06-16-01-0006), located in Coshocton, Ohio, contracted Air Compliance Testing, Inc. of Cleveland, Ohio, to conduct compliance stack emission testing for their Cupola Emission System (P901). Testing was performed to satisfy the emission testing requirements pursuant to Appendix 3 Section III of the McWane, Inc. Consent Decree and the testing requirements outlined in the National Emission Standards for Hazardous Air Pollutants (NESHAP) for Iron and Steel Foundries Area Sources (40 CFR Part 63 Subpart ZZZZZ). The testing was performed on May 2, 2013.

Sampling was performed at the P901 Scrubber Exhaust Stack to determine the emissions of filterable particulate matter (PM). In addition, observations were performed at the P901 Scrubber System Shroud Area to determine the percent opacity of visible emissions (VE's) and at the Flange Fabrication Building to determine the frequency of fugitive emissions. Testing was conducted during maximum achievable operations. During this test, emissions from P901 were controlled by an afterburner, wet cap, venturi scrubber, and Ring Jet scrubber system which includes packed bed, Ring Jets and demister.

The test methods that were conducted during this test were EPA Methods 1, 2, 3, 4, 5, and 9. EPA Method 22 observations were performed by Clow Water Systems personnel.

1.2 Key Personnel

The key personnel who coordinated this test program (and their phone numbers) were:

Heather Rainwater, Environmental Manager, Clow Water Systems Company, 740-622-6651

Marco Deshaies, Ohio EPA, SEDO DAPC, 740-380-5255

Tyson Houchin QSTI, Operations Director, Air Compliance Testing, Inc., 800-372-2471

Sin Hoi Chiew QI, Reporting Engineer, Air Compliance Testing, Inc., 800-372-2471

2.0 SUMMARY AND DISCUSSION OF TEST RESULTS

2.1 Objectives and Test Matrix

The purpose of this test was to determine the emissions of filterable PM at the P901 Scrubber System Exhaust Stack, the percent opacity of VE's at the P901 Scrubber System Shroud Area, and the frequency of fugitive emissions at the Flange Fabrication Building during maximum achievable operations. Testing was performed to satisfy the emission testing requirements pursuant to Appendix 3 Section III of the McWane, Inc. Consent Decree and the testing requirements outlined in 40 CFR Part 63 Subpart ZZZZZ.

The specific test objectives for this test were to:

Measure the concentration of filterable PM at the P901 Scrubber System Exhaust Stack.

Measure the dry standard and actual volumetric flow rate of the stack gas at the P901 Scrubber Exhaust Stack.

Utilize the above variables to determine the emissions of filterable PM at the P901 Scrubber Exhaust Stack during maximum achievable operations.

Determine the VE's (as %-opacity) at the P901 Scrubber System Shroud Area during maximum achievable operations.

Table 2.1 presents the sampling and analytical matrix log for this test.

2.2 Field Test Changes and Problems

No field test changes or problems occurred during the performance of this test that would bias the accuracy of the results of this test.

2.3 Presentation of Results

A single sampling train was utilized during each run at the P901 Scrubber Exhaust Stack to determine the emissions of filterable PM. This sampling train measured the stack gas volumetric flow rate, dry molecular weight, moisture content, and concentration of filterable PM.

Table 2.2 displays the emissions of filterable PM measured at the P901 Scrubber Exhaust Stack.

Table 2.3 summarizes the VE results. The table displays the minimum, maximum, and six-minute average opacity readings. Table 2.3 also displays the frequency of fugitive emissions recorded at the Flange Fabrication Building. Fugitive emission frequencies were recorded by Clow Water Systems personnel.

Tables 2.4.1 - 2.4.3 display the measured results for the VE readings at the P901 Scrubber System Shroud Area. The data displays the minimum, maximum, and maximum six-minute average opacity readings.

EPA TEST METHODS UTILIZED						
Date	Run No.	Sampling Location	M1/M2 (Flow)	M3 (Dry Mol. Wt.)	M4 (%H ₂ O)	M5 (Filterable PM)
5/2/2013	1	P901 Scrubber Exhaust Stack	7:43 - 8:51 60	7:43 - 8:51 60	7:43 - 8:51 60	7:43 - 8:51 60
5/2/2013	2	P901 Scrubber Exhaust Stack	9:17 - 10:24 60	9:17 - 10:24 60	9:17 - 10:24 60	9:17 - 10:24 60
5/2/2013	3	P901 Scrubber Exhaust Stack	10:50 - 11:54 60	10:50 - 11:54 60	10:50 - 11:54 60	10:50 - 11:54 60

All times are Eastern Daylight Time.

Table 2.1 - Sampling and Analytical Matrix

P901 Scrubber Exhaust Stack				
	Run 1	Run 2	Run 3	Average
Total Metal Charged (ton/hr)*	81	78	67	75
Filterable Particulate Matter Mass Emission Rate (lb/ton)	0.044	0.043	0.049	0.046
Filterable Particulate Matter Mass Emission Rate (lb/hr)	3.58	3.36	3.32	3.42
Filterable Particulate Matter Concentration (grains/dscf)	0.0077	0.0071	0.0072	0.0073
Stack Gas Average Flow Rate (acfm)	67,184	68,364	67,338	67,629
Stack Gas Average Flow Rate (scfm)	57,687	58,347	57,509	57,848
Stack Gas Average Flow Rate (dscfm)	54,554	54,843	53,771	54,389
Stack Gas Average Velocity (fpm)	3,074	3,128	3,081	3,095
Stack Gas Average Static Pressure (in-H ₂ O)	-0.83	-0.40	-0.63	-0.62
Stack Gas Average Temperature (°F)	140	144	144	143
Stack Gas Percent by Volume Moisture (%H ₂ O)	5.43	6.01	6.50	5.98
Measured Stack Inner Diameter (in)†	63.30	63.30	63.30	63.30
Percent by Volume Carbon Dioxide in Stack Gas (%-dry)	11.00	12.47	11.00	11.49
Percent by Volume Oxygen in Stack Gas (%-dry)	12.00	12.37	11.50	11.96
Percent by Volume Nitrogen in Stack Gas (%-dry)	77.00	75.17	77.50	76.56

* Provided by Clow Water Systems personnel.

† The P901 Scrubber Exhaust Stack was elliptical in shape.

Table 2.2 - Emission Results

Date	Run No.	Sampling Location	Test Run Start Time	Test Run Stop Time	Test Run Duration (min)	Minimum Reading (%-opacity)	Maximum Reading (%-opacity)	Highest Six-Minute Average (%-opacity)
5/2/2013	1	P901 Scrubber System Shroud Area	7:45	8:45	60	0.0	15.0	5.2
5/2/2013	2	P901 Scrubber System Shroud Area	9:17	10:17	60	0.0	15.0	8.1
5/2/2013	3	P901 Scrubber System Shroud Area	10:50	11:50	60	0.0	15.0	6.3

Date	Run No.	Sampling Location	Test Run Start Time	Test Run Stop Time	Test Run Duration (min)	Accumulated Emission Time (min)
5/2/2013	1	Flange Fabrication Building	7:56	8:46	40	0.0
5/2/2013	2	Flange Fabrication Building	9:18	10:08	40	0.0
5/2/2013	3	Flange Fabrication Building	10:52	11:42	40	0.0

Note: EPA Method 22 observations were performed by Clow Water Systems personnel.

Table 2.3 - Opacity Test Result Summary

					Max 6 min average	5.21	
					Minimum Reading	0	
					Maximum Reading	15.00	
Start Time	7:45						
End Time	8:45						
Sec.	0	15	30	45	Six minute averages:		
Min.							
0	0	10	0	5	3.13	3.33	2.92
1	5	10	0	0	2.92	2.71	2.50
2	0	0	0	0	2.92	2.92	2.92
3	5	5	15	5	3.75	3.75	3.75
4	0	0	0	0	2.92	2.92	3.13
5	5	0	5	5	3.54	3.75	3.96
6	5	0	0	5	4.17	3.96	3.96
7	0	5	5	5	3.96	4.17	3.96
8	0	0	10	10	3.75	4.17	4.68
9	5	5	0	0	3.96	3.96	4.17
10	0	5	10	0	4.38	4.38	4.17
11	10	5	10	5	3.96	3.75	3.54
12	0	0	0	5	3.13	3.75	3.96
13	5	0	0	5	3.96	3.96	4.17
14	10	10	0	5	4.38	4.38	4.38
15	5	10	5	0	4.38	4.17	3.96
16	0	0	0	5	3.96	4.17	4.38
17	5	0	0	5	4.38	4.17	4.17
18	15	0	5	5	3.96	3.33	3.54
19	5	5	0	10	3.33	3.13	2.92
20	10	10	5	0	2.50	2.08	1.88
21	0	5	0	5	2.08	2.71	2.71
22	5	5	0	5	2.92	3.13	3.13
23	0	0	0	0	2.92	3.13	3.13
24	0	5	5	0	3.13	3.13	2.92
25	0	0	0	0	3.13	3.13	3.33
26	0	5	5	5	3.33	3.33	3.33
27	15	5	5	5	3.33	2.71	2.92
28	10	5	0	0	2.71	2.71	2.92
29	5	0	0	0	2.92	2.71	2.92
30	0	0	5	5	3.13	3.33	3.54
31	0	5	0	0	3.33	3.75	3.75
32	0	5	10	0	3.75	3.75	3.54
33	0	10	5	0	3.54	4.17	3.75
34	10	10	0	0	4.17	3.96	3.96
35	0	5	5	0	4.79	4.79	4.58
36	5	5	0	5	4.38	4.17	3.96
37	10	5	0	0	4.17	3.96	3.75
38	0	5	5	0	4.38	4.58	4.79
39	15	0	10	5	5.00	4.79	5.21
40	5	10	5	15	4.79	5.00	4.58
41	0	0	0	0	4.17	4.17	4.38
42	0	0	5	5	4.38	4.38	4.38
43	5	0	5	10	4.38	4.38	4.17
44	5	10	0	10	3.75	3.54	3.13
45	10	10	0	5	2.71	2.29	1.88
46	10	0	5	5	1.67	1.25	1.25
47	0	5	0	0	1.04	1.04	0.83
48	0	5	0	5	0.83	1.04	0.83
49	5	0	0	0	0.63	0.42	0.42
50	0	0	0	0	0.83	1.25	1.46
51	0	0	0	0	2.29	2.50	2.50
52	0	0	0	5	2.71	2.71	3.13
53	0	0	0	0	3.33	3.54	3.54
54	5	0	0	0	3.75		
55	0	0	0	10			
56	10	5	10	10			
57	5	0	5	0			
58	0	10	10	0			
59	5	0	0	5			

Table 2.4.1 - Visible Emissions

					Max 6 min average	8.13		
					Minimum Reading	0		
					Maximum Reading	15.00		
	Start Time	9:17						
	End Time	10:17						
Sec.	0	15	30	45	Six minute averages:			
Min.								
0	5	5	10	5	4.58	4.79	4.79	4.58
1	5	0	5	0	4.79	4.79	4.79	5.00
2	5	5	0	5	5.21	5.00	4.79	4.79
3	10	10	5	5	4.79	4.58	4.38	4.17
4	5	5	5	0	4.38	4.17	4.38	4.38
5	0	5	0	10	4.38	4.58	4.58	5.00
6	10	5	5	10	5.00	5.00	5.21	5.42
7	5	0	10	5	5.63	5.83	6.04	5.83
8	0	0	0	5	5.83	6.04	6.25	6.46
9	5	5	0	10	6.25	6.04	6.25	6.88
10	0	10	5	0	7.08	7.50	7.29	7.50
11	5	5	10	10	8.13	8.13	7.92	7.71
12	10	10	10	15	7.29	6.88	6.67	6.46
13	10	5	5	5	6.04	6.04	6.25	6.46
14	5	5	5	0	6.46	6.25	6.46	6.88
15	0	10	15	15	7.50	7.92	7.92	7.29
16	10	5	10	15	7.08	6.88	6.88	6.46
17	5	0	5	0	5.83	5.63	5.63	5.42
18	0	5	5	5	5.42	5.42	5.42	5.42
19	10	10	10	5	5.42	5.00	4.79	4.58
20	0	10	15	15	4.38	4.79	4.58	3.96
21	10	10	0	10	3.33	2.92	2.50	2.50
22	5	5	0	0	2.08	1.88	1.67	2.08
23	0	0	0	0	2.29	2.50	2.71	2.71
24	0	5	5	5	2.92	2.92	2.92	2.71
25	0	5	5	0	2.50	2.50	2.29	2.08
26	10	5	0	0	2.29	2.08	2.08	2.50
27	0	0	0	0	2.50	2.50	2.71	2.92
28	0	0	10	5	3.13	3.54	3.54	3.54
29	5	5	0	5	3.54	3.75	4.17	4.58
30	0	5	0	0	4.68	4.58	4.58	4.79
31	0	0	0	5	5.21	5.63	5.83	5.83
32	5	5	10	0	5.63	5.63	5.63	5.42
33	0	5	5	5	5.42	5.42	5.83	6.04
34	10	0	10	5	6.25	6.46	7.08	7.29
35	10	15	10	5	7.50	7.50	7.08	6.88
36	0	5	5	10	6.88	7.08	7.08	7.08
37	10	5	0	0	7.08	6.67	6.88	7.08
38	5	5	5	0	7.08	7.29	7.29	7.08
39	0	15	10	10	7.08	7.08	6.46	6.25
40	15	15	15	10	6.04	5.63	5.42	5.00
41	10	5	5	5	4.79	4.38	4.38	4.38
42	5	5	5	10	4.58	4.58	4.58	4.38
43	0	10	5	0	3.96	4.17	3.75	3.54
44	10	5	0	0	3.54	3.33	3.13	3.33
45	0	0	5	5	3.54	3.54	3.75	3.54
46	5	10	5	5	3.54	3.54	3.13	2.92
47	0	5	5	10	2.71	2.71	2.50	2.29
48	5	5	0	0	1.88	1.67	1.67	1.88
49	5	0	0	0	2.08	1.88	1.88	1.88
50	5	0	5	5	2.08	1.88	2.29	2.50
51	0	5	0	5	2.50	2.71	2.71	2.92
52	5	0	0	0	2.71	2.50	2.71	3.13
53	0	0	0	0	3.54	3.96	4.17	4.38
54	0	5	5	5	4.58			
55	0	0	0	5				
56	0	10	10	5				
57	5	5	5	0				
58	0	5	10	10				
59	10	5	5	5				

Table 2.4.2 - Visible Emissions

					Max 6 min average	6.25	
					Minimum Reading	0	
					Maximum Reading	15.00	
Start Time	10:50						
End Time	11:50						
Sec.	0	15	30	45	Six minute averages:		
Min.							
0	0	5	0	10	4.79	5.21	5.21
1	5	5	10	5	4.79	4.58	4.38
2	0	10	10	5	3.75	3.75	3.33
3	0	0	5	5	2.92	3.13	3.33
4	5	5	5	5	3.13	2.92	2.71
5	0	5	5	10	2.92	3.13	3.13
6	10	5	0	0	2.50	2.08	2.08
7	0	0	0	0	2.50	2.92	3.33
8	0	0	0	5	3.96	3.96	4.17
9	5	5	0	5	4.17	3.96	3.75
10	0	0	5	10	3.75	3.75	3.75
11	5	5	0	0	3.54	3.33	3.13
12	0	5	5	5	3.33	3.33	3.13
13	10	10	5	10	2.71	2.29	2.08
14	0	5	5	0	1.88	1.88	1.88
15	0	0	5	0	1.67	1.67	1.67
16	0	0	5	5	2.29	2.50	2.71
17	0	0	5	0	3.13	3.54	3.54
18	0	0	0	0	3.54	3.75	4.17
19	0	5	5	5	4.38	4.38	4.17
20	0	5	0	0	4.17	4.38	4.38
21	0	5	10	5	4.79	5.21	5.21
22	5	5	10	10	5.00	4.79	5.00
23	10	0	0	5	5.00	4.79	5.00
24	5	10	5	0	5.63	5.63	5.21
25	0	0	5	5	5.21	5.42	5.63
26	5	5	5	5	5.83	6.04	6.04
27	10	5	5	5	6.04	5.63	5.63
28	0	10	10	10	5.83	5.83	5.42
29	5	5	10	10	4.79	4.79	4.79
30	5	0	0	5	4.17	3.96	3.96
31	5	5	5	10	4.17	3.96	3.96
32	10	5	5	5	3.96	3.96	4.17
33	0	5	5	10	4.17	4.58	4.58
34	0	0	5	0	5.00	5.21	5.63
35	5	5	5	0	6.04	6.25	6.25
36	0	0	5	5	6.04	6.04	5.83
37	0	5	5	10	5.83	6.04	5.83
38	10	10	5	5	6.04	5.63	5.21
39	10	5	15	10	4.79	4.58	4.58
40	5	10	10	5	3.96	3.96	3.54
41	10	5	0	0	3.33	2.92	2.71
42	0	0	0	5	2.92	2.92	2.92
43	5	0	10	10	2.71	2.71	2.92
44	0	0	0	0	2.08	2.29	2.71
45	5	5	5	5	3.54	3.54	3.54
46	5	0	5	5	3.54	3.54	3.33
47	0	0	0	5	3.33	3.54	3.54
48	0	0	0	0	3.75	3.96	4.17
49	5	5	0	0	4.17	3.96	3.96
50	5	10	10	10	4.38	4.58	4.38
51	5	5	5	5	4.38	4.38	4.58
52	5	0	0	5	4.58	4.38	4.79
53	5	0	5	5	4.58	4.58	4.79
54	5	5	0	0	4.79		
55	0	5	5	5			
56	10	5	10	10			
57	5	10	5	5			
58	0	10	0	0			
59	5	5	5	5			

Table 2.4.3 - Visible Emissions

3.0 PLANT AND SAMPLING LOCATION DESCRIPTIONS

3.1 Process Description and Operation

Clow Water Systems Company manufactures ductile iron pipe and fittings. As part of the grey and ductile iron casting process, scrap metal is melted in a cupola, poured into specially designed sand molds or centrifugal casting machines, and then, undergoes a controlled solidification and cooling process. The P901 Cupola Melting Furnace was in operation for this test event and has a permitted capacity of 85 tons/hr.

Figure 3.1 depicts the process schematic.

3.2 Control Equipment Description

During this test, emissions from P901 were controlled by an afterburner, wet cap, venturi scrubber, and Ring Jet scrubber system which includes packed bed, Ring Jets and demister.

3.3 Flue Gas Sampling Locations

The P901 Scrubber Exhaust Stack had a measured inner diameter of 63.3-inches, was oriented in the vertical plane, and was accessed from a manlift. Two (2) 6.0-inch I.D. sampling ports were located 90° apart from one another at a location that met EPA Method 1, Section 11.1.1 criteria. Prior to emissions sampling, the stack was traversed to verify the absence of cyclonic flow. An average yaw angle of 7.29° was measured. Therefore, the sampling location also met EPA Method 1, Section 11.4.2 criteria. During emissions sampling, the stack was traversed for stack gas volumetric flow rate, dry molecular weight, moisture content, and filterable PM concentration determinations.

Figure 3.2 schematically illustrates the traverse point and sample port locations utilized.

3.4 Process Sampling Location

The EPA Reference Test Methods performed did not specifically require that process samples were to be taken during the performance of this testing event. It is in the best knowledge of Air Compliance Testing that no process samples were obtained and therefore no process sampling location was identified in this report.




Figure 3.1 - Cupola Emission Control System Schematic




Figure 3.2 - P901 Scrubber Exhaust Stack Traverse Point Location Drawing

4.0 SAMPLING AND ANALYTICAL PROCEDURES

4.1 Test Methods

4.1.1 EPA Method 1: Sample and Velocity Traverses for Stationary Sources

Principle: To aid in the representative measurement of pollutant emissions and/or total volumetric flow rate from a stationary source, a measurement site where the effluent stream is flowing in a known direction is selected, and the cross-section of the stack is divided into a number of equal areas. A traverse point is then located within each of these equal areas. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.2 EPA Method 2: Determination of Stack Gas Velocity and Volumetric Flow Rate (Type S)

Principle: The average gas velocity in a stack is determined from the gas density and from measurement of the average velocity head with a Type S (Stausscheibe or reverse type) pitot tube. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.3 EPA Method 3: Gas Analysis for the Determination of Dry Molecular Weight

Principle: A gas sample is extracted from a stack by one of the following methods: (1) single-point, grab sampling; (2) single-point, integrated sampling; or (3) multi-point, integrated sampling. The gas sample is analyzed for percent CO₂, percent O₂, and if necessary, for percent CO. For dry molecular weight determination a Fyrite analyzer will be used for the analysis. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.4 EPA Method 4: Determination of Moisture Content in Stack Gases

Principle: A gas sample is extracted at a constant rate from the source; moisture is removed from the sample stream and determined either volumetrically or gravimetrically. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.5 EPA Method 5: Determination of Particulate Emissions from Stationary Sources (Filterable PM only)

Principle: Particulate matter (PM) is withdrawn isokinetically from the source and collected on a glass fiber filter maintained at a temperature in the range of 120 ± 14°C (248 ± 25°F) or such other temperature as specified by an applicable subpart of the standards or approved by the Administrator, U.S. Environmental Protection Agency, for a particular application. The PM mass, which includes any material that condenses at or above the filtration temperature, is determined gravimetrically after removal of uncombined water. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.6 EPA Method 9: Visual Determination of the Opacity of Emissions from Stationary Sources

Principle: The opacity of emissions from stationary sources is determined visually by a qualified observer. This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

4.1.7 EPA Method 22: Visual Determination of Fugitive Emissions from Material Sources and Smoke Emissions from Flares

Principle: Fugitive emissions produced during material processing, handling, and transfer operations or smoke emissions from flares are visually determined by an observer without the aid of instruments. This method is used also to determine visible smoke emissions from flares used for combustion of waste process materials. This method determines the amount of time that visible emissions occur during the observation period (i.e., the accumulated emission time.). This method was utilized in its entirety as per the procedures outlined in 40 CFR Part 60, Appendix A.

The sampling train utilized during this testing project is depicted in Figure 4.1.

4.2 Procedures for Obtaining Process Data

Process data was recorded by Clow Water Systems Co. personnel utilizing their typical record keeping procedures. Recorded process data was provided to Air Compliance Testing, Inc. personnel at the conclusion of this test event. The process data is located in Table 2.2 and in the Appendix.




Figure 4.1 - EPA Method 5 Sampling Train Schematic

5.0 INTERNAL QA/QC ACTIVITIES

5.1 QA Audits

Tables 5.1 and 5.2 illustrate the QA audit activities that were performed during this test.

All meter boxes and sampling trains used during sampling performed within the requirements of their respective methods as is shown in Tables 5.1 and 5.2. All pre-test and post-test leak checks were well below the applicable limit. Minimum metered volumes and percent isokinetics were also met where applicable.

Aleksandr Spektor was certified on April 10, 2013 as a Visible Emissions Evaluator. The expiration date is six months from the issue date.

For quality assurance, the observers obtained a view of the emissions with the best available contrasting background and with the sun oriented in the 140° sector to their back. Readings were taken every 15 seconds and made to the nearest 5% opacity.

5.2 QA/QC Problems

No QA/QC problems occurred during this test event.

P901 Scrubber Exhaust Stack			
Method 5 Sampling Train	Run 1	Run 2	Run 3
Leak Rate Observed (Pre/Post) (cfm)	0.001 / 0.000	0.003 / 0.000	0.002 / 0.000
Applicable Method Allowable Leak Rate (cfm)	< 0.020	< 0.020	< 0.020
Acceptable	Yes	Yes	Yes
Volume of Dry Gas Collected (dscf)	40.723	41.694	40.551
Recommended Volume of Dry Gas Collected (dscf)	21,000	21,000	21,000
Acceptable	Yes	Yes	Yes
Percent of Isokinetic Sampling Rate (%)	98.5	100.3	99.5
Applicable Method Allowable Isokinetic Sampling Rate (%)	100 ± 10	100 ± 10	100 ± 10
Acceptable	Yes	Yes	Yes

Table 5.1 - EPA Method 5 Sample Train Audit Results Table

P901 Scrubber Exhaust Stack				
Pre-Test Dry Gas Meter Calibration Factor (Y)	Average Post-Test Dry Gas Meter Calibration Check Value (Yqa)	Post Test Dry Gas Meter Calibration Difference From Pre-Test Calibration Factor (%)		
		Applicable Method	Allowable Difference (%)	Acceptable
1.0008	1.0255	2.47%	5.00%	Yes

Table 5.2 - EPA Method 5 Dry Gas Meter Audit Results Table

6.0 APPENDIX

Appendix attached.

APPENDIX
to
Compliance Stack Emission Test Report

**Determination of Filterable Particulate
Matter and Visible Emissions**

Cupola Emission System (P901)

EPA Methods 1, 2, 3, 4, 5, 9, and 22

Clow Water Systems Co.
Coshocton, Ohio

Date Conducted: May 2, 2013
Job Number: 130502

Prepared by:
Air Compliance Testing, Inc.
PO Box 41156
Cleveland OH 44141-0156
Phone: (800) EPA-AIR1 (372-2471)

Report Date: May 28, 2013

Appendix Contents

1-PROCESS DATA

- Process Operational Data

2-LABORATORY DATA

- Laboratory Results

3-FIELD DATA

- Excel Test Data
- Excel Method Specific Data
- Excel Run Data
- Example Calculation

- Test Log (CEMS Methods)
- Main Method Field Data Sheets
- Isokinetic Field Data Sheets
- EPA Method 9 Field Data
- EPA Method 4 and ALT-008 Moisture Recovery
- EPA Method 3 Fyrite/Orsat Field Data
- EPA Method 3 Dry Molecular Weight Calculation
- EPA Method 2 Flow Data Sheets
- EPA Method 1 Cyclonic Flow
- EPA Method 1 Preliminary Field Data

4-CALIBRATIONS AND CERTIFICATIONS

ANALYZER CALIBRATIONS

- Analyzer Calibration Error
- Analyzer System Bias and System Drift

EQUIPMENT INSPECTIONS / CALIBRATIONS

- Probe Nozzle Inspections
- Pre-Test Pitot Tube / Probe Inspections
- Post-Test Pitot Tube / Probe Inspections

- Pre-Test Thermocouple System Audit
- Post-Test Thermocouple Check

- 10-Minute Cals
- Pre-Test Meter Box Leak Check
- Pre-Test Dry Gas Meter / Orifice Calibration
- Pre-Test Meter Console Calibration
- Post-Test dry Gas Meter ALT-009 Leak Check

- Post-Test Dry Gas Meter / Orifice and Console Calibration

- Post-Test Mini Meter / Orifice and Console Calibration

EQUIPMENT CERTIFICATIONS / HISTORY

- Dry Gas Meter Calibration History
- Aneroid Barometer/ DPG Calibration History
- Acetone Residuals History

- Calibration Gas Certifications
- Calibration Gas Diluter Certifications
- Reagent Certifications
- Quartz or Glass Fiber Filter Certification
- True Primary Flow Standard
- Reference Meter Calibration
- Micromanometer Certificate
- Thermocouple Certificate of Calibration
- Lake Balance (Method 4 and ALT-008)
- Lake Balance Report for H64 (Gravimetrics)
- Balance Calibration Weights Certification
- Balance Calibration History
- VE Azimuth Tables
- VE Declination
- VE Certificates
- Intent to Test Notification / Test Protocol

CLOW WATER OPERATIONAL DATA
05/02/13 SUMMARY

Run	Start Time	Stop Time	Pause Time	60 minute averages			
				Total Metal Charged (ton/hr)	Emission System Total DP (in.H2O)	Ring Jet Water Flow Rate (gpm)	Venturi Pump Pressure (psi)
1	7:43am	8:13am - 8:21am	8:51am	81	76	752	34
2	9:17am	9:47am-9:54am	10:14am	78	76	752	34
3	10:50am	11:20am-11:24am	11:54am	67	76	751	34
			AVERAGE	76	752	34	359
							13

Run 1

(7:43am-8:13am; 8:21am-8:51am)

Emission System Monitoring Data

Date	Time	Emission System Total DP (in.H2O)	Ring Jet Water Flow Rate (gpm)	Ring Jet Pump Pressure (psi)	Venturi Water Flow Rate (gpm)	Venturi Pump Pressure (psi)
5/2/2013	07:43:41.713	77	752	34	360	14
5/2/2013	07:44:41.739	75	752	34	362	14
5/2/2013	07:45:41.893	75	753	34	360	14
5/2/2013	07:46:41.946	76	753	34	360	14
5/2/2013	07:47:42.004	75	752	34	362	14
5/2/2013	07:48:42.104	76	752	34	361	14
5/2/2013	07:49:42.186	75	752	34	359	14
5/2/2013	07:50:42.292	75	753	34	361	14
5/2/2013	07:51:42.435	75	751	34	361	14
5/2/2013	07:52:42.473	76	753	34	360	14
5/2/2013	07:53:42.651	76	752	34	361	14
5/2/2013	07:54:42.899	76	751	34	360	14
5/2/2013	07:55:42.960	76	752	34	360	13
5/2/2013	07:56:43.038	76	753	34	361	13
5/2/2013	07:57:43.108	77	752	34	360	14
5/2/2013	07:58:43.251	76	752	34	359	14
5/2/2013	07:59:43.395	76	753	34	359	13
5/2/2013	08:00:43.486	76	752	34	358	14
5/2/2013	08:01:43.500	75	752	34	359	14
5/2/2013	08:02:43.672	76	752	34	360	14
5/2/2013	08:03:43.799	76	752	34	361	13
5/2/2013	08:04:43.821	75	753	34	359	13
5/2/2013	08:05:43.984	76	751	34	361	14
5/2/2013	08:06:44.090	75	752	34	361	14
5/2/2013	08:07:44.165	75	753	34	360	13
5/2/2013	08:08:44.374	77	751	34	361	14
5/2/2013	08:09:44.534	76	751	34	361	14
5/2/2013	08:10:44.764	74	751	34	361	13
5/2/2013	08:11:44.873	77	752	34	361	14
5/2/2013	08:12:45.096	76	753	34	364	14
5/2/2013	08:21:46.161	77	753	34	363	14
5/2/2013	08:22:46.428	77	752	34	362	14
5/2/2013	08:23:46.515	75	752	34	362	14
5/2/2013	08:24:46.583	74	753	34	360	13
5/2/2013	08:25:46.803	75	752	34	360	13
5/2/2013	08:26:46.975	75	752	34	359	14
5/2/2013	08:27:47.068	76	753	34	360	14
5/2/2013	08:28:47.161	76	753	34	361	14
5/2/2013	08:29:47.192	76	752	34	361	13
5/2/2013	08:30:47.417	75	752	34	361	13
5/2/2013	08:31:47.669	76	752	34	361	14
5/2/2013	08:32:47.746	77	753	34	360	14
5/2/2013	08:33:47.899	76	752	34	360	13
5/2/2013	08:34:48.061	75	753	34	361	14
5/2/2013	08:35:48.101	77	753	34	361	14
5/2/2013	08:36:48.120	76	752	34	361	14
5/2/2013	08:37:48.217	75	751	34	361	14
5/2/2013	08:38:48.298	75	753	34	361	14
5/2/2013	08:39:48.378	77	752	34	361	13
5/2/2013	08:40:48.496	76	753	34	363	14
5/2/2013	08:41:48.607	77	753	34	361	14
5/2/2013	08:42:48.656	74	753	34	360	14
5/2/2013	08:43:48.744	75	753	34	362	14
5/2/2013	08:44:48.782	75	753	34	361	14
5/2/2013	08:45:49.014	77	751	34	360	13
5/2/2013	08:46:49.206	76	753	34	362	14
5/2/2013	08:47:49.328	75	753	34	361	14
5/2/2013	08:48:49.605	76	752	34	361	14
5/2/2013	08:49:49.720	76	753	34	360	14
5/2/2013	08:50:49.787	75	751	34	361	14
AVERAGE		76	752	34	361	14

Run 1
(7:43am-8:13am; 8:21am-8:51am)
Cupola Melt Data

Date	Time	Total Metal Charged (lb)
5/2/2013	07:43:32	7181
5/2/2013	07:46:08	7030
5/2/2013	07:48:45	7050
5/2/2013	07:51:23	7018
5/2/2013	07:54:06	7133
5/2/2013	07:56:42	7032
5/2/2013	07:59:19	7103
5/2/2013	08:01:56	7028
5/2/2013	08:05:05	7090
5/2/2013	08:07:40	6996
5/2/2013	08:10:17	7050
5/2/2013	08:12:55	7033
5/2/2013	08:23:22	7065
5/2/2013	08:26:08	7140
5/2/2013	08:28:45	7109
5/2/2013	08:31:22	7141
5/2/2013	08:34:00	7034
5/2/2013	08:36:47	7122
5/2/2013	08:39:25	7040
5/2/2013	08:42:31	7115
5/2/2013	08:45:07	7052
5/2/2013	08:47:43	7018
5/2/2013	08:50:21	7050
	TOTAL	162,630
	TOTAL	81 ton/hr

Run 2

(9:17am-9:47am; 9:54am-10:14am)

Emission System Monitoring Data

Date	Time	Emission System Total DP (in.H2O)	Ring Jet Water Flow Rate (gpm)	Ring Jet Pump Pressure (psi)	Venturi Water Flow Rate (gpm)	Venturi Pump Pressure (psi)
5/2/2013	09:17:52.220	77	754	34	360	14
5/2/2013	09:18:52.258	76	752	34	360	13
5/2/2013	09:19:52.405	77	751	34	359	13
5/2/2013	09:20:52.513	74	753	34	360	13
5/2/2013	09:21:52.762	75	752	34	361	14
5/2/2013	09:22:52.835	76	752	34	361	13
5/2/2013	09:23:52.893	77	753	34	358	13
5/2/2013	09:24:52.997	77	752	34	357	13
5/2/2013	09:25:53.137	77	752	34	358	13
5/2/2013	09:26:53.238	75	752	34	357	14
5/2/2013	09:27:53.266	77	753	34	358	13
5/2/2013	09:28:53.309	73	751	34	357	13
5/2/2013	09:29:53.443	76	754	34	358	14
5/2/2013	09:30:53.510	76	753	34	360	14
5/2/2013	09:31:53.528	75	753	34	360	14
5/2/2013	09:32:53.585	76	752	34	358	14
5/2/2013	09:33:53.873	77	753	34	357	14
5/2/2013	09:34:53.882	77	751	34	358	13
5/2/2013	09:35:53.963	76	752	34	359	13
5/2/2013	09:36:54.032	77	753	34	358	13
5/2/2013	09:37:54.072	78	751	34	358	13
5/2/2013	09:38:54.061	77	752	34	358	13
5/2/2013	09:39:54.280	76	752	34	358	13
5/2/2013	09:39:54.283	76	752	34	358	13
5/2/2013	09:40:54.497	77	753	34	358	13
5/2/2013	09:41:54.592	76	752	34	357	13
5/2/2013	09:42:54.665	77	752	34	358	13
5/2/2013	09:43:54.763	78	753	34	359	14
5/2/2013	09:44:54.889	76	752	34	360	14
5/2/2013	09:45:55.015	77	752	34	359	13
5/2/2013	09:46:55.114	77	753	34	358	13
5/2/2013	09:54:55.853	78	753	34	360	13
5/2/2013	09:55:56.007	75	751	34	360	13
5/2/2013	09:56:56.181	76	753	34	358	14
5/2/2013	09:57:56.280	74	752	34	358	13
5/2/2013	09:58:56.454	77	752	34	359	13
5/2/2013	09:59:56.708	75	753	34	359	14
5/2/2013	10:00:56.801	77	752	34	358	14
5/2/2013	10:01:56.853	76	753	34	358	14
5/2/2013	10:02:56.863	75	753	34	359	14
5/2/2013	10:03:56.894	77	753	34	360	14
5/2/2013	10:04:56.904	76	752	34	358	13
5/2/2013	10:05:56.952	75	751	34	357	13
5/2/2013	10:06:56.968	77	754	34	358	13
5/2/2013	10:07:56.979	76	752	34	359	13
5/2/2013	10:08:57.071	76	753	34	358	13
5/2/2013	10:09:57.141	75	751	34	359	13
5/2/2013	10:10:57.240	76	752	34	359	14
5/2/2013	10:11:57.421	76	751	34	359	13
5/2/2013	10:12:57.452	76	752	34	358	13
5/2/2013	10:13:57.563	73	750	34	358	13
AVERAGE		76	752	34	359	13

Run 2
(9:17am-9:47am; 9:54am-10:14am)
Cupola Melt Data

Date	Time	Total Metal Charged (lb)
5/2/2013	09:17:49	7077
5/2/2013	09:20:40	7141
5/2/2013	09:23:16	7005
5/2/2013	09:25:53	7070
5/2/2013	09:28:31	7041
5/2/2013	09:31:24	6989
5/2/2013	09:34:02	7005
5/2/2013	09:36:38	6991
5/2/2013	09:39:22	7105
5/2/2013	09:41:57	7162
5/2/2013	09:44:34	7131
5/2/2013	09:55:02	7095
5/2/2013	09:57:38	7131
5/2/2013	10:00:15	7116
5/2/2013	10:02:52	7216
5/2/2013	10:05:45	7218
5/2/2013	10:08:22	7034
5/2/2013	10:10:59	7024
5/2/2013	10:13:36	7025
5/2/2013	10:16:21	7136
5/2/2013	10:18:57	7000
5/2/2013	10:21:33	7253
TOTAL		155,965
TOTAL	78	ton/hr

Run 3

(10:50am-11:20am; 11:24am-11:54am)

Emission System Monitoring Data

Date	Time	Emission System Total DP (in.H2O)	Ring Jet Water Flow Rate (gpm)	Ring Jet Pump Pressure (psi)	Venturi Water Flow Rate (gpm)	Venturi Pump Pressure (psi)
5/2/2013	10:50:00.916	76	751	34	359	14
5/2/2013	10:51:01.016	76	750	34	360	14
5/2/2013	10:52:01.100	76	751	34	359	13
5/2/2013	10:53:01.214	75	751	34	359	14
5/2/2013	10:54:01.462	75	751	34	359	13
5/2/2013	10:55:01.600	74	751	34	361	13
5/2/2013	10:56:01.683	77	750	34	357	13
5/2/2013	10:57:01.771	73	750	34	358	13
5/2/2013	10:58:01.830	76	751	34	355	13
5/2/2013	10:59:01.914	76	750	34	356	13
5/2/2013	11:00:01.973	75	751	34	357	14
5/2/2013	11:01:02.082	76	751	34	358	13
5/2/2013	11:02:02.304	75	751	34	358	13
5/2/2013	11:03:02.459	77	751	34	360	13
5/2/2013	11:04:02.584	76	752	34	358	14
5/2/2013	11:05:02.793	76	750	34	358	13
5/2/2013	11:06:02.844	77	752	34	361	13
5/2/2013	11:07:03.030	77	752	34	358	13
5/2/2013	11:08:03.118	77	752	34	359	13
5/2/2013	11:09:03.166	75	752	34	358	13
5/2/2013	11:10:03.286	76	749	34	360	13
5/2/2013	11:11:03.514	75	751	34	358	13
5/2/2013	11:12:03.661	78	752	34	358	13
5/2/2013	11:13:03.815	77	752	34	358	13
5/2/2013	11:14:03.981	77	750	34	359	14
5/2/2013	11:15:04.147	76	751	34	358	13
5/2/2013	11:16:04.252	76	751	34	358	13
5/2/2013	11:17:04.337	77	752	34	358	14
5/2/2013	11:17:04.338	77	752	34	358	14
5/2/2013	11:18:04.437	76	751	34	357	13
5/2/2013	11:19:04.593	75	751	34	358	13
5/2/2013	11:24:05.033	76	751	34	357	13
5/2/2013	11:25:05.262	77	750	34	358	14
5/2/2013	11:26:05.316	76	752	34	359	14
5/2/2013	11:27:05.381	76	752	34	356	13
5/2/2013	11:28:05.465	76	751	34	356	13
5/2/2013	11:29:05.481	77	751	34	359	13
5/2/2013	11:30:05.626	76	750	34	356	13
5/2/2013	11:31:05.775	74	753	34	357	14
5/2/2013	11:32:05.839	76	751	34	357	14
5/2/2013	11:33:05.867	75	750	34	357	13
5/2/2013	11:34:05.981	73	750	34	356	13
5/2/2013	11:35:06.039	76	752	34	358	14
5/2/2013	11:36:06.150	76	752	34	355	13
5/2/2013	11:37:06.321	74	750	34	355	13
5/2/2013	11:38:06.574	75	751	34	356	13
5/2/2013	11:39:06.648	75	751	34	356	14
5/2/2013	11:40:06.821	76	750	34	353	13
5/2/2013	11:41:06.954	76	751	34	355	13
5/2/2013	11:42:06.993	75	752	34	353	13
5/2/2013	11:43:06.984	76	752	34	354	13
5/2/2013	11:44:07.036	75	753	34	354	14
5/2/2013	11:45:07.036	76	753	34	354	13
5/2/2013	11:46:07.129	75	752	34	354	13
5/2/2013	11:47:07.209	74	751	34	354	13
5/2/2013	11:48:07.317	74	750	34	355	13
5/2/2013	11:49:07.467	78	751	34	354	14
5/2/2013	11:50:07.585	75	752	34	354	14
5/2/2013	11:51:07.650	74	750	34	354	14
5/2/2013	11:52:07.705	75	751	34	352	13
5/2/2013	11:53:07.764	76	751	34	355	13
AVERAGE		76	751	34	357	13


Run 3
(10:50am-11:20am; 11:24am-11:54am)
Cupola Melt Data

Date	Time	Total Metal Charged (lb)
5/2/2013	10:52:53	7051
5/2/2013	10:56:31	7071
5/2/2013	11:01:11	6980
5/2/2013	11:06:57	7135
5/2/2013	11:09:34	7119
5/2/2013	11:12:21	7212
5/2/2013	11:14:56	6988
5/2/2013	11:17:34	6968
5/2/2013	11:25:33	7065
5/2/2013	11:28:10	7071
5/2/2013	11:30:47	7034
5/2/2013	11:33:24	7131
5/2/2013	11:35:59	7195
5/2/2013	11:38:37	7138
5/2/2013	11:41:14	7129
5/2/2013	11:43:51	6984
5/2/2013	11:46:27	7268
5/2/2013	11:49:08	7156
5/2/2013	11:51:46	7296
TOTAL		134,991
TOTAL		67 ton/hr

FUGITIVE OR SMOKE EMISSION INSPECTION OUTDOOR LOCATION

Company <u>Clow Water</u>	Observer <u>Eric Sguire</u>
Location _____	Affiliation <u>Env. Manager</u>
Company Rep. <u>Eric Sguire</u>	Date <u>5-2-13</u>
Sky Conditions <u>Clear</u>	Wind Direction <u>5 MPH</u>
Precipitation <u>NONE</u>	Wind Speed <u>South</u>
Industry <u>Ductile Iron Foundry</u>	Process Unit <u>Machining & Fabrication</u>


Sketch process unit: indicate observer position relative to source and sun, indicate potential emission points and/or actual emission points.



FLUENT OR SMOKE EMISSION INSPECTION OUTDOOR LOCATION

Company <u>Crown Water</u>	Observer <u>Eric Squire</u>
Location	Affiliation <u>ENR Manager</u>
Company Rep. <u>Eric Squire</u>	Date <u>5-2-13</u>
Sky Conditions <u>Clear</u>	Wind Direction <u>South</u>
Precipitation <u>NONE</u>	Wind Speed <u>5-10 mph</u>
Industry <u>Castile Iron Foundry</u>	Process Unit <u>Machining & Fabrication</u>

Sketch process unit; indicate observer position relative to source and sun, indicate potential emission points and/or actual emission points.




Observations	Start Observation Clock Time	Observation Period Duration, min:sec	Accumulated Emission Time, min:sec
Begin Observation	<u>9:15am</u>	<u>20 min</u>	<u>0</u>
	<i>End 9:35am</i>		
	<u>9:44am</u>	<u>20 min</u>	<u>0</u>
	<u>10:05am</u>		
End Observation			

FUGITIVE OR SMOKE EMISSION INSPECTION OUTDOOR LOCATION

Company <u>Clow Water</u>	Observer <u>Eric Squire</u>
Location _____	Affiliation <u>END. Manager</u>
Company Rep. <u>Eric Squire</u>	Date <u>5-8-13</u>
Sky Conditions <u>clear</u>	Wind Direction <u>South</u>
Precipitation <u>none found</u>	Wind Speed <u>10-15 mph</u>
Industry <u>Ductile Iron Foundry</u>	Process Unit <u>Machining & Fabrication</u>

Sketch process unit; indicate observer position relative to source and sun, indicate potential emission points and/or actual emission points.



OBSERVATIONS	Observation Period	Accumulated Emission
	Duration, min:sec	Time, min:sec
Begin Observation	<u>10:52 am</u>	<u>0</u>
	<u>11:12 am</u>	<u>0</u>
	<u>11:22 am</u>	<u>0</u>
	<u>11:42 am</u>	<u>0</u>
	_____	_____
	_____	_____
	_____	_____
	_____	_____
	_____	_____
End Observation	_____	_____

Method 5 Filter Gravimetric

Plant Name: Clow Water Systems Location: Cupola Emission System (P901) Exhaust Stack

Run Number	<u>1</u> <th>Run Number</th> <td><u>2</u><th>Run Date</th><td><u>5-2-13</u><th>Run Date</th><td><u>5-2-13</u></td></td></td>	Run Number	<u>2</u> <th>Run Date</th> <td><u>5-2-13</u><th>Run Date</th><td><u>5-2-13</u></td></td>	Run Date	<u>5-2-13</u> <th>Run Date</th> <td><u>5-2-13</u></td>	Run Date	<u>5-2-13</u>
Filter Recovered By	<u>AC</u> <th>Filter Recovered By</th> <td><u>AC</u><th>Filter Loading - It / med / heavy</th><td><u>Heavy</u><th>Filter Loading - It / med / heavy</th><td><u>Heavy</u></td></td></td>	Filter Recovered By	<u>AC</u> <th>Filter Loading - It / med / heavy</th> <td><u>Heavy</u><th>Filter Loading - It / med / heavy</th><td><u>Heavy</u></td></td>	Filter Loading - It / med / heavy	<u>Heavy</u> <th>Filter Loading - It / med / heavy</th> <td><u>Heavy</u></td>	Filter Loading - It / med / heavy	<u>Heavy</u>
Were filters intact upon opening filter assembly?	<u>Yes</u>	Were filters intact upon opening filter assembly?	<u>Yes</u>	Were there any visible filter fragments remaining on the filter after initial filter removal?**	<u>No</u>	Were there any visible filter fragments remaining on the filter after initial filter removal?**	<u>No</u>
Were there any visible filter fragments rinsed into acetone rinse container?**	<u>No</u>	Were there any visible filter fragments rinsed into acetone rinse container?**	<u>No</u>	Were filter fragments rinsed into acetone rinse container?	<u>No</u>	Were filter fragments rinsed into acetone rinse container?	<u>No</u>
Date/Time Sample Placed in Dessicator	<u>5-2-13, 16:52</u>	Date/Time Sample Placed in Dessicator	<u>5-2-13, 17:00</u>	Sample Color	<u>59165</u>	Sample Color	<u>58222</u>
Weight Number	Total Weight (g) (Includes Vessel)*	Done By	Lab Temp/RH (°F)(%)	Weight Number	Total Weight (g) (Includes Vessel)*	Done By	Lab Temp/RH (°F)(%)
1	<u>6.5791</u>	<u>AC</u>	<u>81.9</u>	<u>1</u>	<u>6.5795</u>	<u>AC</u>	<u>70.33</u>
2	<u>6.5792</u>	<u>AC</u>	<u>184.1</u>	<u>2</u>	<u>6.5795</u>	<u>AC</u>	<u>28.73</u>
3				<u>3</u>			<u>70.13</u>
4				<u>4</u>			<u>70.13</u>
5				<u>5</u>			<u>70.13</u>
6				<u>6</u>			<u>70.13</u>
7				<u>7</u>			<u>70.13</u>
8				<u>8</u>			<u>70.13</u>
9				<u>9</u>			<u>70.13</u>
10				<u>10</u>			<u>70.13</u>
Final	<u>6.5792</u>				<u>6.5795</u>		
	<u>0.3511</u>	Filter Tare Weight (g)	<u>0.3513</u>	Filter Catch Weight (mg)	<u>0.2147</u>	Vessel Tare Weight (g)	<u>0.2147</u>
	<u>6.2160</u>			<u>13.5</u>	Filter Catch Weight (mg)		
Describe Sample:	<u>Santorini 3004026</u>						
Circle Analytical Balance I.D. used:	<u>GR-202 14202198</u>						
Balance Located in Stable, Draft-Free Area?	<u>Yes</u>						

* Consecutive weighings must not differ by more than 0.5mg or 1% of the total catch weight, whichever is greater.
** If visible filter fragments were removed from filter, then negative filter weight values may be possible.

Method 5 Filter Gravimetric

Plant Name	Clow Water Systems	Location	Cupola Emission System (P901) Exhaust Stack	Run Number	Run Date	Filter Recovered By
				<u>3</u>	<u>5-2-13</u>	<u>AC</u>
<u>Were filters intact upon opening filter assembly?</u>						
<u>Yes</u>						
<u>Were there any visible filter fragments remaining on the frit after initial filter removal?**</u>						
<u>No</u>						
<u>Were filter fragments rinsed into acetone rinse container?</u>						
<u>Yes</u>						
Date/Time Sample Placed in Desiccator	Sample Loading - It / med / heavy	Sample Color	Filter Number	Weight Number	Total Weight (g) (Includes Vessel)*	Done By
<u>5-3-13, 9:57</u>	<u>It</u>	<u>SSS</u>	<u>454</u>	<u>1</u>	<u>28.73</u>	<u>AC</u>
Weight Number	Total Weight (g) (Includes Vessel)*	Done By	Date/Time	Lab Temp/RH (°F)(%)	PBar (Hg)	Date/Time
1	<u>6.6380</u>	<u>AC</u>	<u>5-6-13 820</u>	<u>70.133</u>	<u>28.75</u>	<u>1</u>
2	<u>6.6381</u>	<u>AC</u>	<u>5-6-13 1544</u>	<u>72.135</u>	<u>28.73</u>	<u>1</u>
3				<u>1</u>	<u>1</u>	<u>1</u>
4				<u>1</u>	<u>1</u>	<u>1</u>
5				<u>1</u>	<u>1</u>	<u>1</u>
6				<u>1</u>	<u>1</u>	<u>1</u>
7				<u>1</u>	<u>1</u>	<u>1</u>
8				<u>1</u>	<u>1</u>	<u>1</u>
9				<u>1</u>	<u>1</u>	<u>1</u>
10				<u>1</u>	<u>1</u>	<u>1</u>
Final	<u>10.6381</u>			<u>1</u>	<u>1</u>	<u>1</u>
	<u>0.3617</u>				<u>Filter Tare Weight (g)</u>	<u>GR-202 14202198</u>
	<u>10.2629</u>				<u>Vessel Tare Weight (g)</u>	
	<u>13.5</u>				<u>Filter Catch Weight (mg)</u>	
Describe Sample:						
Sample: <u>Sartorius 3004028</u>						
Circle Analytical Balance I.D. used:						
Balance Located in Stable, Draft-Free Area?						
<u>Yes</u> <u>No</u>						
* Consecutive weighings must not differ by more than 0.5mg or 1% of the total catch weight, whichever is greater.						
** If visible filter fragments were removed from frit, then negative filter weight values may be possible.						

APPENDIX - Lab Data - Page 2 of 7

Method 5 Rinse Gravimetric

Plant Name Clow Water Systems Location Cupola Emission System (P901) Exhaust Stack

		Run Number	Run Number	Run Date	Rinse Recovered By	Date/Time Sample Placed in Desiccator	Sample Loading - It / med / heavy	Sample Loading - It / med / heavy	Sample Color	Vessel ID
Date/Time Sample Placed in Desiccator	5-3-13 , 9:51	Run Date	5-2-13	Run Date	5-2-13	Sample Placed in Desiccator	5-3-13 , 9:51	Sample Placed in Desiccator	Airy	1694
		Rinse Recovered By	AC		AC					
		Sample Loading - It / med / heavy	It							
		Sample Color	Airy							
Weight Number	Total Weight (g) (Includes Vessel)*	Done By	Date/Time	Temp/RH (°F)(%)	PBar (hg)		Weight Number	Total Weight (g) (Includes Vessel)*	Done By	Date/Time
1	2.5544	AC	5-6-13 82L	70.33	28.75		1	2.5401	AC	5-6-13 8222
2	2.5545	AC	5-6-13 1545	72.35	28.73		2	2.5401	AC	5-6-13 1546
3							3			70.33
4							4			72.35
5							5			
6							6			
7							7			
8							8			
9							9			
10							10			
Final	2.5545	Vessel Tare Weight (g)						Final	2.5401	
	2.5454	Rinse Volume (ml)							2.5333	Vessel Tare Weight (g)
	12.5	Residue Weight (g)							12.5	Rinse Volume (ml)
	0.0010	Rinse Catch Weight (mg)							0.0010	Residue Weight (g)
	8.1								5.8	Rinse Catch Weight (mg)
Describe Sample:								Describe Sample:		
Circle Analytical Balance I.D. used:	Sartorius 3004026	/	GR-202 14202168							

Balance Located in Stable, Draft-Free Area? Yes/No

* Consecutive weighings must not differ by more than 0.5mg or 1% of the total catch weight, whichever is greater.

** If no visible fragments remain on filter, then negative filter weight values may be deemed a zero value.

Method 5 Rinse Gravimetric

Effective Date: 7/16/12
Rev. No. 0
Issued by Quality Manager

Plant Name	Cowl Water Systems	Location	Cupola Emission System (P901) Exhaust Stack	Run Number	3	Run Number	132
Date/Time Sample Placed in Desiccator	Sample Loading - It / med / heavy	Rinse Recovered By	AC	Run Date	5-2-13	Run Date	5-2-13
Vessel ID	Total Weight (g) (Includes Vessel)*	Done By	Date/Time	Temp/RH (°F)/(%)	PBar ("Hg)	Date/Time	Temp/RH (°F)(%)
1 2.5438	2.5438	AC	5-6-13 1541	822	70.13	28.75	70.13
2		AC	5-6-13 1541	7235	72.73		
3				1			
4				1			
5				1			
6				1			
7				1			
8				1			
9				1			
10				1			
Final	2.5438			1			
	2.5374	Vessel Tare Weight (g)					
	125	Rinse Volume (ml)					
	0.0010	Residue Weight (g)					
	5.4	Rinse Catch Weight (mg)					
Describe Sample:							
Describe Sample:							
Cowl Analytical Balance I.D. used:	Sartorius 3004026	/	GR-202 14202198				
Balance Located in Stable, Draft-Free Area?	Yes	No					

Balance Located in Stable, Draft-Free Area? Yes/No
 *Consecutive weighings must not differ by more than 0.5mg or 1% of the total catch weight, whichever is greater.
 ** If no visible fragments remain on filter, then negative filter weight values may be deemed a zero value.

Air Compliance Testing Inc.
Drilling/CCT Test Methods/Method 5
(Rinse & Rinse Gravimetric) 5/22/2013
1 of 1

Job Number: 136502 A
Done By / Date: AC / 5-2-13
Final Check By / Date: SC / 5-22-13

Method 5 Acetone Residual Data

Effective Date: 7/19/11.
Rev No. 0
Issued by: Quality Manager

Determine weight of acetone residuals (g) 0.0024
Divide by the volume of the acetone blank (ml) 2.50
Acetone residuals measured (g/ml) 0.000096 (should be less than 0.000079g/ml)
Acetone residuals used (g/ml) 0.000079

	Run 1	Run 2	Run 3	Run 4
Determine volume of front half rinse (ml)	<u>1.25</u>	<u>1.25</u>	<u>1.25</u>	<u>1.25</u>
Acetone residuals in sample (g)	<u>0.0010</u>	<u>0.0010</u>	<u>0.0010</u>	<u>0.0010</u>

*Subtract sample residuals from sample catch weight (g)

Method 5 Record of Custody Sheet Filter

Effective Date: 7/18/12
Rev No. 0
Issued by: Quality Manager

Shipping/Transportation Container Number: _____

Sample ID		Full Signature	Date	Time	Notes	Filter Number	Vessel ID
130502 A - 1 - M5/F	S	Amber (SG)	4.19.13	1521		5965	452
	B	Amber	5.2.13	1653			
130502 A - 2 - M5/F	S					5822	453
	B						
130502 A - 3 - M5/F	S	Amber (SG)	4.18.13	1548		5818	454
	B	Amber	5.3.13	0510			
130502 A - 4 - M5/F	S	Amber	4.30.13	110:18		5986	
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						
	S						
	B						

Were all seals intact? Yes No (Describe seal and reasoning in the "Remarks")

Received By Sample Custodian _____

(Full Signature)

(Date)

(Time)

Remarks: _____

Method 5 Record of Custody Sheet AR

Effective Date: 7/16/12
 Rev No. 0
 Issued by: Quality Manager

Shipping/Transportation Container Number: 5

Sample ID	Full Signature	Date	Time	Notes	Final Vol. ml	Vessel ID
130502 A - 1 - M5/AR	S <u>Dale H.</u>	5/2/13	12:11		125	1693
	B <u>Anne E.</u>	5.2.13	16:53			
130502 A - 2 - M5/AR	S <u>Dale H.</u>	5/2/13	12:11		125	1694
	B <u>Anne E.</u>	5.2.13	16:59			
130502 A - 3 - M5/AR	S <u>Dale H.</u>	5/2/13	12:26		125	1695
	B <u>Anne E.</u>	5.2.13	9:56			
130502 A - 4 - M5/AR	S					
	B					
	S					
	B					
	S					
	B					
	S					
	B					
	S					
	B					
	S					
	B					
130502 A - BL - M5/AR	S <u>Dale H.</u>	5/2/13	12:26:54		250	1696
	B <u>Anne E.</u>	5.2.13	10:00			

Were all seals intact? Yes Yes No (Describe seal and reasoning in the "Remarks")Were all liquid levels at marked levels? Yes Yes No (Estimate loss in the "Remarks")

Received By Sample Custodian _____

(Full Signature)

(Date)

(Time)

Remarks: _____

TEST DATA

Number of Test Runs	3				
Traverse Points	24	Run 1	Run 2	Run 3	Average
Stack Cross-Sectional Diameter 1 (circular) (in)	63.30	63.30	63.30	63.30	63.30
Stack Cross-Sectional Diameter 2 (circular) (in)	63.30	63.30	63.30	63.30	63.30
Pitot Tube Coefficient (Cp)	0.84	0.84	0.84	0.84	0.84
Barometric Pressure at Ground Level (Pbar) (in Hg)	29.31	29.29	29.30	29.30	29.30
Elevation Difference Between Ground Level and Meter Box Locations (ft)	5.00	5.00	5.00	5.00	5.00
Elevation Difference Between Ground Level and Sampling Locations (ft)	35.00	35.00	35.00	35.00	35.00
initial Dry Gas Meter Reading (ft3)	955.170	997.325	41.028		
Final Dry Gas Meter Reading (ft3)	997.100	1040.712	83.587		
Dry Gas Meter Calibration Factor (Gamma)	1.0008	1.0008	1.0008	1.0008	1.0008
Dry Gas Meter Calibration Coefficient (Delta H@)	2.187	2.187	2.187	2.187	2.187
Total Sampling Run Time (Ttheta) (min)	60	60	60	60	60
Volume of Water Vapor Condensed in the Impingers (g)	39.8	44.2	51.1	45.0	45.0
Weight of Water Vapor Collected in Silica Gel (g)	9.8	12.3	8.7	10.3	10.3
Air Percent by Volume Carbon Dioxide in Stack Gas (%-dry)	11.0	12.5	11.0	11.5	11.5
Air Percent by Volume Oxygen in Stack Gas (%-dry)	12.0	12.4	11.5	12.0	12.0
Air Percent by Volume Nitrogen in Stack Gas (%-dry)	77.0	75.2	77.5	76.6	76.6
Average Pitot Rotation Angle	Port Number 1 9.0	Port Number 2 5.6			
Test Run Start Time (hr:min)	5/2/2013 7:43	5/2/2013 9:17	5/2/2013 10:50		
Test Run Stop Time (hr:min)	5/2/2013 8:51	5/2/2013 10:24	5/2/2013 11:54		

DETAILED RESULTS

Stack Gas Conditions	Run 1	Run 2	Run 3	Average
Stack Cross-Sectional Area (A) (ft ²)	21.854	21.854	21.854	21.854
Barometric Pressure at Sampling Location (in Hg)	29.28	29.26	29.27	29.27
Dry Molecular Weight of Stack Gas (Md) (lb/lb-mole)	30.24	30.49	30.22	30.32
Wet Molecular Weight of Stack Gas (Ms) (lb/lb-mole)	29.58	29.74	29.43	29.58
Average Absolute Stack Gas Pressure (Ps) (in Hg)	29.21	29.23	29.22	29.22
Average Stack Gas Static Pressure (ps) (in H ₂ O)	-0.83	-0.40	-0.63	-0.62
Average Stack Gas Temperature (Ts) (°F)	140.4	144.3	143.8	142.8
Average Stack Gas Temperature (Ts) (°R)	600.4	604.3	603.8	602.8
Average Stack Gas Velocity (Vs) (ft/sec)	51.24	52.14	51.35	51.58
Average Stack Gas Velocity (Vs) (ft/min)	3,074	3,128	3,081	3,095
Wet Volumetric Stack Gas Flow at Actual Conditions (Qaw) (acfm)	67,184	68,364	67,338	67,629
Wet Volumetric Stack Gas Flow at Standard Conditions (scfm)	57,687	58,347	57,509	57,848
Dry Volumetric Stack Gas Flow at Standard Conditions (Qstd) (dscfm)	54,554	54,843	53,771	54,389
Percent by Volume Moisture as measured in Stack Gas (%H ₂ O)	5.43	6.01	6.50	5.98

Test Results

Volume of Dry Gas Sampled at Standard Conditions (Vmstd) (dscf)	40.723	41.694	40.551	40.989
Rate of Dry Gas Sampled at Standard Conditions (dscfm)	0.679	0.695	0.676	0.683
<u>Predicted</u> 1-Hour Sample Volume Based on Current Sampling Rate (dscf)	40.723	41.694	40.551	40.989
Dry Mole Fraction of Flue Gas (Mfd) (1-bw/100)	0.946	0.940	0.935	0.940
Average Velocity Pressure (Delta P) (in H ₂ O)	0.7354	0.7608	0.7308	0.7424
Average Square Root of Delta P	0.8659	0.8707	0.8534	0.8600
Average Pressure Differential of Orifice Meter (Delta H) (in H ₂ O)	2.0375	2.1313	2.0458	2.0715
Average DGM Temperature (tm) (°F)	75.625	81.083	85.792	80.833
Average Dry Gas Meter Temperature (Tm) (°R)	535.625	541.083	545.792	540.833
Volume of Metered Gas Sample (Vm) (dry) (acf)	41.930	43.387	42.559	42.625
Post-Test Calibration (Yqa)	1.0301	1.0193	1.0270	1.0255
Post-Test/Pre-Test Calibration Factor Difference (%)	-2.93	-1.85	-2.62	-2.47

SAMPLING QA

Current Predicted Allowable Post-Test Leak Rate (dscfm)	0.020	0.020	0.020
Current Sampling Rate Status	OK	OK	OK
Probe Nozzle Diameter (in)	0.225	0.225	0.225
Percent Isokinetic of Sampling Rate (% I)	98.5	100.3	99.5
In Field Isokinetic QA	GOOD	GOOD	GOOD
Count of Velocity Pressure Readings Below 0.05 in H ₂ O	0	0	0
Sensitivity Factor for Differential Pressure Gauge (T)	1.003	1.003	1.003
Is Meter Box Manometer Adequate (Yes / No) ?	YES	YES	YES

Compliance Stack Emission Test Report

Clow Water Systems Co.
Cupola Emission System (P901)
Scrubber
Exhaust Stack

MEASURED DATA FROM TEST RUNS

Point Count	Run #	Run Pitot Delta Time (min)	P (in H2O)	Square Root of Delta P	Orifice Delta H (in H2O)	DGM Temp OUT (°F)	Average DGM Temp (°F)	Stack Pressure (in H2O)	Stack Temp (°F)
1	1	0	0.55	0.742	1.55	70	70.00	-0.83	137
2	1	2.5	0.60	0.775	1.70	70	70.00		139
3	1	5	0.64	0.800	1.80	71	71.00		140
4	1	7.5	0.71	0.843	2.00	72	72.00		140
5	1	10	0.74	0.860	2.05	73	73.00		141
6	1	12.5	0.82	0.906	2.20	73	73.00		140
7	1	15	0.73	0.854	2.00	74	74.00		141
8	1	17.5	0.73	0.854	2.00	75	75.00		140
9	1	20	0.82	0.906	2.20	75	75.00		141
10	1	22.5	0.90	0.949	2.45	76	76.00		140
11	1	25	0.84	0.917	2.25	77	77.00		139
12	1	27.5	0.75	0.866	2.05	77	77.00		139
13	1	30	0.65	0.806	1.80	76	76.00		138
14	1	32.5	0.64	0.800	1.80	76	76.00		140
15	1	35	0.65	0.806	1.80	77	77.00		141
16	1	37.5	0.63	0.794	1.75	77	77.00		141
17	1	40	0.65	0.806	1.85	77	77.00		141
18	1	42.5	0.74	0.860	2.05	78	78.00		142
19	1	45	0.84	0.917	2.35	78	78.00		142
20	1	47.5	0.83	0.911	2.30	78	78.00		142
21	1	50	0.82	0.906	2.30	78	78.00		142
22	1	52.5	0.82	0.906	2.30	79	79.00		142
23	1	55	0.82	0.906	2.30	79	79.00		142
24	1	57.5	0.73	0.854	2.05	79	79.00		140
25	2	0	0.58	0.762	1.60	77	77.00	-0.4	141
26	2	2.5	0.62	0.787	1.75	78	78.00		143
27	2	5	0.67	0.819	1.90	78	78.00		143
28	2	7.5	0.72	0.849	2.00	79	79.00		143
29	2	10	0.80	0.894	2.25	79	79.00		143
30	2	12.5	0.86	0.927	2.40	80	80.00		144
31	2	15	0.78	0.883	2.20	80	80.00		144
32	2	17.5	0.81	0.900	2.25	80	80.00		144
33	2	20	0.90	0.949	2.50	81	81.00		144
34	2	22.5	0.92	0.959	2.60	81	81.00		144
35	2	25	0.82	0.906	2.30	81	81.00		143
36	2	27.5	0.62	0.787	1.75	81	81.00		142
37	2	30	0.65	0.806	1.80	80	80.00		144
38	2	32.5	0.70	0.837	1.95	81	81.00		144
39	2	35	0.72	0.849	2.00	81	81.00		145
40	2	37.5	0.71	0.843	2.00	82	82.00		145
41	2	40	0.74	0.860	2.10	82	82.00		146
42	2	42.5	0.75	0.866	2.10	83	83.00		146
43	2	45	0.86	0.927	2.40	83	83.00		146
44	2	47.5	0.83	0.911	2.30	83	83.00		146
45	2	50	0.85	0.922	2.40	84	84.00		146
46	2	52.5	0.79	0.889	2.20	84	84.00		146
47	2	55	0.82	0.906	2.30	84	84.00		146
48	2	57.5	0.74	0.860	2.10	84	84.00		145

MEASURED DATA FROM TEST RUNS

Point Count	Run #	Run Time (min)	Pitot Delta P (in H2O)	Square Root of Delta P (in H2O)	Orifice Delta H (in H2O)	DGM Temp OUT (°F)	Average DGM Temp (°F)	Stack Pressure (in H2O)	Stack Temp (°F)
49	3	0	0.52	0.721	1.50	83	83.00	-0.63	139
50	3	2.5	0.59	0.768	1.65	83	83.00		141
51	3	5	0.64	0.800	1.80	83	83.00		142
52	3	7.5	0.70	0.837	1.95	84	84.00		143
53	3	10	0.75	0.866	2.10	84	84.00		143
54	3	12.5	0.80	0.894	2.25	84	84.00		143
55	3	15	0.72	0.849	2.00	85	85.00		144
56	3	17.5	0.78	0.883	2.20	85	85.00		144
57	3	20	0.82	0.906	2.30	85	85.00		144
58	3	22.5	0.86	0.927	2.40	86	86.00		143
59	3	25	0.83	0.911	2.30	86	86.00		143
60	3	27.5	0.73	0.854	2.05	86	86.00		142
61	3	30	0.63	0.794	1.75	86	86.00		144
62	3	32.5	0.67	0.819	1.90	86	86.00		144
63	3	35	0.66	0.812	1.85	86	86.00		145
64	3	37.5	0.69	0.831	1.95	86	86.00		145
65	3	40	0.68	0.825	1.90	87	87.00		145
66	3	42.5	0.72	0.849	2.00	87	87.00		145
67	3	45	0.83	0.911	2.30	87	87.00		145
68	3	47.5	0.82	0.906	2.30	88	88.00		146
69	3	50	0.82	0.906	2.30	88	88.00		145
70	3	52.5	0.79	0.889	2.20	88	88.00		146
71	3	55	0.79	0.889	2.20	88	88.00		145
72	3	57.5	0.70	0.837	1.95	88	88.00		144

TEST DATA

	<u>Run 1</u>	<u>Run 2</u>	<u>Run 3</u>	<u>Average</u>
Particulate Weight in Probe Rinse (mg)	8.10	5.80	5.40	6.43
Particulate Weight in Filter Catch (mg)	12.10	13.50	13.50	13.03

DETAILED RESULTS**Emission Results**

Filterable Particulate Matter Emission Rate (lb/ton)	0.044	0.043	0.049	0.046
Filterable Particulate Matter Emission Rate (lb/hr)	3.579	3.358	3.315	3.417
Filterable Particulate Matter Concentration (grains/dscf)	0.0077	0.0071	0.0072	0.0073

**EPA Methods 1, 2, 3, 4, and 5 Nomenclature and
Sample Calculations**
Run No. - 1

Constants

$\text{CO}_2 F_{\text{wt}} = 44.0$	$\text{in wg} = 0.073529$	$\text{NO}_2 F_{\text{wt}} = 46.01$	$\text{HCIF}_{\text{wt}} = 36.46$
$\text{O}_2 F_{\text{wt}} = 32.0$	$\text{gr} = 0.000142857$	$\text{COF}_{\text{wt}} = 28.01$	$\text{SO}_2 F_{\text{wt}} = 64.06$
$\text{CON}_2 F_{\text{wt}} = 28.0$	$\text{mmBtu} = 1000000 \text{ Btu}$	$\text{H}_2\text{SO}_4 F_{\text{wt}} = 98.08$	$\text{Cl}_2 F_{\text{wt}} = 70.91$
$\text{H}_2\text{OF}_{\text{wt}} = 18.0$	$\text{CF}_{\text{wt}} = 12.011$	$T_{\text{std}} = 528$	$P_{\text{std}} = 29.92$
			$P_{\text{wt}} = 44.0962$

Stack Variables

$C_p = 0.84$	pitot tube coefficient (dimensionless)
$P_{\text{bar}} = 29.31 \text{ in. Hg}$	barometric pressure
$E_{\text{box}} = 5 \text{ ft}$	elevation difference between ground level and meter box
$E_{\text{sam}} = 35 \text{ ft}$	elevation difference between ground level and sampling ports
$\gamma = 1.0008$	gamma, dry gas meter calibration factor (dimensionless)
$\theta = 60.0 \text{ min}$	net run time (minutes)
$V_{\text{lc}} = 49.6 \text{ g}$	total mass of liquid collected in impingers (g)
$\% \text{CO}_2 = 11.00 \%$	percent CO_2 by volume (dry basis) (dimensionless)
$\% \text{O}_2 = 12.00 \%$	percent O_2 by volume (dry basis) (dimensionless)
$\% \text{CO} = 0.00 \%$	percent CO by volume (dry basis) (dimensionless)
$\% \text{N}_2 = 77.00 \%$	percent N_2 by volume (dry basis) (dimensionless)
$A = 21.8542 \text{ ft}^2$	stack cross-sectional area
$P_g = -0.83 \text{ in. H}_2\text{O}$	flue gas static pressure
$T_{\text{avg}} = 600.42 \text{ R}$	average absolute flue gas temperature ($460R + t_{\text{avg}}$ °F)
$\text{SQ}\Delta P_{\text{avg}} = 0.86 \text{ in. wg}$	average square root ΔP
$\Delta H = 2.04 \text{ in. wg}$	average pressure differential of orifice meter
$T_m = 535.63 \text{ R}$	dry gas meter temperature ($460R + t_{\text{avg}}$ °F)
$V_m = 41.93 \text{ ft}^3$	volume of metered gas sample (dry actual cubic feet)
$D_n = 0.225 \text{ in.}$	sampling nozzle diameter

Calculated Stack Variables**Barometric pressure at sampling location**

NOTE: Barometric pressure recorded at ground level

$$P_{\text{sam}} = P_{\text{bar}} - [(E_{\text{sam}} / 100 \text{ ft}) * 0.1 \text{ in. Hg}]$$

$$P_{\text{sam}} = 29.31 - ((35.0 / 100) * 0.1)$$

$$P_{\text{sam}} = 29.28 \text{ in. Hg}$$

Volume of dry gas sampled at standard conditions (dsfcf)

$$V_{\text{mstd}} = \gamma * V_m * [P_{\text{bar}} - [((E_{\text{box}} / 100 \text{ ft}) * 0.1 \text{ in. Hg}) + (\Delta H / 13.6)] / P_{\text{std}}] * (T_{\text{std}} / T_m)$$

$$V_{\text{mstd}} = 1.0008 * 41.930 * ((29.31 - ((5.0 / 100) * 0.1) + (2.0375 / 13.6)) / 29.92) * (528.0 / 535.625)$$

$$V_{\text{mstd}} = 40.723 \text{ ft}^3$$

Volume of water vapor at standard conditions (68 °F, scf)

$$V_{\text{wstd}} = (0.04715 \text{ ft}^3/\text{g}) * V_{\text{lc}}$$

$$V_{\text{wstd}} = (0.04715 * 49.6)$$

$$V_{\text{wstd}} = 2.3 \text{ ft}^3$$

Percent moisture by volume as measured in flue gas

$$\%H_2O \text{ (Measured)} = 100 * [V_{wstd} / (V_{wstd} + V_{mstd})]$$

$$\%H_2O \text{ (Measured)} = 100 * (2.339 / (2.339 + 40.723))$$

$$\%H_2O \text{ (Measured)} = 5.43$$

$$\%H_2O \text{ (Saturated)} = (100 / P_{sat}) * 10^{(6.6911 - (3144 / (T_{avg} + 390.86 - 460)))}$$

$$\%H_2O \text{ (Saturated)} = (100 / 29.213971) * 10^{(6.6911 - (3144 / (600.416667 + 390.86 - 460)))}$$

$$\%H_2O \text{ (Saturated)} = 20.31$$

$$\%H_2O = 5.43$$

Absolute flue gas pressure

$$P_s = P_{sat} + (Pg / 13.6)$$

$$P_s = 29.28 + (-0.83 / 13.6)$$

$$P_s = 29.21 \text{ in. Hg}$$

Dry mole fraction of flue gas (dimensionless)

$$M_{fd} = 1 - (\%H_2O / 100)$$

$$M_{fd} = 1 - (5.43 / 100)$$

$$M_{fd} = 0.946$$

Dry molecular weight of flue gas (lb/lb-mole)

$$M_d = [(\%CO_2 / 100) * 44.0] + [(\%O_2 / 100) * 32.0] + [((100 - \%CO_2 - \%O_2) / 100) * 28.0]$$

$$M_d = ((11.00 / 100) * 44.0) + ((12.00 / 100) * 32.0) + ((100 - 11.00 - 12.00) / 100) * 28.0$$

$$M_d = 30.24 \text{ lb/lb-mole}$$

$$M_d = 30.24$$

Wet molecular weight of flue gas (lb/lb-mole)

$$M_w = M_d * M_{fd} + (H_2O \cdot F_w * (\%H_2O / 100))$$

$$M_w = 30.240 * 0.946 + 18.00 * (5.43 / 100)$$

$$M_w = 29.58 \text{ lb/lb-mole}$$

Average flue gas velocity (ft/sec)

$$v_s = 85.49 * C_p * (SQ\Delta P_{avg}) * (T_{avg} / (P_s * M_w))^{0.5}$$

$$v_s = 85.49 * 0.84 * (0.8559) * (600.42 / (29.214 * 29.575))^{0.5}$$

$$v_s = 51.24 \text{ ft/sec}$$

Wet volumetric flue gas flow rate at actual conditions (acfm)

$$Q_{aw} = v_s * A * 60 \text{ sec/min}$$

$$Q_{aw} = 51.237 * 21.854 * 60$$

$$Q_{aw} = 67,184 \text{ ft}^3/\text{min}$$

Wet volumetric flue gas flow rate at standard conditions (scfm)

$$Q_{sdw} = v_s * A * (T_{std} / T_{avg}) * (P_s / P_{std}) * 60 \text{ sec/min}$$

$$Q_{sdw} = 51.237 * 21.854 * (528.0 / 600.417) * (29.214 / 29.92) * 60$$

$$Q_{sdw} = 57,687 \text{ ft}^3/\text{min}$$

Dry volumetric flue gas flow rate at standard conditions (dscfm)

$$Q_{sd} = M_{fd} * v_s * A * (T_{std} / T_{avg}) * (P_s / P_{std}) * 60 \text{ sec/min}$$

$$Q_{sd} = 0.946 * 51.2365 * 21.8542 * (528.0 / 600.417) * (29.214 / 29.92) * 60$$

$$Q_{sd} = 54,554 \text{ ft}^3/\text{min}$$

Isokinetic Calculations**Percent isokinetic of sampling rate (%)**

$$\%I = (P_{std} / T_{std}) * (T_{avg} / P_s) * [V_{msid} / (v_s * M_{fd} * \theta * \pi * (D_n / 2)^2)]$$

$$\%I = (((29.92 / 528.0) * (600.417 / 29.214)) * (40.723 / (51.2365 * 0.946 * 60.0 * ((3.141593 * (0.225 / 2)^2) / 144))) / 60) * 100$$

$$\%I \approx 98.5 \%$$

Method 5 Calculations**Filterable PM total catch weight (mg)**

$$mg_{quan} = 20.20 \text{ mg}$$

Filterable PM concentration (grains/dscf)

$$C_{grain} = 0.154322 * mg_{quan} / V_{msid}$$

$$C_{grain} = 0.0154322 * 20.20 / 40.723$$

$$C_{grain} = 0.0077 \text{ gr/ft}^3$$

Filterable PM mass emission rate (lb/hr)

$$EMR_{lbhr} = (mg_{quan} / V_{msid}) * Q_{sd} * (60 / 453592)$$

$$EMR_{lbhr} = 20.20 / 40.723 * 54,553.817 * (60 / 453592)$$

$$EMR_{lbhr} = 3.58 \text{ lb/hr}$$

Method 5 Isotactic Field Data

Effective Date: 7/16/12
Rev No: 0
Issued by Manager:

Plant	Clow Water Systems Co.	Meter box no.	T-MTB-015
Run no.	143	Pump no.	T-PPB-015
Test start time	10:13	Probe no.	T-PRB-015
Test stop time	10:15	Filter box no.	T-FLB-015
Pre-test leak rate @ 15 psig Hg	0.01	Impinger box no.	T-IMB-015
Post-test leak rate @ 5 in.Hg G	0.00	Umbilical cord no.	T-UUC-015
Pre-test pilot leak check - total static ✓		Umbilical adapter no.	T-UAM-015
Post-test pilot leak check - total static ✓		Filter Exit Therm. no.	T-FXT-020

Gamma 1.000
K Factor 2.5
Nozzle Size, in. 0.725
Barometric pressure in Hg 29.91
Ambient temperature, °F 70
Filter box temperature setting, °F 244°F
Probe temperature setting, °F 244°F
Orsat flow rate setting, SCFH 0.33
Orsat bag no. 1430502A-1-M31782

POINT	CLOCK	DRY GAS METER CF	PITOT In. H ₂ O	ORIFICE AH In. H ₂ O	PROBE DESIRED	PROBE ACTUAL °F	STACK TEMP °F	DRY GAS TEMP °F	FILTER INLET	FILTER OUTLET °F	IMPINGER TEMP °F	FILTER EXIT TEMP °F	PUMP VACUUM	ORSAT FLOW	STATIC PRESSURE ± in. H ₂ O
1	0	150	170	0.55	1.80	250	37	—	70	229	52	227	1.0	0.3	4.2-4.4
2	2.5	150	720	0.120	1.68	170	34	—	70	218	49	228	1.0	0.3	1-0.23
3	5	150	10	0.645	1.70	180	40	—	71	219	48	229	1.0	0.3	—
4	7.5	150	86	0.74	1.99	265	40	—	72	217	47	229	1.0	0.3	—
5	10	150	1.57	0.71	2.07	265	41	—	73	214	48	234	1.0	0.3	—
6	12.5	150	92	0.52	2.21	266	40	—	73	214	49	234	1.0	0.3	—
7	15	150	115	0.73	1.97	266	40	—	73	212	47	229	1.0	0.2	—
8	17.5	150	1.73	0.73	1.9	266	40	—	74	211	51	211	1.0	0.2	—
9	20	150	1.2	0.62	2.21	267	41	—	75	205	53	205	1.0	0.2	—
10	22.5	150	43	0.40	2.43	268	40	—	76	204	54	213	1.0	0.2	—
11	25	150	90	0.77	2.25	268	40	—	76	205	55	215	1.0	0.2	—
12	27.5	150	34	0.73	2.43	268	41	—	77	206	57	215	1.0	0.2	—
13	30	150	67	0.45	2.03	269	41	—	77	206	59	215	1.0	0.2	—
14	32.5	150	64	0.75	1.80	269	41	—	77	206	57	215	1.0	0.2	—
15	35	150	64	0.64	1.78	269	40	—	77	206	57	215	1.0	0.2	—
16	37.5	150	126	0.125	1.75	269	40	—	77	206	57	215	1.0	0.2	—
17	40	150	87	0.63	1.75	267	41	—	77	205	57	215	1.0	0.2	—
18	42.5	150	43	0.63	1.83	265	41	—	77	206	54	211	1.0	0.3	—
19	45	150	85	0.74	2.06	265	41	—	78	206	54	210	1.0	0.3	—
20	47.5	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
21	50	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
22	52.5	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
23	55	150	126	0.125	1.80	265	40	—	77	205	57	215	1.0	0.3	—
24	57.5	150	87	0.63	1.75	267	41	—	77	205	57	215	1.0	0.3	—
25	60	150	43	0.63	1.83	265	41	—	77	206	54	211	1.0	0.3	—
26	62.5	150	85	0.74	2.06	265	41	—	78	206	54	210	1.0	0.3	—
27	65	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
28	67.5	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
29	70	150	85	0.81	2.06	265	41	—	78	206	54	210	1.0	0.3	—
30	72.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
31	75	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
32	77.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
33	80	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
34	82.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
35	85	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
36	87.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
37	90	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
38	92.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
39	95	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
40	97.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
41	100	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
42	102.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
43	105	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
44	107.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
45	110	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
46	112.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
47	115	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
48	117.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
49	120	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
50	122.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
51	125	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
52	127.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
53	130	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
54	132.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
55	135	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
56	137.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
57	140	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
58	142.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
59	145	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
60	147.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
61	150	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
62	152.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
63	155	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
64	157.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
65	160	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
66	162.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
67	165	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
68	167.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
69	170	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
70	172.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
71	175	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
72	177.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
73	180	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
74	182.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
75	185	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
76	187.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
77	190	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
78	192.5	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
79	195	150	85	0.81	2.06	265	41	—	79	206	54	210	1.0	0.3	—
80</td															

Method 5 Isothermal Field Data

Executive Unit, Rev No 0
by Manager

Plant	Clow Water Systems Co.	Meter box no.	T-MTB-015	Gamma = 0.005									
Location	PB01 Exhaust Stack (A)	Pump no.	T-PMP-015	K Factor	2.4	1	1	1	1	1	1		
Run no.	2117	Probe no.	T-PRB-015										
Test start time	10:31:41	Filter box no.	T-FIB-015										
Test stop time	10:32:41	Impinger box no.	T-IMB-015										
Pre-test leak rate @ 15in Hg	0.0053	Umbilical cord no.	T-UMB-CORD										
Post-test leak rate @ 15in Hg	0.005	Umbilical adapter pt.	T-UML-015										
Pre-test pilot leak check - static	✓	Filter/Exit Therm. no.	T-FXT-015										
Post-test pilot leak check - total	✓	Orsat flow rate setting, SCFH	0.1										
		Orsat bag no.	130362-B-2-NIT-B										
POINT	CLOCK	DRY GAS METER CF	PITOT In. H ₂ O ΔP	ORIFICE AH DESIRED ACTUAL	PROBE TEMP °F	STACK TEMP °F	DRY GAS TEMP °F	FILTER TEMP °F	IMPINGER TEMP °F	FILTER EXIT TEMP °F	PUMP VACUUM inHg	ORSAT FLOW SCFH	STATIC PRESSURE ± in.H ₂ O
POINT	TIME min			In. H ₂ O ΔP			INLET OUTLET						
1	0	10:31:41	0.58	1.67	1.60	16.9	17.1	16.8	17.1	17.1	1.0	0.1	-0.40
2	7.6	10:31:41	0.52	1.74	1.75	16.1	16.3	16.3	16.3	16.3	1.0	0.2	-0.40
3	9.0	10:31:41	0.57	1.83	1.90	16.9	17.3	17.3	17.3	17.3	1.0	0.3	-
4	10.6	10:31:41	0.52	1.62	2.0	16.9	16.3	16.3	16.3	16.3	1.0	0.3	-
5	11.0	10:31:41	0.52	1.80	2.24	16.5	16.3	16.3	16.3	16.3	1.0	0.3	-
6	12.5	10:31:41	0.51	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
7	13.9	10:31:41	0.51	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
8	15.3	10:31:41	0.51	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
9	16.7	10:31:41	0.51	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
10	21.8	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
11	26.5	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
12	27.9	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
13	30.4	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
14	32.8	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
15	35.3	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
16	36.7	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
17	40.8	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
18	45.9	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
19	49.3	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
20	52.5	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
21	55.9	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-
22	57.3	10:31:41	0.52	1.86	2.40	16.5	16.5	16.5	16.5	16.5	1.0	0.3	-

Final Non-graph Calibration Variables

Comments:

Leak Checks

Int. DGM Reading

Final DGM Reading

AH@ 2.181 cp 0.34 TS ✓

Time / Pm ✓

Bns ✓

K Factor

Nozzle Size, in.

Barometric pressure, in.Hg

Ambient temperature, °F

Filter box temperature setting, °F

Probe temperature setting, °F

Orsat flow rate setting, SCFH

Orsat bag no.

Job Number: 130502-A

Date: 15/2/13

Final Check By / Date: 38/3/2013

Method 5 Isokinetic Field Data

Effective Date 7/16/12
Rev. No. 0
Issued by Manager

Plant	Clean Water Systems Co.	Meter box no.	T-MTB-015
Location	P901 Exhaust Stack (A)	Pump no.	T-PMP-015
Run no.	3	Probe no.	T-PRB-015
Test start time	10:45:00	Filter box no.	T-FB-015
Test stop time	10:55:00	Hosing box no.	T-HB-015
Pre-test leak rate @ 12 in.Hg	18.4 ft³/min	Umbilical cord no.	T-UML-015
Post-test leak rate @ 12 in.Hg	0.00 ft³/min	Umbilical adapter no.	T-UMA-015
Pre-test pilot leak check - static	✓	Filter Exit Therm. no.	T-FXT-015
Post-test pilot leak check - total	✓ static ✓	Orsat flow rate setting, SCFH	0.2 MCFH

POINT	CLOCK TIME	DRY GAS METER CF	PIROT In. H ₂ O ΔP	ORIFICE AH In. H ₂ O	PROBE TEMP DESIRED ACTUAL °F	STACK TEMP °F	PROBE TEMP °F	DRY GAS INLET °F	DRY GAS OUTLET °F	FILTER TEMP °F	IMPINGER TEMP °F	FILTER EXIT TEMP °F	PUMP VACUUM in.Hg	ORSAT FLOW SCFH	STATIC PRESSURE ± in.H ₂ O
1	0	41.828	0.72	1.110	1.830	155	155	163	163	167	167	170	-0.3	0.3	-0.3
2	10:45:00	42.820	0.79	1.105	1.835	151	151	153	153	167	167	170	-0.3	0.3	-0.3
3	10:46:00	42.820	0.64	1.104	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
4	10:47:00	42.818	0.70	1.105	1.830	150	150	152	152	167	167	170	-0.3	0.3	-0.3
5	10:48:00	42.817	0.76	1.105	1.835	151	151	153	153	167	167	170	-0.3	0.3	-0.3
6	10:48:15	42.816	0.70	1.105	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
7	10:48:30	42.815	0.74	1.102	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
8	10:49:00	42.814	0.78	1.108	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
9	10:49:30	42.813	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
10	10:50:00	42.812	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
11	10:50:30	42.811	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
12	10:51:00	42.810	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
13	10:51:30	42.809	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
14	10:52:00	42.808	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
15	10:52:30	42.807	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
16	10:53:00	42.806	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
17	10:53:30	42.805	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
18	10:54:00	42.804	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
19	10:54:30	42.803	0.82	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3
20	10:55:00	42.802	0.85	1.109	1.830	151	151	153	153	167	167	170	-0.3	0.3	-0.3

Final	60	83.987	Avg. 218.1 cfm/sq ft	Is.	Tm	Ps	Pm	Bws
Nomograph Calibration Variables								
Comments:								
Leak Checks								
Int. DGM Reading								
Final DGM Reading								
Pause Times								
Pause: 11:24								
Resume: 11:24								
Done By / Date:								

Air Compliance Testing, Inc.
DreiTempACT Test Method 5 isokinetic
Method 5 Site Specific Field Data 4/20/2013
1 of 1

YJ-2013-07

Job Number: 130502-A
Date: 5/2/13

Method 9 Visible Emissions Observation Form-1

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Company Name	Clow Water Systems Co.	Observation Date	5/2/13	Run No.	1
Facility Name	Clow Water Systems Co.	Start Time	7:45		
Street Address	S Sixth St	End Time	8:45		
City	Coshocton	State	OH	Zip	43812

Process & Unit #	Cupola Emission System	Operating Mode	Maximum Achievable Operations
Control Equipment	Scrubber System	Operating Mode	N/A

Describe Emission Point	Shroud Area, covered area with crane operations, olive green building	Sec. 0 15 30 45	Sec. 0 15 30 45
Height of Emission Point	Start 100'	Min. 0 0 0 5	30 0 0 5 5
Height Relative to Observer	Start at 35'	1 5 10 0 0	31 0 5 0 0
Distance from Observer	Start at 450'	2 0 0 0 0	32 0 5 10 0
Direction from Observer (°)	Start 303°	3 5 5 15 5	33 0 10 5 0
Vertical Angle to Observation Point (°)	Start 10°	4 0 0 0 0	34 10 10 0 0
Distance and Direction to Observation Point from Emission Point	Start 30' North directly above	5 5 0 5 5	35 0 5 5 0
Start	Same	6 5 0 0 5	36 5 5 0 5
End	Same	7 0 5 5 5	37 10 5 0 0
		8 0 0 10 10	38 0 5 5 0
Describe Emissions	Start white/brown lifting	9 5 5 0 0	39 15 0 10 5
Emission Color	Start white/brown	10 0 5 10 0	40 5 10 5 15
If Water Droplet Plume	Attached N/A	11 10 5 10 5	41 0 0 0 0
Point in the Plume at which Opacity was Determined	Start at the tip of the roof when it comes out of the shroud area	12 0 0 0 5	42 0 0 5 5
Start	Same	13 5 0 0 5	43 5 0 5 10
End	Same	14 10 10 0 5	44 5 10 0 10
		15 5 10 5 0	45 10 10 0 5
Describe Plume Background	Start pipes and sky	16 0 0 0 5	46 10 0 5 5
Background Color	Start blue sky, rusted pipes	17 5 0 0 5	47 0 5 0 0
Sky Conditions	Start clear	18 15 0 5 5	48 0 5 0 5
Wind Speed (mph)	Start 4-6	19 5 5 0 10	49 5 0 0 0
Wind Direction (From)	Start ESE	20 10 10 5 0	50 0 0 0 0
Ambient Temperature (°F)	Start 53	21 0 5 0 5	51 0 0 0 0
Relative Humidity (%)	Start 65%	22 5 5 0 5	52 0 0 0 5
		23 0 0 0 0	53 0 0 0 0
		24 0 5 5 0	54 5 0 0 0
		25 0 0 0 0	55 0 0 0 10
		26 0 5 5 5	56 10 5 10 10
		27 15 5 5 5	57 5 0 5 0
		28 10 5 0 0	58 0 10 10 0
		29 5 0 0 0	59 5 0 0 5
Source Layout Sketch		Draw North Arrow	
		<input type="checkbox"/> Draw North Arrow <input checked="" type="checkbox"/> <input checked="" type="checkbox"/>	
Latitude 40° 16' 13" N Longitude 75° 51' 38" W		Sun Location Line Longitude 75° 51' 38" W Declination 20° 52' 55" S	
Range of Opacity Readings			
Minimum 0		Maximum 15	
Average Opacity for Highest Period 5.21			
Observer's Name (Print) Alex Spektor			
Observer's Signature			
Date 5/2/13			
Organization Air Compliance Testing, Inc.			
Certified By (Check below where applicable):			
<input checked="" type="checkbox"/> Eastern Technical Associates		Date: 4/10/13	
<input type="checkbox"/> Whitlow Enterprises, LLC		Date:	
<input type="checkbox"/> Compliance Assurance Associates		Date:	

Air Compliance Testing, Inc.
D:\Testing\ACT Test Methods\W009\Method 9.xls
(Method 9.xls - Observation Form-1) 4/30/2013

1 of 1

Job Number: 130502 B

Done By / Date: 5/2/13
Final Check By / Date: 5/2/13

Method 9 Visible Emissions Observation Form-1

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Company Name	Clow Water Systems Co.	Observation Date	5/12/13	Run No.	2
Facility Name	Clow Water Systems Co.	Start Time	9:17		
Street Address	S Sixth St	End Time	10:17		
City	Coshocton	State	OH	Zip	43812

Process & Unit #	Cupola Emission System	Operating Mode	Maximum Achievable Operations
Control Equipment	Scrubber System	Operating Mode	NA

Describe Emission Point	Shroud area, covered area with crane operations, olive green building	Sec.	0	15	30	45	Sec.	0	15	30	45
		Min.	X	X	X	X		X	X	X	X
Height of Emission Point	Start ~100' End same	0	5	5	10	5	30	0	5	0	0
Height Relative to Observer	Start ~73' End same	1	5	0	5	0	31	0	0	0	5
Distance from Observer	Start 4450' End same	2	5	5	0	5	32	5	5	10	0
Direction from Observer (°)	Start 302° End same	3	10	10	5	5	33	0	5	5	5
Vertical Angle to Observation Point (°)	Start 10° End same	4	5	5	5	0	34	10	0	10	5
Distance and Direction to Observation Point from Emission Point	Start 30' North directly above	5	0	5	0	10	35	10	15	10	5
	End same	6	10	5	5	10	36	0	5	5	10
		7	5	0	10	5	37	10	5	0	0
		8	0	0	0	5	38	5	5	5	0
Describe Emissions	Start white/brown lifting End same	9	5	5	0	10	39	0	15	10	10
Emission Color	Start white/brown End same	10	0	10	5	0	40	15	15	15	10
If Water Droplet Plume	Attached NA Detached NA	11	5	5	10	10	41	10	5	5	5
Point in the Plume at which Opacity was Determined	Start at the tip of the roof when it comes out of the shroud area	12	10	10	10	15	42	5	5	5	10
	End same	13	10	5	5	5	43	0	10	5	0
		14	5	5	5	0	44	10	5	0	0
		15	0	10	15	15	45	0	0	5	5
Describe Plume Background	Start pipes and sky End same	16	10	5	10	15	46	5	10	5	5
Background Color	Start blue sky/rust pipes End same	17	5	0	5	0	47	0	5	5	10
Sky Conditions	Start clear End same	18	0	5	5	5	48	5	5	0	0
Wind Speed (mph)	Start 4-6 7-10 End 7-10	19	10	10	10	5	49	5	0	0	0
Wind Direction (From)	Start ESE SE End SSE	20	0	10	15	15	50	5	0	5	5
Ambient Temperature (°F)	Start 58 64 End 67	21	10	10	0	10	51	0	5	0	5
Relative Humidity (%)	Start 65 48% End 45%	22	5	5	0	0	52	5	0	0	0
Source Layout Sketch											
Draw North Arrow											
<input type="checkbox"/> N <input checked="" type="checkbox"/> S <input type="checkbox"/> E <input type="checkbox"/> W											
(A) Observation Point											
Shroud area											
Observer's Position											
(B) Sun Location Line											
Latitude 40° 14' 34" N Longitude 81° 51' 38" W Declination 10° 50' 18" W											
Scale: 100 FEET											
Stock With Plume Sun Wind											
Job Number: 130502 B											
Done By / Date: AS 5/12/13											
Final Check By / Date: SS 5/22/13											

Air Compliance Testing, Inc.
D:\Testing\ACT Test Methods\W009\Method 9.xls
(Method 9.xls-Observation Form-1) 4/30/2013
1 of 1

Method 9 Visible Emissions Observation Form-1

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Company Name	Clow Water Systems Co.	Observation Date	5/21/13	Run No.	3
Facility Name	Clow Water Systems Co.	Start Time	10:50		
Street Address	S Sixth St	End Time	11:50		
City	Coshocton	State	OH	Zip	43812

Process & Unit #	Cupola Emission System	Operating Mode	Maximum Achievable Operations
Control Equipment	Scrubber System	Operating Mode	NA

Describe Emission Point	Shroud Area, covered area with crane operations, olive green building		Sec.	0	15	30	45	Sec.	0	15	30	45		
Height of Emission Point	Start 100'	End Same	Min.	X	X	X	X	Min.	X	X	X	X		
Height Relative to Observer	Start ~35'	End Same	0	0	5	10	15	30	5	0	0	5		
Distance from Observer	Start 450'	End Same	1	5	5	10	5	31	5	5	5	10		
Direction from Observer (°)	Start 202°	End Same	2	0	10	10	5	32	10	5	5	5		
Vertical Angle to Observation Point (°)	Start 10°	End Same	3	0	0	5	5	33	0	5	5	10		
Distance and Direction to Observation Point from Emission Point	Start 30' directly above		4	5	5	5	5	34	0	0	5	0		
Start	30' directly above	End Same	5	0	5	5	10	35	5	5	5	0		
End	Same		6	10	5	0	0	36	0	0	5	5		
Describe Emissions	Start white/brown lofting	End Same	7	0	0	0	0	37	0	5	5	10		
Emission Color	Start white/brown	End Same	8	0	0	0	5	38	10	10	5	5		
If Water Droplet Plume	Attached NA	Detached NA	9	5	5	0	5	39	10	6	15	10		
Point in the Plume at which Opacity was Determined	Start at the tip of the roof when it comes out of the shroud area		10	0	0	5	10	40	5	10	10	5		
Start	Same	End Same	11	5	5	0	0	41	10	5	0	0		
End	Same		12	0	5	5	5	42	0	0	0	5		
Describe Plume Background	Start pipes and sky	End Same	13	10	10	5	10	43	5	0	10	10		
Background Color	Start blue sky w/ white clouds	End Same	14	0	5	5	0	44	0	0	0	0		
Sky Conditions	Start clear	End same	15	0	0	5	0	45	5	5	5	5		
Wind Speed (mph)	Start 7-10	End 7-10	16	0	0	5	5	46	5	0	5	5		
Wind Direction (From)	Start SSE	End S	17	0	0	5	0	47	0	0	0	5		
Ambient Temperature (°F)	Start 67	End 72	18	0	0	0	0	48	0	0	0	0		
Relative Humidity (%)	Start 45%	End 43%	19	0	5	5	5	49	5	5	0	0		
Source Layout Sketch			20	0	5	0	0	50	5	10	10	10		
			21	0	5	10	5	51	5	5	5	5		
			22	5	5	10	10	52	5	0	0	5		
			23	10	0	0	5	53	5	0	5	5		
			24	5	10	5	0	54	5	5	0	0		
			25	0	0	5	5	55	0	5	5	5		
			26	5	5	5	5	56	10	5	10	10		
			27	10	5	5	5	57	5	10	5	5		
			28	0	10	10	10	58	0	10	0	0		
			29	5	5	10	10	59	5	5	5	5		
Range of Opacity Readings														
Minimum	0			Maximum	15									
Average Opacity for Highest Period 6.04% 6.25%														
Observer's Name (Print) Alex Speller														
Observer's Signature														
Date 5/21/13														
Organization Air Compliance Testing, Inc.														
Certified By (Check below where applicable):														
<input checked="" type="checkbox"/> Eastern Technical Associates	Date: 4/10/13													
<input type="checkbox"/> Whitlow Enterprises, LLC	Date:													
<input type="checkbox"/> Compliance Assurance Associates	Date:													

Longitude: 81° 58' W Latitude: 40° 14' 39" N Decination: 70° 50' 18" W

Air Compliance Testing, Inc.
D:\Testing\ACT Test Methods\Method 9.xls
(Method 9.xls-Observation Form-1) 4/30/2013
1 of 1

Job Number: 130502-B
Done By / Date: ASA / 5/21/13
Final Check By / Date: SS/5-22-13

Method 4 Moisture Recovery

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Method 4 Gravimetric Determination for Moisture

Method 5 Sample Train

Company Name: Clow Water Systems
Location: P901
Prepared By: ASA Date: 4/26/13 Shop Balance ID: A-BAL-005 Field Balance ID: A-BAL-008

Run Number	1	2	3
Run Date	5/2/13	5/2/13	/
Recovery Date	5/2/13	5/2/13	/
Recovery Time	9:43	10:42	/
Recovered By	ASA	ASA	/
Impinger Box No.	001	006	/
Turbidity / Color (Clear, Cloudy, Suspended Particulates, etc.)	no change	no change	/

Impinger Initial Weights (Grams)			
Knockout Initial			
No. 1 Initial	689.0	689.5	691.7
No. 2 Initial	680.5	676.1	674.1
No. 3 Initial	597.7	587.9	587.5
Silica Gel Initial	892.7	874.6	912.1

Impinger Final Weights (Grams)			
Knockout Final			
No. 1 Final	707.3	711.9	740.5
No. 2 Final	698.3	694.0	713.4
No. 3 Final	601.4	594.0	604.2
Silica Gel Final	902.5	886.9	911.2

Method 4 Gravimetric Calculation for Moisture

Method 5 Sampling Train

Run 1	Run 2	Run 3
-------	-------	-------

IMPINGER #1

Final Weight (g)
 Tared Weight (g)
Condensed H₂O (ml,g)

707.3	711.9	740.5
689.0	691.7	707.3
18.3	20.2	33.2

IMPINGER #2

Final Weight (g)
 Tared Weight (g)
Condensed H₂O (ml,g)

698.3	694.0	713.4
680.5	676.1	698.3
17.8	17.9	15.1

IMPINGER #3

Final Weight (g)
 Tared Weight (g)
Condensed H₂O (ml,g)
Total Condensed (ml,g)

601.4	594.0	604.2
597.7	587.9	601.4
3.7	6.1	2.8
39.8	44.2	51.1

SILICA GEL

Final Weight (g)
 Tared Weight (g)
Adsorbed H₂O (ml,g)

902.5	886.9	911.2
892.7	874.6	902.5
9.8	12.3	8.7

Total H₂O Collected (ml,g)

49.6	56.5	59.8
------	------	------

Method 3 Fyrite Field Data

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Plant Name: Clow Water Systems Co.

Test Location: P901 Exhaust Stack (A)

CO₂ Zero: N

O₂ Zero: N

Run Number: 1		Operator: QAE		
Time of Sample Collection	Time of Analysis	%CO ₂ (A)	%O ₂ (B)	%N ₂ (100 - (A + B))
7:43 8:51	10:31	11.0	12.0	77.0
	↓	11.0	12.0	77.0
	10:36	11.0	12.0	77.0
Average		11.0	12.0	77.0

Analyzer I.D. - A - FYR - 003 Tedlar Bag I.D.: 130502 A - 1 - M3/TB

Run Number: 2		Operator: ASA		
Time of Sample Collection	Time of Analysis	%CO ₂ (A)	%O ₂ (B)	%N ₂ (100 - (A + B))
9:07 10:24	11:58	12.5	12.5	75.0
	12:01	12.4	12.5	75.1
	12:05	12.5	12.1	75.4
Average		12.45	12.37	75.17

Analyzer I.D. - A - FYR - 003 Tedlar Bag I.D.: 130502 A - 2 - M3/TB

Run Number: 3		Operator: ASA		
Time of Sample Collection	Time of Analysis	%CO ₂ (A)	%O ₂ (B)	%N ₂ (100 - (A + B))
10:50 11:54	12:09	11.0	11.5	77.5
	12:11	11.0	11.5	77.5
	12:13	11.0	11.5	77.5
Average		11.0	11.5	77.5

Analyzer I.D. - A - FYR - 003 Tedlar Bag I.D.: 130502 A - 3 - M3/TB

Method 3 Dry Molecular Weight Calculation

Run 1			
%CO ₂	%O ₂	%N ₂	Molecular Weight
11.0	12.0	77.0	30.24
11.0	12.0	77.0	30.24
11.0	12.0	77.0	30.24
Average	11.00	12.00	30.24

Run 2			
%CO ₂	%O ₂	%N ₂	Molecular Weight
12.5	12.5	75.0	30.50
12.4	12.5	75.1	30.48
12.5	12.1	75.4	30.48
Average	12.47	12.37	30.49

Run 3			
%CO ₂	%O ₂	%N ₂	Molecular Weight
11.0	11.5	77.5	30.22
11.0	11.5	77.5	30.22
11.0	11.5	77.5	30.22
Average	11.00	11.50	30.22

Cyclonic Flow Determination

Effective Date: 7/1/01
Rev No. 0
Issued by: Quality Manager

Plant Name	Clow Water Systems Co.																																																																																																																																																																				
City, State	Coshocton, OH																																																																																																																																																																				
Test Location	P901 Exhaust Stack (A)																																																																																																																																																																				
Pilot I.D. - T - DIT-B01	Manometer I.D. - T - MTB-DTS	Umbilical I.D. T - MZD-25 b																																																																																																																																																																			
Run Number - 1 Date - 3/7/13 Barometric Pressure (in.Hg) : 29.32 Ambient Temperature (°F) : 30 Barometer ID- DPG - 010 Start Time - 1208 Finish Time - 1224 Manometer Zero and Level - Yes <input checked="" type="checkbox"/> Apparatus Leak Check - Done By: TS/JH Pre Impact Side - Pass <input checked="" type="checkbox"/> Pre Static Side - Pass <input checked="" type="checkbox"/>		Run Number - Date - Barometric Pressure (in.Hg) : Ambient Temperature (°F): Barometer ID- Start Time - Finish Time - Manometer Zero and Level - Yes <input type="checkbox"/> Apparatus Leak Check - Done By: Pre Impact Side - Pass <input type="checkbox"/> Pre Static Side - Pass <input type="checkbox"/>																																																																																																																																																																			
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Test Point</th> <th>Notes</th> <th>Yaw Angle (°)</th> </tr> </thead> <tbody> <tr><td>1</td><td></td><td>-7</td></tr> <tr><td>2</td><td></td><td>-8</td></tr> <tr><td>3</td><td></td><td>-9</td></tr> <tr><td>4</td><td></td><td>-8</td></tr> <tr><td>5</td><td></td><td>12</td></tr> <tr><td>6</td><td></td><td>9</td></tr> <tr><td>7</td><td>(0.0)</td><td>6</td></tr> <tr><td>8</td><td>(0.35) 0</td><td>5</td></tr> <tr><td>9</td><td>0</td><td>3</td></tr> <tr><td>10</td><td></td><td>8</td></tr> <tr><td>11</td><td></td><td>18</td></tr> <tr><td>12</td><td></td><td>14</td></tr> <tr><td>13</td><td></td><td>12</td></tr> <tr><td>14</td><td></td><td>7</td></tr> <tr><td>15</td><td></td><td>4</td></tr> <tr><td>16</td><td></td><td>3</td></tr> <tr><td>17</td><td></td><td>4</td></tr> <tr><td>18</td><td>(5.50)</td><td>1</td></tr> <tr><td>19</td><td></td><td>3</td></tr> <tr><td>20</td><td></td><td>6</td></tr> <tr><td>21</td><td></td><td>2</td></tr> <tr><td>22</td><td></td><td>12</td></tr> <tr><td>23</td><td></td><td>8</td></tr> <tr><td>24</td><td></td><td>5</td></tr> <tr><td>25</td><td></td><td></td></tr> <tr> <td>Avg.</td> <td></td> <td>11.29</td> </tr> </tbody> </table>		Test Point	Notes	Yaw Angle (°)	1		-7	2		-8	3		-9	4		-8	5		12	6		9	7	(0.0)	6	8	(0.35) 0	5	9	0	3	10		8	11		18	12		14	13		12	14		7	15		4	16		3	17		4	18	(5.50)	1	19		3	20		6	21		2	22		12	23		8	24		5	25			Avg.		11.29	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Test Point</th> <th>Notes</th> <th>Yaw Angle (°)</th> </tr> </thead> <tbody> <tr><td>1</td><td></td><td></td></tr> <tr><td>2</td><td></td><td></td></tr> <tr><td>3</td><td></td><td></td></tr> <tr><td>4</td><td></td><td></td></tr> <tr><td>5</td><td></td><td></td></tr> <tr><td>6</td><td></td><td></td></tr> <tr><td>7</td><td></td><td></td></tr> <tr><td>8</td><td></td><td></td></tr> <tr><td>9</td><td></td><td></td></tr> <tr><td>10</td><td></td><td></td></tr> <tr><td>11</td><td></td><td></td></tr> <tr><td>12</td><td></td><td></td></tr> <tr><td>13</td><td></td><td></td></tr> <tr><td>14</td><td></td><td></td></tr> <tr><td>15</td><td></td><td></td></tr> <tr><td>16</td><td></td><td></td></tr> <tr><td>17</td><td></td><td></td></tr> <tr><td>18</td><td></td><td></td></tr> <tr><td>19</td><td></td><td></td></tr> <tr><td>20</td><td></td><td></td></tr> <tr><td>21</td><td></td><td></td></tr> <tr><td>22</td><td></td><td></td></tr> <tr><td>23</td><td></td><td></td></tr> <tr><td>24</td><td></td><td></td></tr> <tr><td>25</td><td></td><td></td></tr> <tr> <td>Avg.</td> <td></td> <td></td> </tr> </tbody> </table>		Test Point	Notes	Yaw Angle (°)	1			2			3			4			5			6			7			8			9			10			11			12			13			14			15			16			17			18			19			20			21			22			23			24			25			Avg.		
Test Point	Notes	Yaw Angle (°)																																																																																																																																																																			
1		-7																																																																																																																																																																			
2		-8																																																																																																																																																																			
3		-9																																																																																																																																																																			
4		-8																																																																																																																																																																			
5		12																																																																																																																																																																			
6		9																																																																																																																																																																			
7	(0.0)	6																																																																																																																																																																			
8	(0.35) 0	5																																																																																																																																																																			
9	0	3																																																																																																																																																																			
10		8																																																																																																																																																																			
11		18																																																																																																																																																																			
12		14																																																																																																																																																																			
13		12																																																																																																																																																																			
14		7																																																																																																																																																																			
15		4																																																																																																																																																																			
16		3																																																																																																																																																																			
17		4																																																																																																																																																																			
18	(5.50)	1																																																																																																																																																																			
19		3																																																																																																																																																																			
20		6																																																																																																																																																																			
21		2																																																																																																																																																																			
22		12																																																																																																																																																																			
23		8																																																																																																																																																																			
24		5																																																																																																																																																																			
25																																																																																																																																																																					
Avg.		11.29																																																																																																																																																																			
Test Point	Notes	Yaw Angle (°)																																																																																																																																																																			
1																																																																																																																																																																					
2																																																																																																																																																																					
3																																																																																																																																																																					
4																																																																																																																																																																					
5																																																																																																																																																																					
6																																																																																																																																																																					
7																																																																																																																																																																					
8																																																																																																																																																																					
9																																																																																																																																																																					
10																																																																																																																																																																					
11																																																																																																																																																																					
12																																																																																																																																																																					
13																																																																																																																																																																					
14																																																																																																																																																																					
15																																																																																																																																																																					
16																																																																																																																																																																					
17																																																																																																																																																																					
18																																																																																																																																																																					
19																																																																																																																																																																					
20																																																																																																																																																																					
21																																																																																																																																																																					
22																																																																																																																																																																					
23																																																																																																																																																																					
24																																																																																																																																																																					
25																																																																																																																																																																					
Avg.																																																																																																																																																																					
Apparatus Leak Check - Done By: TS/JH Post Impact Side - Pass <input checked="" type="checkbox"/> Post Static Side - Pass <input checked="" type="checkbox"/>		Apparatus Leak Check - Done By: Post Impact Side - Pass <input type="checkbox"/> Post Static Side - Pass <input type="checkbox"/>																																																																																																																																																																			

Note: Yaw angle average is the sum of the absolute values divided by the number of measurements, and must be $\leq 20^{\circ}$.
 Yaw angle is the angle measured from the point where zero ΔP should be obtained to the point where zero ΔP is actually obtained.

Air Compliance Testing, Inc.
 DTESTINGVACT Test Method WDO2/WMethod 2
 (Method 2-Cyclonic Flow Determination) 3/12/01
 1 of 1

Job Number: 130312 A
 Done By / Date: 3/31/01
 Final Check By / Date: 4/3/01

Method 1.xls Preliminary Field Data-Round

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Plant Clow Water Systems Co.
City, State Coshocton, OH
Location P901 Exhaust Stack (A)

Duct Depth (Inner Diameter):

Port 1	Port 2	Port 3	Port 4
<u>L</u>	<u>R</u>		
<u>10.1</u>	<u>10.1</u>		
<u>6.8</u>	<u>6.8</u>		
<u>0.</u>	<u>0</u>		
<u>63.3</u>	<u>63.3</u>		
<u>0</u>	<u>0</u>		
<u>6</u>	<u>6</u>		

Relative Location

From Far Inside Wall to Outside of Port (in.)

Nipple Length and/or Wall Thickness (in.)

Nipple Protrusion (in.)

Stack or Duct Depth (Inner Diameter) (in.)

Stack Outer Circumference (in.)

Port Hole Inner Diameter (in.)

Sample Port Access

Elevation of Meter Box from Ground Level (ft)

Elevation of Ports from Ground Level (ft)

Number of Ports

Direction of Flow

Isokinetic Sample (Yes / No)

Measured Particulate Build-up (in.)

MAN LIFT			
<u>@ 50 0</u>			
<u>50</u>			
<u>2</u>			
<u>A</u>			
<u>Y</u>			
<u>NONE</u>			

Distance Upstream from Flow Disturbance (in.)

171.0

Diameters Upstream from Flow Disturbance ($\geq 0.5 D_o$)

2.7

Minimum Traverse Points Needed *

12

Distance Downstream from Flow Disturbance (in.)

190

Diameters Downstream from Flow Disturbance ($\geq 2 D_o$)

3

Minimum Traverse Points Needed *

24

*Circle Larger of the Two

Stack or Duct Area = 3247.0 in.²

Location of Points in Circular Stacks or Ducts											
	4	6	8	10	12	14	16	18	20	22	24
1	6.7	4.4	3.2	2.6	2.1	1.8	1.6	1.4	1.3	1.1	1.1
2	25.0	14.8	10.5	8.2	6.7	5.7	4.9	4.4	3.9	3.5	3.2
3	75.0	29.8	19.4	14.6	11.8	9.9	8.5	7.5	6.7	6.0	5.5
4	93.3	70.4	32.3	22.6	17.7	14.6	12.5	10.9	9.7	8.7	7.9
5	85.4	67.7	34.2	25.0	20.1	16.9	14.6	12.9	11.6	10.5	
6	95.6	80.6	65.8	35.6	26.9	22.0	18.8	16.5	14.6	13.2	
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											

Note:

1) Stacks having a diameter greater than 24in, shall have no traverse points located within 1.0in of the Stack walls.

2) Stacks having a diameter less than or equal to 24in, shall have no traverse points located within .50in of the Stack walls.

3) Add nipple protrusion length to Point 1 only.
Actual nipple length = (length - protrusion)

Relocate to a distance equal to the inside diameter of the nozzle being used or to the above minimum distances, whichever is larger.

Port Number	1	2
Relative Location	L	R
From Far Wall to Outside of Port (in.)	70.10	70.10
Nipple Length or Wall Thickness (in.)	6.80	6.80
Port Protrusion Length (opt) (in.)	0.00	0.00
Depth of Stack or Duct (in.)	63.30	63.30
Stack or Duct Type	Circular	
Port Hole Inner Diameter (in.)	6.0	
Stack or Duct Width (if Rectangular) (in.)		#N/A
Stack Outer Circumference (in.)		
Number of Ports	2.0	
Elevation of Meter Box from Ground Level (ft)	5.0	
Elevation of Ports from Ground Level (ft)	35.0	

Equivalent Diameter = D_e (in.)

$$D_e = \frac{2 \times (\text{Depth} \times \text{Width})}{(\text{Depth} + \text{Width})} = \text{_____}$$

"Velocity" or "Particulate" Traverse

particulate

Distance Upstream from Flow Disturbance (in.)	171.0
Diameter Upstream from Flow Disturbance ($\pm 0.5 D_e$)	2.70
Minimum Traverse Points Needed for a Velocity Traverse *	12
Minimum Traverse Points Needed for a Particulate Traverse *	12
Distance Downstream from Flow Disturbance (in.)	190.0
Diameter Downstream from Flow Disturbance ($\pm 2 D_e$)	3.00
Minimum Traverse Points Needed for a Velocity Traverse *	16
Minimum Traverse Points Needed for a Particulate Traverse *	24

Minimum Traverse Points

24

Traverse Point Overlap

Duct Area - m^2

3147.00

Duct Area - ft^2

21.8542

Diameter Check via Circumference (in.)

0.0690

Location of Points in Circular Stacks or Ducts

4	6	8	10	12	14	16	18	20	22	24
1	5.7	4.4	3.2	2.6	2.3	1.8	1.2	1.1	1.1	1.1
2	25.0	14.6	10.5	8.2	6.7	5.7	4.4	3.8	3.5	3.2
3	75.6	28.0	19.4	14.6	11.8	9.8	8.5	7.5	6.7	6.5
4	93.3	70.4	32.2	22.6	17.7	14.0	12.5	10.9	9.7	7.9
5	85.4	67.7	34.2	25.0	20.4	16.9	14.8	12.6	11.6	10.5
6	93.6	80.6	65.6	35.6	26.5	22.0	18.8	16.5	14.6	13.2
7	89.5	77.4	64.4	36.6	23.3	23.8	20.4	18.0	16.1	14.4
8	95.4	85.4	75.6	63.4	37.6	29.8	26.0	21.8	19.4	17.4
9	91.8	82.3	73.1	62.5	33.2	36.6	28.2	22.6	20.2	18.0
10	97.4	88.2	78.9	71.7	49.8	38.9	31.5	27.2	23.5	20.2
11	93.3	85.4	78.0	70.4	61.2	39.3	32.3	27.8	23.5	20.2
12	97.9	93.1	83.1	76.4	68.4	60.7	58.6	53.2	48.2	43.2
13	94.8	97.5	87.5	81.2	75.5	68.5	65.2	59.8	54.5	49.2
14	96.2	91.5	85.4	79.4	73.8	67.7	62.4	56.2	50.1	44.9
15	98.1	93.1	83.5	78.2	72.8	66.5	61.2	55.0	49.0	43.8
16	98.4	92.5	87.1	82.0	77.0	72.4	67.1	61.8	56.5	51.2
17	95.8	90.3	85.4	80.6	74.8	69.5	64.2	58.9	53.6	48.4
18	98.6	93.3	88.4	83.9	79.4	74.1	68.8	63.5	58.2	52.9
19	96.1	91.3	86.6	81.9	76.4	71.1	65.8	60.5	55.2	49.9
20	93.7	94.0	82.5	78.2	72.8	67.5	62.2	56.9	51.6	46.3
21	95.3	92.1	84.5	79.8	74.5	69.2	64.0	58.7	53.4	48.1
22	95.9	94.5	86.8	82.0	77.0	71.7	66.4	61.1	55.8	50.5
23	96.8	95.8	88.9	84.1	79.4	74.1	68.8	63.5	58.2	52.9
24	98.9	98.9	91.9	87.1	82.3	77.0	71.7	66.4	61.1	55.8

Note:

1) Stacks having a diameter greater than 24in, shall have no traverse points located within 1.0in of the Stack walls.

2) Stacks having a diameter less than or equal to 24in, shall have no traverse points located within .50in of the Stack walls.

3) Add nipple protrusion length to Point 1 only.
Actual nipple length = (length - protrusion)

Relocate to a distance equal to the inside diameter of the nozzle being used or to the above minimum distances, whichever is larger.

Number of Ports: 2.0
Direction of Flow: Up
Isokinetic Sample: Yes
Stack Build-up: No

Port	Point	% of Duct Depth	Dist. From Inside Wall (Decimal)	Dist. From Outside Wall (Decimal)
1	1	2.1	1.3	8.1
1	2	6.7	4.2	11.0
1	3	11.8	7.5	14.3
1	4	17.7	11.2	18.0
1	5	25	15.8	22.6
1	6	35.6	22.5	29.3
1	7	64.4	40.8	47.6
1	8	75	47.5	54.3
1	9	82.3	52.1	58.9
1	10	88.2	55.8	62.6
1	11	93.3	59.1	65.9
1	12	97.9	62.0	68.8
2	1	2.1	1.3	8.1
2	2	6.7	4.2	11.0
2	3	11.8	7.5	14.3
2	4	17.7	11.2	18.0
2	5	25	15.8	22.6
2	6	35.6	22.5	29.3
2	7	64.4	40.8	47.6
2	8	75	47.5	54.3
2	9	82.3	52.1	58.9
2	10	88.2	55.8	62.6
2	11	93.3	59.1	65.9
2	12	97.9	62.0	68.8

Method 5 Probe Nozzle Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

The sampling nozzle must be calibrated before use in a source experiment. Calibration should be done in the laboratory and checked just before use in the field. Inside / outside calipers are used to measure the interior nozzle diameter to the nearest 0.025mm (0.001 inch).


The calipers are inserted as close to the edge of the nozzle opening as possible; readings are taken on three separate diameters and recorded. The average of the three readings will be the Assigned Nozzle Size. Each reading must agree within 0.1 mm (0.004 inch), or the nozzle must be reshaped. Any nozzle that has been nicked, dented, or corroded must be reshaped and recalibrated. All calibrated nozzles should be permanently identified.

Run #	Nozzle ID #	Measured Nozzle Size (inches)	Assigned Nozzle Size (inches)	Difference Between High and Low Measurements
1/2/13	8-22-11	0.225	0.225	0.001 <= 0.004in
		0.226		
		0.226		
Run # 2				
Run # 3				




Type S Pitot Tube Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Alignment and Tubing Dimensions




Degree indicating level position for determining α_1 and α_2 .




Degree indicating level position for determining θ .

γ




Degree indicating level position for determining γ then calculating Z .


Probe / Pitot Number	T-PIT-801
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	0.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	0.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	1.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	-1.0
γ	3.00
θ	2.00
A	0.830
$z = A \tan \gamma$ ($< 0.125"$)	0.043
$w = A \tan \theta$ ($< 0.03125"$)	0.029
D_t ($0.1875" < D_t < 0.375"$)	0.375
P_A ($1.05D_t < P_A < 1.5D_t$)	0.415
P_B ($1.05D_t < P_B < 1.5D_t$)	0.415
$P_A = P_B \pm 0.0625$	0.000



Assembly Inter-Component Spacing Requirements




Effective Length (in.)	97.20
W ($\geq 3.0"$)	37.500
-or- AA ($\geq 2.0"$)	
X	
D _n	
X / D _n (≥ 1.5)	
Y ($\geq 3.0"$)	
Z ($\geq 0.75"$)	1.000





Type S Pitot Tube Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager


Alignment and Tubing Dimensions





Degree indicating level position for determining α_1 and α_2 .



Degree indicating level position for determining θ .




Probe / Pitot Number	T-PRB-808
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	0.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	1.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	1.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	1.0
γ	1.00
θ	0.00
A	0.923
$z = A \tan \gamma$ ($< 0.125"$)	0.016
$w = A \tan \theta$ ($< 0.03125"$)	0.000
D_t ($0.1875" < D_t < 0.375"$)	0.375
P_A ($1.05D_t < P_A < 1.5D_t$)	0.462
P_B ($1.05D_t < P_B < 1.5D_t$)	0.461
$P_A = P_B \pm 0.0625$	0.001






Degree indicating level position for determining γ then calculating Z .

Assembly Inter-Component Spacing Requirements




Effective Length (in.)	86.40
W ($\geq 3.0"$)	7.000
-or- AA ($\geq 2.0"$)	
X	1.000
D_n	0.493
$X / D_n (\geq 1.5)$	2.028
Y ($\geq 3.0"$)	3.700
Z $\geq 0.75"$	1.000







Type S Pitot Tube Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Alignment and Tubing Dimensions




Degree indicating level position for determining α_1 and α_2 .




Degree indicating level position for determining θ .

γ




Probe / Pitot Number	T-PRB-810
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	0.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	0.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	0.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	0.0
γ	0.00
θ	0.00
A	0.906
$z = A \tan \gamma$ ($< 0.125''$)	0.000
$w = A \tan \theta$ ($< 0.03125''$)	0.000
D_t ($0.1875'' < D_t < 0.375''$)	0.375
P_A ($1.05D_t < P_A < 1.5D_t$)	0.480
P_B ($1.05D_t < P_B < 1.5D_t$)	0.426
$P_A = P_B \pm 0.0625$	0.054




Degree indicating level position for determining γ then calculating Z.

Assembly Inter-Component Spacing Requirements




Effective Length (in.)	88.00
W ($\geq 3.0''$)	7.000
-or- AA ($\geq 2.0''$)	
X	0.875
D _n	0.480
X / D _n (≥ 1.5)	1.823
Y ($\geq 3.0''$)	4.375
Z $\geq 0.75''$	1.875






Type S Pitot Tube Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager



Alignment and Tubing Dimensions



Degree indicating level position for determining α_1 and α_2 .




Degree indicating level position for determining θ .




Degree indicating level position for determining γ then calculating Z .


Probe / Pitot Number	T-PIT-801
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	0.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	-1.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	2.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	3.0
γ	1.00
θ	1.00
A	0.826
$z = A \tan \gamma$ (< 0.125")	0.014
$w = A \tan \theta$ (< 0.03125")	0.014
D_t (0.1875" < D_t < 0.375")	0.375
P_A (1.05 D_t < P_A < 1.5 D_t)	0.413
P_B (1.05 D_t < P_B < 1.5 D_t)	0.413
$P_A = P_B \pm 0.0625$	0.000



Assembly Inter-Component Spacing Requirements




Effective Length (in.)	97.00
W ($\geq 3.0"$)	3.100
-or- AA ($\geq 2.0"$)	
X	
D_n	
$X / D_n \geq 1.5$	
Y ($\geq 3.0"$)	
Z $\geq 0.75"$	0.900




Type S Pitot Tube Inspection

Effective Date: 7/18/12
Rev No. 0
Issued by: Quality Manager


Alignment and Tubing Dimensions



Degree indicating level position for determining α_1 and α_2 .




Degree indicating level position for determining θ .




Degree indicating level position for determining γ then calculating Z.


Probe / Pitot Number	T-PRB-808
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	0.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	1.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	1.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	1.0
γ	1.00
θ	0.00
A	0.924
$z = A \tan \gamma$ (< 0.125")	0.016
w = A tan θ (< 0.03125")	0.000
D_t (0.1875" < D_t < 0.375")	0.375
P_A (1.05 D_t < P_A < 1.5 D_t)	0.462
P_B (1.05 D_t < P_B < 1.5 D_t)	0.462
$P_A = P_B \pm 0.0625$	0.000



Assembly Inter-Component Spacing Requirements




Effective Length (in.)	86.40
W ($\geq 3.0"$)	7.000
-or- AA ($\geq 2.0"$)	
X	1.000
D_n	0.493
X / D_n (≥ 1.5)	2.028
Y ($\geq 3.0"$)	3.700
Z $\geq 0.75"$	1.000





Type S Pitot Tube Inspection

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Alignment and Tubing Dimensions




Degree indicating level position for determining α_1 and α_2 .



Degree indicating level position for determining θ .




Probe / Pitot Number	T-PRB-811
Level and Perpendicular	<input checked="" type="checkbox"/>
No Obstructions	<input checked="" type="checkbox"/>
No Damage	<input checked="" type="checkbox"/>
α_1 ($-10^\circ < \alpha_1 < +10^\circ$)	1.0
α_2 ($-10^\circ < \alpha_2 < +10^\circ$)	0.0
β_1 ($-5^\circ < \beta_1 < +5^\circ$)	2.0
β_2 ($-5^\circ < \beta_2 < +5^\circ$)	2.0
γ	4.00
θ	1.00
A	0.984
$z = A \tan \gamma$ ($< 0.125''$)	0.069
$w = A \tan \theta$ ($< 0.03125''$)	0.017
D_t ($0.1875'' < D_t < 0.375''$)	0.375
P_A ($1.05D_t < P_A < 1.5D_t$)	0.492
P_B ($1.05D_t < P_B < 1.5D_t$)	0.492
$P_A = P_B \pm 0.0625$	0.000





Degree indicating level position for determining γ then calculating Z.

Assembly Inter-Component Spacing Requirements



Effective Length (in.)	87.00
W ($\geq 3.0''$)	7.000
-or- AA ($\geq 2.0''$)	
X	1.000
D_n	0.493
$X / D_n (\geq 1.5)$	2.028
Y ($\geq 3.0''$)	3.700
Z ($\geq 0.75''$)	1.800



Method 4 Thermocouple System Audit

Reference Thermometer I.D. :	T-THR-011
Temperature Readout I.D.:	T-MTB- 015
Umbilical Cord I.D. :	T-UMC- 104
Umbilical Cord I.D. :	T-M2U- 451
Umbilical Cord I.D. :	

Probe/Pitot Thermocouple ID	T-PIT- 603		
Filter Exit ID	T-FXT-	T-FXT-	T-FXT-
Umbilical Adapter ID	T-UMA- 014	T-UMA-	T-UMA-

Sample Train Thermocouple Audit

	Run 1	Run 2	Run 3
Ref. Thermometer Temp (°F)	65		
Stack Thermocouple Temp (°F)	64		
Meterbox Temp IN (°F)			
Meterbox Temp OUT (°F)	62		
Filter Exit Temp (°F)			
Impinger Exit Temp (°F)	63		

Meterbox Thermocouple Audit

Thermocouple Simulator Setting (°F)	Stack Temp (°F)	Filter Exit Temp (°F)	Impinger Exit Temp (°F)
50	51		51
100	100		100
200	200		
300	301		
400	399		
600	600		
800	800		
1000	1000		
1500	1497		

Tolerance Ranges

Stack $\pm 8.0^{\circ}\text{F}$ or $\pm 1.5\%$ absolute

Filter Exit $\pm 5.4^{\circ}\text{F}$

Meter Box $\pm 5.4^{\circ}\text{F}$

Impinger Exit $\pm 2.0^{\circ}\text{F}$

Job Number: 130201

Performed by : AS2 Date: 04/15/2013

Method 2 Post-Test Thermocouple Check

ALT-011 Post-Test Stack Thermocouple System Check Procedure

Reference Thermometer ID and Serial No.:	THR-006
Temperature Display ID (Hanna/MTB):	T-MTB-015
Umbilical Cord I.D.:	UMC-106
Umbilical Cord I.D.:	
Umbilical Cord I.D.:	
Continuity Check Performed:	<input checked="" type="checkbox"/>

	Run 1	Run 2	Run 3	Run 4
Probe/Pitot ID:	T-PRB-811	T-PRB-808	T-PRB-811	
Reference Thermometer Ambient Readout (°F):	68	68	68	
Stack Temperature Thermocouple Ambient Readout (°F):	68	68	68	
Temperature Difference (must be ±2°F):	0	0	0	0

Air Compliance Testing, Inc.

Performed by: AS2 Job Number: 130502A
Date: 05/03/2013

Issued 9/4/2012 rev 11/9/12

Method 4 Pre-Test Orifice Meter Check

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

- Assemble meter box - level / zero the manometer
- Operate the meter box at the $\Delta H@$ pressure differential for at least 10 minutes.
The $\Delta H@$ number is taken from the meter console calibration sheet or the tag.
- During the warm-up period, verify flow through the Method 3 flowmeter.
- Record the dry gas meter volume, meter temperatures and barometric pressure (in.Hg).

Meter Box No. T-MTB- 015

Calibration Date 3/25/13

Pump No. T-PMP- 016

Barometric Pressure (in.Hg) 29.72

Gamma (γ) 1.0008

Initial Dry Gas Meter Volume (cf) 946.860

$\Delta H@$ 9.187

Final Dry Gas Meter Volume (cf) 954.493

Time (min)	Meter In (°F)	Meter Out (°F)
2	—	80
4	—	81
6	—	82
8	—	82
10	—	82
Avg.		81.88

Pass

Calculate the Dry Gas Meter Calibration Value (γ_c) and compare γ_c against the Dry Gas Meter Calibration Factor (γ) to determine if $\gamma_c = \gamma \pm 3\%$

If the γ_c is not within this range, the Meter Box should be investigated before beginning the test.

Method 4 Pre-Test Orifice Meter Check**Method 5 Sampling Train**

Meter Box No.	015
Calibration Date	3/25/13
$\gamma =$	1.0008
$\Delta H@ =$	2.187

Initial Dry Gas Meter Volume	946.850
Final Dry Gas Meter Volume	954.493
Net Dry Gas Meter Volume	7.643
Barometric Pressure (inHg)	29.13

Time (min)	Meter In (°F)	Meter Out (°F)
2	80	80
4	81	81
6	82	82
8	82	82
10	82	82
Avg.	81.4	81.4
Avg. of Avgs.	81.4	

 Calculate the Dry Gas Meter Calibration Value (γ_c)

$$\gamma_c = (10 / V_m) * [0.0319 (T_m/P_{bar})]^{1/2}$$

$$0.97(\gamma) < \gamma_c < 1.03(\gamma)$$

 0.9708 < **1.0074** < 1.0308

Meter Box Pre-Test Leak Check

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

- Remove the front panel from the meter box
- Disconnect the fan
- Hook up the proper pump to the meter box
- Close both the fine and coarse adjustment valves
- Connect the DH hoses on the front of the meter box
- Remove the copper elbow from stainless tube at the exit side of gas meter
- Stopper the stainless tube with a rubber stopper
- Disconnect the DH static line from the orifice (bottom)
- Plug in leak check tube into the static side of the orifice
- Blowing into the leak check tube, pressurize the system to 5-7 inches and clamp off
- Hold for one minute
- No leakage should occur. If leak is present, it must be corrected
- Affix (w/ electrical tape) the copper elbow onto the stainless tube at the exit side of gas meter
- Reassemble meter box
- Plug in capped swagelok stem at sample inlet
- Start pump, bringing system vacuum to at least 15 in. Hg
- Note DGM reading, start timer
- Observe DGM for one minute
- No leakage should occur. If leak is present, it must be corrected
- Check oil wick position (should be 1/4" above the black O-ring)
- Check pump oil level (should be at fill line)

Meter Box Number MTB- 015

Pump Number PMP- 015

Method 4 Pre-Test Meter Calculation Orifice Calibration Data

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Meter Box I.D:	T - MTB - 015
Meter Box Serial Number:	352795
Standard Meter I.D:	T - DGM - 006
Temp Sensor I.D:	T - DGM 015
Barometer I.D:	T DPG- MIC-003
Meter Box Level?	<input checked="" type="checkbox"/>

Standard Meter

Calibrated By: Apex Instruments Inc.

Calibration Date: February 25, 2013

Gamma: 0.9977

Serial Number: 1512377

REMOVE CAPS FROM STANDARD METER

Run 1		Meter Readings				Temperatures			
Pressures			Time	Std Meter	Meter Box		Time	Std Meter	Meter Box
ΔH:	1.00 in.H ₂ O		Begin	0.0	781.554	506.275			
Meter Box Vac:	5.0 in.Hg		End	12.0	787.823	512.512			
P Bar:	28.30 in.Hg		Net	12.0	6.269	6.237			
		(>5.0 dcf)							
Run 2		Meter Readings				Temperatures			
Pressures			Time	Std Meter	Meter Box		Time	Std Meter	Meter Box
ΔH:	2.00 in.H ₂ O		Begin	0.0	788.392	513.080			
Meter Box Vac:	5.0 in.Hg		End	12.0	797.081	521.753			
P Bar:	28.30 in.Hg		Net	12.0	8.689	8.673			
		(>5.0 dcf)							
Run 3		Meter Readings				Temperatures			
Pressures			Time	Std Meter	Meter Box		Time	Std Meter	Meter Box
ΔH:	3.00 in.H ₂ O		Begin	0.0	823.212	547.734			
Meter Box Vac:	4.2 in.Hg		End	12.0	833.973	558.372			
P Bar:	28.30 in.Hg		Net	12.0	10.761	10.638			
		(>5.0 dcf)							

ΔH:	<u>ΔH_@</u>	<u>γ</u>
1	2.150	0.9993
2	2.229	0.9979
3	2.183	1.0053
AVG.	2.187	1.0008

* Adjust and recalculate if γ does not equal 1.00 ± 0.02

Method 4 Pre-Test Meter Console Calibration

Effective Date: 7/16/12
Rev No. 0
Issued by: Quality Manager

Run No.	Calibration Meter Correction Factor (γ_c)	Barometric Press. (P_b) (in.Hg)	Meter Box Volume (V_d) (cu.ft.)	Average Meter Box Temperature (T_m) (F)	Standard Meter Volume (V_c) (cu.ft.)	Standard Meter Temperature (T_c) (F)	Time (min.)	Gamma (Y)	Tolerance (plus or minus 0.02)	Tolerance (plus or minus 0.2)
1	0.9977	28.30	1.000	6.237	60.33	6.269	60.83	12	0.9993	-0.001539
2	0.9977	28.30	2.000	8.673	63.00	8.689	61.17	12	0.9979	-0.002928
3	0.9977	28.30	3.000	10.638	64.00	10.761	62.00	12	1.0053	0.004467
Average									2.183	-0.004
									PASS	PASS
									2.187	

Pump Number	Meter Box Number	Reference Meter Number	Reference Meter Number
T-PMP- 015	T-MTB- 015		

Add Values to 30 Day Calibration History
Add Values to Dry Gas Meter Calibration History
Tag Meter Box

ALT-009 Post-Test Leak Check

NOTE: Do not perform leak check if meter failed ALT-009 requirements.

- Remove the front panel from the meter box
- Disconnect the fan
- Hook up the proper pump to the meter box
- Close both the fine and coarse adjustment valves
- Connect the DH hoses on the front of the meter box
- Remove the copper elbow from stainless tube at the exit side of gas meter
- Stopper the stainless tube with a rubber stopper
- Disconnect the DH static line from the orifice (bottom)
- Plug in leak check tube into the static side of the orifice
- Blowing into the leak check tube, pressurize the system to 5-7 inches and clamp off
- Hold for one minute
- No leakage should occur.
- Affix (w/ electrical tape) the copper elbow onto the stainless tube at the exit side of gas meter
- Reassemble meter box

Meter Box Number MTB- 015

Pump Number PMP- 015

Job Number: 130502A
Done By / Date: AS2 /05/03/2013

Air Compliance Testing, Inc.

(Post-Cal Template (JobNumber)-ALT-009 Post-Test Leak Check) 05/03/2013

Method 4 DGM Calibration History

Type	Date	Standard Meter Serial #	Meter Box #	Delta H	Delta H@	Delta H	Delta H@	Delta H	Delta H@	Gamma	Average Delta H@	By
PRE	7/13/2012	1512377	T-MTB- 012	1.00	1.856	2.00	1.890	3.00	1.882	0.9876	1.876	JL
PRE	7/13/2012	1512377	T-MTB- 009	1.00	1.930	2.00	1.933	3.00	1.896	1.0048	1.920	JL
PRE	7/26/2012	1512377	T-MTB- 014	1.00	1.548	2.00	1.640	3.00	1.669	0.9950	1.619	PB
PRE	7/26/2012	1512377	T-MTB- 010	1.00	1.959	2.00	2.028	3.00	1.980	1.0127	1.989	PB
PRE	8/8/2012	1512377	T-MTB- 006	1.00	2.133	2.00	2.149	3.00	2.124	0.9897	2.135	PB
PRE	8/10/2012	1512377	T-MTB- 019	1.00	1.914	2.00	1.838	3.00	1.857	1.0057	1.870	PB
PRE	8/10/2012	1512377	T-MTB- 018	1.00	1.929	2.00	1.909	3.00	1.878	1.0054	1.905	PB
PRE	8/10/2012	1512377	T-MTB- 017	1.00	1.883	2.00	1.908	3.00	1.856	0.9956	1.882	PB
PRE	8/24/2012	1512377	T-MTB- 003	1.00	1.756	2.00	1.818	3.00	1.796	0.9942	1.790	PB
PRE	9/17/2012	1512377	T-MTB- 012	1.00	1.880	2.00	1.945	3.00	1.915	0.9811	1.913	PB
POST	9/17/2012	1512377	T-MTB- 012	1.50	1.942	1.50	1.940	3.00	1.927	0.9911	1.936	PB
PRE	9/18/2012	1512377	T-MTB- 009	1.00	1.903	2.00	1.897	3.00	1.852	0.9858	1.884	PB
PRE	9/19/2012	1512377	T-MTB- 014	1.00	1.805	2.00	1.919	3.00	1.919	0.9821	1.881	PB
PRE	9/24/2012	1512377	T-MTB- 015	1.00	2.135	2.00	2.222	3.00	2.173	0.9967	2.176	PB
PRE	9/28/2012	1512377	T-MTB- 010	1.00	1.999	2.00	2.053	3.00	2.006	0.9956	2.019	PB
PRE	10/8/2012	1512377	T-MTB- 006	1.00	2.077	2.00	2.166	3.00	2.171	0.9967	2.138	PB
PRE	10/24/2012	1512377	T-MTB- 003	1.00	1.804	2.00	1.858	3.00	1.839	1.0000	1.834	RS
POST	10/25/2012	1512377	T-MTB- 009	1.83	1.916	1.83	1.857	1.83	1.896	0.9868	1.890	PB
PRE	10/26/2012	1512377	T-MTB- 018	1.00	1.939	2.00	1.879	3.00	1.880	0.9973	1.899	PB
PRE	10/26/2012	1512377	T-MTB- 019	1.00	1.897	2.00	1.862	3.00	1.917	1.0082	1.892	PB
POST	11/2/2012	1512377	T-MTB- 012	1.64	1.970	1.64	1.959	1.64	1.961	0.9939	1.963	PB
POST	11/6/2012	1512377	T-MTB- 009	1.41	1.617	1.41	1.899	1.41	1.884	0.9842	1.800	PB
PRE	11/16/2012	1512377	T-MTB- 012	1.00	1.922	2.00	1.970	3.00	1.962	0.9848	1.951	PB
PRE	11/16/2012	1612377	T-MTB- 014	1.00	1.704	2.00	1.812	3.00	1.830	0.9837	1.782	PB
PRE	11/29/2012	1512377	T-MTB- 006	1.00	2.101	2.00	2.207	3.00	2.161	0.9941	2.156	AS
PRE	11/29/2012	1512377	T-MTB- 015	1.00	2.188	2.00	2.304	3.00	2.242	0.9836	2.244	AS
POST	11/23/2012	1512377	T-MTB- 018	1.14	1.928	1.14	1.948	1.14	2.021	0.9973	1.966	PB
POST	11/23/2012	1512377	T-MTB- 014	1.00	1.794	1.00	1.775	1.00	1.768	0.9837	1.779	JL
POST	12/7/2012	1512377	T-MTB- 012	1.50	1.970	1.50	1.934	1.50	1.933	0.9917	1.946	JL
POST	12/7/2012	1512377	T-MTB- 018	1.14	1.928	1.14	1.948	1.14	2.021	0.9973	1.966	JL
PRE	12/7/2012	1512377	T-MTB- 017	1.00	1.932	2.00	1.881	3.00	1.907	0.9840	1.906	JL
POST	12/14/2012	1512377	T-MTB- 015	1.01	2.186	1.01	2.160	1.01	2.183	0.9893	2.176	WD
PRE	12/26/2012	1512377	T-MTB- 003	1.00	1.766	2.00	1.858	3.00	1.830	0.9844	1.818	PB
PRE	12/26/2012	1512377	T-MTB- 019	1.00	1.922	2.00	1.885	3.00	1.872	0.9993	1.893	PB
PRE	12/28/2013	1512377	T-MTB- 018	1.00	2.005	2.00	1.960	3.00	1.911	0.9918	1.958	WD
POST	1/4/2013	1512377	T-MTB- 006	2.00	2.224	2.00	2.211	2.00	2.211	0.9872	2.215	PB
PRE	1/11/2013	1512377	T-MTB- 014	1.00	1.579	2.00	1.554	3.00	1.599	0.9880	1.577	WD
PRE	1/16/2013	1512377	T-MTB- 012	1.00	1.800	2.00	1.867	3.00	1.831	0.9857	1.833	PB
PRE	1/24/2013	1512377	T-MTB- 006	1.00	2.106	2.00	2.158	3.00	2.133	0.9891	2.132	WD
PRE	1/25/2013	1512377	T-MTB- 015	1.00	2.141	2.00	2.127	3.00	2.120	0.9818	2.129	PB
PRE	2/1/2013	1512377	T-MTB- 010	1.00	2.013	2.00	2.011	3.00	2.015	1.0023	2.013	JL
PRE	2/1/2013	1512377	T-MTB- 017	1.00	1.920	2.00	1.913	3.00	1.888	0.9635	1.907	JL
PRE	2/1/2013	1512377	T-MTB- 003	1.00	1.819	2.00	1.838	3.00	1.821	0.9904	1.826	JL
POST	2/11/2013	1512377	T-MTB- 012	1.06	1.868	1.06	1.875	1.06	1.854	1.0051	1.866	JL
POST	2/11/2013	1512377	T-MTB- 012	0.92	1.881	0.92	1.873	0.92	1.752	1.0095	1.835	JL
POST	2/26/2013	1512377	T-MTB- 014	1.40	1.528	1.40	1.698	1.40	1.722	1.0011	1.649	PB
POST	2/27/2013	1512377	T-MTB- 014	1.71	1.571	1.71	1.583	1.71	1.588	1.0000	1.580	PB
POST	3/1/2013	1512377	T-MTB- 003	1.09	1.744	1.09	1.742	1.09	1.737	1.0112	1.741	PB
POST	3/1/2013	1512377	T-MTB- 003	1.91	1.739	1.91	1.731	1.91	1.732	1.0007	1.734	PB
POST	3/1/2013	1512377	T-MTB- 015	2.00	2.177	2.00	2.169	2.00	2.165	1.0077	2.170	PB
PRE	3/1/2013	1512377	T-MTB- 019	1.00	1.901	2.00	1.821	3.00	1.812	1.0099	1.844	JL
PRE	3/1/2013	1512377	T-MTB- 018	1.00	1.936	2.00	1.866	3.00	1.830	1.0103	1.877	JL
POST	3/11/2013	1512377	T-MTB- 015	1.35	2.173	1.35	2.170	1.35	2.157	1.0044	2.167	PB
POST	3/12/2013	1512377	T-MTB- 012	1.50	1.881	1.50	1.881	1.50	1.884	0.9945	1.882	PB
PRE	3/12/2013	1512377	T-MTB- 012	1.00	1.934	2.00	1.962	3.00	1.915	0.9951	1.937	PB
PRE	3/12/2013	1512377	T-MTB- 014	1.00	1.612	2.00	1.736	3.00	1.683	0.9927	1.677	PB
PRE	3/16/2013	1512377	T-MTB- 006	1.00	2.054	2.00	2.148	3.00	2.114	0.9981	2.105	PB
PRE	3/25/2013	1512377	T-MTB- 015	1.00	2.150	2.00	2.229	3.00	2.183	1.0008	2.187	AS2
PRE	4/3/2013	1512377	T-MTB- 003	1.00	1.799	2.00	1.865	3.00	1.841	0.9868	1.835	AS2
POST	4/8/2013	1512377	T-MTB- 003	1.50	1.850	1.50	1.863	1.50	1.813	0.9936	1.842	AS2
PRE	4/12/2013	1512377	T-MTB- 010	1.00	1.967	2.00	2.017	3.00	2.007	1.0056	1.997	AS2
PRE	4/19/2013	1512377	T-MTB- 018	1.00	1.942	2.00	1.896	3.00	1.849	1.0078	1.896	JL

Method 5 Acetone Residuals History

DATE	VOL (ml)	RESIDUAL (g/ml)	DATE	VOL (ml)	RESIDUAL (g/ml)	DATE	VOL (ml)	RESIDUAL (g/ml)
10/09/09	200	0.0000008	10/01/10	200	0.0000079	09/12/11	200	0.0000005
10/12/09	200	0.0000015	10/06/10	200	0.0000000	09/26/11	200	0.0000018
10/14/09	200	0.0000000	10/14/10	200	0.0000015	09/28/11	200	0.0000020
10/14/09	200	0.0000005	10/14/10	200	0.0000015	09/29/11	200	0.0000005
10/20/09	200	0.0000005	10/15/10	200	0.0000053	09/29/11	200	0.0000015
10/20/09	200	0.0000008	10/22/10	200	0.0000000	09/26/11	200	0.0000000
10/26/09	200	0.0000079	10/24/10	200	0.0000025	10/05/11	200	0.0000030
11/04/09	200	0.0000010	10/29/10	200	0.0000000	10/05/11	200	0.0000028
11/30/09	200	0.0000000	11/02/10	200	0.0000000	10/05/11	200	0.0000025
11/30/09	200	0.0000000	11/05/10	200	0.0000000	10/22/11	200	0.0000015
12/02/09	200	0.0000000	11/13/10	200	0.0000000	10/26/11	200	0.0000038
01/04/10	200	0.0000010	11/15/10	200	0.0000000	10/26/11	200	0.0000013
01/05/10	200	0.0000000	11/23/10	200	0.0000000	11/07/11	100	0.0000000
01/11/10	200	0.0000000	11/26/10	200	0.0000005	11/21/11	200	0.0000005
01/15/10	250	0.0000002	12/10/10	200	0.0000000	11/21/11	200	0.0000000
01/20/10	200	0.0000030	12/13/10	200	0.0000000	11/23/11	200	0.0000015
02/02/10	200	0.0000010	12/17/10	200	0.0000018	12/14/11	200	0.0000000
02/11/10	200	0.0000060	01/06/11	200	0.0000003	12/18/11	200	0.0000000
02/11/10	200	0.0000050	01/07/11	200	0.0000075	12/19/11	200	0.0000000
02/12/10	200	0.0000000	01/27/11	200	0.0000018	12/23/11	200	0.0000000
02/17/10	220	0.0000016	01/28/11	200	0.0000000	12/29/11	200	0.0000030
03/02/10	200	0.0000027	01/28/11	200	0.0000010	12/29/11	200	0.0000050
03/02/10	200	0.0000000	01/28/11	200	0.0000020	12/29/11	200	0.0000000
03/29/10	300	0.0000012	02/18/11	200	0.0000000	01/18/12	200	0.0000000
04/16/10	200	0.0000070	02/28/11	200	0.0000000	01/19/12	200	0.0000025
04/16/10	200	0.0000005	03/06/11	200	0.0000013	01/31/12	200	0.0000005
04/16/10	200	0.0000000	03/06/11	200	0.0000008	02/03/12	200	0.0000000
04/20/10	200	0.0000013	03/16/11	200	0.0000008	02/29/12	200	0.0000079
04/22/10	200	0.0000018	03/23/11	200	0.0000000	03/08/12	200	0.0000035
05/12/10	200	0.0000018	04/01/11	200	0.0000079	03/16/12	200	0.0000100
05/24/10	200	0.0000070	04/01/11	200	0.0000048	03/26/12	200	0.0000060
05/24/10	200	0.0000079	04/08/11	200	0.0000000	03/26/12	200	0.0000065
05/25/10	100	0.0000079	04/22/11	200	0.0000015	03/30/12	200	0.0000079
06/04/10	100	0.0000050	04/23/11	200	0.0000058	04/03/12	200	0.0000079
06/16/10	200	0.0000025	04/24/11	200	0.0000000	04/05/12	200	0.0000079
06/29/10	200	0.0000033	04/29/11	200	0.0000010	04/11/12	150	0.0000079
07/29/10	200	0.0000018	05/08/11	200	0.0000005	04/17/12	200	0.0000079
07/29/10	200	0.0000033	05/15/11	200	0.0000068	04/27/12	100	0.0000079
08/11/10	200	0.0000010	05/20/11	200	0.0000005	04/28/12	100	0.0000000
08/12/10	200	0.0000079	05/21/11	200	0.0000010	05/01/12	200	0.0000079
08/20/10	200	0.0000043	06/04/11	200	0.0000079	05/02/12	200	0.0000079
08/21/10	200	0.0000079	06/06/11	200	0.0000043	05/04/12	200	0.0000079
08/31/10	200	0.0000079	06/10/11	200	0.0000005	05/05/12	200	0.0000023
08/31/10	200	0.0000010	06/24/11	200	0.0000079	05/13/12	200	0.0000000
09/01/10	200	0.0000079	07/07/11	200	0.0000079	05/20/12	100	0.0000790
09/01/10	200	0.0000063	07/16/11	200	0.0000079	05/24/12	100	0.0000270
09/12/10	200	0.0000065	08/08/11	200	0.0000045	06/08/12	200	0.0000040
09/21/10	200	0.0000079	08/09/11	200	0.0000020	06/14/12	200	0.0000079
09/22/10	200	0.0000079	08/24/11	200	0.0000079	07/02/12	200	0.0000079

Method 5 Acetone Residuals History

DATE	VOL (ml)	RESIDUAL (g/ml)	DATE	VOL (ml)	RESIDUAL (g/ml)	DATE	VOL (ml)	RESIDUAL (g/ml)
07/05/12	200	0.0000079	03/05/13	200	0.0000045			
07/20/12	200	0.0000048	03/06/13	200	0.0000030			
07/20/12	200	0.0000050	03/18/13	200	0.0000030			
07/21/12	200	0.0000050	03/18/13	250	0.0000060			
08/01/12	200	0.0000079	03/22/13	250	0.0000016			
08/09/12	100	0.0000060	03/25/13	250	0.0000079			
08/09/12	200	0.0000000	03/28/13	250	0.0000040			
08/10/12	200	0.0000000	03/29/13	200	0.0000050			
08/17/12	400	0.0000018	04/18/13	200	0.0000055			
08/24/12	150	0.0000013	04/10/13	215	0.0000047			
08/26/12	200	0.0000060	04/25/13	200	0.0000070			
09/04/12	200	0.0000045	05/02/13	250	0.0000079			
09/04/12	200	0.0000079						
09/06/12	200	0.0000025						
09/14/12	200	0.0000050						
09/17/12	200	0.0000030						
09/17/12	200	0.0000015						
09/28/12	200	0.0000053						
10/07/12	200	0.0000000						
10/11/12	200	0.0000000						
10/13/12	200	0.0000045						
10/13/12	200	0.0000000						
10/17/12	200	0.0000000						
10/18/12	200	0.0000000						
10/20/12	200	0.0000055						
10/23/12	200	0.0000010						
11/06/12	200	0.0000020						
11/08/12	200	0.0000079						
11/09/12	200	0.0000079						
11/15/12	200	0.0000050						
11/25/12	125	0.0000079						
11/28/12	275	0.0000065						
11/28/12	250	0.0000052						
11/28/12	275	0.0000065						
12/11/12	200	0.0000079						
12/13/13	200	0.0000045						
12/17/12	200	0.0000040						
12/31/13	200	0.0000025						
01/04/13	250	0.0000044						
01/11/13	200	0.0000045						
01/16/13	200	0.0000040						
01/18/13	200	0.0000079						
01/24/13	350	0.0000077						
02/01/13	200	0.0000079						
02/04/13	200	0.0000045						
02/08/13	275	0.0000079						
02/13/13	250	0.0000040						
02/22/13	250	0.0000056						
02/28/13	200	0.0000070						



Gelman Laboratory

New! Pallflex® Filters

Wide range of filters uniquely suited for a broad range of air monitoring applications.

- Can be used for high temperature and hot gas air monitoring applications.

Applications

Tissuquartz™ Filters

- Heat treated for reduction of trace organics and superior chemical purity.
- High temperature use for analysis of acidic gases and stack sampling aerosols.
- High flow rate and filtration efficiency.
- Ultra-pure soft water processing to reduce residual ion content. Contact us for typical values.

Emfab™ Filters

- Withstands folding for weighing and transport.
- Every filter flushed with DI water to remove any water-soluble residue.
- Low air resistance for use in critical aerosol sampling tests such as diesel exhaust.

Complementary Products

For other products related to these applications see:

In-line Holders.....172-174
Open-face Holders.....175

Fiberfilm™ Filters

- Fiberfilm is well suited for a broad range of air sampling applications.
- Moisture variations in air or gases during air sampling will not cause chemical reactions on the filter.
- Heat-treated (HT) version available for reduction of trace organics.

Description	Tissuquartz	Emfab	Fiberfilm
Filter Media	Pure quartz, no binder	Borosilicate microfibers reinforced with woven glass cloth and bonded with PTFE	Heat resistant borosilicate glass fiber coated with fluorocarbon (TFE)
Diameter	25 - 90 mm (and 8 x 10 in.)	12 - 142 mm (and 8 x 10 in.)	25 - 100 mm (and 8 x 10 in.)
Typical Thickness	432 µm (17 mils)	178 µm (7 mils)	203 µm (8 mils)
Typical Filter Weight	5.8 mg/cm²	5.0 mg/cm²	3.4 mg/cm²
Typical Water Flow Rate at 0.35 bar (5 psi)	220 mL/min/cm²	32 mL/min/cm²	220 mL/min/cm²
Typical Air Flow Rate at 0.7 bar (10 psi)	73 L/min/cm²	68 L/min/cm²	180 L/min/cm²
Maximum Operating Temperature - Air	1093 °C (2000 °F)	260 °C (500 °F)	315.5 °C (600 °F)
Typical Aerosol Retention*	99.9%	99.9%	96.4%
pH in Boiled Water Extract	6.5 - 7.5	Not available	Not available

*Following ASTM D 2986-71 0.3 µm (DOP) at 32 L/min/100 cm² filter media

Filter Specifications

Air Compliance Testing, Inc.

APEX INSTRUMENTS REFERENCE METER VERIFICATION

USING WET-TEST METER #11AE6

2-POINT ENGLISH UNITS

Calibration Meter Information

WTM Model#	A120
WTM Serial#	11AE6
WTM Gamma	0.9999
Original 15pt Gamma	0.9977

Calibration Conditions

Factors/Conversions			
Std Temp	52.8	°R	
Std Press	29.92	in Hg	
K _t	17.647	°R/in Hg	

Dry Gas Meter

Calibration Data

Run Time	DGM Input Pressure (P_m) in H ₂ O	Metering Console		Calibration Meter		Results	
		Elapsed (e) min	Volume Initial (V_m) cubic feet	Volume Final (V_m) cubic feet	Volume Initial (V_m) cubic feet	Volume Final (V_m) cubic feet	Dry Gas Meter Calibration Factor Current (Y)
6.00	3.6	82.459	88.371	5.912	71.6	71.6	0.986

Run Time	DGM Input Pressure (P_m) in H ₂ O	Metering Console		Calibration Meter		Results	
		Elapsed (e) min	Volume Initial (V_m) cubic feet	Volume Final (V_m) cubic feet	Volume Initial (V_m) cubic feet	Volume Final (V_m) cubic feet	Dry Gas Meter Calibration Factor Current (Y)
10.00	-2.1	88.371	93.937	5.566	71.6	71.6	0.959

certify that the above Dry Gas Meter was calibrated in accordance with USEPA Methods, CFR 40 Part 60, App A, Method 5, Paragraph 7.1.2.2, using the Precision Wet Test Meter # 11AE6, which in turn was calibrated using the American Bell Prover # 3755, certificate # F107, which is traceable to the National Bureau of Standards (N.I.S.T.).

Signature Date 2/25/13

**APPEX INSTRUMENTS REFERENCE METER CALIBRATION
USING WET-TEST METER #11AE5**

16-POINT ENGLISH UNITS

Calibration Meter Information			
Wet Test Meter Model #	AL-20		
Wet Test Meter Serial #	11AE5		
Wet Test Meter Gamma	0.9890		

Calibration Conditions						
Date	Time	16-Apr-09	2:15			
Barometric Pressure		28.9	in Hg			
Calibration Technician		EW				
DGM Serial Number		S-120-15-12377				


Calibration Data											
Run Time	Elapsed	Dry Gas Meter	Calibration Meter			Calibration Factor			Dry Gas Meter		
			Initial	Final	Volume	Initial	Final	Volume	Initial	Final	Flownote
6.00	-4.2	Wet Test Meter	511.684	517.778	6.0144	86.0	86.0	904.035	909.850	5.815	0.9858
6.00	-4.2	Wet Test Meter	517.728	523.804	6.076	86.0	87.8	909.850	915.695	5.845	0.9869
6.00	-4.2	Wet Test Meter	523.804	529.895	6.081	87.8	87.8	915.895	921.540	5.845	0.9872
											Averages 0.9861
7.00	-3.3	Wet Test Meter	529.885	535.485	5.600	87.8	89.6	921.540	926.930	5.390	0.9980
7.00	-3.3	Wet Test Meter	535.485	541.071	5.596	89.6	89.6	926.830	932.300	5.370	0.9984
7.00	-3.3	Wet Test Meter	541.071	546.659	5.598	89.6	89.6	932.300	937.670	5.370	0.9980
											Averages 0.9966
10.00	-2.5	Wet Test Meter	546.659	552.300	5.641	89.6	89.6	937.670	943.120	5.450	0.9999
10.00	-2.5	Wet Test Meter	552.300	557.928	5.628	89.6	89.6	943.120	948.545	5.425	0.9982
10.00	-2.5	Wet Test Meter	557.928	563.595	5.637	89.6	89.6	948.545	953.980	5.435	0.9984
											Averages 0.9992
15.00	-2.3	Wet Test Meter	493.460	499.555	6.095	86.0	86.0	886.310	892.255	5.825	1.0014
15.00	-2.3	Wet Test Meter	499.555	505.615	6.060	86.0	86.0	892.255	898.140	5.885	1.0004
15.00	-2.3	Wet Test Meter	505.615	511.684	6.068	86.0	86.0	898.140	904.035	5.895	1.0006
											Averages 0.9998
											Overall Average Y 0.9977

Note: For Calibration Factor 'Y', the ratio of the reading of the calibration meter to the dry gas meter, acceptable tolerance of individual values from the average is ± 0.02 .

I certify that the above Dry Gas Meter was calibrated in accordance with USFPA Methods, CFR 40 Part 60, using the Precision Wet Test Meter # 11AE5, which in turn was calibrated using the American Bell Prover # 3705, certificate # F-107, which is traceable to the National Bureau of Standards (N.B.S.).

Signature *[Signature]*

Date *[Date]*



Industrial Environmental Monitoring Instruments, Inc.

7410 Worthington-Galena Road
Worthington, Ohio 43085
Phone: (614) 436-4933
Fax: (614) 436-9144

Website: www.iерентс.com

Temperature Calibrator/Termometer Certificate

Model: Omega CL25
Serial #: T-286993

Date: 5/10/2013
Technition Sam Shultz

Thermometer Calibration

Type K, J & T multiple points over Full Scale Results: +/- .7 F
Unit Accuracy: +/- 1.0 F

Calibrator Mode Calibration

Type K, J & T multiple points over Full Scale Results: +/- .5 F
Unit Accuracy: +/- 1.0 F

Thermocouple Test


Lab Std.	Actual		Lab Std.	Actual
32.0 F	31.6 F	Type K	140.0 F	139.0 F
80.0 F	79.2 F		275.0 F	274.1 F

NIST Reference Standards

Agilent 34401A Multimeter sn. MY41002352 Calibration Due 12/1/2013
Analogic DigiCalc II Calibration Due: 14/22/2012
Hart 9103 Temperature Well Calibration Due: 4/27/2012

Calibration Standards are NIST Traceable
Instrument must be calibrated and operated according to manufacturers specifications

Specializing in Safety and Environmental Test Equipment and Supplies.



Industrial Environmental Monitoring Instruments, Inc.

7410 Worthington-Galena Road
Worthington, Ohio 43085
Phone: (614) 436-4933
Fax: (614) 436-9144

Website: www.ierents.com

Temperature Calibrator/Termometer Certificate

Model: Omega CL3512A
Serial #: 11000091

Date: 7/17/2012
Technition Sam Shults

Thermometer Calibration

Type K, J, E & T multiple points over Full Scale Results: +/- 1.0 F
Unit Accuracy: +/- 1.8 F

Calibrator Mode Calibration


Type K, J,E & T multiple points over Full Scale Results: +/- 1.0 F
Unit Accuracy: +/- 1.8 F

NIST Reference Standards

Agilent 34401A Multimeter sn. MY41002352 Calibration Due 12/1/2013
Analogic DigiCalc II Calibration Due: 17/13/2013
Hart 9103 Temperature Well Calibration Due: 5/16/2013

Calibration Standards are NIST Traceable
Instrument must be calibrated and operated according to manufacturers specifications

Specializing in Safety and Environmental Test Equipment and Supplies.



Industrial Environmental Monitoring Instruments, Inc.

7410 Worthington-Galena Road
Worthington, Ohio 43085
Phone: (614) 436-4933
Fax: (614) 436-9144

Website: www.jerents.com

Temperature Calibrator/Termometer Certificate

Model: Omega CL3512A
Serial #: 11000622

Date: 9/14/2012
Technition Sam Shults

Thermometer Calibration

Type K, J & T multiple points over Full Scale Results: +/- .3 F
Unit Accuracy: +/- 2.0 F

Calibrator Mode Calibration

Type K, J & T multiple points over Full Scale Results: +/- 1.0 F
Unit Accuracy: +/- 3.0 F

NIST Reference Standards


Agilent 34401A Multimeter sn. MY41002352 Calibration Due 12/1/2013
Analogic DigiCalc II Calibration Due: 7/13/2013

Calibration Standards are NIST Traceable
Instrument must be calibrated and operated according to manufacturers specifications

Specializing in Safety and Environmental Test Equipment and Supplies.



Certificate of Calibration



CERT# L1152-1 Calibration

CUSTOMER:

AIR COMPLIANCE TESTING, INC.
 10060 BRECKSVILLE ROAD
 BRECKSVILLE, OH 44141

ASSET NUMBER:	B26978	PERFORMED ON:	01 Feb 2013
OWNER ASSET #:	BAL-005	DATE DUE:	01 Feb 2014
UNIT UNDER TEST:	A&D EK-1200G BALANCE, 1200G X 0.1G	TEST RESULT:	PASS
SERIAL NUMBER:	J8084811	DATA TYPE:	FOUND-LEFT
LOCATION:		TEMP / HUMIDITY:	68.0 °F / 32 %RH
PROCEDURE NAME:	NIST HANDBOOK 44,g,2 STDS	SERVICE SITE:	ON-SITE
		CALIBRATED BY:	ANGELO COLOMBO
		APPROVED BY:	

Unless Otherwise Noted: OCS Technologies, Inc. certifies that the above listed instrument has been tested with a 2:1 Test Uncertainty Ratio (TUR) using standards that are traceable to the International System of Units (SI) through the National Institute of Standards & Technology (NIST), or through NIST accepted Intrinsic standards of measurement, or through another National Metrology Institute (NMI). The item tested meets or exceeds all specifications as stated in the referenced procedure solely at the time of calibration. Measurement uncertainty if reported has been calculated at k=2 providing a 95% confidence interval and has been excluded from the Pass/Fail Result above. OCS is ISO/IEC 17025 accredited by the Laboratory Accreditation Bureau. Calibration performed in accordance with ISO 17025:2005 and ISO 10012:2003. This report may only be reproduced in full. Temperature and Humidity for on-site work may be reported above as the mean of high and low values recorded for all items on the day of service. If the data type is FOUNDLEFT then the As Found and As Left data are the same.

Remarks:

Standards Used

Asset	Traceable Through	Description	Cal Date	Cal Due Date
B947	CERT#1867044	RICE LAKE 1MG - 100G CLASS 1 WEIGHT KIT (210.886G TOTAL)	17 May 2012	17 May 2013
B947A	CERT#216195	RICE LAKE 50G - 5KG CLASS 1 WEIGHT KIT (10950G TOTAL)	21 May 2012	21 May 2013

Test Results

Test Description	Range	True Value	Test Result	Lower Limit	Upper Limit	%TOL	Status
TESTED IN ACCORDANCE WITH NIST Handbook 44-Current Rev							
Section 2.20 Paragraphs N1.1, N1.3, N1.11, N.2,N.3.2							
T.N.5 & Tables 4, T.11, 7A as Applicable.							

REPEATABILITY VERIFICATION:

Result of Operator Evaluation Pass

SHIFT TEST VERIFICATION:

Result of Operator Evaluation Pass

LINEARITY:

1.00 g	1.00	1.0	0.9	1.1	g	0	Pass
10.00 g	10.00	10.0	9.9	10.1	g	0	Pass
100.00 g	100.00	100.0	99.8	100.2	g	0	Pass
500.00 g	500.00	499.9	499.5	500.5	g	20	Pass
1000.00 g	1000.00	1000.0	999.5	1000.5	g	0	Pass

Uncertainty of Measurement is +/- 0.13 G



1300 East Granger Road; Brooklyn Hts, OH 44131

(800) 362-0364 www.ocscal.com

Certificate of Calibration



CERT# L1152-1 Calibration

CUSTOMER:

AIR COMPLIANCE TESTING, INC.

10060 BRECKSVILLE ROAD

BRECKSVILLE, OH 44141

ASSET NUMBER:	B26975	PERFORMED ON:	01 Feb 2013
OWNER ASSET #:	BAL-008	DATE DUE:	01 Feb 2014
UNIT UNDER TEST:	A&D EK-1200I BALANCE, 1200G X 0.1G	TEST RESULT:	PASS
SERIAL NUMBER:	EP1861727	DATA TYPE:	FOUND-LEFT
LOCATION:		TEMP / HUMIDITY:	68.0 °F / 32 %RH
PROCEDURE NAME:	NIST HANDBOOK 44,g,1 STD	SERVICE SITE:	ON-SITE
		CALIBRATED BY:	ANGELO COLOMBO
		APPROVED BY:	

Unless Otherwise Noted: OCS Technologies, Inc. certifies that the above listed instrument has been tested with a 2:1 Test Uncertainty Ratio (TUR) using standards that are traceable to the International System of Units (SI) through the National Institute of Standards & Technology (NIST), or through NIST accepted intrinsic standards of measurement, or through another National Metrology Institute (NMI). This item tested meets or exceeds all specifications as stated in the referenced procedure solely at the time of calibration. Measurement uncertainty if reported has been calculated at k=2 providing a 95% confidence interval and has been excluded from the Pass/Fail Result above. OCS is ISO/IEC 17025 accredited by the Laboratory Accreditation Bureau. Calibration performed in accordance with ISO 17025:2005 and ISO 10012:2003. This report may only be reproduced in full. Temperature and Humidity for on-site work may be reported above as the mean of high and low values recorded for all items on the day of service. If the data type is FOUNDLEFT then the As Found and As Left data are the same.

Remarks:**Standards Used**

Asset	Traceable Through	Description	Cal Date	Cal Due Date
B947A	CERT#216195	RICE LAKE 50G ~ 5KG CLASS 1 WEIGHT KIT (10950G TOTAL)	21 May 2012	21 May 2013

Test Results

Test Description	Range	True Value	Test Result	Lower Limit	Upper Limit	%TOL	Status
TESTED IN ACCORDANCE WITH NIST Handbook 44-Current Rev							
Section 2.20 Paragraphs N1.1, N1.3, N1.11, N.2,N.3.2							
T.N.5 & Tables 4, T.11, 7A as Applicable.							

REPEATABILITY VERIFICATION:

Result of Operator Evaluation Pass

SHIFT TEST VERIFICATION:

Result of Operator Evaluation Pass

LINEARITY:


100.00 g	100.00	100.0	99.8	100.2	g	0	Pass
200.00 g	200.00	200.0	199.8	200.2	g	0	Pass
500.00 g	500.00	500.1	499.5	500.5	g	20	Pass

Uncertainty of Measurement is +/- 0.13 G



1300 East Granger Road: Brooklyn Hts, OH 44131
(800) 362-0364 www.ocscal.com

Certificate of Calibration



CERT# L1152-1 Calibration

CUSTOMER:

AIR COMPLIANCE TESTING, INC.
10060 BRECKSVILLE ROAD
BRECKSVILLE, OH 44141

ASSET NUMBER:	B26977	PERFORMED ON:	01 Feb 2013
OWNER ASSET #:		DATE DUE:	01 Feb 2014
UNIT UNDER TEST:	SARTORIUS 1602MP BALANCE, 160G X 0.0001G	TEST RESULT:	PASS
SERIAL NUMBER:	3004026	DATA TYPE:	AS-LEFT
LOCATION:		TEMP / HUMIDITY:	68.0 °F / 32 %RH
PROCEDURE NAME:	NIST HANDBOOK 44,g,1 STD	SERVICE SITE:	ON-SITE
		CALIBRATED BY:	ANGELO COLOMBO
		APPROVED BY:	

Unless Otherwise Noted: OCS Technologies, Inc. certifies that the above listed instrument has been tested with a 2:1 Test Uncertainty Ratio (TUR) using standards that are traceable to the International System of Units (SI) through the National Institute of Standards & Technology (NIST), or through NIST accepted intrinsic standards of measurement; or through another National Metrology Institute (NMI). The item tested meets or exceeds all specifications as stated in the referenced procedure solely at the time of calibration. Measurement uncertainty if reported has been calculated at k=2 providing a 95% confidence interval and has been excluded from the Pass/Fail Result above. OCS is ISO/IEC 17025 accredited by the Laboratory Accreditation Bureau. Calibration performed in accordance with ISO 17025:2005 and ISO 10012:2003. This report may only be reproduced in full. Temperature and Humidity for on-site work may be reported above as the mean of high and low values recorded for all items on the day of service. If the data type is POUND/LEFT then the As Found and As Left data are the same.

Remarks: AFTER ADJUSTMENTS

Standards Used

Asset	Traceable Through	Description	Cal Date	Cal Due Date
B947	CERT#1867044	RICE LAKE 1MG - 100G CLASS 1 WEIGHT KIT (210.886G TOTAL)	17 May 2012	17 May 2013

Test Results

Test Description	Range	True Value	Test Result	Lower Limit	Upper Limit	%TOL	Status
TESTED IN ACCORDANCE WITH NIST Handbook 44-Current Rev							
Section 2.20 Paragraphs N1.1, N1.3, N1.11, N.2,N.3.2							
T.N.5 & Tables 4, T.11, 7A as Applicable.							

REPEATABILITY VERIFICATION:

Result of Operator Evaluation Pass

SHIFT TEST VERIFICATION:

Result of Operator Evaluation Pass

LINEARITY:

0.00100 g	0.00100	0.0010	0.0009	0.0011	g	0	Pass
0.01000 g	0.01000	0.0100	0.0099	0.0101	g	0	Pass
0.10000 g	0.10000	0.1000	0.0999	0.1001	g	0	Pass
10.00000 g	10.00000	10.0000	9.9998	10.0002	g	0	Pass
50.00000 g	50.00000	49.9999	49.9995	50.0005	g	20	Pass

Uncertainty of Measurement is +/- 0.0002 G

Certificate # EF114D4C1082CE4D8687DE9226810F09

Date Printed: 01 Feb 2013

Form No.: 133 Rev 09/2011

Page 1 of 1



1300 East Granter Road; Brooklyn Hts. OH 44131
(800) 362-0364 www.ocscal.com

Certificate of Calibration



CERT# L1152-1 Calibration

CUSTOMER:
AIR COMPLIANCE TESTING, INC.
10060 BRECKSVILLE ROAD
BRECKSVILLE, OH 44141

ASSET NUMBER:	B26977	PERFORMED ON:	01 Feb 2013
OWNER ASSET #:		DATE DUE:	01 Feb 2013
UNIT UNDER TEST:	SARTORIUS 1602MP BALANCE, 160G X 0.0001G	TEST RESULT:	FAIL
SERIAL NUMBER:	3004026	DATA TYPE:	AS-FOUND
LOCATION:		TEMP / HUMIDITY:	68.0 °F / 32 %RH
PROCEDURE NAME:	NIST HANDBOOK 44,g,1 STD	SERVICE SITE:	ON-SITE
		CALIBRATED BY:	ANGELO COLOMBO
		APPROVED BY:	

Unless Otherwise Noted: OCS Technologies, Inc. certifies that the above listed instrument has been tested with a 2:1 Test Uncertainty Ratio (TUR) using standards that are traceable to the International System of Units (SI) through the National Institute of Standards & Technology (NIST), or through NIST accepted intrinsic standards of measurement or through another National Metrology Institute (NMI). The item tested meets or exceeds all specifications as stated in the referenced procedure solely at the time of calibration. Measurement uncertainty if reported has been calculated at k=2 providing a 95% confidence interval and has been excluded from the Pass/Fail Result above. OCS is ISO/IEC 17025 accredited by the Laboratory Accreditation Bureau. Calibration performed in accordance with ISO 17025:2005 and ISO 10012:2003. This report may only be reproduced in full. Temperature and Humidity for on-site work may be reported above as the mean of high and low values recorded for all items on the day of service. If the data type is FOUNDLEFT then the As Found and As Left data are the same.

Remarks: BEFORE ADJUSTMENTS

Standards Used

Asset	Traceable Through	Description	Cal Date	Cal Due Date
B947	CERT#1867044	RICE LAKE 1MG - 100G CLASS 1 WEIGHT KIT (210.886G TOTAL)	17 May 2012	17 May 2013

Test Results

Test Description	Range	True Value	Test Result	Lower Limit	Upper Limit	%TOL	Status
TESTED IN ACCORDANCE WITH NIST Handbook 44-Current Rev							
Section 2.20 Paragraphs N1.1, N1.3, N1.11, N.2,N.3.2							
T.N.5 & Tables 4, T.11, 7A as Applicable.							

REPEATABILITY VERIFICATION:

Result of Operator Evaluation Pass

SHIFT TEST VERIFICATION:

Result of Operator Evaluation Pass

LINEARITY:

0.00100 g	0.00100	0.0010	0.0009	0.0011	g	0	Pass
0.01000 g	0.01000	0.0100	0.0099	0.0101	g	0	Pass
0.10000 g	0.10000	0.1000	0.0999	0.1001	g	0	Pass
10.00000 g	10.00000	10.0001	9.9998	10.0002	g	50	Pass
50.00000 g	50.00000	49.9965	49.9995	50.0005	g	700	Fail

Uncertainty of Measurement is +/- 0.0002 G

Astronomical Applications Dept.
 U.S. Naval Observatory
 Washington, DC 20392-5420
 COSHOCTON, OHIO


 ° °
 W 81 50, N40 16
 Altitude and Azimuth of the Sun
 May 22, 2013


Eastern Daylight Time

Altitude	Azimuth (E of N)
h m	°
05:00	-11.2
05:10	-9.7
05:20	-8.2
05:30	-6.6
05:40	-5.0
05:50	-3.4
06:00	-1.7
06:10	0.4
06:20	2.0
06:30	3.6
06:40	5.3
06:50	7.0
07:00	8.8
07:10	10.6
07:20	12.4
07:30	14.2
07:40	16.1
07:50	17.9
08:00	19.8
08:10	21.7
08:20	23.5
08:30	25.4
08:40	27.3
08:50	29.2
09:00	31.1
09:10	33.1
09:20	35.0
09:30	36.9
09:40	38.8
09:50	40.7
10:00	42.5
10:10	44.4
10:20	46.3
10:30	48.1
10:40	50.0
10:50	51.8
11:00	53.6
11:10	55.3
11:20	57.0
11:30	58.7
11:40	60.3
11:50	61.9
12:00	63.3
12:10	64.7
12:20	66.0
12:30	67.1
12:40	68.1

12:50	69.0	157.3
13:00	69.6	163.7
13:10	70.0	170.3
13:20	70.2	177.2
13:30	70.2	184.1
13:40	70.0	191.0
13:50	69.5	197.6
14:00	68.8	203.9
14:10	68.0	209.8
14:20	66.9	215.3
14:30	65.8	220.3
14:40	64.5	225.0
14:50	63.1	229.2
15:00	61.6	233.1
15:10	60.0	236.7
15:20	58.4	240.0
15:30	56.7	243.1
15:40	55.0	245.9
15:50	53.3	248.5
16:00	51.5	251.0
16:10	49.7	253.3
16:20	47.8	255.5
16:30	46.0	257.6
16:40	44.1	259.6
16:50	42.2	261.5
17:00	40.3	263.4
17:10	38.4	265.1
17:20	36.5	266.9
17:30	34.6	268.5
17:40	32.7	270.2
17:50	30.8	271.8
18:00	28.9	273.3
18:10	27.0	274.9
18:20	25.1	276.4
18:30	23.2	277.9
18:40	21.4	279.4
18:50	19.5	280.9
19:00	17.6	282.4
19:10	15.8	283.9
19:20	13.9	285.4
19:30	12.1	286.9
19:40	10.3	288.4
19:50	8.5	289.9
20:00	6.8	291.4
20:10	5.0	293.0
20:20	3.3	294.5
20:30	1.7	296.1
20:40	0.2	297.7
20:50	-2.0	299.3
21:00	-3.6	301.0
21:10	-5.2	302.7
21:20	-6.8	304.4
21:30	-8.4	306.2
21:40	-9.9	308.0
21:50	-11.4	309.8

[Back to form](#)





VISIBLE EMISSIONS EVALUATOR

Aleksandr Spektor

This is to certify that the above named observer has met the specifications of Federal Reference Method 9 and is qualified as a visible emissions evaluator. Maximum deviation on white and black smoke did not exceed 7.5% opacity and no single error exceeding 15% opacity was incurred during the certification test conducted by Eastern Technical Associates, Inc. of Raleigh, N.C.

This certificate is valid for six months from date of issue.

412193

Certificate Number

SPE603125

Student ID Number

4/10/2013

Date of Certification

Pittsburgh, PA

Location

10/10/2013

Certification Expiration Date

PGHS13

Last Lecture

Marty Hughes
Director of Training

**Superior Quality
Emission Testing.**

**Valid Results
Guaranteed.**



Cleveland, Ohio and Gainesville, Florida
1-800-EPA-AIR1 www.aircomp.com

March 26, 2013

Kim Reibold
Ohio EPA, SEDO DAPC
2195 Front St
Logan, OH 43138

Dear Kim:

This letter accompanies the attached Intent to Test (ITT) Notification Form that we have completed on the behalf of our client, Clow Water Systems Company, located in Coshocton, OH. The purpose of this emissions testing project is to satisfy the emission testing requirements pursuant to Appendix 3 Section III of the McWane, Inc. Consent Decree and the testing requirements outlined in 40 CFR Part 63, Subpart ZZZZZ.

The scope of this testing project is to measure Total Front-Half Particulate Matter (PM) using EPA Method 5 from the Cupola Emission System (P901) at the Scrubber System Exhaust Stack during Maximum Achievable Operations.

Please note that this scope of work also includes Visible Emissions using EPA Method 9 from the Cupola Emission System (P901) at the Shroud Area. This testing will be completed simultaneously with the aforementioned EPA Method 5 testing.

As is written in this ITT, a date of **May 2, 2013** has been selected as the test day with testing equipment set-up occurring on the day before. Typically Run No. 1's start time is targeted for 7:30 am. If this start time changes, Air Compliance Testing or facility personnel will contact you in advance to notify you of the new starting time.

If you have any questions regarding the scope of this testing project, the scheduled test day, or the process(es) being tested, please don't hesitate to call Heather Rainwater of Clow Water Systems Company at 740-622-6651, or myself, and we would be happy to assist you in any way possible.

Thank you again for your careful consideration, and I am looking forward to working with you on this upcoming compliance testing project.

Sincerely,

Air Compliance Testing, Inc.



By: _____

Tyson E. Houchin
Operations Director

cc: Heather Rainwater, Clow Water Systems Company

INTENT TO TEST NOTIFICATION (One Emissions Unit Per Sheet)

Agency Use Only	
Date Received	
Assigned	

Facility Premise No. 0516010006 Proposed Test Date May 2, 2013
 Emissions Unit PTI No. P0105615 Proposed Start Time 7:30 am
 SCC Number 30400301

A. Facility Contact Information:

Name Clow Water Systems Company
 Address PO Box 6001, Coshocton OH 43812-6001
 Contact Person Heather Rainwater
 Telephone (O) 740-291-1087 (Cell) 740-502-0577
 E-Mail heather.rainwater@clowwater.com

B. Test Location Information

Name Clow Water Systems Co.
 Contact Person Heather Rainwater

C. Test Plan and Emissions Unit Information Table: List the applicable information under each respective column heading.

Emission Unit	StackID	Test Location	Control Equipment	Monitoring Equipment	Pollutant(s) to be Tested	EPA Test Method	Number of Sampling Points	Total Time per Test Run (min)	Number of Sampling Runs
Cupola Emission System (P901)	A	Scrubber System Exhaust Stack	Scrubber System	Pressure Drop and Water Flow Rates	Volumetric Flow Rate	1, 2, 3, and 4	24	60	3
	B	Shroud Area	N/A	N/A	PM	5	24	60	3
Flange / Fabrication Building	C	Central Roof Vent	N/A	N/A	VES	9	1	60	3 (if possible)
					VES	22	24	60	3 (if possible)

Are any modifications or alternatives as spelled within the test methods being proposed? Yes No If "no", then no modifications or alternatives, however minor, will be accepted. If yes, list each test method and section being modified, and attach a detailed modification description and justification.

Source is testing to comply with (check all that apply): McWane Consent Decree Appendix 3 Section III and 40 CFR Part 63, Subpart ZZZZZZ.

D. What is the maximum rated capacity or throughput of the emissions unit given its permit-to-install or permit-to-operate? 85 Tons / hour

Has the facility scheduled production or throughput so that the emissions unit can be operated at the maximum capacity given its permit-to-install or permit-to-operate during the test? Yes No

Specify how the operating rate will be demonstrated during the testing: Normal facility process and recordkeeping procedures

Sampling Location(s): Inlet Outlet Simultaneous

Fuel Sampling: Coal-Proximate Ultimate Other If other specify: N/A

Emission Rate to be calculated using: F-Factor Ultimate Coal Analysis Other If other specify: As dictated by EPA Method 5 calculation algorithms in terms of lb/hr and lb/ton

Has any maintenance or parts replacement been performed on the emissions unit or the control equipment within the last year? Yes No 6/2012: Replacement in kind of Ring-Jet tower shell. Ring Jet demister. 12/2012: Replaced Final Exhaust Stack

(Note: Some maintenance, such as installing new filter bags in a baghouse, or replacing the activated carbon in an adsorber, may disqualify the emissions unit from a performance test until a sufficient amount of time has elapsed to ensure a test which will be representative of normal operations.)

- E. Sample Train Calibration: All affected measuring and monitoring equipment should be calibrated within 60 days of the scheduled testing.
- APPENDIX - Calibrations & Certifications - Page 36 of 37

THE FOLLOWING ADDITIONAL INFORMATION SHALL BE SUBMITTED AS ATTACHMENTS:

F. Sample Train Information:

1. A schematic diagram of each sampling train.
 2. The type or types of capture media to be used to collect each gas stream pollutant. (Include filter specification sheets)
 3. Sample tube type, (e.g., glass, teflon, stainless steel, etc.)
 4. Probe cleaning method and solvent to be used, if applicable.
1. See attached Site-Specific Test Plan.
2. Type or types of capture media: M3 - Fyrite: The Fyrite analyzer utilizes a chromium chloride-zinc chloride-hydrochloric acid solution for O₂ absorption and a potassium hydroxide solution for CO₂ absorption. M4: Samples are condensed in H₂O and adsorbed onto Silica Gel. M5: Samples are collected on Glass Filter (filter specification sheets attached). M9 / 22: N/A
3. Sample tube type: M3 - Fyrite: borosilicate glass or stainless steel with connecting borosilicate glassware. M4: borosilicate glass or stainless steel with connecting borosilicate glassware. M5: Probe liner is borosilicate glass or stainless steel with a borosilicate glass or stainless steel nozzle.
4. Probe cleaning method and solvent to be used: M3 - Fyrite: N/A M4: N/A M5: Reagent Grade Acetone. M9 / 22: N/A

G. Laboratory Analysis:

A description of the laboratory analysis methods to be used to determine the concentration of each pollutant.
M3 - Fyrite: A Fyrite analyzer will be used for the analysis in a manner consistent with manufacturer's specifications. M4: A gas sample is extracted at a constant rate (or isokinetically in conjunction with other methods) from the source; moisture is removed from the sample stream and determined either volumetrically or gravimetrically. M5: The analysis for Particulate Matter (PM) will be a gravimetric analysis. M9 / 22: N/A

H. Description of Operations:

- A description of any operation, process, or activity that could vent exhaust gases to the stack being tested. This shall include the description and feed rate of all materials capable of producing pollutant emissions used in each separate operation. Maximum process weight rate, or coating rate, and parameters such as line speed, VOC content etc. should be specifically documented with calculations to confirm worst case scenario emissions.

Note 1: All compliance demonstration testing shall be performed at maximum rate capacity as specified by the equipment manufacturer or at the maximum rate actually used in the emissions unit operation, whichever is greater, or at any other rate as agreed upon with Ohio EPA.

Note 2: If the emissions unit is not operated at maximum capacity, or as close as possible thereto, the emissions unit might be derated to the production capacity achieved during the test.

The only operations, processes, and/or activities that could vent exhaust gases to the test stack are those described above in this document.

I. Stack and Vent Description:

- A dimensional sketch or sketches showing the plan and elevation view of the entire ducting and stack arrangement. The sketch should include the relative position of all processes or operations venting to the stack or vent to be tested. It should also include the position of the ports relative to the nearest upstream and downstream gas flow disturbance or duct dimensional change. The sketches should include the relative position, type, and manufacturer's claimed efficiency of all gas cleaning equipment.
- A cross sectional dimensional sketch of the stack or duct at the sampling ports, showing the position of sampling points. In case of a rectangular duct, show division of duct into equal areas.
- For Fugitive emissions testing, a sketch illustrating the specific emissions points to be observed must be included.

See attachments to this ITT.

J. Safety:

Describe all possible safety hazards including such items as the presence of toxic fumes, high noise levels, areas where eye protection is required, etc. Note: Conditions considered unsafe at the time of the test will cause postponement.

The Plant requires the use of safety glasses, safety shoes, hard hats, and hearing protection (in designated areas). At this time, and to the best of our belief and knowledge, there are no toxic fumes or other hazards expected to be on site at this facility that would cause you to formally prepare for your exposure to them. It is our recommendation however, to consult plant personnel regarding its safety policies before accessing the production areas on this site. Air Compliance Testing personnel will be required to wear safety shoes and safety glasses at all times while on site at the facility to comply with our own company policy.