UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
Region 3 Environmental Science Center
Office of Analytical Services and Quality Assurance
701 Mapes Road
Fort Meade, Maryland 20755-5350

Final Analytical Report

Site Name.....	Metal Bank of America - State Road Site
Sample Collection Date(s).....	04/27/11 10:25- 04/27/11 11:45
Contact.....	Mike Towle
Report Date.....	07/01/11 14:51
Project #.....	DAS R33687
Work Order.....	1104020

Analyses included in this report:

PCB Congeners

Approved for Release

Susan C. Warner

OASQA Representative

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

Report Narrative

This note refers to the Dry Weight PD105 determination:
Due to the inability of the samples to achieve constant dry weight after 3 sequential attempts at drying for >16 hours at 105 degrees C. each, the values for dry weight are only an estimate. The calculations for dry weight use the averages for the weights of the dish and sample after each drying. This follows the specification for constant weight given in SOP R3 QA-105, Total Dissolved Solids TDS, Section 11.2.7.

Sample 1104020-04 (SD-05) was received broken. No analysis was done for this sample.

The notes below refer to the PCB Congener analysis
Sample 1104020-04 (SD-05) was received broken. No analysis was done for this sample.

Sample 1104020-02 was not a sediment sample – it was mostly water with a fluffy, mucous solid floating in it. Gene Nance (Tech Law) requested that the sample be analyzed as a solid by either filtering or centrifuging. The full aliquot of sample was transferred into 40 mL vials and centrifuged for 30 minutes. The water was decanted off and the solid portion of the sample was transferred to a beaker and weighed. This centrifuged solid measured 100% water using SW846 Method 9001. **This sample was noted as having 0.1 % solids and results are reported on a dry weight basis.**

All samples, except 1104020-06, were concentrated to 100 µL and screened for PCBs on a GC/ECD. Screening did indicate that all the samples had PCBs present. All samples, except 1104020-06, were run at a 50X dilution.

The MS/MSD samples were not run, as the spike was too dilute to obtain any spiking information. All MS/MSD samples were qualified "TD" for too dilute. All blank spike results were within quality control criteria.

Samples that required 50X dilution had to be refortified with labeled compounds in order to quantify results. Adding additional labeled compounds voids quantitation by isotope dilution. All results for 1104020-01, -02, -03, -05, -07, -08, -09, and -10 are biased low.

Results for 1104020-09 and -10 were very low and were rerun at the 5 X dilution. Matrix interferences with the labeled compounds precluded using these results. Visual review of the chromatograms did not indicate additional PCBs present.

If a result was qualified "B" due to blank contamination, it was not included in the calculation of Total Congeners or Total PCBs.

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

ANALYTICAL REPORT FOR SAMPLES

Station ID	Laboratory ID	Matrix	Date Sampled	Date Received
SD-01	1104020-01	Sediment	4/27/11 10:28	4/29/11 10:55
SD-02	1104020-02	Sediment	4/27/11 10:54	4/29/11 10:55
SD-03	1104020-03	Sediment	4/27/11 11:08	4/29/11 10:55
WW-05	1104020-05	Wastewater	4/27/11 10:52	4/29/11 10:55
FB-01	1104020-06	Wastewater	4/27/11 10:42	4/29/11 10:55
WW-01	1104020-07	Wastewater	4/27/11 10:25	4/29/11 10:55
WW-02	1104020-08	Wastewater	4/27/11 10:50	4/29/11 10:55
WW-03	1104020-09	Wastewater	4/27/11 11:06	4/29/11 10:55
WW-04	1104020-10	Wastewater	4/27/11 11:45	4/29/11 10:55

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

Page 1 of 1

USEPA CLP Generic COC (LAB COPY)
DateShipped: 4/28/2011
CarrierName: FedEx
AirbillNo: 7970 4192 8753

CHAIN OF CUSTODY RECORD
DAS Case R33687
Project Code:
Cooler #:

No: 3-042811-171101-0003
Lab: OASQA
Lab Contact: Kevin Martin
Lab Phone: 410-305-3031

Sample #	Matrix/Sampler	Coll. Method	Analysis/Turnaround	Tag/Preservative/Bottles	Station Location	Collected	For Lab Use Only
R33687-01	Sediment/ (b) (4)	Grab	PCB_C(14)	1001 (4 C) (1)	SD-01	04/27/2011 10:28	1104020-01
R33687-02	Sediment/ (b) (4)	Grab	PCB_C(14)	1003 (4 C) (1)	SD-02	04/27/2011 10:54	1104020-02
R33687-03	Sediment/ (b) (4)	Grab	PCB_C(14)	1005 (4 C) (1)	SD-03	04/27/2011 11:08	1104020-03
R33687-05	Sediment/ (b) (4)	Grab	PCB_C(14)	1009 (4 C) (1)	SD-05	04/27/2011 10:56	1104020-04
R33687-11	Waste Water/ (b) (4)	Grab	PCB_C(14), PCB_C(14)	1035 (4 C), 1036 (4 C) (2)	WW-05	04/27/2011 10:52	1104020-05
R33687-13	Blank/ (b) (4)	Grab	PCB_C(14), PCB_C(14)	1039 (4 C), 1040 (4 C) (2)	FB-01	04/27/2011 10:42	1104020-06

Special Instructions: 3°C PLK 4/29/11

Shipment for Case Complete? Y
Samples Transferred From Chain of Custody #

Analysis Key: PCB_C=PCBs (CONGENERS)

Items/Reason	Relinquished by	Date	Received by	Date	Time	Items/Reason	Relinquished By	Date	Received by	Date	Time
Shipped to lab	(b) (4)	4/28/11	(b) (4)	4/29/11	10:55						

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

Page 1 of 1

USEPA CLP Generic COC (LAB COPY)
DateShipped: 4/28/2011
CarrierName: FedEx
AirbillNo: 7970 4191 4378

CHAIN OF CUSTODY RECORD
DAS Case R33687
Project Code:
Cooler #:

No: 3-042011-125656-0002
Lab: OASQA
Lab Contact: Kevin Martin
Lab Phone: 410-305-3031

Sample #	Matrix/Sampler	Coll. Method	Analysis/Turnaround	Tag/Preservative/Bottles	Station Location	Collected	For Lab Use Only
R33687-07	Waste Water/ (b) (4)	Grab	PCB_C(14), PCB_C(14)	1027 (4 C), 1028 (4 C) (2)	WW-01	04/27/2011 10:25	1104020-07
R33687-08	Waste Water/ (b) (4)	Grab	PCB_C(14), PCB_C(14)	1029 (4 C), 1030 (4 C) (2)	WW-02	04/27/2011 10:50	1104020-08
R33687-09	Waste Water/ (b) (4)	Grab	PCB_C(14), PCB_C(14)	1031 (4 C), 1032 (4 C) (2)	WW-03	04/27/2011 11:06	1104020-09
R33687-10	Waste Water/ (b) (4)	Grab	PCB_C(14), PCB_C(14), PCB_C(14), PCB_C(14), PCB_C(14), PCB_C(14)	1033 (4 C), 1034 (4 C), 1041 (4 C), 1042 (4 C), 1043 (4 C), 1044 (4 C) (6)	WW-04	04/27/2011 11:45	1104020-10

Sample(s) to be used for Lab QC: R33687-10 3°C PCK 4/29/11

Shipment for Case Complete? Y
Samples Transferred From Chain of Custody #

Analysis Key: PCB_C=PCBs (CONGENERS)

Items/Reason	Relinquished by	Date	Received by	Date	Time	Items/Reason	Relinquished By	Date	Received by	Date	Time
Shipped to lab	(b) (4)	4/28/11	(b) (4)	4/29/11	10:55						

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10404 **Sample Weight:** %Solids: 86.00 Sample Wet Weight: 20.03g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	72.0		58.1	50	06/08/11 00:04
2	**3-Monochlorobiphenyl**	11.6	J	58.1	50	06/08/11 00:04
3	**4-Monochlorobiphenyl**	33.7	J	58.1	50	06/08/11 00:04
4	**2,2'-Dichlorobiphenyl**	978		58.1	50	06/08/11 00:04
5	2,3-Dichlorobiphenyl	U		58.1	50	06/08/11 00:04
6	**2,3'-Dichlorobiphenyl**	822		58.1	50	06/08/11 00:04
7	**2,4-Dichlorobiphenyl**	41.2	J	58.1	50	06/08/11 00:04
8	**2,4'-Dichlorobiphenyl**	1360		58.1	50	06/08/11 00:04
9	**2,5-Dichlorobiphenyl**	66.2		58.1	50	06/08/11 00:04
10	**2,6-Dichlorobiphenyl**	38.9	J	58.1	50	06/08/11 00:04
11	**3,3'-Dichlorobiphenyl**	111		58.1	50	06/08/11 00:04
12/13	**3,4-DiCB/3,4'-DiCB**	271		58.1	50	06/08/11 00:04
14	3,5-Dichlorobiphenyl	U		58.1	50	06/08/11 00:04
15	**4,4'-Dichlorobiphenyl**	850		58.1	50	06/08/11 00:04
16/24	**2,2',3-TrCB/2,3,6-TrCB**	945		58.1	50	06/08/11 00:04
17	**2,2',4-Trichlorobiphenyl**	1220		58.1	50	06/08/11 00:04
18/30	**2,2',5-TrCB/2,4,6-TrCB**	2590		58.1	50	06/08/11 00:04
19	**2,2',6-Trichlorobiphenyl**	361		58.1	50	06/08/11 00:04
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	4170		58.1	50	06/08/11 00:04
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	1050		58.1	50	06/08/11 00:04
22	**2,3,4'-Trichlorobiphenyl**	1170		58.1	50	06/08/11 00:04
23	2,3,5-Trichlorobiphenyl	U		58.1	50	06/08/11 00:04
25	**2,3',4-Trichlorobiphenyl**	921		58.1	50	06/08/11 00:04
26/29	**2,3',5-TrCB/2,4,5-TrCB**	1210		58.1	50	06/08/11 00:04
27	**2,3',6-Trichlorobiphenyl**	258		58.1	50	06/08/11 00:04
31	**2,4',5-Trichlorobiphenyl**	3080		58.1	50	06/08/11 00:04
32	**2,4',6-Trichlorobiphenyl**	1380		58.1	50	06/08/11 00:04
34	2,3',5'-Trichlorobiphenyl	U		58.1	50	06/08/11 00:04
35	**3,3',4-Trichlorobiphenyl**	47.0	J	58.1	50	06/08/11 00:04
36	3,3',5-Trichlorobiphenyl	U		58.1	50	06/08/11 00:04
37	**3,4,4'-Trichlorobiphenyl**	797		58.1	50	06/08/11 00:04
38	3,4,5-Trichlorobiphenyl	U		58.1	50	06/08/11 00:04
39	3,4',5-Trichlorobiphenyl	U		58.1	50	06/08/11 00:04
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	991		58.1	50	06/08/11 00:04
42	**2,2',3,4'-Tetrachlorobiphenyl**	462		58.1	50	06/08/11 00:04
43/73	**2,2',3,5-TeCB/2,3',5',6-TeCB**	35.4	J	58.1	50	06/08/11 00:04
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	2230		58.1	50	06/08/11 00:04
45/51	**2,2',3,6-TeCB/2,2',4,6'-TeCB**	455		58.1	50	06/08/11 00:04
46	**2,2',3,6'-Tetrachlorobiphenyl**	122		58.1	50	06/08/11 00:04
48	**2,2',4,5-Tetrachlorobiphenyl**	243		58.1	50	06/08/11 00:04

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 86.00 Sample Wet Weight: 20.03g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	1580		58.1	50	06/08/11 00:04
50/53	**2,2',4,6-TeCB/2,2',5,6'-TeCB**	421		58.1	50	06/08/11 00:04
52	**2,2',5,5'-Tetrachlorobiphenyl**	2210		58.1	50	06/08/11 00:04
54	**2,2',6,6'-Tetrachlorobiphenyl**	23.8	J	58.1	50	06/08/11 00:04
55	**2,3,3',4-Tetrachlorobiphenyl**	55.1	J	58.1	50	06/08/11 00:04
56	**2,3,3',4'-Tetrachlorobiphenyl**	742		58.1	50	06/08/11 00:04
57	**2,3,3',5-Tetrachlorobiphenyl**	37.7	J	58.1	50	06/08/11 00:04
58	**2,3,3',5'-Tetrachlorobiphenyl**	61.5		58.1	50	06/08/11 00:04
59/62/75	**2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB**	192		58.1	50	06/08/11 00:04
60	**2,3,4,4'-Tetrachlorobiphenyl**	374		58.1	50	06/08/11 00:04
61/70/74/76	**TeCB-61/70/74/76**	3280		58.1	50	06/08/11 00:04
63	**2,3,4',5-Tetrachlorobiphenyl**	112		58.1	50	06/08/11 00:04
64	**2,3,4',6-Tetrachlorobiphenyl**	798		58.1	50	06/08/11 00:04
66	**2,3',4,4'-Tetrachlorobiphenyl**	1600		58.1	50	06/08/11 00:04
67	**2,3',4,5-Tetrachlorobiphenyl**	171		58.1	50	06/08/11 00:04
68	**2,3',4,5'-Tetrachlorobiphenyl**	29.6	J	58.1	50	06/08/11 00:04
72	**2,3',5,5'-Tetrachlorobiphenyl**	38.3	J	58.1	50	06/08/11 00:04
77	**3,3',4,4'-Tetrachlorobiphenyl**	185		58.1	50	06/08/11 00:04
78	3,3',4,5-Tetrachlorobiphenyl	U		58.1	50	06/08/11 00:04
79	**3,3',4,5'-Tetrachlorobiphenyl**	56.9	J	58.1	50	06/08/11 00:04
80	3,3',5,5'-Tetrachlorobiphenyl	U		58.1	50	06/08/11 00:04
81	3,4,4',5-Tetrachlorobiphenyl	U		58.1	50	06/08/11 00:04
82	**2,2',3,3',4-Pentachlorobiphenyl**	235		58.1	50	06/08/11 00:04
83/99/112	**2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB**	1460		58.1	50	06/08/11 00:04
84	**2,2',3,3',6-Pentachlorobiphenyl**	551		58.1	50	06/08/11 00:04
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	493		58.1	50	06/08/11 00:04
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	2010		58.1	50	06/08/11 00:04
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	500		58.1	50	06/08/11 00:04
89	2,2',3,4,6'-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	3460		58.1	50	06/08/11 00:04
92	**2,2',3,5,5'-Pentachlorobiphenyl**	652		58.1	50	06/08/11 00:04
93/100	**2,2',3,5,6-PeCB/2,2',4,4',6-PeCB**	47.6	J	58.1	50	06/08/11 00:04
94	**2,2',3,5,6'-Pentachlorobiphenyl**	33.1	J	58.1	50	06/08/11 00:04
95	**2,2',3,5',6-Pentachlorobiphenyl**	2290		58.1	50	06/08/11 00:04
96	**2,2',3,6,6'-Pentachlorobiphenyl**	44.1	J	58.1	50	06/08/11 00:04
98/102	**2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB**	85.3		58.1	50	06/08/11 00:04
103	**2,2',4,5',6-Pentachlorobiphenyl**	64.4		58.1	50	06/08/11 00:04

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 86.00 Sample Wet Weight: 20.03g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
104	2,2',4,6,6'-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
105	**2,3,3',4,4'-Pentachlorobiphenyl**	1120		58.1	50	06/08/11 00:04
106	2,3,3',4,5-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
107	**2,3,3',4',5-Pentachlorobiphenyl**	232		58.1	50	06/08/11 00:04
108/124	**2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB**	100		58.1	50	06/08/11 00:04
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	4130		58.1	50	06/08/11 00:04
111	2,3,3',5,5'-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
114	**2,3,4,4',5-Pentachlorobiphenyl**	71.4		58.1	50	06/08/11 00:04
118	**2,3',4,4',5-Pentachlorobiphenyl**	2900		58.1	50	06/08/11 00:04
120	2,3',4,5,5'-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
121	2,3',4,5',6-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
122	**2,3,3',4',5'-Pentachlorobiphenyl**	34.8	J	58.1	50	06/08/11 00:04
123	**2,3',4,4',5'-Pentachlorobiphenyl**	41.8	J	58.1	50	06/08/11 00:04
126	3,3',4,4',5-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
127	3,3',4,5,5'-Pentachlorobiphenyl	U		58.1	50	06/08/11 00:04
128/166	**2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB**	647		58.1	50	06/08/11 00:04
129/138/163	**HxCB-129/138/163**	5430		58.1	50	06/08/11 00:04
130	**2,2',3,3',4,5'-Hexachlorobiphenyl**	222		58.1	50	06/08/11 00:04
131	**2,2',3,3',4,6-Hexachlorobiphenyl**	38.3	J	58.1	50	06/08/11 00:04
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	1370		58.1	50	06/08/11 00:04
133	**2,2',3,3',5,5'-Hexachlorobiphenyl**	73.1		58.1	50	06/08/11 00:04
134/143	**2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB**	196		58.1	50	06/08/11 00:04
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	1750		58.1	50	06/08/11 00:04
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	868		58.1	50	06/08/11 00:04
137/164	**2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB**	477		58.1	50	06/08/11 00:04
139/140	**2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB**	66.2		58.1	50	06/08/11 00:04
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	874		58.1	50	06/08/11 00:04
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
144	**2,2',3,4,5',6-Hexachlorobiphenyl**	223	EMPC	58.1	50	06/08/11 00:04
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
146	**2,2',3,4',5,5'-Hexachlorobiphenyl**	789		58.1	50	06/08/11 00:04
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	4130		58.1	50	06/08/11 00:04
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	5140		58.1	50	06/08/11 00:04
154	**2,2',4,4',5,6'-Hexachlorobiphenyl**	69.1		58.1	50	06/08/11 00:04
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	572		58.1	50	06/08/11 00:04
158	**2,3,3',4,4',6-Hexachlorobiphenyl**	621		58.1	50	06/08/11 00:04

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 86.00 Sample Wet Weight: 20.03g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	184		58.1	50	06/08/11 00:04
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		58.1	50	06/08/11 00:04
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	1320		58.1	50	06/08/11 00:04
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	414		58.1	50	06/08/11 00:04
172	**2,2',3,3',4,5,5'-Heptachlorobiphenyl**	213		58.1	50	06/08/11 00:04
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	1530		58.1	50	06/08/11 00:04
175	**2,2',3,3',4,5',6-Heptachlorobiphenyl**	56.9	EMPC, J	58.1	50	06/08/11 00:04
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	250		58.1	50	06/08/11 00:04
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	844		58.1	50	06/08/11 00:04
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	272		58.1	50	06/08/11 00:04
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	866		58.1	50	06/08/11 00:04
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	3680		58.1	50	06/08/11 00:04
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U		58.1	50	06/08/11 00:04
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	945		58.1	50	06/08/11 00:04
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	1830		58.1	50	06/08/11 00:04
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
189	**2,3,3',4,4',5,5'-Heptachlorobiphenyl**	61.5		58.1	50	06/08/11 00:04
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	333		58.1	50	06/08/11 00:04
191	**2,3,3',4,4',5',6-Heptachlorobiphenyl**	67.9		58.1	50	06/08/11 00:04
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		58.1	50	06/08/11 00:04
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	704		58.1	50	06/08/11 00:04
195	**2,2',3,3',4,4',5,6-Octachlorobiphenyl**	244		58.1	50	06/08/11 00:04
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	340		58.1	50	06/08/11 00:04
197/200	**2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB**	148		58.1	50	06/08/11 00:04
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	828		58.1	50	06/08/11 00:04
201	**2,2',3,3',4,5',6,6'-Octachlorobiphenyl**	114		58.1	50	06/08/11 00:04
202	**2,2',3,3',5,5',6,6'-Octachlorobiphenyl**	181		58.1	50	06/08/11 00:04
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	498		58.1	50	06/08/11 00:04
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		58.1	50	06/08/11 00:04
205	**2,3,3',4,4',5,5',6-Octachlorobiphenyl**	48.8	J	58.1	50	06/08/11 00:04
206	**2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl**	492		58.1	50	06/08/11 00:04

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 86.00 Sample Wet Weight: 20.03g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
207	**2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl**	61.5		58.1	50	06/08/11 00:04
208	**2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl**	140		58.1	50	06/08/11 00:04
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	96.9		58.1	50	06/08/11 00:04
1-3	**Total Monochlorobiphenyl**	117		58.1	50	06/08/11 00:04
4-15	**Total Dichlorobiphenyl**	4540		58.1	50	06/08/11 00:04
16-39	**Total Trichlorobiphenyl**	19200		58.1	50	06/08/11 00:04
40-81	**Total Tetrachlorobiphenyl**	16500		58.1	50	06/08/11 00:04
82-127	**Total Pentachlorobiphenyl**	20600		58.1	50	06/08/11 00:04
128-169	**Total Hexachlorobiphenyl**	23700		58.1	50	06/08/11 00:04
170-193	**Total Heptachlorobiphenyl**	12700		58.1	50	06/08/11 00:04
194-205	**Total Octachlorobiphenyl**	3100		58.1	50	06/08/11 00:04
206-208	**Total Nonachlorobiphenyl**	694		58.1	50	06/08/11 00:04
209	**Decachlorobiphenyl**	96.9		58.1	50	06/08/11 00:04
Total PCBs	**Total PCBs**	101000		58.1	50	06/08/11 00:04

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	75.6		76 %	*15-150*	*06/08/11 00:04*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	84.9		85 %	*15-150*	*06/08/11 00:04*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	69.2		69 %	*25-150*	*06/08/11 00:04*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	110		110 %	*25-150*	*06/08/11 00:04*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	90.5		90 %	*25-150*	*06/08/11 00:04*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	135		135 %	*25-150*	*06/08/11 00:04*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	89.8		90 %	*25-150*	*06/08/11 00:04*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	127		127 %	*25-150*	*06/08/11 00:04*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	128		128 %	*25-150*	*06/08/11 00:04*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	71.5		72 %	*25-150*	*06/08/11 00:04*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	109		109 %	*25-150*	*06/08/11 00:04*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	105		105 %	*25-150*	*06/08/11 00:04*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	108		108 %	*25-150*	*06/08/11 00:04*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	112		112 %	*25-150*	*06/08/11 00:04*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	108		108 %	*25-150*	*06/08/11 00:04*
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	106		106 %	*25-150*	*06/08/11 00:04*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	219		109 %	*25-150*	*06/08/11 00:04*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	109		109 %	*25-150*	*06/08/11 00:04*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	127		127 %	*25-150*	*06/08/11 00:04*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	92.6		93 %	*25-150*	*06/08/11 00:04*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	116		116 %	*25-150*	*06/08/11 00:04*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	94.5		95 %	*25-150*	*06/08/11 00:04*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 00:04*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	114		114 %	*25-150*	*06/08/11 00:04*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	102		102 %	*25-150*	*06/08/11 00:04*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	101		101 %	*25-150*	*06/08/11 00:04*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	129		129 %	*30-135*	*06/08/11 00:04*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	102		102 %	*30-135*	*06/08/11 00:04*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	114		114 %	*30-135*	*06/08/11 00:04*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10404 **Sample Weight:** %Solids: 0.10 Sample Wet Weight: 42.47g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	9180	J	23500	50	06/08/11 01:27
2	3-Monochlorobiphenyl	U		23500	50	06/08/11 01:27
3	4-Monochlorobiphenyl	U		23500	50	06/08/11 01:27
4	**2,2'-Dichlorobiphenyl**	176000		23500	50	06/08/11 01:27
5	2,3-Dichlorobiphenyl	U		23500	50	06/08/11 01:27
6	**2,3'-Dichlorobiphenyl**	81000		23500	50	06/08/11 01:27
7	2,4-Dichlorobiphenyl	U		23500	50	06/08/11 01:27
8	**2,4'-Dichlorobiphenyl**	105000		23500	50	06/08/11 01:27
9	2,5-Dichlorobiphenyl	U		23500	50	06/08/11 01:27
10	2,6-Dichlorobiphenyl	U		23500	50	06/08/11 01:27
11	**3,3'-Dichlorobiphenyl**	21000	J	23500	50	06/08/11 01:27
12/13	**3,4-DiCB/3,4'-DiCB**	16500	J	23500	50	06/08/11 01:27
14	3,5-Dichlorobiphenyl	U		23500	50	06/08/11 01:27
15	**4,4'-Dichlorobiphenyl**	79100		23500	50	06/08/11 01:27
16/24	**2,2',3-TrCB/2,3,6-TrCB**	76500		23500	50	06/08/11 01:27
17	**2,2',4-Trichlorobiphenyl**	77000		23500	50	06/08/11 01:27
18/30	**2,2',5-TrCB/2,4,6-TrCB**	186000		23500	50	06/08/11 01:27
19	**2,2',6-Trichlorobiphenyl**	39600		23500	50	06/08/11 01:27
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	246000		23500	50	06/08/11 01:27
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	43600		23500	50	06/08/11 01:27
22	**2,3,4'-Trichlorobiphenyl**	63800		23500	50	06/08/11 01:27
23	2,3,5-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
25	**2,3',4-Trichlorobiphenyl**	45400		23500	50	06/08/11 01:27
26/29	**2,3',5-TrCB/2,4,5-TrCB**	83100		23500	50	06/08/11 01:27
27	**2,3',6-Trichlorobiphenyl**	23100	J	23500	50	06/08/11 01:27
31	**2,4',5-Trichlorobiphenyl**	190000		23500	50	06/08/11 01:27
32	**2,4',6-Trichlorobiphenyl**	94700		23500	50	06/08/11 01:27
34	2,3',5'-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
35	3,3',4-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
36	3,3',5-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
37	**3,4,4'-Trichlorobiphenyl**	39600		23500	50	06/08/11 01:27
38	3,4,5-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
39	3,4',5-Trichlorobiphenyl	U		23500	50	06/08/11 01:27
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	54400		23500	50	06/08/11 01:27
42	**2,2',3,4'-Tetrachlorobiphenyl**	29000		23500	50	06/08/11 01:27
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		23500	50	06/08/11 01:27
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	104000		23500	50	06/08/11 01:27
45/51	**2,2',3,6-TeCB/2,2',4,6'-TeCB**	24300		23500	50	06/08/11 01:27
46	**2,2',3,6'-Tetrachlorobiphenyl**	8010	J	23500	50	06/08/11 01:27

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 0.10 Sample Wet Weight: 42.47g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	2,2',4,5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	85700		23500	50	06/08/11 01:27
50/53	**2,2',4,6-TeCB/2,2',5,6'-TeCB**	23500		23500	50	06/08/11 01:27
52	**2,2',5,5'-Tetrachlorobiphenyl**	131000		23500	50	06/08/11 01:27
54	2,2',6,6'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
55	2,3,3',4-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
56	**2,3,3',4'-Tetrachlorobiphenyl**	31600		23500	50	06/08/11 01:27
57	2,3,3',5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
58	2,3,3',5'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
59/62/75	**2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB**	11500	J	23500	50	06/08/11 01:27
60	**2,3,4,4'-Tetrachlorobiphenyl**	17200	EMPC, J	23500	50	06/08/11 01:27
61/70/74/76	**TeCB-61/70/74/76**	326000	EMPC	23500	50	06/08/11 01:27
63	2,3,4',5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
64	**2,3,4',6-Tetrachlorobiphenyl**	48000		23500	50	06/08/11 01:27
66	**2,3',4,4'-Tetrachlorobiphenyl**	82400		23500	50	06/08/11 01:27
67	2,3',4,5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
68	2,3',4,5'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
72	2,3',5,5'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
77	3,3',4,4'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
78	3,3',4,5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
79	3,3',4,5'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
80	3,3',5,5'-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
81	3,4,4',5-Tetrachlorobiphenyl	U		23500	50	06/08/11 01:27
82	**2,2',3,3',4-Pentachlorobiphenyl**	13700	J	23500	50	06/08/11 01:27
83/99/112	**2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB**	79400		23500	50	06/08/11 01:27
84	**2,2',3,3',6-Pentachlorobiphenyl**	29400		23500	50	06/08/11 01:27
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	27300		23500	50	06/08/11 01:27
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	113000		23500	50	06/08/11 01:27
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	22600	J	23500	50	06/08/11 01:27
89	2,2',3,4,6'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	195000		23500	50	06/08/11 01:27
92	**2,2',3,5,5'-Pentachlorobiphenyl**	34100		23500	50	06/08/11 01:27
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		23500	50	06/08/11 01:27
94	2,2',3,5,6'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
95	**2,2',3,5',6-Pentachlorobiphenyl**	124000		23500	50	06/08/11 01:27
96	2,2',3,6,6'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 0.10 Sample Wet Weight: 42.47g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		23500	50	06/08/11 01:27
103	2,2',4,5',6-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
104	2,2',4,6,6'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
105	**2,3,3',4,4'-Pentachlorobiphenyl**	59300		23500	50	06/08/11 01:27
106	2,3,3',4,5-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
107	2,3,3',4',5-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U		23500	50	06/08/11 01:27
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	211000		23500	50	06/08/11 01:27
111	2,3,3',5,5'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
114	2,3,4,4',5-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
118	**2,3',4,4',5-Pentachlorobiphenyl**	143000		23500	50	06/08/11 01:27
120	2,3',4,5,5'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
121	2,3',4,5',6-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
122	2,3,3',4',5'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
123	2,3',4,4',5'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
126	3,3',4,4',5-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
127	3,3',4,5,5'-Pentachlorobiphenyl	U		23500	50	06/08/11 01:27
128/166	**2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB**	36500		23500	50	06/08/11 01:27
129/138/163	**HxCB-129/138/163**	333000		23500	50	06/08/11 01:27
130	**2,2',3,3',4,5'-Hexachlorobiphenyl**	12000	J	23500	50	06/08/11 01:27
131	**2,2',3,3',4,6-Hexachlorobiphenyl**	3300	EMPC, J	23500	50	06/08/11 01:27
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	80800		23500	50	06/08/11 01:27
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
134/143	**2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB**	11300	EMPC, J	23500	50	06/08/11 01:27
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	104000		23500	50	06/08/11 01:27
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	53200		23500	50	06/08/11 01:27
137/164	**2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB**	35800		23500	50	06/08/11 01:27
139/140	**2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB**	3770	J	23500	50	06/08/11 01:27
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	62200		23500	50	06/08/11 01:27
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
144	**2,2',3,4,5',6-Hexachlorobiphenyl**	14600	J	23500	50	06/08/11 01:27
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
146	**2,2',3,4',5,5'-Hexachlorobiphenyl**	47300		23500	50	06/08/11 01:27
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	240000		23500	50	06/08/11 01:27
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	345000		23500	50	06/08/11 01:27
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 0.10 Sample Wet Weight: 42.47g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	37200		23500	50	06/08/11 01:27
158	**2,3,3',4,4',6-Hexachlorobiphenyl**	41000		23500	50	06/08/11 01:27
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	13000	EMPC, J	23500	50	06/08/11 01:27
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		23500	50	06/08/11 01:27
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	101000		23500	50	06/08/11 01:27
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	30100		23500	50	06/08/11 01:27
172	**2,2',3,3',4,5,5'-Heptachlorobiphenyl**	16700	J	23500	50	06/08/11 01:27
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	108000		23500	50	06/08/11 01:27
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	20200	J	23500	50	06/08/11 01:27
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	59100		23500	50	06/08/11 01:27
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	20000	J	23500	50	06/08/11 01:27
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	58400	EMPC	23500	50	06/08/11 01:27
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	278000		23500	50	06/08/11 01:27
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U		23500	50	06/08/11 01:27
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	71100		23500	50	06/08/11 01:27
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	134000		23500	50	06/08/11 01:27
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
189	**2,3,3',4,4',5,5'-Heptachlorobiphenyl**	6120	EMPC, J	23500	50	06/08/11 01:27
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	24000		23500	50	06/08/11 01:27
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		23500	50	06/08/11 01:27
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	66900		23500	50	06/08/11 01:27
195	**2,2',3,3',4,4',5,6-Octachlorobiphenyl**	23500		23500	50	06/08/11 01:27
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	29900		23500	50	06/08/11 01:27
197/200	**2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB**	14100	J	23500	50	06/08/11 01:27
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	56000		23500	50	06/08/11 01:27
201	**2,2',3,3',4,5',6,6'-Octachlorobiphenyl**	9180	J	23500	50	06/08/11 01:27
202	**2,2',3,3',5,5',6,6'-Octachlorobiphenyl**	13400	J	23500	50	06/08/11 01:27

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 0.10 Sample Wet Weight: 42.47g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	41000		23500	50	06/08/11 01:27
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		23500	50	06/08/11 01:27
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U		23500	50	06/08/11 01:27
206	**2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl**	27500		23500	50	06/08/11 01:27
207	**2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl**	4470	J	23500	50	06/08/11 01:27
208	**2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl**	6120	J	23500	50	06/08/11 01:27
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	7300	EMPC, J	23500	50	06/08/11 01:27
1-3	**Total Monochlorobiphenyl**	9180	J	23500	50	06/08/11 01:27
4-15	**Total Dichlorobiphenyl**	479000		23500	50	06/08/11 01:27
16-39	**Total Trichlorobiphenyl**	1210000		23500	50	06/08/11 01:27
40-81	**Total Tetrachlorobiphenyl**	976000		23500	50	06/08/11 01:27
82-127	**Total Pentachlorobiphenyl**	1050000		23500	50	06/08/11 01:27
128-169	**Total Hexachlorobiphenyl**	1470000		23500	50	06/08/11 01:27
170-193	**Total Heptachlorobiphenyl**	927000		23500	50	06/08/11 01:27
194-205	**Total Octachlorobiphenyl**	254000		23500	50	06/08/11 01:27
206-208	**Total Nonachlorobiphenyl**	38100		23500	50	06/08/11 01:27
209	**Decachlorobiphenyl**	7300	J	23500	50	06/08/11 01:27
Total PCBs	**Total PCBs**	6420000		23500	50	06/08/11 01:27

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	76.7		77 %	*15-150*	*06/08/11 01:27*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	85.8		86 %	*15-150*	*06/08/11 01:27*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	73.5		73 %	*25-150*	*06/08/11 01:27*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	108		108 %	*25-150*	*06/08/11 01:27*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	89.3		89 %	*25-150*	*06/08/11 01:27*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	141		141 %	*25-150*	*06/08/11 01:27*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	88.9		89 %	*25-150*	*06/08/11 01:27*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	123		123 %	*25-150*	*06/08/11 01:27*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	125		125 %	*25-150*	*06/08/11 01:27*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	73.2		73 %	*25-150*	*06/08/11 01:27*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	107		107 %	*25-150*	*06/08/11 01:27*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	103		103 %	*25-150*	*06/08/11 01:27*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 01:27*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	109		109 %	*25-150*	*06/08/11 01:27*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 01:27*
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	106		106 %	*25-150*	*06/08/11 01:27*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	218		109 %	*25-150*	*06/08/11 01:27*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	106		106 %	*25-150*	*06/08/11 01:27*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	128		128 %	*25-150*	*06/08/11 01:27*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	89.4		89 %	*25-150*	*06/08/11 01:27*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	117		117 %	*25-150*	*06/08/11 01:27*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	85.6		86 %	*25-150*	*06/08/11 01:27*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	105		105 %	*25-150*	*06/08/11 01:27*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	117		117 %	*25-150*	*06/08/11 01:27*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 01:27*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	99.3		99 %	*25-150*	*06/08/11 01:27*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	151		151 %	*30-135*	*06/08/11 01:27*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	106		106 %	*30-135*	*06/08/11 01:27*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	124		124 %	*30-135*	*06/08/11 01:27*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10404 **Sample Weight:** %Solids: 65.90 Sample Wet Weight: 24.88g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	6.10	J	61.0	50	06/08/11 02:50
2	3-Monochlorobiphenyl	U		61.0	50	06/08/11 02:50
3	4-Monochlorobiphenyl	U		61.0	50	06/08/11 02:50
4	**2,2'-Dichlorobiphenyl**	76.8		61.0	50	06/08/11 02:50
5	2,3-Dichlorobiphenyl	U		61.0	50	06/08/11 02:50
6	**2,3'-Dichlorobiphenyl**	53.7	J	61.0	50	06/08/11 02:50
7	2,4-Dichlorobiphenyl	U		61.0	50	06/08/11 02:50
8	**2,4'-Dichlorobiphenyl**	251		61.0	50	06/08/11 02:50
9	2,5-Dichlorobiphenyl	U		61.0	50	06/08/11 02:50
10	2,6-Dichlorobiphenyl	U		61.0	50	06/08/11 02:50
11	**3,3'-Dichlorobiphenyl**	92.1		61.0	50	06/08/11 02:50
12/13	3,4-DiCB/3,4'-DiCB	U		61.0	50	06/08/11 02:50
14	3,5-Dichlorobiphenyl	U		61.0	50	06/08/11 02:50
15	**4,4'-Dichlorobiphenyl**	182		61.0	50	06/08/11 02:50
16/24	**2,2',3-TrCB/2,3,6-TrCB**	177		61.0	50	06/08/11 02:50
17	**2,2',4-Trichlorobiphenyl**	202		61.0	50	06/08/11 02:50
18/30	**2,2',5-TrCB/2,4,6-TrCB**	447		61.0	50	06/08/11 02:50
19	**2,2',6-Trichlorobiphenyl**	57.3	J	61.0	50	06/08/11 02:50
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	868		61.0	50	06/08/11 02:50
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	479		61.0	50	06/08/11 02:50
22	**2,3,4'-Trichlorobiphenyl**	304		61.0	50	06/08/11 02:50
23	2,3,5-Trichlorobiphenyl	U		61.0	50	06/08/11 02:50
25	**2,3',4-Trichlorobiphenyl**	70.1		61.0	50	06/08/11 02:50
26/29	**2,3',5-TrCB/2,4,5-TrCB**	136		61.0	50	06/08/11 02:50
27	**2,3',6-Trichlorobiphenyl**	52.5	J	61.0	50	06/08/11 02:50
31	**2,4',5-Trichlorobiphenyl**	728		61.0	50	06/08/11 02:50
32	**2,4',6-Trichlorobiphenyl**	243		61.0	50	06/08/11 02:50
34	2,3',5'-Trichlorobiphenyl	U		61.0	50	06/08/11 02:50
35	**3,3',4-Trichlorobiphenyl**	14.0	EMPC, J	61.0	50	06/08/11 02:50
36	3,3',5-Trichlorobiphenyl	U		61.0	50	06/08/11 02:50
37	**3,4,4'-Trichlorobiphenyl**	233		61.0	50	06/08/11 02:50
38	3,4,5-Trichlorobiphenyl	U		61.0	50	06/08/11 02:50
39	3,4',5-Trichlorobiphenyl	U		61.0	50	06/08/11 02:50
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	265		61.0	50	06/08/11 02:50
42	**2,2',3,4'-Tetrachlorobiphenyl**	115		61.0	50	06/08/11 02:50
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		61.0	50	06/08/11 02:50
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	490		61.0	50	06/08/11 02:50
45/51	**2,2',3,6-TeCB/2,2',4,6'-TeCB**	94.5		61.0	50	06/08/11 02:50
46	**2,2',3,6'-Tetrachlorobiphenyl**	25.6	J	61.0	50	06/08/11 02:50
48	**2,2',4,5-Tetrachlorobiphenyl**	90.3		61.0	50	06/08/11 02:50

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 65.90 Sample Wet Weight: 24.88g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	301		61.0	50	06/08/11 02:50
50/53	**2,2',4,6-TeCB/2,2',5,6'-TeCB**	70.1		61.0	50	06/08/11 02:50
52	**2,2',5,5'-Tetrachlorobiphenyl**	661		61.0	50	06/08/11 02:50
54	2,2',6,6'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
55	2,3,3',4-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
56	**2,3,3',4'-Tetrachlorobiphenyl**	242		61.0	50	06/08/11 02:50
57	2,3,3',5-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
58	2,3,3',5'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
59/62/75	**2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB**	57.3	J	61.0	50	06/08/11 02:50
60	**2,3,4,4'-Tetrachlorobiphenyl**	138		61.0	50	06/08/11 02:50
61/70/74/76	**TeCB-61/70/74/76**	1280		61.0	50	06/08/11 02:50
63	2,3,4',5-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
64	**2,3,4',6-Tetrachlorobiphenyl**	296		61.0	50	06/08/11 02:50
66	**2,3',4,4'-Tetrachlorobiphenyl**	502		61.0	50	06/08/11 02:50
67	2,3',4,5-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
68	2,3',4,5'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
72	2,3',5,5'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
77	**3,3',4,4'-Tetrachlorobiphenyl**	65.3		61.0	50	06/08/11 02:50
78	3,3',4,5-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
79	3,3',4,5'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
80	3,3',5,5'-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
81	3,4,4',5-Tetrachlorobiphenyl	U		61.0	50	06/08/11 02:50
82	**2,2',3,3',4-Pentachlorobiphenyl**	138		61.0	50	06/08/11 02:50
83/99/112	**2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB**	745		61.0	50	06/08/11 02:50
84	**2,2',3,3',6-Pentachlorobiphenyl**	259		61.0	50	06/08/11 02:50
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	293		61.0	50	06/08/11 02:50
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	1170		61.0	50	06/08/11 02:50
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	160		61.0	50	06/08/11 02:50
89	2,2',3,4,6'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	1710		61.0	50	06/08/11 02:50
92	**2,2',3,5,5'-Pentachlorobiphenyl**	260		61.0	50	06/08/11 02:50
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		61.0	50	06/08/11 02:50
94	2,2',3,5,6'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
95	**2,2',3,5',6-Pentachlorobiphenyl**	881		61.0	50	06/08/11 02:50
96	**2,2',3,6,6'-Pentachlorobiphenyl**	7.93	EMPC, J	61.0	50	06/08/11 02:50
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		61.0	50	06/08/11 02:50
103	2,2',4,5',6-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 65.90 Sample Wet Weight: 24.88g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
104	2,2',4,6,6'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
105	**2,3,3',4,4'-Pentachlorobiphenyl**	776		61.0	50	06/08/11 02:50
106	2,3,3',4,5-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
107	**2,3,3',4',5-Pentachlorobiphenyl**	134		61.0	50	06/08/11 02:50
108/124	**2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB**	81.7		61.0	50	06/08/11 02:50
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	2150		61.0	50	06/08/11 02:50
111	2,3,3',5,5'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
114	**2,3,4,4',5-Pentachlorobiphenyl**	47.6	J	61.0	50	06/08/11 02:50
118	**2,3',4,4',5-Pentachlorobiphenyl**	1900		61.0	50	06/08/11 02:50
120	2,3',4,5,5'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
121	2,3',4,5',6-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
122	2,3,3',4',5'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
123	**2,3',4,4',5'-Pentachlorobiphenyl**	25.6	J	61.0	50	06/08/11 02:50
126	3,3',4,4',5-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
127	3,3',4,5,5'-Pentachlorobiphenyl	U		61.0	50	06/08/11 02:50
128/166	**2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB**	409		61.0	50	06/08/11 02:50
129/138/163	**HxCB-129/138/163**	2370		61.0	50	06/08/11 02:50
130	**2,2',3,3',4,5'-Hexachlorobiphenyl**	120		61.0	50	06/08/11 02:50
131	**2,2',3,3',4,6-Hexachlorobiphenyl**	24.4	J	61.0	50	06/08/11 02:50
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	550		61.0	50	06/08/11 02:50
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
134/143	**2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB**	80.5		61.0	50	06/08/11 02:50
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	425		61.0	50	06/08/11 02:50
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	216		61.0	50	06/08/11 02:50
137/164	**2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB**	277		61.0	50	06/08/11 02:50
139/140	**2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB**	35.4	J	61.0	50	06/08/11 02:50
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	367		61.0	50	06/08/11 02:50
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
144	**2,2',3,4,5',6-Hexachlorobiphenyl**	75.6		61.0	50	06/08/11 02:50
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
146	**2,2',3,4',5,5'-Hexachlorobiphenyl**	255		61.0	50	06/08/11 02:50
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	1210		61.0	50	06/08/11 02:50
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	1940		61.0	50	06/08/11 02:50
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	417		61.0	50	06/08/11 02:50

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 65.90 Sample Wet Weight: 24.88g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
158	**2,3,3',4,4',6-Hexachlorobiphenyl**	347		61.0	50	06/08/11 02:50
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	115		61.0	50	06/08/11 02:50
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		61.0	50	06/08/11 02:50
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	303		61.0	50	06/08/11 02:50
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	89.0		61.0	50	06/08/11 02:50
172	**2,2',3,3',4,5,5'-Heptachlorobiphenyl**	54.3	J	61.0	50	06/08/11 02:50
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	312		61.0	50	06/08/11 02:50
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	44.5	J	61.0	50	06/08/11 02:50
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	156		61.0	50	06/08/11 02:50
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	51.8	J	61.0	50	06/08/11 02:50
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	132		61.0	50	06/08/11 02:50
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	777		61.0	50	06/08/11 02:50
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U		61.0	50	06/08/11 02:50
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	171		61.0	50	06/08/11 02:50
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	353		61.0	50	06/08/11 02:50
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
189	**2,3,3',4,4',5,5'-Heptachlorobiphenyl**	15.9	EMPC, J	61.0	50	06/08/11 02:50
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	73.8		61.0	50	06/08/11 02:50
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		61.0	50	06/08/11 02:50
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	188		61.0	50	06/08/11 02:50
195	**2,2',3,3',4,4',5,6-Octachlorobiphenyl**	61.0		61.0	50	06/08/11 02:50
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	86.6		61.0	50	06/08/11 02:50
197/200	**2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB**	39.0	J	61.0	50	06/08/11 02:50
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	273		61.0	50	06/08/11 02:50
201	**2,2',3,3',4,5',6,6'-Octachlorobiphenyl**	37.8	J	61.0	50	06/08/11 02:50
202	**2,2',3,3',5,5',6,6'-Octachlorobiphenyl**	72.0		61.0	50	06/08/11 02:50
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	187		61.0	50	06/08/11 02:50
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		61.0	50	06/08/11 02:50

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10404 **Sample Weight:** %Solids: 65.90 Sample Wet Weight: 24.88g **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/g dry	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
205	**2,3,3',4,4',5,5',6-Octachlorobiphenyl**	10.4	J	61.0	50	06/08/11 02:50
206	**2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl**	226		61.0	50	06/08/11 02:50
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U		61.0	50	06/08/11 02:50
208	**2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl**	64.7		61.0	50	06/08/11 02:50
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	55.5	J	61.0	50	06/08/11 02:50
1-3	**Total Monochlorobiphenyl**	6.10	J	61.0	50	06/08/11 02:50
4-15	**Total Dichlorobiphenyl**	656		61.0	50	06/08/11 02:50
16-39	**Total Trichlorobiphenyl**	4010		61.0	50	06/08/11 02:50
40-81	**Total Tetrachlorobiphenyl**	4690		61.0	50	06/08/11 02:50
82-127	**Total Pentachlorobiphenyl**	10700		61.0	50	06/08/11 02:50
128-169	**Total Hexachlorobiphenyl**	9240		61.0	50	06/08/11 02:50
170-193	**Total Heptachlorobiphenyl**	2530		61.0	50	06/08/11 02:50
194-205	**Total Octachlorobiphenyl**	955		61.0	50	06/08/11 02:50
206-208	**Total Nonachlorobiphenyl**	290		61.0	50	06/08/11 02:50
209	**Decachlorobiphenyl**	55.5	J	61.0	50	06/08/11 02:50
Total PCBs	**Total PCBs**	33200		61.0	50	06/08/11 02:50

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	78.0		78 %	*15-150*	*06/08/11 02:50*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	84.4		84 %	*15-150*	*06/08/11 02:50*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	76.2		76 %	*25-150*	*06/08/11 02:50*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	107		107 %	*25-150*	*06/08/11 02:50*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	95.0		95 %	*25-150*	*06/08/11 02:50*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	144		144 %	*25-150*	*06/08/11 02:50*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	96.0		96 %	*25-150*	*06/08/11 02:50*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	127		127 %	*25-150*	*06/08/11 02:50*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	131		131 %	*25-150*	*06/08/11 02:50*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	74.6		75 %	*25-150*	*06/08/11 02:50*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	109		109 %	*25-150*	*06/08/11 02:50*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 02:50*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	107		107 %	*25-150*	*06/08/11 02:50*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	113		113 %	*25-150*	*06/08/11 02:50*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	108		108 %	*25-150*	*06/08/11 02:50*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	104		104 %	*25-150*	*06/08/11 02:50*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	223		111 %	*25-150*	*06/08/11 02:50*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	111		111 %	*25-150*	*06/08/11 02:50*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	137		137 %	*25-150*	*06/08/11 02:50*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	92.6		93 %	*25-150*	*06/08/11 02:50*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	123		123 %	*25-150*	*06/08/11 02:50*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	85.6		86 %	*25-150*	*06/08/11 02:50*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	111		111 %	*25-150*	*06/08/11 02:50*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	118		118 %	*25-150*	*06/08/11 02:50*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	102		102 %	*25-150*	*06/08/11 02:50*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	100		100 %	*25-150*	*06/08/11 02:50*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	154		154 %	*30-135*	*06/08/11 02:50*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	109		109 %	*30-135*	*06/08/11 02:50*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	127		127 %	*30-135*	*06/08/11 02:50*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1070ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	131	J	935	50	06/08/11 04:13
2	3-Monochlorobiphenyl	U		935	50	06/08/11 04:13
3	4-Monochlorobiphenyl	U		935	50	06/08/11 04:13
4	**2,2'-Dichlorobiphenyl**	2130		935	50	06/08/11 04:13
5	2,3-Dichlorobiphenyl	U		935	50	06/08/11 04:13
6	**2,3'-Dichlorobiphenyl**	617	J	935	50	06/08/11 04:13
7	2,4-Dichlorobiphenyl	U		935	50	06/08/11 04:13
8	**2,4'-Dichlorobiphenyl**	907	J	935	50	06/08/11 04:13
9	2,5-Dichlorobiphenyl	U		935	50	06/08/11 04:13
10	2,6-Dichlorobiphenyl	U		935	50	06/08/11 04:13
11	3,3'-Dichlorobiphenyl	U		935	50	06/08/11 04:13
12/13	3,4-DiCB/3,4'-DiCB	U		935	50	06/08/11 04:13
14	3,5-Dichlorobiphenyl	U		935	50	06/08/11 04:13
15	**4,4'-Dichlorobiphenyl**	421	J	935	50	06/08/11 04:13
16/24	**2,2',3-TrCB/2,3,6-TrCB**	523	J	935	50	06/08/11 04:13
17	**2,2',4-Trichlorobiphenyl**	430	J	935	50	06/08/11 04:13
18/30	**2,2',5-TrCB/2,4,6-TrCB**	1070		935	50	06/08/11 04:13
19	**2,2',6-Trichlorobiphenyl**	336	J	935	50	06/08/11 04:13
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	813	J	935	50	06/08/11 04:13
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	271	J	935	50	06/08/11 04:13
22	**2,3,4'-Trichlorobiphenyl**	271	J	935	50	06/08/11 04:13
23	**2,3,5-Trichlorobiphenyl**	280	J	935	50	06/08/11 04:13
25	2,3',4-Trichlorobiphenyl	U		935	50	06/08/11 04:13
26/29	2,3',5-TrCB/2,4,5-TrCB	U		935	50	06/08/11 04:13
27	2,3',6-Trichlorobiphenyl	U		935	50	06/08/11 04:13
31	**2,4',5-Trichlorobiphenyl**	673	J	935	50	06/08/11 04:13
32	**2,4',6-Trichlorobiphenyl**	402	J	935	50	06/08/11 04:13
34	2,3',5'-Trichlorobiphenyl	U		935	50	06/08/11 04:13
35	3,3',4-Trichlorobiphenyl	U		935	50	06/08/11 04:13
36	3,3',5-Trichlorobiphenyl	U		935	50	06/08/11 04:13
37	**3,4,4'-Trichlorobiphenyl**	196	J	935	50	06/08/11 04:13
38	3,4,5-Trichlorobiphenyl	U		935	50	06/08/11 04:13
39	3,4',5-Trichlorobiphenyl	U		935	50	06/08/11 04:13
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	121	J	935	50	06/08/11 04:13
42	2,2',3,4'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		935	50	06/08/11 04:13
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	308	J	935	50	06/08/11 04:13
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U		935	50	06/08/11 04:13
46	2,2',3,6'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1070ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	2,2',4,5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	206	EMPC, J	935	50	06/08/11 04:13
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U		935	50	06/08/11 04:13
52	**2,2',5,5'-Tetrachlorobiphenyl**	271	J	935	50	06/08/11 04:13
54	2,2',6,6'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
55	2,3,3',4-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
56	2,3,3',4'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
57	2,3,3',5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
58	2,3,3',5'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U		935	50	06/08/11 04:13
60	2,3,4,4'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
61/70/74/76	**TeCB-61/70/74/76**	2400	EMPC	935	50	06/08/11 04:13
63	2,3,4',5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
64	**2,3,4',6-Tetrachlorobiphenyl**	93.5	J	935	50	06/08/11 04:13
66	2,3',4,4'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
67	2,3',4,5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
68	2,3',4,5'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
72	2,3',5,5'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
77	3,3',4,4'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
78	3,3',4,5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
79	3,3',4,5'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
80	3,3',5,5'-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
81	3,4,4',5-Tetrachlorobiphenyl	U		935	50	06/08/11 04:13
82	2,2',3,3',4-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	U		935	50	06/08/11 04:13
84	2,2',3,3',6-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	U		935	50	06/08/11 04:13
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	U		935	50	06/08/11 04:13
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	U		935	50	06/08/11 04:13
89	2,2',3,4,6'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	701	J	935	50	06/08/11 04:13
92	2,2',3,5,5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		935	50	06/08/11 04:13
94	2,2',3,5,6'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
95	**2,2',3,5',6-Pentachlorobiphenyl**	477	J	935	50	06/08/11 04:13
96	2,2',3,6,6'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		935	50	06/08/11 04:13

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1070ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
103	2,2',4,5',6-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
104	2,2',4,6,6'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
105	**2,3,3',4,4'-Pentachlorobiphenyl**	402	EMPC, J	935	50	06/08/11 04:13
106	2,3,3',4,5-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
107	2,3,3',4',5-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U		935	50	06/08/11 04:13
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	570	J	935	50	06/08/11 04:13
111	2,3,3',5,5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
114	2,3,4,4',5-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
118	**2,3',4,4',5-Pentachlorobiphenyl**	421	EMPC, J	935	50	06/08/11 04:13
120	2,3',4,5,5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
121	2,3',4,5',6-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
122	2,3,3',4',5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
123	2,3',4,4',5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
126	3,3',4,4',5-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
127	3,3',4,5,5'-Pentachlorobiphenyl	U		935	50	06/08/11 04:13
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		935	50	06/08/11 04:13
129/138/163	**HxCB-129/138/163**	1510		935	50	06/08/11 04:13
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
131	2,2',3,3',4,6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	439	J	935	50	06/08/11 04:13
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U		935	50	06/08/11 04:13
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	579	J	935	50	06/08/11 04:13
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	271	J	935	50	06/08/11 04:13
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		935	50	06/08/11 04:13
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U		935	50	06/08/11 04:13
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	355	J	935	50	06/08/11 04:13
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
144	2,2',3,4,5',6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
146	2,2',3,4',5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	1220		935	50	06/08/11 04:13
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	1770		935	50	06/08/11 04:13
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1070ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	178	J	935	50	06/08/11 04:13
158	2,3,3',4,4',6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		935	50	06/08/11 04:13
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	654	J	935	50	06/08/11 04:13
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	187	J	935	50	06/08/11 04:13
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	598	J	935	50	06/08/11 04:13
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	159	EMPC, J	935	50	06/08/11 04:13
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	327	J	935	50	06/08/11 04:13
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	336	J	935	50	06/08/11 04:13
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	1630	EMPC	935	50	06/08/11 04:13
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	308	J	935	50	06/08/11 04:13
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	673	J	935	50	06/08/11 04:13
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	187	J	935	50	06/08/11 04:13
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		935	50	06/08/11 04:13
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	318	EMPC, J	935	50	06/08/11 04:13
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U		935	50	06/08/11 04:13
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	150	EMPC, J	935	50	06/08/11 04:13
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U		935	50	06/08/11 04:13
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	318	J	935	50	06/08/11 04:13
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U		935	50	06/08/11 04:13
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U		935	50	06/08/11 04:13
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	196	J	935	50	06/08/11 04:13
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		935	50	06/08/11 04:13

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1070ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U		935	50	06/08/11 04:13
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U		935	50	06/08/11 04:13
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U		935	50	06/08/11 04:13
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U		935	50	06/08/11 04:13
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U		935	50	06/08/11 04:13
1-3	**Total Monochlorobiphenyl**	131	J	935	50	06/08/11 04:13
4-15	**Total Dichlorobiphenyl**	4070		935	50	06/08/11 04:13
16-39	**Total Trichlorobiphenyl**	5270		935	50	06/08/11 04:13
40-81	**Total Tetrachlorobiphenyl**	3400		935	50	06/08/11 04:13
82-127	**Total Pentachlorobiphenyl**	2570		935	50	06/08/11 04:13
128-169	**Total Hexachlorobiphenyl**	6330		935	50	06/08/11 04:13
170-193	**Total Heptachlorobiphenyl**	5060		935	50	06/08/11 04:13
194-205	**Total Octachlorobiphenyl**	981		935	50	06/08/11 04:13
206-208	Total Nonachlorobiphenyl	U		935	50	06/08/11 04:13
209	Decachlorobiphenyl	U		935	50	06/08/11 04:13
Total PCBs	**Total PCBs**	27800		935	50	06/08/11 04:13

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	73.0		73 %	*15-150*	*06/08/11 04:13*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	86.0		86 %	*15-150*	*06/08/11 04:13*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	69.7		70 %	*25-150*	*06/08/11 04:13*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	109		109 %	*25-150*	*06/08/11 04:13*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	89.0		89 %	*25-150*	*06/08/11 04:13*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	134		134 %	*25-150*	*06/08/11 04:13*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	90.4		90 %	*25-150*	*06/08/11 04:13*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	124		124 %	*25-150*	*06/08/11 04:13*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	129		129 %	*25-150*	*06/08/11 04:13*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	69.4		69 %	*25-150*	*06/08/11 04:13*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	109		109 %	*25-150*	*06/08/11 04:13*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	107		107 %	*25-150*	*06/08/11 04:13*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	106		106 %	*25-150*	*06/08/11 04:13*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	112		112 %	*25-150*	*06/08/11 04:13*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	105		105 %	*25-150*	*06/08/11 04:13*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-05
Lab ID: 1104020-05
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	100		100 %	*25-150*	*06/08/11 04:13*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	213		106 %	*25-150*	*06/08/11 04:13*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	105		105 %	*25-150*	*06/08/11 04:13*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	125		125 %	*25-150*	*06/08/11 04:13*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	84.5		85 %	*25-150*	*06/08/11 04:13*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	114		114 %	*25-150*	*06/08/11 04:13*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	77.8		78 %	*25-150*	*06/08/11 04:13*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	111		111 %	*25-150*	*06/08/11 04:13*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	107		107 %	*25-150*	*06/08/11 04:13*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	96.5		96 %	*25-150*	*06/08/11 04:13*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	99.0		99 %	*25-150*	*06/08/11 04:13*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	140		140 %	*30-135*	*06/08/11 04:13*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	104		104 %	*30-135*	*06/08/11 04:13*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	96.7		97 %	*30-135*	*06/08/11 04:13*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	66.7		19.6	1	06/02/11 02:47
2	3-Monochlorobiphenyl	U		19.6	1	06/02/11 02:47
3	4-Monochlorobiphenyl	U		19.6	1	06/02/11 02:47
4	**2,2'-Dichlorobiphenyl**	133		19.6	1	06/02/11 02:47
5	2,3-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
6	**2,3'-Dichlorobiphenyl**	17.6	J	19.6	1	06/02/11 02:47
7	2,4-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
8	**2,4'-Dichlorobiphenyl**	70.0		19.6	1	06/02/11 02:47
9	2,5-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
10	2,6-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
11	**3,3'-Dichlorobiphenyl**	50.4	B	19.6	1	06/02/11 02:47
12/13	3,4-DiCB/3,4'-DiCB	U		19.6	1	06/02/11 02:47
14	3,5-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
15	4,4'-Dichlorobiphenyl	U		19.6	1	06/02/11 02:47
16/24	**2,2',3-TrCB/2,3,6-TrCB**	12.5	B, J	19.6	1	06/02/11 02:47
17	**2,2',4-Trichlorobiphenyl**	9.61	B, J	19.6	1	06/02/11 02:47
18/30	**2,2',5-TrCB/2,4,6-TrCB**	26.7	B	19.6	1	06/02/11 02:47
19	**2,2',6-Trichlorobiphenyl**	8.24	J	19.6	1	06/02/11 02:47
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	10.2	B, EMPC, J	19.6	1	06/02/11 02:47
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	8.82	B, J	19.6	1	06/02/11 02:47
22	**2,3,4'-Trichlorobiphenyl**	6.86	EMPC, B, J	19.6	1	06/02/11 02:47
23	2,3,5-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
25	**2,3',4-Trichlorobiphenyl**	2.75	B, EMPC, J	19.6	1	06/02/11 02:47
26/29	**2,3',5-TrCB/2,4,5-TrCB**	3.73	B, J	19.6	1	06/02/11 02:47
27	2,3',6-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
31	**2,4',5-Trichlorobiphenyl**	15.3	B, J	19.6	1	06/02/11 02:47
32	**2,4',6-Trichlorobiphenyl**	12.5	B, J	19.6	1	06/02/11 02:47
34	2,3',5'-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
35	3,3',4-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
36	3,3',5-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
37	**3,4,4'-Trichlorobiphenyl**	8.43	B, J	19.6	1	06/02/11 02:47
38	3,4,5-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
39	3,4',5-Trichlorobiphenyl	U		19.6	1	06/02/11 02:47
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	3.14	B, J	19.6	1	06/02/11 02:47
42	2,2',3,4'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		19.6	1	06/02/11 02:47
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	9.41	B, J	19.6	1	06/02/11 02:47
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U		19.6	1	06/02/11 02:47
46	2,2',3,6'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	2,2',4,5-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	2.55	B, J	19.6	1	06/02/11 02:47
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U		19.6	1	06/02/11 02:47
52	**2,2',5,5'-Tetrachlorobiphenyl**	3.53	B, J	19.6	1	06/02/11 02:47
54	2,2',6,6'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
55	2,3,3',4-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
56	**2,3,3',4'-Tetrachlorobiphenyl**	5.88	B, EMPC, J	19.6	1	06/02/11 02:47
57	2,3,3',5-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
58	2,3,3',5'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U		19.6	1	06/02/11 02:47
60	2,3,4,4'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
61/70/74/76	**TeCB-61/70/74/76**	8.43	B, J	19.6	1	06/02/11 02:47
63	2,3,4',5-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
64	**2,3,4',6-Tetrachlorobiphenyl**	1.57	B, EMPC, J	19.6	1	06/02/11 02:47
66	**2,3',4,4'-Tetrachlorobiphenyl**	4.71	B, J	19.6	1	06/02/11 02:47
67	2,3',4,5-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
68	2,3',4,5'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
72	2,3',5,5'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
77	**3,3',4,4'-Tetrachlorobiphenyl**	5.49	B, J	19.6	1	06/02/11 02:47
78	3,3',4,5-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
79	3,3',4,5'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
80	3,3',5,5'-Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
81	**3,4,4',5-Tetrachlorobiphenyl**	2.75	B, EMPC, J	19.6	1	06/02/11 02:47
82	2,2',3,3',4-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	U		19.6	1	06/02/11 02:47
84	**2,2',3,3',6-Pentachlorobiphenyl**	2.55	B, EMPC, J	19.6	1	06/02/11 02:47
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	U		19.6	1	06/02/11 02:47
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	5.49	B, J	19.6	1	06/02/11 02:47
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	1.76	B, EMPC, J	19.6	1	06/02/11 02:47
89	2,2',3,4,6'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	6.47	B, J	19.6	1	06/02/11 02:47
92	2,2',3,5,5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		19.6	1	06/02/11 02:47
94	2,2',3,5,6'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
95	**2,2',3,5',6-Pentachlorobiphenyl**	4.71	B, J	19.6	1	06/02/11 02:47
96	2,2',3,6,6'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		19.6	1	06/02/11 02:47

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
103	2,2',4,5',6-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
104	2,2',4,6,6'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
105	**2,3,3',4,4'-Pentachlorobiphenyl**	18.0	B, EMPC, J	19.6	1	06/02/11 02:47
106	2,3,3',4,5-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
107	2,3,3',4',5-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U		19.6	1	06/02/11 02:47
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	7.65	B, EMPC, J	19.6	1	06/02/11 02:47
111	2,3,3',5,5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
114	2,3,4,4',5-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
118	**2,3',4,4',5-Pentachlorobiphenyl**	7.65	B, J	19.6	1	06/02/11 02:47
120	2,3',4,5,5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
121	2,3',4,5',6-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
122	2,3,3',4',5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
123	2,3',4,4',5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
126	**3,3',4,4',5-Pentachlorobiphenyl**	2.55	B, J	19.6	1	06/02/11 02:47
127	3,3',4,5,5'-Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		19.6	1	06/02/11 02:47
129/138/163	**HxCB-129/138/163**	11.4	B, J	19.6	1	06/02/11 02:47
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
131	2,2',3,3',4,6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	3.33	B, J	19.6	1	06/02/11 02:47
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U		19.6	1	06/02/11 02:47
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	4.31	B, J	19.6	1	06/02/11 02:47
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	2.16	B, J	19.6	1	06/02/11 02:47
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		19.6	1	06/02/11 02:47
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U		19.6	1	06/02/11 02:47
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	1.76	B, J	19.6	1	06/02/11 02:47
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
144	2,2',3,4,5',6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
146	2,2',3,4',5,5'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	8.04	B, J	19.6	1	06/02/11 02:47
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	10.4	B, J	19.6	1	06/02/11 02:47
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	3.14	B, J	19.6	1	06/02/11 02:47
158	2,3,3',4,4',6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
162	**2,3,3',4',5,5'-Hexachlorobiphenyl**	4.12	B, EMPC, J	19.6	1	06/02/11 02:47
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	1.18	B, EMPC, J	19.6	1	06/02/11 02:47
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	7.06	B, EMPC, J	19.6	1	06/02/11 02:47
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	1.37	B, J	19.6	1	06/02/11 02:47
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	4.51	B, EMPC, J	19.6	1	06/02/11 02:47
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	1.76	B, J	19.6	1	06/02/11 02:47
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	1.37	J	19.6	1	06/02/11 02:47
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	2.75	B, EMPC, J	19.6	1	06/02/11 02:47
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	7.45	B, J	19.6	1	06/02/11 02:47
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	1.96	B, EMPC, J	19.6	1	06/02/11 02:47
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	3.14	B, EMPC, J	19.6	1	06/02/11 02:47
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		19.6	1	06/02/11 02:47
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	1.18	B, EMPC, J	19.6	1	06/02/11 02:47
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U		19.6	1	06/02/11 02:47
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	1.57	B, J	19.6	1	06/02/11 02:47
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U		19.6	1	06/02/11 02:47
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	2.16	B, J	19.6	1	06/02/11 02:47
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U		19.6	1	06/02/11 02:47
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U		19.6	1	06/02/11 02:47
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	1.18	B, EMPC, J	19.6	1	06/02/11 02:47
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		19.6	1	06/02/11 02:47

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U		19.6	1	06/02/11 02:47
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U		19.6	1	06/02/11 02:47
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U		19.6	1	06/02/11 02:47
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U		19.6	1	06/02/11 02:47
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	2.35	B, EMPC, J	19.6	1	06/02/11 02:47
1-3	**Total Monochlorobiphenyl**	66.7		19.6	1	06/02/11 02:47
4-15	**Total Dichlorobiphenyl**	221		19.6	1	06/02/11 02:47
16-39	**Total Trichlorobiphenyl**	8.24	J	19.6	1	06/02/11 02:47
40-81	Total Tetrachlorobiphenyl	U		19.6	1	06/02/11 02:47
82-127	Total Pentachlorobiphenyl	U		19.6	1	06/02/11 02:47
128-169	Total Hexachlorobiphenyl	U		19.6	1	06/02/11 02:47
170-193	**Total Heptachlorobiphenyl**	1.37	J	19.6	1	06/02/11 02:47
194-205	Total Octachlorobiphenyl	U		19.6	1	06/02/11 02:47
206-208	Total Nonachlorobiphenyl	U		19.6	1	06/02/11 02:47
209	**Decachlorobiphenyl**	2.35	J	19.6	1	06/02/11 02:47
Total PCBs	**Total PCBs**	297		19.6	1	06/02/11 02:47

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	9.41	*A*	9 %	*15-150*	*06/02/11 02:47*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	13.7	*A*	14 %	*15-150*	*06/02/11 02:47*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	16.4	*A*	16 %	*25-150*	*06/02/11 02:47*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	38.6		39 %	*25-150*	*06/02/11 02:47*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	29.8		30 %	*25-150*	*06/02/11 02:47*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	58.4		58 %	*25-150*	*06/02/11 02:47*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	38.8		39 %	*25-150*	*06/02/11 02:47*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	68.2		68 %	*25-150*	*06/02/11 02:47*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	67.7		68 %	*25-150*	*06/02/11 02:47*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	41.0		41 %	*25-150*	*06/02/11 02:47*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	67.0		67 %	*25-150*	*06/02/11 02:47*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	62.1		62 %	*25-150*	*06/02/11 02:47*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	63.6		64 %	*25-150*	*06/02/11 02:47*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	66.6		67 %	*25-150*	*06/02/11 02:47*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	67.0		67 %	*25-150*	*06/02/11 02:47*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: FB-01
Lab ID: 1104020-06
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	56.4		56 %	*25-150*	*06/02/11 02:47*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	120		60 %	*25-150*	*06/02/11 02:47*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	64.6		65 %	*25-150*	*06/02/11 02:47*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	69.1		69 %	*25-150*	*06/02/11 02:47*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	66.1		66 %	*25-150*	*06/02/11 02:47*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	78.2		78 %	*25-150*	*06/02/11 02:47*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	75.1		75 %	*25-150*	*06/02/11 02:47*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	66.6		67 %	*25-150*	*06/02/11 02:47*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	69.5		69 %	*25-150*	*06/02/11 02:47*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	81.4		81 %	*25-150*	*06/02/11 02:47*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	60.3		60 %	*25-150*	*06/02/11 02:47*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	64.3		64 %	*30-135*	*06/02/11 02:47*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	68.8		69 %	*30-135*	*06/02/11 02:47*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	84.1		84 %	*30-135*	*06/02/11 02:47*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	4380		952	50	06/07/11 16:17
2	**3-Monochlorobiphenyl**	686	J	952	50	06/07/11 16:17
3	**4-Monochlorobiphenyl**	1650		952	50	06/07/11 16:17
4	**2,2'-Dichlorobiphenyl**	46600		952	50	06/07/11 16:17
5	**2,3-Dichlorobiphenyl**	1410		952	50	06/07/11 16:17
6	**2,3'-Dichlorobiphenyl**	66300		952	50	06/07/11 16:17
7	**2,4-Dichlorobiphenyl**	4270		952	50	06/07/11 16:17
8	**2,4'-Dichlorobiphenyl**	107000		952	50	06/07/11 16:17
9	**2,5-Dichlorobiphenyl**	7500		952	50	06/07/11 16:17
10	**2,6-Dichlorobiphenyl**	2390		952	50	06/07/11 16:17
11	**3,3'-Dichlorobiphenyl**	2870		952	50	06/07/11 16:17
12/13	**3,4-DiCB/3,4'-DiCB**	16200		952	50	06/07/11 16:17
14	3,5-Dichlorobiphenyl	U		952	50	06/07/11 16:17
15	**4,4'-Dichlorobiphenyl**	36000		952	50	06/07/11 16:17
16/24	**2,2',3-TrCB/2,3,6-TrCB**	49400		952	50	06/07/11 16:17
17	**2,2',4-Trichlorobiphenyl**	61800		952	50	06/07/11 16:17
18/30	**2,2',5-TrCB/2,4,6-TrCB**	143000		952	50	06/07/11 16:17
19	**2,2',6-Trichlorobiphenyl**	14800		952	50	06/07/11 16:17
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	201000		952	50	06/07/11 16:17
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	34600		952	50	06/07/11 16:17
22	**2,3,4'-Trichlorobiphenyl**	61000		952	50	06/07/11 16:17
23	**2,3,5-Trichlorobiphenyl**	400	J	952	50	06/07/11 16:17
25	**2,3',4-Trichlorobiphenyl**	39500		952	50	06/07/11 16:17
26/29	**2,3',5-TrCB/2,4,5-TrCB**	63800		952	50	06/07/11 16:17
27	**2,3',6-Trichlorobiphenyl**	10600		952	50	06/07/11 16:17
31	**2,4',5-Trichlorobiphenyl**	156000		952	50	06/07/11 16:17
32	**2,4',6-Trichlorobiphenyl**	51200		952	50	06/07/11 16:17
34	**2,3',5'-Trichlorobiphenyl**	1630		952	50	06/07/11 16:17
35	**3,3',4-Trichlorobiphenyl**	1300		952	50	06/07/11 16:17
36	3,3',5-Trichlorobiphenyl	U		952	50	06/07/11 16:17
37	**3,4,4'-Trichlorobiphenyl**	27500		952	50	06/07/11 16:17
38	3,4,5-Trichlorobiphenyl	U		952	50	06/07/11 16:17
39	**3,4',5-Trichlorobiphenyl**	590	J	952	50	06/07/11 16:17
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	32500		952	50	06/07/11 16:17
42	**2,2',3,4'-Tetrachlorobiphenyl**	16600		952	50	06/07/11 16:17
43/73	**2,2',3,5-TeCB/2,3',5',6-TeCB**	2330		952	50	06/07/11 16:17
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	64500		952	50	06/07/11 16:17
45/51	**2,2',3,6-TeCB/2,2',4,6'-TeCB**	12800		952	50	06/07/11 16:17
46	**2,2',3,6'-Tetrachlorobiphenyl**	3570		952	50	06/07/11 16:17
48	**2,2',4,5-Tetrachlorobiphenyl**	11400		952	50	06/07/11 16:17

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	48900		952	50	06/07/11 16:17
50/53	**2,2',4,6-TeCB/2,2',5,6'-TeCB**	9190		952	50	06/07/11 16:17
52	**2,2',5,5'-Tetrachlorobiphenyl**	82900		952	50	06/07/11 16:17
54	**2,2',6,6'-Tetrachlorobiphenyl**	229	EMPC, J	952	50	06/07/11 16:17
55	**2,3,3',4-Tetrachlorobiphenyl**	2060		952	50	06/07/11 16:17
56	**2,3,3',4'-Tetrachlorobiphenyl**	14800		952	50	06/07/11 16:17
57	2,3,3',5-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
58	**2,3,3',5'-Tetrachlorobiphenyl**	5130		952	50	06/07/11 16:17
59/62/75	**2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB**	7830		952	50	06/07/11 16:17
60	**2,3,4,4'-Tetrachlorobiphenyl**	7220		952	50	06/07/11 16:17
61/70/74/76	**TeCB-61/70/74/76**	118000		952	50	06/07/11 16:17
63	2,3,4',5-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
64	**2,3,4',6-Tetrachlorobiphenyl**	36500		952	50	06/07/11 16:17
66	**2,3',4,4'-Tetrachlorobiphenyl**	47300		952	50	06/07/11 16:17
67	**2,3',4,5-Tetrachlorobiphenyl**	4390		952	50	06/07/11 16:17
68	**2,3',4,5'-Tetrachlorobiphenyl**	552	J	952	50	06/07/11 16:17
72	**2,3',5,5'-Tetrachlorobiphenyl**	876	J	952	50	06/07/11 16:17
77	**3,3',4,4'-Tetrachlorobiphenyl**	5250		952	50	06/07/11 16:17
78	3,3',4,5-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
79	3,3',4,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
80	3,3',5,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
81	3,4,4',5-Tetrachlorobiphenyl	U		952	50	06/07/11 16:17
82	**2,2',3,3',4-Pentachlorobiphenyl**	6980		952	50	06/07/11 16:17
83/99/112	**2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB**	46900		952	50	06/07/11 16:17
84	**2,2',3,3',6-Pentachlorobiphenyl**	12800		952	50	06/07/11 16:17
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	13600		952	50	06/07/11 16:17
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	65900		952	50	06/07/11 16:17
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	8170		952	50	06/07/11 16:17
89	**2,2',3,4,6'-Pentachlorobiphenyl**	629	J	952	50	06/07/11 16:17
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	159000		952	50	06/07/11 16:17
92	**2,2',3,5,5'-Pentachlorobiphenyl**	15000		952	50	06/07/11 16:17
93/100	**2,2',3,5,6-PeCB/2,2',4,4',6-PeCB**	1030		952	50	06/07/11 16:17
94	2,2',3,5,6'-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
95	**2,2',3,5',6-Pentachlorobiphenyl**	102000		952	50	06/07/11 16:17
96	**2,2',3,6,6'-Pentachlorobiphenyl**	667	J	952	50	06/07/11 16:17
98/102	**2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB**	2300		952	50	06/07/11 16:17
103	**2,2',4,5',6-Pentachlorobiphenyl**	1590		952	50	06/07/11 16:17

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
104	2,2',4,6,6'-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
105	**2,3,3',4,4'-Pentachlorobiphenyl**	31300		952	50	06/07/11 16:17
106	2,3,3',4,5-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
107	**2,3,3',4',5-Pentachlorobiphenyl**	6660		952	50	06/07/11 16:17
108/124	**2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB**	3380		952	50	06/07/11 16:17
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	141000		952	50	06/07/11 16:17
111	2,3,3',5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
114	**2,3,4,4',5-Pentachlorobiphenyl**	2180		952	50	06/07/11 16:17
118	**2,3',4,4',5-Pentachlorobiphenyl**	96700		952	50	06/07/11 16:17
120	2,3',4,5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
121	2,3',4,5',6-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
122	**2,3,3',4',5'-Pentachlorobiphenyl**	829	J	952	50	06/07/11 16:17
123	**2,3',4,4',5'-Pentachlorobiphenyl**	1470		952	50	06/07/11 16:17
126	3,3',4,4',5-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
127	3,3',4,5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 16:17
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		952	50	06/07/11 16:17
129/138/163	**HxCB-129/138/163**	487000		952	50	06/07/11 16:17
130	**2,2',3,3',4,5'-Hexachlorobiphenyl**	17900		952	50	06/07/11 16:17
131	**2,2',3,3',4,6-Hexachlorobiphenyl**	2610		952	50	06/07/11 16:17
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	116000		952	50	06/07/11 16:17
133	**2,2',3,3',5,5'-Hexachlorobiphenyl**	4300		952	50	06/07/11 16:17
134/143	**2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB**	21600		952	50	06/07/11 16:17
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	193000		952	50	06/07/11 16:17
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	82800		952	50	06/07/11 16:17
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		952	50	06/07/11 16:17
139/140	**2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB**	5020		952	50	06/07/11 16:17
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	125000		952	50	06/07/11 16:17
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
144	**2,2',3,4,5',6-Hexachlorobiphenyl**	27100		952	50	06/07/11 16:17
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
146	**2,2',3,4',5,5'-Hexachlorobiphenyl**	71200		952	50	06/07/11 16:17
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	416000		952	50	06/07/11 16:17
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	614000		952	50	06/07/11 16:17
154	**2,2',4,4',5,6'-Hexachlorobiphenyl**	2770		952	50	06/07/11 16:17
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	34900		952	50	06/07/11 16:17

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
158	**2,3,3',4,4',6-Hexachlorobiphenyl**	54100		952	50	06/07/11 16:17
159	**2,3,3',4,5,5'-Hexachlorobiphenyl**	5610		952	50	06/07/11 16:17
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 16:17
165	**2,3,3',5,5',6-Hexachlorobiphenyl**	1030		952	50	06/07/11 16:17
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	12100		952	50	06/07/11 16:17
169	**3,3',4,4',5,5'-Hexachlorobiphenyl**	1130		952	50	06/07/11 16:17
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	139000		952	50	06/07/11 16:17
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	45700		952	50	06/07/11 16:17
172	**2,2',3,3',4,5,5'-Heptachlorobiphenyl**	23500		952	50	06/07/11 16:17
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	163000		952	50	06/07/11 16:17
175	**2,2',3,3',4,5',6-Heptachlorobiphenyl**	6960		952	50	06/07/11 16:17
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	30600		952	50	06/07/11 16:17
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	88900		952	50	06/07/11 16:17
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	32500		952	50	06/07/11 16:17
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	101000		952	50	06/07/11 16:17
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	417000		952	50	06/07/11 16:17
181	**2,2',3,4,4',5,6-Heptachlorobiphenyl**	448	J	952	50	06/07/11 16:17
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		952	50	06/07/11 16:17
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	120000		952	50	06/07/11 16:17
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 16:17
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 16:17
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	217000		952	50	06/07/11 16:17
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 16:17
189	**2,3,3',4,4',5,5'-Heptachlorobiphenyl**	6810		952	50	06/07/11 16:17
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	40300		952	50	06/07/11 16:17
191	**2,3,3',4,4',5',6-Heptachlorobiphenyl**	7860		952	50	06/07/11 16:17
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		952	50	06/07/11 16:17
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	89500		952	50	06/07/11 16:17
195	**2,2',3,3',4,4',5,6-Octachlorobiphenyl**	34300		952	50	06/07/11 16:17
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	47800		952	50	06/07/11 16:17
197/200	**2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB**	19200		952	50	06/07/11 16:17
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	86200		952	50	06/07/11 16:17
201	**2,2',3,3',4,5',6,6'-Octachlorobiphenyl**	13600		952	50	06/07/11 16:17
202	**2,2',3,3',5,5',6,6'-Octachlorobiphenyl**	16300		952	50	06/07/11 16:17
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	58500		952	50	06/07/11 16:17
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		952	50	06/07/11 16:17
205	**2,3,3',4,4',5,5',6-Octachlorobiphenyl**	5500		952	50	06/07/11 16:17
206	**2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl**	21000		952	50	06/07/11 16:17

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
207	**2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl**	3520		952	50	06/07/11 16:17
208	**2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl**	3340		952	50	06/07/11 16:17
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	552	J	952	50	06/07/11 16:17
1-3	**Total Monochlorobiphenyl**	6710		952	50	06/07/11 16:17
4-15	**Total Dichlorobiphenyl**	291000		952	50	06/07/11 16:17
16-39	**Total Trichlorobiphenyl**	918000		952	50	06/07/11 16:17
40-81	**Total Tetrachlorobiphenyl**	534000		952	50	06/07/11 16:17
82-127	**Total Pentachlorobiphenyl**	720000		952	50	06/07/11 16:17
128-169	**Total Hexachlorobiphenyl**	2380000		952	50	06/07/11 16:17
170-193	**Total Heptachlorobiphenyl**	1440000		952	50	06/07/11 16:17
194-205	**Total Octachlorobiphenyl**	371000		952	50	06/07/11 16:17
206-208	**Total Nonachlorobiphenyl**	27800		952	50	06/07/11 16:17
209	**Decachlorobiphenyl**	552	J	952	50	06/07/11 16:17
Total PCBs	**Total PCBs**	6690000		952	50	06/07/11 16:17

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	78.4		78 %	*15-150*	*06/07/11 16:17*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	87.5		88 %	*15-150*	*06/07/11 16:17*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	69.5		69 %	*25-150*	*06/07/11 16:17*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	104		104 %	*25-150*	*06/07/11 16:17*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	84.6		85 %	*25-150*	*06/07/11 16:17*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	128		128 %	*25-150*	*06/07/11 16:17*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	88.4		88 %	*25-150*	*06/07/11 16:17*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	114		114 %	*25-150*	*06/07/11 16:17*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	117		117 %	*25-150*	*06/07/11 16:17*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	103		103 %	*25-150*	*06/07/11 16:17*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	129		129 %	*25-150*	*06/07/11 16:17*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	124		124 %	*25-150*	*06/07/11 16:17*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	129		129 %	*25-150*	*06/07/11 16:17*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	135		135 %	*25-150*	*06/07/11 16:17*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	123		123 %	*25-150*	*06/07/11 16:17*
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	48.0		48 %	*25-150*	*06/07/11 16:17*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	205		103 %	*25-150*	*06/07/11 16:17*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-01
Lab ID: 1104020-07
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	102		102 %	*25-150*	*06/07/11 16:17*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	117		117 %	*25-150*	*06/07/11 16:17*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	115		115 %	*25-150*	*06/07/11 16:17*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	123		123 %	*25-150*	*06/07/11 16:17*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 16:17*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	111		111 %	*25-150*	*06/07/11 16:17*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	111		111 %	*25-150*	*06/07/11 16:17*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	109		109 %	*25-150*	*06/07/11 16:17*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 16:17*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	132		132 %	*30-135*	*06/07/11 16:17*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	126		126 %	*30-135*	*06/07/11 16:17*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	120		120 %	*30-135*	*06/07/11 16:17*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-02
Lab ID: 1104020-08
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	**2-Monochlorobiphenyl**	137	J	980	50	06/07/11 17:38
2	3-Monochlorobiphenyl	U		980	50	06/07/11 17:38
3	4-Monochlorobiphenyl	U		980	50	06/07/11 17:38
4	**2,2'-Dichlorobiphenyl**	3070		980	50	06/07/11 17:38
5	2,3-Dichlorobiphenyl	U		980	50	06/07/11 17:38
6	**2,3'-Dichlorobiphenyl**	784	J	980	50	06/07/11 17:38
7	2,4-Dichlorobiphenyl	U		980	50	06/07/11 17:38
8	**2,4'-Dichlorobiphenyl**	2520		980	50	06/07/11 17:38
9	2,5-Dichlorobiphenyl	U		980	50	06/07/11 17:38
10	2,6-Dichlorobiphenyl	U		980	50	06/07/11 17:38
11	3,3'-Dichlorobiphenyl	U		980	50	06/07/11 17:38
12/13	3,4-DiCB/3,4'-DiCB	U		980	50	06/07/11 17:38
14	3,5-Dichlorobiphenyl	U		980	50	06/07/11 17:38
15	**4,4'-Dichlorobiphenyl**	1450		980	50	06/07/11 17:38
16/24	**2,2',3-TrCB/2,3,6-TrCB**	2440		980	50	06/07/11 17:38
17	**2,2',4-Trichlorobiphenyl**	2750		980	50	06/07/11 17:38
18/30	**2,2',5-TrCB/2,4,6-TrCB**	7360		980	50	06/07/11 17:38
19	**2,2',6-Trichlorobiphenyl**	873	J	980	50	06/07/11 17:38
20/28	**2,3,3'-TrCB/2,4,4'-TrCB**	7640		980	50	06/07/11 17:38
21/33	**2,3,4-TrCB/2,3',4'-TrCB**	3220		980	50	06/07/11 17:38
22	**2,3,4'-Trichlorobiphenyl**	2500		980	50	06/07/11 17:38
23	2,3,5-Trichlorobiphenyl	U		980	50	06/07/11 17:38
25	**2,3',4-Trichlorobiphenyl**	686	J	980	50	06/07/11 17:38
26/29	**2,3',5-TrCB/2,4,5-TrCB**	1550		980	50	06/07/11 17:38
27	**2,3',6-Trichlorobiphenyl**	529	J	980	50	06/07/11 17:38
31	**2,4',5-Trichlorobiphenyl**	7510		980	50	06/07/11 17:38
32	**2,4',6-Trichlorobiphenyl**	2650		980	50	06/07/11 17:38
34	2,3',5'-Trichlorobiphenyl	U		980	50	06/07/11 17:38
35	3,3',4-Trichlorobiphenyl	U		980	50	06/07/11 17:38
36	3,3',5-Trichlorobiphenyl	U		980	50	06/07/11 17:38
37	**3,4,4'-Trichlorobiphenyl**	1680		980	50	06/07/11 17:38
38	3,4,5-Trichlorobiphenyl	U		980	50	06/07/11 17:38
39	3,4',5-Trichlorobiphenyl	U		980	50	06/07/11 17:38
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	1890		980	50	06/07/11 17:38
42	**2,2',3,4'-Tetrachlorobiphenyl**	961	J	980	50	06/07/11 17:38
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		980	50	06/07/11 17:38
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	4890		980	50	06/07/11 17:38
45/51	**2,2',3,6-TeCB/2,2',4,6'-TeCB**	686	J	980	50	06/07/11 17:38
46	**2,2',3,6'-Tetrachlorobiphenyl**	206	EMPC, J	980	50	06/07/11 17:38

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-02
Lab ID: 1104020-08
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	**2,2',4,5-Tetrachlorobiphenyl**	843	J	980	50	06/07/11 17:38
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	3110		980	50	06/07/11 17:38
50/53	**2,2',4,6-TeCB/2,2',5,6'-TeCB**	627	J	980	50	06/07/11 17:38
52	**2,2',5,5'-Tetrachlorobiphenyl**	7830		980	50	06/07/11 17:38
54	2,2',6,6'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
55	2,3,3',4-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
56	**2,3,3',4'-Tetrachlorobiphenyl**	2230		980	50	06/07/11 17:38
57	2,3,3',5-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
58	2,3,3',5'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
59/62/75	**2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB**	363	J	980	50	06/07/11 17:38
60	**2,3,4,4'-Tetrachlorobiphenyl**	1080		980	50	06/07/11 17:38
61/70/74/76	**TeCB-61/70/74/76**	19000	EMPC	980	50	06/07/11 17:38
63	2,3,4',5-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
64	**2,3,4',6-Tetrachlorobiphenyl**	2380		980	50	06/07/11 17:38
66	**2,3',4,4'-Tetrachlorobiphenyl**	5250		980	50	06/07/11 17:38
67	2,3',4,5-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
68	2,3',4,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
72	2,3',5,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
77	**3,3',4,4'-Tetrachlorobiphenyl**	422	J	980	50	06/07/11 17:38
78	3,3',4,5-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
79	3,3',4,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
80	3,3',5,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
81	3,4,4',5-Tetrachlorobiphenyl	U		980	50	06/07/11 17:38
82	**2,2',3,3',4-Pentachlorobiphenyl**	1030		980	50	06/07/11 17:38
83/99/112	**2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB**	6490		980	50	06/07/11 17:38
84	**2,2',3,3',6-Pentachlorobiphenyl**	2250		980	50	06/07/11 17:38
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	2100		980	50	06/07/11 17:38
86/87/97/109/119/125	**PeCB-86/87/97/109/119/125**	9660		980	50	06/07/11 17:38
88/91	**2,2',3,4,6-PeCB/2,2',3,4',6-PeCB**	1280		980	50	06/07/11 17:38
89	2,2',3,4,6'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	17100		980	50	06/07/11 17:38
92	**2,2',3,5,5'-Pentachlorobiphenyl**	2490		980	50	06/07/11 17:38
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		980	50	06/07/11 17:38
94	2,2',3,5,6'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
95	**2,2',3,5',6-Pentachlorobiphenyl**	9230		980	50	06/07/11 17:38
96	**2,2',3,6,6'-Pentachlorobiphenyl**	88.2	J	980	50	06/07/11 17:38
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		980	50	06/07/11 17:38

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-02
Lab ID: 1104020-08
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
103	2,2',4,5',6-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
104	2,2',4,6,6'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
105	**2,3,3',4,4'-Pentachlorobiphenyl**	5840		980	50	06/07/11 17:38
106	2,3,3',4,5-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
107	**2,3,3',4',5-Pentachlorobiphenyl**	951	J	980	50	06/07/11 17:38
108/124	**2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB**	539	J	980	50	06/07/11 17:38
110/115	**2,3,3',4',6-PeCB/2,3,4,4',6-PeCB**	18300		980	50	06/07/11 17:38
111	2,3,3',5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
114	2,3,4,4',5-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
118	**2,3',4,4',5-Pentachlorobiphenyl**	15400		980	50	06/07/11 17:38
120	2,3',4,5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
121	2,3',4,5',6-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
122	2,3,3',4',5'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
123	**2,3',4,4',5'-Pentachlorobiphenyl**	255	J	980	50	06/07/11 17:38
126	3,3',4,4',5-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
127	3,3',4,5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 17:38
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		980	50	06/07/11 17:38
129/138/163	**HxCB-129/138/163**	27300		980	50	06/07/11 17:38
130	**2,2',3,3',4,5'-Hexachlorobiphenyl**	951	J	980	50	06/07/11 17:38
131	2,2',3,3',4,6-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	6220		980	50	06/07/11 17:38
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
134/143	**2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB**	941	J	980	50	06/07/11 17:38
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	7960		980	50	06/07/11 17:38
136	**2,2',3,3',6,6'-Hexachlorobiphenyl**	3810		980	50	06/07/11 17:38
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		980	50	06/07/11 17:38
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U		980	50	06/07/11 17:38
141	**2,2',3,4,5,5'-Hexachlorobiphenyl**	5340		980	50	06/07/11 17:38
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
144	**2,2',3,4,5',6-Hexachlorobiphenyl**	1270	EMPC	980	50	06/07/11 17:38
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
146	**2,2',3,4',5,5'-Hexachlorobiphenyl**	3340		980	50	06/07/11 17:38
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	19400		980	50	06/07/11 17:38
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	29100		980	50	06/07/11 17:38
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38

Site Name: Metal Bank of America - State Road Site
Station ID: WW-02
Sample Matrix: Wastewater
Project #: DAS R33687
Lab ID: 1104020-08
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
156/157	**2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB**	3130		980	50	06/07/11 17:38
158	**2,3,3',4,4',6-Hexachlorobiphenyl**	3190		980	50	06/07/11 17:38
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
167	**2,3',4,4',5,5'-Hexachlorobiphenyl**	961	J	980	50	06/07/11 17:38
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 17:38
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	6030		980	50	06/07/11 17:38
171/173	**2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB**	2190		980	50	06/07/11 17:38
172	**2,2',3,3',4,5,5'-Heptachlorobiphenyl**	1050		980	50	06/07/11 17:38
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	6810		980	50	06/07/11 17:38
175	**2,2',3,3',4,5',6-Heptachlorobiphenyl**	353	EMPC, J	980	50	06/07/11 17:38
176	**2,2',3,3',4,6,6'-Heptachlorobiphenyl**	1230		980	50	06/07/11 17:38
177	**2,2',3,3',4,5',6'-Heptachlorobiphenyl**	3700		980	50	06/07/11 17:38
178	**2,2',3,3',5,5',6-Heptachlorobiphenyl**	1320		980	50	06/07/11 17:38
179	**2,2',3,3',5,6,6'-Heptachlorobiphenyl**	4030		980	50	06/07/11 17:38
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	18500		980	50	06/07/11 17:38
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
183/185	**2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB**	4590		980	50	06/07/11 17:38
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	8790		980	50	06/07/11 17:38
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
190	**2,3,3',4,4',5,6-Heptachlorobiphenyl**	1770		980	50	06/07/11 17:38
191	**2,3,3',4,4',5',6-Heptachlorobiphenyl**	402	J	980	50	06/07/11 17:38
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		980	50	06/07/11 17:38
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	3910		980	50	06/07/11 17:38
195	**2,2',3,3',4,4',5,6-Octachlorobiphenyl**	1620		980	50	06/07/11 17:38
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	1940		980	50	06/07/11 17:38
197/200	**2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB**	696	J	980	50	06/07/11 17:38
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	3730		980	50	06/07/11 17:38
201	**2,2',3,3',4,5',6,6'-Octachlorobiphenyl**	637	J	980	50	06/07/11 17:38
202	**2,2',3,3',5,5',6,6'-Octachlorobiphenyl**	696	J	980	50	06/07/11 17:38
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	2600		980	50	06/07/11 17:38
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		980	50	06/07/11 17:38
205	**2,3,3',4,4',5,5',6-Octachlorobiphenyl**	265	J	980	50	06/07/11 17:38

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-02
Lab ID: 1104020-08
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
206	**2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl**	1060		980	50	06/07/11 17:38
207	**2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl**	196	J	980	50	06/07/11 17:38
208	**2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl**	235	J	980	50	06/07/11 17:38
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	127	J	980	50	06/07/11 17:38
1-3	**Total Monochlorobiphenyl**	137	J	980	50	06/07/11 17:38
4-15	**Total Dichlorobiphenyl**	7820		980	50	06/07/11 17:38
16-39	**Total Trichlorobiphenyl**	41400		980	50	06/07/11 17:38
40-81	**Total Tetrachlorobiphenyl**	52100		980	50	06/07/11 17:38
82-127	**Total Pentachlorobiphenyl**	90500		980	50	06/07/11 17:38
128-169	**Total Hexachlorobiphenyl**	119000		980	50	06/07/11 17:38
170-193	**Total Heptachlorobiphenyl**	60800		980	50	06/07/11 17:38
194-205	**Total Octachlorobiphenyl**	16100		980	50	06/07/11 17:38
206-208	**Total Nonachlorobiphenyl**	1490		980	50	06/07/11 17:38
209	**Decachlorobiphenyl**	127	J	980	50	06/07/11 17:38
Total PCBs	**Total PCBs**	389000		980	50	06/07/11 17:38

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	78.2		78 %	*15-150*	*06/07/11 17:38*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	86.4		86 %	*15-150*	*06/07/11 17:38*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	74.3		74 %	*25-150*	*06/07/11 17:38*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	106		106 %	*25-150*	*06/07/11 17:38*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	85.8		86 %	*25-150*	*06/07/11 17:38*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	130		130 %	*25-150*	*06/07/11 17:38*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	88.0		88 %	*25-150*	*06/07/11 17:38*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	114		114 %	*25-150*	*06/07/11 17:38*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	115		115 %	*25-150*	*06/07/11 17:38*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	85.1		85 %	*25-150*	*06/07/11 17:38*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	108		108 %	*25-150*	*06/07/11 17:38*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 17:38*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	107		107 %	*25-150*	*06/07/11 17:38*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	111		111 %	*25-150*	*06/07/11 17:38*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 17:38*
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	115		115 %	*25-150*	*06/07/11 17:38*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-02
Lab ID: 1104020-08
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	210		105 %	*25-150*	*06/07/11 17:38*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 17:38*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	121		121 %	*25-150*	*06/07/11 17:38*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	106		106 %	*25-150*	*06/07/11 17:38*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	117		117 %	*25-150*	*06/07/11 17:38*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	89.4		89 %	*25-150*	*06/07/11 17:38*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	118		118 %	*25-150*	*06/07/11 17:38*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	119		119 %	*25-150*	*06/07/11 17:38*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	97.1		97 %	*25-150*	*06/07/11 17:38*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	110		110 %	*25-150*	*06/07/11 17:38*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	135		135 %	*30-135*	*06/07/11 17:38*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	104		104 %	*30-135*	*06/07/11 17:38*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	125		125 %	*30-135*	*06/07/11 17:38*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	2-Monochlorobiphenyl	U		952	50	06/07/11 19:01
2	3-Monochlorobiphenyl	U		952	50	06/07/11 19:01
3	4-Monochlorobiphenyl	U		952	50	06/07/11 19:01
4	2,2'-Dichlorobiphenyl	U		952	50	06/07/11 19:01
5	2,3-Dichlorobiphenyl	U		952	50	06/07/11 19:01
6	2,3'-Dichlorobiphenyl	U		952	50	06/07/11 19:01
7	2,4-Dichlorobiphenyl	U		952	50	06/07/11 19:01
8	2,4'-Dichlorobiphenyl	U		952	50	06/07/11 19:01
9	2,5-Dichlorobiphenyl	U		952	50	06/07/11 19:01
10	2,6-Dichlorobiphenyl	U		952	50	06/07/11 19:01
11	3,3'-Dichlorobiphenyl	U		952	50	06/07/11 19:01
12/13	3,4-DiCB/3,4'-DiCB	U		952	50	06/07/11 19:01
14	3,5-Dichlorobiphenyl	U		952	50	06/07/11 19:01
15	4,4'-Dichlorobiphenyl	U		952	50	06/07/11 19:01
16/24	2,2',3-TrCB/2,3,6-TrCB	U		952	50	06/07/11 19:01
17	2,2',4-Trichlorobiphenyl	U		952	50	06/07/11 19:01
18/30	2,2',5-TrCB/2,4,6-TrCB	U		952	50	06/07/11 19:01
19	2,2',6-Trichlorobiphenyl	U		952	50	06/07/11 19:01
20/28	2,3,3'-TrCB/2,4,4'-TrCB	U		952	50	06/07/11 19:01
21/33	2,3,4-TrCB/2,3',4'-TrCB	U		952	50	06/07/11 19:01
22	2,3,4'-Trichlorobiphenyl	U		952	50	06/07/11 19:01
23	2,3,5-Trichlorobiphenyl	U		952	50	06/07/11 19:01
25	2,3',4-Trichlorobiphenyl	U		952	50	06/07/11 19:01
26/29	2,3',5-TrCB/2,4,5-TrCB	U		952	50	06/07/11 19:01
27	2,3',6-Trichlorobiphenyl	U		952	50	06/07/11 19:01
31	2,4',5-Trichlorobiphenyl	U		952	50	06/07/11 19:01
32	2,4',6-Trichlorobiphenyl	U		952	50	06/07/11 19:01
34	2,3',5'-Trichlorobiphenyl	U		952	50	06/07/11 19:01
35	3,3',4-Trichlorobiphenyl	U		952	50	06/07/11 19:01
36	3,3',5-Trichlorobiphenyl	U		952	50	06/07/11 19:01
37	3,4,4'-Trichlorobiphenyl	U		952	50	06/07/11 19:01
38	3,4,5-Trichlorobiphenyl	U		952	50	06/07/11 19:01
39	3,4',5-Trichlorobiphenyl	U		952	50	06/07/11 19:01
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	U		952	50	06/07/11 19:01
42	2,2',3,4'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		952	50	06/07/11 19:01
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	U		952	50	06/07/11 19:01
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U		952	50	06/07/11 19:01
46	2,2',3,6'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	2,2',4,5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	U		952	50	06/07/11 19:01
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U		952	50	06/07/11 19:01
52	2,2',5,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
54	2,2',6,6'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
55	2,3,3',4-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
56	2,3,3',4'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
57	2,3,3',5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
58	2,3,3',5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U		952	50	06/07/11 19:01
60	2,3,4,4'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
61/70/74/76	**TeCB-61/70/74/76**	8050	EMPC	952	50	06/07/11 19:01
63	2,3,4',5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
64	2,3,4',6-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
66	2,3',4,4'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
67	2,3',4,5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
68	2,3',4,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
72	2,3',5,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
77	3,3',4,4'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
78	3,3',4,5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
79	3,3',4,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
80	3,3',5,5'-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
81	3,4,4',5-Tetrachlorobiphenyl	U		952	50	06/07/11 19:01
82	2,2',3,3',4-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	U		952	50	06/07/11 19:01
84	2,2',3,3',6-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
85/116/117	**2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB**	267	J	952	50	06/07/11 19:01
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	U		952	50	06/07/11 19:01
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	U		952	50	06/07/11 19:01
89	2,2',3,4,6'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
90/101/113	**2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB**	181	J	952	50	06/07/11 19:01
92	2,2',3,5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		952	50	06/07/11 19:01
94	2,2',3,5,6'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
95	**2,2',3,5',6-Pentachlorobiphenyl**	133	J	952	50	06/07/11 19:01
96	2,2',3,6,6'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		952	50	06/07/11 19:01
103	2,2',4,5',6-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
104	2,2',4,6,6'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
105	**2,3,3',4,4'-Pentachlorobiphenyl**	352	EMPC, J	952	50	06/07/11 19:01
106	2,3,3',4,5-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
107	2,3,3',4',5-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U		952	50	06/07/11 19:01
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	U		952	50	06/07/11 19:01
111	2,3,3',5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
114	2,3,4,4',5-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
118	**2,3',4,4',5-Pentachlorobiphenyl**	229	J	952	50	06/07/11 19:01
120	2,3',4,5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
121	2,3',4,5',6-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
122	2,3,3',4',5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
123	2,3',4,4',5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
126	3,3',4,4',5-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
127	3,3',4,5,5'-Pentachlorobiphenyl	U		952	50	06/07/11 19:01
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		952	50	06/07/11 19:01
129/138/163	**HxCB-129/138/163**	305	J	952	50	06/07/11 19:01
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
131	2,2',3,3',4,6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
132	**2,2',3,3',4,6'-Hexachlorobiphenyl**	105	J	952	50	06/07/11 19:01
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U		952	50	06/07/11 19:01
135/151	**2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB**	133	J	952	50	06/07/11 19:01
136	2,2',3,3',6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		952	50	06/07/11 19:01
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U		952	50	06/07/11 19:01
141	2,2',3,4,5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
144	2,2',3,4,5',6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
146	2,2',3,4',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
147/149	**2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB**	248	J	952	50	06/07/11 19:01
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
153/168	**2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB**	295	J	952	50	06/07/11 19:01
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	U		952	50	06/07/11 19:01
158	2,3,3',4,4',6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		952	50	06/07/11 19:01
170	**2,2',3,3',4,4',5-Heptachlorobiphenyl**	200	EMPC, J	952	50	06/07/11 19:01
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	U		952	50	06/07/11 19:01
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
174	**2,2',3,3',4,5,6'-Heptachlorobiphenyl**	105	EMPC, J	952	50	06/07/11 19:01
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	229	J	952	50	06/07/11 19:01
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	U		952	50	06/07/11 19:01
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
187	**2,2',3,4',5,5',6-Heptachlorobiphenyl**	124	EMPC, J	952	50	06/07/11 19:01
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		952	50	06/07/11 19:01
194	**2,2',3,3',4,4',5,5'-Octachlorobiphenyl**	95.2	J	952	50	06/07/11 19:01
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U		952	50	06/07/11 19:01
196	**2,2',3,3',4,4',5,6'-Octachlorobiphenyl**	57.1	EMPC, J	952	50	06/07/11 19:01
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U		952	50	06/07/11 19:01
198/199	**2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB**	57.1	J	952	50	06/07/11 19:01
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U		952	50	06/07/11 19:01
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U		952	50	06/07/11 19:01
203	**2,2',3,4,4',5,5',6-Octachlorobiphenyl**	57.1	EMPC, J	952	50	06/07/11 19:01

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1050ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		952	50	06/07/11 19:01
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U		952	50	06/07/11 19:01
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U		952	50	06/07/11 19:01
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U		952	50	06/07/11 19:01
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U		952	50	06/07/11 19:01
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U		952	50	06/07/11 19:01
1-3	Total Monochlorobiphenyl	U		952	50	06/07/11 19:01
4-15	Total Dichlorobiphenyl	U		952	50	06/07/11 19:01
16-39	Total Trichlorobiphenyl	U		952	50	06/07/11 19:01
40-81	**Total Tetrachlorobiphenyl**	8050		952	50	06/07/11 19:01
82-127	**Total Pentachlorobiphenyl**	1160		952	50	06/07/11 19:01
128-169	**Total Hexachlorobiphenyl**	1090		952	50	06/07/11 19:01
170-193	**Total Heptachlorobiphenyl**	657	J	952	50	06/07/11 19:01
194-205	**Total Octachlorobiphenyl**	267	J	952	50	06/07/11 19:01
206-208	Total Nonachlorobiphenyl	U		952	50	06/07/11 19:01
209	Decachlorobiphenyl	U		952	50	06/07/11 19:01
Total PCBs	**Total PCBs**	11200		952	50	06/07/11 19:01

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	77.7		78 %	*15-150*	*06/07/11 19:01*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	88.8		89 %	*15-150*	*06/07/11 19:01*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	72.2		72 %	*25-150*	*06/07/11 19:01*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	110		110 %	*25-150*	*06/07/11 19:01*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	83.7		84 %	*25-150*	*06/07/11 19:01*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	134		134 %	*25-150*	*06/07/11 19:01*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	88.8		89 %	*25-150*	*06/07/11 19:01*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	126		126 %	*25-150*	*06/07/11 19:01*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	129		129 %	*25-150*	*06/07/11 19:01*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	101		101 %	*25-150*	*06/07/11 19:01*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	148		148 %	*25-150*	*06/07/11 19:01*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	142		142 %	*25-150*	*06/07/11 19:01*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	144		144 %	*25-150*	*06/07/11 19:01*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	153		153 %	*25-150*	*06/07/11 19:01*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-03
Lab ID: 1104020-09
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	141		141 %	*25-150*	*06/07/11 19:01*
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	71.4		71 %	*25-150*	*06/07/11 19:01*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	200		100 %	*25-150*	*06/07/11 19:01*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	99.8		100 %	*25-150*	*06/07/11 19:01*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	115		115 %	*25-150*	*06/07/11 19:01*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	96.6		97 %	*25-150*	*06/07/11 19:01*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	113		113 %	*25-150*	*06/07/11 19:01*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	91.3		91 %	*25-150*	*06/07/11 19:01*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	111		111 %	*25-150*	*06/07/11 19:01*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	112		112 %	*25-150*	*06/07/11 19:01*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	105		105 %	*25-150*	*06/07/11 19:01*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	101		101 %	*25-150*	*06/07/11 19:01*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	129		129 %	*30-135*	*06/07/11 19:01*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	134		134 %	*30-135*	*06/07/11 19:01*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	115		115 %	*30-135*	*06/07/11 19:01*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
1	2-Monochlorobiphenyl	U		980	50	06/07/11 20:24
2	3-Monochlorobiphenyl	U		980	50	06/07/11 20:24
3	4-Monochlorobiphenyl	U		980	50	06/07/11 20:24
4	2,2'-Dichlorobiphenyl	U		980	50	06/07/11 20:24
5	2,3-Dichlorobiphenyl	U		980	50	06/07/11 20:24
6	2,3'-Dichlorobiphenyl	U		980	50	06/07/11 20:24
7	2,4-Dichlorobiphenyl	U		980	50	06/07/11 20:24
8	2,4'-Dichlorobiphenyl	U		980	50	06/07/11 20:24
9	2,5-Dichlorobiphenyl	U		980	50	06/07/11 20:24
10	2,6-Dichlorobiphenyl	U		980	50	06/07/11 20:24
11	3,3'-Dichlorobiphenyl	U		980	50	06/07/11 20:24
12/13	3,4-DiCB/3,4'-DiCB	U		980	50	06/07/11 20:24
14	3,5-Dichlorobiphenyl	U		980	50	06/07/11 20:24
15	4,4'-Dichlorobiphenyl	U		980	50	06/07/11 20:24
16/24	2,2',3-TrCB/2,3,6-TrCB	U		980	50	06/07/11 20:24
17	2,2',4-Trichlorobiphenyl	U		980	50	06/07/11 20:24
18/30	**2,2',5-TrCB/2,4,6-TrCB**	127	J	980	50	06/07/11 20:24
19	2,2',6-Trichlorobiphenyl	U		980	50	06/07/11 20:24
20/28	2,3,3'-TrCB/2,4,4'-TrCB	U		980	50	06/07/11 20:24
21/33	2,3,4-TrCB/2,3',4'-TrCB	U		980	50	06/07/11 20:24
22	2,3,4'-Trichlorobiphenyl	U		980	50	06/07/11 20:24
23	2,3,5-Trichlorobiphenyl	U		980	50	06/07/11 20:24
25	2,3',4-Trichlorobiphenyl	U		980	50	06/07/11 20:24
26/29	2,3',5-TrCB/2,4,5-TrCB	U		980	50	06/07/11 20:24
27	2,3',6-Trichlorobiphenyl	U		980	50	06/07/11 20:24
31	**2,4',5-Trichlorobiphenyl**	265	J	980	50	06/07/11 20:24
32	2,4',6-Trichlorobiphenyl	U		980	50	06/07/11 20:24
34	2,3',5'-Trichlorobiphenyl	U		980	50	06/07/11 20:24
35	3,3',4-Trichlorobiphenyl	U		980	50	06/07/11 20:24
36	3,3',5-Trichlorobiphenyl	U		980	50	06/07/11 20:24
37	3,4,4'-Trichlorobiphenyl	U		980	50	06/07/11 20:24
38	3,4,5-Trichlorobiphenyl	U		980	50	06/07/11 20:24
39	3,4',5-Trichlorobiphenyl	U		980	50	06/07/11 20:24
40/41/71	**2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB**	49.0	EMPC, J	980	50	06/07/11 20:24
42	2,2',3,4'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U		980	50	06/07/11 20:24
44/47/65	**2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB**	98.0	J	980	50	06/07/11 20:24
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U		980	50	06/07/11 20:24
46	2,2',3,6'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
48	2,2',4,5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
49/69	**2,2',4,5'-TeCB/2,3',4,6-TeCB**	68.6	EMPC, J	980	50	06/07/11 20:24
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U		980	50	06/07/11 20:24
52	**2,2',5,5'-Tetrachlorobiphenyl**	88.2	EMPC, J	980	50	06/07/11 20:24
54	2,2',6,6'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
55	2,3,3',4-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
56	2,3,3',4'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
57	2,3,3',5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
58	2,3,3',5'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U		980	50	06/07/11 20:24
60	2,3,4,4'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
61/70/74/76	**TeCB-61/70/74/76**	4210	EMPC	980	50	06/07/11 20:24
63	2,3,4',5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
64	**2,3,4',6-Tetrachlorobiphenyl**	39.2	J	980	50	06/07/11 20:24
66	2,3',4,4'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
67	2,3',4,5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
68	2,3',4,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
72	2,3',5,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
77	3,3',4,4'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
78	3,3',4,5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
79	3,3',4,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
80	3,3',5,5'-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
81	3,4,4',5-Tetrachlorobiphenyl	U		980	50	06/07/11 20:24
82	2,2',3,3',4-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	U		980	50	06/07/11 20:24
84	2,2',3,3',6-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	U		980	50	06/07/11 20:24
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	U		980	50	06/07/11 20:24
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	U		980	50	06/07/11 20:24
89	2,2',3,4,6'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	U		980	50	06/07/11 20:24
92	2,2',3,5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U		980	50	06/07/11 20:24
94	2,2',3,5,6'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
95	2,2',3,5',6-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
96	2,2',3,6,6'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U		980	50	06/07/11 20:24

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
103	2,2',4,5',6-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
104	2,2',4,6,6'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
105	2,3,3',4,4'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
106	2,3,3',4,5-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
107	2,3,3',4',5-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U		980	50	06/07/11 20:24
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	U		980	50	06/07/11 20:24
111	2,3,3',5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
114	2,3,4,4',5-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
118	**2,3',4,4',5-Pentachlorobiphenyl**	118	EMPC, J	980	50	06/07/11 20:24
120	2,3',4,5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
121	2,3',4,5',6-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
122	2,3,3',4',5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
123	2,3',4,4',5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
126	3,3',4,4',5-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
127	3,3',4,5,5'-Pentachlorobiphenyl	U		980	50	06/07/11 20:24
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U		980	50	06/07/11 20:24
129/138/163	HxCB-129/138/163	U		980	50	06/07/11 20:24
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
131	2,2',3,3',4,6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
132	2,2',3,3',4,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U		980	50	06/07/11 20:24
135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	U		980	50	06/07/11 20:24
136	2,2',3,3',6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U		980	50	06/07/11 20:24
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U		980	50	06/07/11 20:24
141	2,2',3,4,5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
142	2,2',3,4,5,6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
144	2,2',3,4,5',6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
146	2,2',3,4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	U		980	50	06/07/11 20:24
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	U		980	50	06/07/11 20:24
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	U		980	50	06/07/11 20:24
158	2,3,3',4,4',6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
160	2,3,3',4,5,6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
161	2,3,3',4,5',6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
165	2,3,3',5,5',6-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U		980	50	06/07/11 20:24
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	U		980	50	06/07/11 20:24
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
180/193	**2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB**	196	J	980	50	06/07/11 20:24
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	U		980	50	06/07/11 20:24
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U		980	50	06/07/11 20:24
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	U		980	50	06/07/11 20:24
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U		980	50	06/07/11 20:24
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	U		980	50	06/07/11 20:24
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U		980	50	06/07/11 20:24
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	U		980	50	06/07/11 20:24
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U		980	50	06/07/11 20:24
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U		980	50	06/07/11 20:24
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	U		980	50	06/07/11 20:24
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U		980	50	06/07/11 20:24

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Targets (Continued)

Batch: BE10403 **Sample Volume:** **1020ml** **Method/SOP#:** EPA 1668a

Congener Number:	Analyte	Result pg/L	Flags Qualifiers	Quantitation Limit	Dilution Factor	Date Analyzed
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U		980	50	06/07/11 20:24
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U		980	50	06/07/11 20:24
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U		980	50	06/07/11 20:24
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U		980	50	06/07/11 20:24
209	**2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl**	196	J	980	50	06/07/11 20:24
1-3	Total Monochlorobiphenyl	U		980	50	06/07/11 20:24
4-15	Total Dichlorobiphenyl	U		980	50	06/07/11 20:24
16-39	**Total Trichlorobiphenyl**	392	J	980	50	06/07/11 20:24
40-81	**Total Tetrachlorobiphenyl**	4550		980	50	06/07/11 20:24
82-127	**Total Pentachlorobiphenyl**	118	J	980	50	06/07/11 20:24
128-169	Total Hexachlorobiphenyl	U		980	50	06/07/11 20:24
170-193	**Total Heptachlorobiphenyl**	196	J	980	50	06/07/11 20:24
194-205	Total Octachlorobiphenyl	U		980	50	06/07/11 20:24
206-208	Total Nonachlorobiphenyl	U		980	50	06/07/11 20:24
209	**Decachlorobiphenyl**	196	J	980	50	06/07/11 20:24
Total PCBs	**Total PCBs**	5450		980	50	06/07/11 20:24

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
1L	*Surrogate: 13C12-2-Monochlorobiphenyl*	77.2		77 %	*15-150*	*06/07/11 20:24*
3L	*Surrogate: 13C12-4-Monochlorobiphenyl*	86.2		86 %	*15-150*	*06/07/11 20:24*
4L	*Surrogate: 13C12-2,2'-Dichlorobiphenyl*	72.0		72 %	*25-150*	*06/07/11 20:24*
15L	*Surrogate: 13C12-4,4'-Dichlorobiphenyl*	113		113 %	*25-150*	*06/07/11 20:24*
19L	*Surrogate: 13C12-2,2',6-Trichlorobiphenyl*	86.9		87 %	*25-150*	*06/07/11 20:24*
37L	*Surrogate: 13C12-3,4,4'-Trichlorobiphenyl*	140		140 %	*25-150*	*06/07/11 20:24*
54L	*Surrogate: 13C12-2,2',6,6'-Tetrachlorobiphenyl*	92.0		92 %	*25-150*	*06/07/11 20:24*
77L	*Surrogate: 13C12-3,3',4,4'-Tetrachlorobiphenyl*	126		126 %	*25-150*	*06/07/11 20:24*
81L	*Surrogate: 13C12-3,4,4',5-Tetrachlorobiphenyl*	129		129 %	*25-150*	*06/07/11 20:24*
104L	*Surrogate: 13C12-2,2',4,6,6'-Pentachlorobiphenyl*	77.0		77 %	*25-150*	*06/07/11 20:24*
105L	*Surrogate: 13C12-2,3,3',4,4'-Pentachlorobiphenyl*	109		109 %	*25-150*	*06/07/11 20:24*
114 L	*Surrogate: 13C12-2,3,4,4',5-Pentachlorobiphenyl*	105		105 %	*25-150*	*06/07/11 20:24*
118 L	*Surrogate: 13C12-2,3',4,4',5-Pentachlorobiphenyl*	108		108 %	*25-150*	*06/07/11 20:24*
123L	*Surrogate: 13C12-2',3,4,4',5-Pentachlorobiphenyl*	113		113 %	*25-150*	*06/07/11 20:24*
126L	*Surrogate: 13C12-3,3',4,4',5-Pentachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 20:24*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: WW-04
Lab ID: 1104020-10
Sample Matrix: Wastewater
Date Collected: 04/27/2011

PCB Congeners

Surrogates

Congener Number:	Analyte	Result ng/mL	Flags Qualifiers	%Rec	%Rec Limit	Date Analyzed
155L	*Surrogate: 13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	108		108 %	*25-150*	*06/07/11 20:24*
156L/157L	*Surrogate: 13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	208		104 %	*25-150*	*06/07/11 20:24*
167L	*Surrogate: 13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	104		104 %	*25-150*	*06/07/11 20:24*
169L	*Surrogate: 13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	120		120 %	*25-150*	*06/07/11 20:24*
188L	*Surrogate: 13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	110		110 %	*25-150*	*06/07/11 20:24*
189L	*Surrogate: 13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	124		124 %	*25-150*	*06/07/11 20:24*
202L	*Surrogate: 13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	100		100 %	*25-150*	*06/07/11 20:24*
205L	*Surrogate: 13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	119		119 %	*25-150*	*06/07/11 20:24*
206L	*Surrogate: 13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	126		126 %	*25-150*	*06/07/11 20:24*
208L	*Surrogate: 13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	103		103 %	*25-150*	*06/07/11 20:24*
209L	*Surrogate: 13C12-Decachlorobiphenyl*	116		116 %	*25-150*	*06/07/11 20:24*
28L	*Surrogate: 13C12-2,4,4'-Trichlorobiphenyl*	140		140 %	*30-135*	*06/07/11 20:24*
111 L	*Surrogate: 13C12-2,3,3',5,5'-Pentachlorobiphenyl*	105		105 %	*30-135*	*06/07/11 20:24*
178L	*Surrogate: 13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	123		123 %	*30-135*	*06/07/11 20:24*

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-01
Lab ID: 1104020-01
Sample Matrix: Sediment
Date Collected: 04/27/2011

Physical Parameters
Targets

Analyte	Result % by Weight	Flags Qualifiers	Quantitation Limit	Dilution	Prepared	Analyzed	Method/SOP#
% Solids	86.0	C, J		1	05/16/11	05/19/11 09:30	USGS I-5753-85

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-02
Lab ID: 1104020-02
Sample Matrix: Sediment
Date Collected: 04/27/2011

Physical Parameters
Targets

Analyte	Result % by Weight	Flags Qualifiers	Quantitation Limit	Dilution	Prepared	Analyzed	Method/SOP#
% Solids	0.1	C, J		1	05/16/11	05/19/11 09:30	USGS I-5753-85

Site Name: Metal Bank of America - State Road Site
Project #: DAS R33687
Station ID: SD-03
Lab ID: 1104020-03
Sample Matrix: Sediment
Date Collected: 04/27/2011

Physical Parameters
Targets

Analyte	Result % by Weight	Flags Qualifiers	Quantitation Limit	Dilution	Prepared	Analyzed	Method/SOP#
% Solids	65.9	C, J		1	05/16/11	05/19/11 09:30	USGS I-5753-85

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
Physical Parameters

Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10201 - PD60/PD105										
Duplicate (BE10201-DUP1)		**Source: 1104020-01**		Prepared: 05/16/11 09:30		Analyzed: 05/19/11 09:30				
% Solids	84.6		% by Weight		86.0			2	20	J, C

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK1) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 21:26

1	2-Monochlorobiphenyl	U	20.0	pg/L							
2	3-Monochlorobiphenyl	U	20.0	"							
3	4-Monochlorobiphenyl	U	20.0	"							
4	2,2'-Dichlorobiphenyl	U	20.0	"							
5	2,3-Dichlorobiphenyl	U	20.0	"							
6	2,3'-Dichlorobiphenyl	U	20.0	"							
7	2,4-Dichlorobiphenyl	U	20.0	"							
8	2,4'-Dichlorobiphenyl	U	20.0	"							
9	2,5-Dichlorobiphenyl	U	20.0	"							
10	2,6-Dichlorobiphenyl	U	20.0	"							
11	3,3'-Dichlorobiphenyl	39.6	20.0	"							EMPC
12/13	3,4-DiCB/3,4'-DiCB	U	20.0	"							
14	3,5-Dichlorobiphenyl	U	20.0	"							
15	4,4'-Dichlorobiphenyl	U	20.0	"							
16/24	2,2',3-TrCB/2,3,6-TrCB	U	20.0	"							
17	2,2',4-Trichlorobiphenyl	4.20	20.0	"							EMPC, J
18/30	2,2',5-TrCB/2,4,6-TrCB	11.4	20.0	"							J
19	2,2',6-Trichlorobiphenyl	U	20.0	"							
20/28	2,3,3'-TrCB/2,4,4'-TrCB	10.0	20.0	"							EMPC, J
21/33	2,3,4-TrCB/2,3',4'-TrCB	14.0	20.0	"							J
22	2,3,4'-Trichlorobiphenyl	6.60	20.0	"							J
23	2,3,5-Trichlorobiphenyl	U	20.0	"							
25	2,3',4-Trichlorobiphenyl	4.20	20.0	"							J
26/29	2,3',5-TrCB/2,4,5-TrCB	3.40	20.0	"							EMPC, J
27	2,3',6-Trichlorobiphenyl	U	20.0	"							
31	2,4',5-Trichlorobiphenyl	16.6	20.0	"							J
32	2,4',6-Trichlorobiphenyl	3.60	20.0	"							J
34	2,3',5'-Trichlorobiphenyl	U	20.0	"							
35	3,3',4-Trichlorobiphenyl	U	20.0	"							
36	3,3',5-Trichlorobiphenyl	U	20.0	"							
37	3,4,4'-Trichlorobiphenyl	20.6	20.0	"							
38	3,4,5-Trichlorobiphenyl	U	20.0	"							
39	3,4',5-Trichlorobiphenyl	U	20.0	"							
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	5.40	20.0	"							J
42	2,2',3,4'-Tetrachlorobiphenyl	U	20.0	"							
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U	20.0	"							
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	14.8	20.0	"							J
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK1) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 21:26

46	2,2',3,6'-Tetrachlorobiphenyl	U	20.0	pg/L							
48	2,2',4,5-Tetrachlorobiphenyl	U	20.0	"							
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	3.40	20.0	"							EMPC, J
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U	20.0	"							
52	2,2',5,5'-Tetrachlorobiphenyl	6.00	20.0	"							J
54	2,2',6,6'-Tetrachlorobiphenyl	1.80	20.0	"							EMPC, J
55	2,3,3',4-Tetrachlorobiphenyl	U	20.0	"							
56	2,3,3',4'-Tetrachlorobiphenyl	12.2	20.0	"							J
57	2,3,3',5-Tetrachlorobiphenyl	U	20.0	"							
58	2,3,3',5'-Tetrachlorobiphenyl	U	20.0	"							
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U	20.0	"							
60	2,3,4,4'-Tetrachlorobiphenyl	U	20.0	"							
61/70/74/76	TeCB-61/70/74/76	20.2	20.0	"							
63	2,3,4',5-Tetrachlorobiphenyl	U	20.0	"							
64	2,3,4',6-Tetrachlorobiphenyl	3.40	20.0	"							J
66	2,3',4,4'-Tetrachlorobiphenyl	8.00	20.0	"							J
67	2,3',4,5-Tetrachlorobiphenyl	U	20.0	"							
68	2,3',4,5'-Tetrachlorobiphenyl	U	20.0	"							
72	2,3',5,5'-Tetrachlorobiphenyl	U	20.0	"							
77	3,3',4,4'-Tetrachlorobiphenyl	14.8	20.0	"							J
78	3,3',4,5-Tetrachlorobiphenyl	U	20.0	"							
79	3,3',4,5'-Tetrachlorobiphenyl	U	20.0	"							
80	3,3',5,5'-Tetrachlorobiphenyl	U	20.0	"							
81	3,4,4',5-Tetrachlorobiphenyl	8.20	20.0	"							J
82	2,2',3,3',4-Pentachlorobiphenyl	U	20.0	"							
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	9.00	20.0	"							J
84	2,2',3,3',6-Pentachlorobiphenyl	6.00	20.0	"							EMPC, J
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	3.20	20.0	"							EMPC, J
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	15.4	20.0	"							EMPC, J
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	2.80	20.0	"							EMPC, J
89	2,2',3,4,6'-Pentachlorobiphenyl	U	20.0	"							
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	17.2	20.0	"							J
92	2,2',3,5,5'-Pentachlorobiphenyl	3.80	20.0	"							J
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U	20.0	"							
94	2,2',3,5,6'-Pentachlorobiphenyl	U	20.0	"							
95	2,2',3,5',6-Pentachlorobiphenyl	7.80	20.0	"							J
96	2,2',3,6,6'-Pentachlorobiphenyl	U	20.0	"							
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK1) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 21:26

103	2,2',4,5',6-Pentachlorobiphenyl	U	20.0	pg/L							
104	2,2',4,6,6'-Pentachlorobiphenyl	U	20.0	"							
105	2,3,3',4,4'-Pentachlorobiphenyl	40.8	20.0	"							EMPC
106	2,3,3',4,5-Pentachlorobiphenyl	U	20.0	"							
107	2,3,3',4',5-Pentachlorobiphenyl	4.00	20.0	"							J
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	2.20	20.0	"							EMPC, J
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	23.0	20.0	"							
111	2,3,3',5,5'-Pentachlorobiphenyl	U	20.0	"							
114	2,3,4,4',5-Pentachlorobiphenyl	U	20.0	"							
118	2,3',4,4',5-Pentachlorobiphenyl	23.0	20.0	"							
120	2,3',4,5,5'-Pentachlorobiphenyl	U	20.0	"							
121	2,3',4,5',6-Pentachlorobiphenyl	U	20.0	"							
122	2,3,3',4',5'-Pentachlorobiphenyl	U	20.0	"							
123	2,3',4,4',5'-Pentachlorobiphenyl	4.00	20.0	"							J
126	3,3',4,4',5-Pentachlorobiphenyl	6.60	20.0	"							J
127	3,3',4,5,5'-Pentachlorobiphenyl	U	20.0	"							
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U	20.0	"							
129/138/163	HxCB-129/138/163	22.4	20.0	"							
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U	20.0	"							
131	2,2',3,3',4,6-Hexachlorobiphenyl	U	20.0	"							
132	2,2',3,3',4,6'-Hexachlorobiphenyl	7.00	20.0	"							J
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U	20.0	"							
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U	20.0	"							
135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	8.40	20.0	"							J
136	2,2',3,3',6,6'-Hexachlorobiphenyl	3.40	20.0	"							EMPC, J
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U	20.0	"							
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U	20.0	"							
141	2,2',3,4,5,5'-Hexachlorobiphenyl	5.00	20.0	"							EMPC, J
142	2,2',3,4,5,6-Hexachlorobiphenyl	U	20.0	"							
144	2,2',3,4,5',6-Hexachlorobiphenyl	U	20.0	"							
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U	20.0	"							
146	2,2',3,4',5,5'-Hexachlorobiphenyl	3.40	20.0	"							EMPC, J
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	16.0	20.0	"							J
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U	20.0	"							
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U	20.0	"							
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U	20.0	"							
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	20.4	20.0	"							
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK1) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 21:26

155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	20.0	pg/L							
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	9.00	20.0	"							J
158	2,3,3',4,4',6-Hexachlorobiphenyl	U	20.0	"							
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U	20.0	"							
160	2,3,3',4,5,6-Hexachlorobiphenyl	U	20.0	"							
161	2,3,3',4,5',6-Hexachlorobiphenyl	U	20.0	"							
162	2,3,3',4',5,5'-Hexachlorobiphenyl	10.0	20.0	"							EMPC, J
165	2,3,3',5,5',6-Hexachlorobiphenyl	U	20.0	"							
167	2,3',4,4',5,5'-Hexachlorobiphenyl	4.60	20.0	"							EMPC, J
169	3,3',4,4',5,5'-Hexachlorobiphenyl	4.20	20.0	"							J
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	15.4	20.0	"							J
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	2.40	20.0	"							J
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U	20.0	"							
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	10.6	20.0	"							EMPC, J
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U	20.0	"							
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U	20.0	"							
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	5.00	20.0	"							EMPC, J
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U	20.0	"							
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	4.80	20.0	"							J
180/193	2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB	20.0	20.0	"							
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U	20.0	"							
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U	20.0	"							
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	4.40	20.0	"							J
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U	20.0	"							
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U	20.0	"							
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	8.20	20.0	"							J
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	20.0	"							
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	3.60	20.0	"							J
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U	20.0	"							
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U	20.0	"							
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U	20.0	"							
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	3.40	20.0	"							EMPC, J
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U	20.0	"							
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	3.00	20.0	"							J
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U	20.0	"							
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	5.40	20.0	"							J
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U	20.0	"							
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
Blank (BE10403-BLK1)					Prepared: 05/09/11 14:52		Analyzed: 06/01/11 21:26				
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	2.40	20.0	pg/L							EMPC, J
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U	20.0	"							
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	20.0	"							
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	20.0	"							
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U	20.0	"							
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	3.00	20.0	"							EMPC, J
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	4.60	20.0	"							EMPC, J
1-3	Total Monochlorobiphenyl	U	20.0	"							
4-15	Total Dichlorobiphenyl	39.6	20.0	"							
16-39	Total Trichlorobiphenyl	94.6	20.0	"							
40-81	Total Tetrachlorobiphenyl	98.2	20.0	"							
82-127	Total Pentachlorobiphenyl	169	20.0	"							
128-169	Total Hexachlorobiphenyl	108	20.0	"							
170-193	Total Heptachlorobiphenyl	74.4	20.0	"							
194-205	Total Octachlorobiphenyl	14.2	20.0	"							J
206-208	Total Nonachlorobiphenyl	3.00	20.0	"							J
209	Decachlorobiphenyl	4.60	20.0	"							J
Total PCBs	Total PCBs	605	20.0	"							
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*11.9*		*ng/mL*	*100.00*		*12*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*13.2*		*"*	*100.00*		*13*	*15-150*			*A*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*13.0*		*"*	*100.00*		*13*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*20.0*		*"*	*100.00*		*20*	*25-150*			*A*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*17.1*		*"*	*100.00*		*17*	*25-150*			*A*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*27.0*		*"*	*100.00*		*27*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*20.0*		*"*	*100.00*		*20*	*25-150*			*A*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*35.6*		*"*	*100.00*		*36*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*34.7*		*"*	*100.00*		*35*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*15.4*		*"*	*100.00*		*15*	*25-150*			*A*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*29.4*		*"*	*100.00*		*29*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*27.4*		*"*	*100.00*		*27*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*27.7*		*"*	*100.00*		*28*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*29.3*		*"*	*100.00*		*29*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*28.4*		*"*	*100.00*		*28*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*25.9*		*"*	*100.00*		*26*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*59.8*		*"*	*200.00*		*30*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*30.8*		*"*	*100.00*		*31*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*33.5*		*"*	*100.00*		*34*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK1) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 21:26

188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*32.0*		*ng/mL*	*100.00*		*32*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*34.7*		*"*	*100.00*		*35*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*34.3*		*"*	*100.00*		*34*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*28.3*		*"*	*100.00*		*28*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*29.2*		*"*	*100.00*		*29*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*29.4*		*"*	*100.00*		*29*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*24.5*		*"*	*100.00*		*25*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*26.0*		*"*	*100.00*		*26*	*30-135*			*A*
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*29.4*		*"*	*100.00*		*29*	*30-135*			*A*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*35.7*		*"*	*100.00*		*36*	*30-135*			

Blank (BE10403-BLK2) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 22:30

1	2-Monochlorobiphenyl	U	20.0	pg/L							
2	3-Monochlorobiphenyl	U	20.0	"							
3	4-Monochlorobiphenyl	U	20.0	"							
4	2,2'-Dichlorobiphenyl	U	20.0	"							
5	2,3-Dichlorobiphenyl	U	20.0	"							
6	2,3'-Dichlorobiphenyl	U	20.0	"							
7	2,4-Dichlorobiphenyl	U	20.0	"							
8	2,4'-Dichlorobiphenyl	U	20.0	"							
9	2,5-Dichlorobiphenyl	U	20.0	"							
10	2,6-Dichlorobiphenyl	U	20.0	"							
11	3,3'-Dichlorobiphenyl	U	20.0	"							
12/13	3,4-DiCB/3,4'-DiCB	U	20.0	"							
14	3,5-Dichlorobiphenyl	U	20.0	"							
15	4,4'-Dichlorobiphenyl	U	20.0	"							
16/24	2,2',3-TrCB/2,3,6-TrCB	8.20	20.0	"							J
17	2,2',4-Trichlorobiphenyl	U	20.0	"							
18/30	2,2',5-TrCB/2,4,6-TrCB	14.0	20.0	"							J
19	2,2',6-Trichlorobiphenyl	U	20.0	"							
20/28	2,3,3'-TrCB/2,4,4'-TrCB	9.60	20.0	"							J
21/33	2,3,4-TrCB/2,3',4'-TrCB	12.0	20.0	"							J
22	2,3,4'-Trichlorobiphenyl	5.20	20.0	"							EMPC, J
23	2,3,5-Trichlorobiphenyl	U	20.0	"							
25	2,3',4-Trichlorobiphenyl	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK2) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 22:30

26/29	2,3',5-TrCB/2,4,5-TrCB	U	20.0	pg/L							
27	2,3',6-Trichlorobiphenyl	U	20.0	"							
31	2,4',5-Trichlorobiphenyl	18.4	20.0	"							J
32	2,4',6-Trichlorobiphenyl	U	20.0	"							
34	2,3',5'-Trichlorobiphenyl	U	20.0	"							
35	3,3',4-Trichlorobiphenyl	U	20.0	"							
36	3,3',5-Trichlorobiphenyl	U	20.0	"							
37	3,4,4'-Trichlorobiphenyl	23.6	20.0	"							
38	3,4,5-Trichlorobiphenyl	U	20.0	"							
39	3,4',5-Trichlorobiphenyl	U	20.0	"							
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	4.60	20.0	"							J
42	2,2',3,4'-Tetrachlorobiphenyl	U	20.0	"							
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U	20.0	"							
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	12.4	20.0	"							J
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U	20.0	"							
46	2,2',3,6'-Tetrachlorobiphenyl	U	20.0	"							
48	2,2',4,5-Tetrachlorobiphenyl	U	20.0	"							
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	4.20	20.0	"							J
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U	20.0	"							
52	2,2',5,5'-Tetrachlorobiphenyl	6.00	20.0	"							J
54	2,2',6,6'-Tetrachlorobiphenyl	U	20.0	"							
55	2,3,3',4-Tetrachlorobiphenyl	U	20.0	"							
56	2,3,3',4'-Tetrachlorobiphenyl	12.8	20.0	"							J
57	2,3,3',5-Tetrachlorobiphenyl	U	20.0	"							
58	2,3,3',5'-Tetrachlorobiphenyl	U	20.0	"							
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U	20.0	"							
60	2,3,4,4'-Tetrachlorobiphenyl	U	20.0	"							
61/70/74/76	TeCB-61/70/74/76	20.4	20.0	"							
63	2,3,4',5-Tetrachlorobiphenyl	U	20.0	"							
64	2,3,4',6-Tetrachlorobiphenyl	U	20.0	"							
66	2,3',4,4'-Tetrachlorobiphenyl	9.00	20.0	"							J
67	2,3',4,5-Tetrachlorobiphenyl	U	20.0	"							
68	2,3',4,5'-Tetrachlorobiphenyl	U	20.0	"							
72	2,3',5,5'-Tetrachlorobiphenyl	U	20.0	"							
77	3,3',4,4'-Tetrachlorobiphenyl	23.2	20.0	"							
78	3,3',4,5-Tetrachlorobiphenyl	U	20.0	"							
79	3,3',4,5'-Tetrachlorobiphenyl	U	20.0	"							
80	3,3',5,5'-Tetrachlorobiphenyl	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK2) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 22:30

81	3,4,4',5-Tetrachlorobiphenyl	9.40	20.0	pg/L							J
82	2,2',3,3',4-Pentachlorobiphenyl	U	20.0	"							
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	U	20.0	"							
84	2,2',3,3',6-Pentachlorobiphenyl	U	20.0	"							
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	16.0	20.0	"							J
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	13.8	20.0	"							J
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	U	20.0	"							
89	2,2',3,4,6'-Pentachlorobiphenyl	U	20.0	"							
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	16.2	20.0	"							J
92	2,2',3,5,5'-Pentachlorobiphenyl	U	20.0	"							
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U	20.0	"							
94	2,2',3,5,6'-Pentachlorobiphenyl	U	20.0	"							
95	2,2',3,5',6-Pentachlorobiphenyl	U	20.0	"							
96	2,2',3,6,6'-Pentachlorobiphenyl	U	20.0	"							
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U	20.0	"							
103	2,2',4,5',6-Pentachlorobiphenyl	U	20.0	"							
104	2,2',4,6,6'-Pentachlorobiphenyl	U	20.0	"							
105	2,3,3',4,4'-Pentachlorobiphenyl	57.8	20.0	"							EMPC
106	2,3,3',4,5-Pentachlorobiphenyl	U	20.0	"							
107	2,3,3',4',5-Pentachlorobiphenyl	U	20.0	"							
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U	20.0	"							
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	U	20.0	"							
111	2,3,3',5,5'-Pentachlorobiphenyl	U	20.0	"							
114	2,3,4,4',5-Pentachlorobiphenyl	U	20.0	"							
118	2,3',4,4',5-Pentachlorobiphenyl	19.0	20.0	"							EMPC, J
120	2,3',4,5,5'-Pentachlorobiphenyl	U	20.0	"							
121	2,3',4,5',6-Pentachlorobiphenyl	U	20.0	"							
122	2,3,3',4',5'-Pentachlorobiphenyl	U	20.0	"							
123	2,3',4,4',5'-Pentachlorobiphenyl	U	20.0	"							
126	3,3',4,4',5-Pentachlorobiphenyl	8.40	20.0	"							J
127	3,3',4,5,5'-Pentachlorobiphenyl	U	20.0	"							
128/162	2,2',3,3',4,4'-HxCB/2,3,3',4',5,5'-HxCB	U	20.0	"							
129/138/163	HxCB-129/138/163	23.6	20.0	"							EMPC
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U	20.0	"							
131	2,2',3,3',4,6-Hexachlorobiphenyl	U	20.0	"							
132	2,2',3,3',4,6'-Hexachlorobiphenyl	7.00	20.0	"							EMPC, J
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U	20.0	"							
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U	20.0	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK2) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 22:30

135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	U	20.0	pg/L							
136	2,2',3,3',6,6'-Hexachlorobiphenyl	4.40	20.0	"							EMPC, J
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U	20.0	"							
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U	20.0	"							
141	2,2',3,4,5,5'-Hexachlorobiphenyl	4.60	20.0	"							J
142	2,2',3,4,5,6-Hexachlorobiphenyl	U	20.0	"							
144	2,2',3,4,5',6-Hexachlorobiphenyl	U	20.0	"							
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U	20.0	"							
146	2,2',3,4',5,5'-Hexachlorobiphenyl	5.60	20.0	"							J
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	15.2	20.0	"							J
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U	20.0	"							
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U	20.0	"							
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U	20.0	"							
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	20.0	20.0	"							
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U	20.0	"							
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	20.0	"							
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	12.8	20.0	"							J
158	2,3,3',4,4',6-Hexachlorobiphenyl	U	20.0	"							
159	2,3,3',4,5,5'-Hexachlorobiphenyl	11.2	20.0	"							EMPC, J
160	2,3,3',4,5,6-Hexachlorobiphenyl	U	20.0	"							
161	2,3,3',4,5',6-Hexachlorobiphenyl	U	20.0	"							
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U	20.0	"							
165	2,3,3',5,5',6-Hexachlorobiphenyl	U	20.0	"							
167	2,3',4,4',5,5'-Hexachlorobiphenyl	4.20	20.0	"							EMPC, J
169	3,3',4,4',5,5'-Hexachlorobiphenyl	5.80	20.0	"							EMPC, J
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	22.2	20.0	"							
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	U	20.0	"							
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U	20.0	"							
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	13.6	20.0	"							J
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U	20.0	"							
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U	20.0	"							
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	6.60	20.0	"							J
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U	20.0	"							
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	U	20.0	"							
180/193	2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB	21.6	20.0	"							
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U	20.0	"							
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U	20.0	"							
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	4.00	20.0	"							EMPC, J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
Blank (BE10403-BLK2)					Prepared: 05/09/11 14:52		Analyzed: 06/01/11 22:30				
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U	20.0	pg/L							
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U	20.0	"							
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	9.20	20.0	"							J
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	20.0	"							
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	20.0	"							
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U	20.0	"							
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U	20.0	"							
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U	20.0	"							
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	5.80	20.0	"							J
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U	20.0	"							
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	4.60	20.0	"							J
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U	20.0	"							
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	6.20	20.0	"							J
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U	20.0	"							
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	2.80	20.0	"							J
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	3.60	20.0	"							EMPC, J
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U	20.0	"							
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	2.80	20.0	"							EMPC, J
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	20.0	"							
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U	20.0	"							
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	20.0	"							
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U	20.0	"							
1-3	Total Monochlorobiphenyl	U	20.0	"							
4-15	Total Dichlorobiphenyl	U	20.0	"							
16-39	Total Trichlorobiphenyl	91.0	20.0	"							
40-81	Total Tetrachlorobiphenyl	102	20.0	"							
82-127	Total Pentachlorobiphenyl	131	20.0	"							
128-169	Total Hexachlorobiphenyl	114	20.0	"							
170-193	Total Heptachlorobiphenyl	77.2	20.0	"							
194-205	Total Octachlorobiphenyl	25.8	20.0	"							
206-208	Total Nonachlorobiphenyl	U	20.0	"							
209	Decachlorobiphenyl	U	20.0	"							
Total PCBs	Total PCBs	542	20.0	"							
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*12.1*		*ng/mL*	*100.00*		*12*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*13.4*		*"*	*100.00*		*13*	*15-150*			*A*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*13.4*		*"*	*100.00*		*13*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*18.0*		*"*	*100.00*		*18*	*25-150*			*A*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*18.0*		*"*	*100.00*		*18*	*25-150*			*A*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Blank (BE10403-BLK2) Prepared: 05/09/11 14:52 Analyzed: 06/01/11 22:30

37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*20.9*		*ng/mL*	*100.00*		*21*	*25-150*			*A*
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*22.2*		*"*	*100.00*		*22*	*25-150*			*A*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*28.1*		*"*	*100.00*		*28*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*27.1*		*"*	*100.00*		*27*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*13.5*		*"*	*100.00*		*14*	*25-150*			*A*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*22.2*		*"*	*100.00*		*22*	*25-150*			*A*
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*21.2*		*"*	*100.00*		*21*	*25-150*			*A*
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*21.3*		*"*	*100.00*		*21*	*25-150*			*A*
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*22.4*		*"*	*100.00*		*22*	*25-150*			*A*
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*21.5*		*"*	*100.00*		*21*	*25-150*			*A*
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*21.0*		*"*	*100.00*		*21*	*25-150*			*A*
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*44.4*		*"*	*200.00*		*22*	*25-150*			*A*
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*22.3*		*"*	*100.00*		*22*	*25-150*			*A*
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*25.0*		*"*	*100.00*		*25*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*22.1*		*"*	*100.00*		*22*	*25-150*			*A*
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*24.5*		*"*	*100.00*		*24*	*25-150*			*A*
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*24.4*		*"*	*100.00*		*24*	*25-150*			*A*
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*23.3*		*"*	*100.00*		*23*	*25-150*			*A*
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*21.8*		*"*	*100.00*		*22*	*25-150*			*A*
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*21.9*		*"*	*100.00*		*22*	*25-150*			*A*
209L	*Surrogate:13C12-Decachlorobiphenyl*	*18.8*		*"*	*100.00*		*19*	*25-150*			*A*
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*23.7*		*"*	*100.00*		*24*	*30-135*			*A*
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*23.5*		*"*	*100.00*		*23*	*30-135*			*A*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*27.0*		*"*	*100.00*		*27*	*30-135*			*A*

LCS (BE10403-BS1) Prepared: 05/09/11 14:52 Analyzed: 06/02/11 03:51

1	2-Monochlorobiphenyl	49.6	20.0	pg/L	50.000		99	50-150			
3	4-Monochlorobiphenyl	59.0	20.0	"	50.000		118	50-150			
4	2,2'-Dichlorobiphenyl	54.4	20.0	"	50.000		109	50-150			
15	4,4'-Dichlorobiphenyl	72.2	20.0	"	50.000		144	50-150			
19	2,2',6-Trichlorobiphenyl	46.0	20.0	"	50.000		92	50-150			
37	3,4,4'-Trichlorobiphenyl	47.2	20.0	"	50.000		94	50-150			
54	2,2',6,6'-Tetrachlorobiphenyl	40.0	20.0	"	50.000		80	50-150			
77	3,3',4,4'-Tetrachlorobiphenyl	50.2	20.0	"	50.000		100	50-150			
81	3,4,4',5-Tetrachlorobiphenyl	48.8	20.0	"	50.000		98	50-150			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
LCS (BE10403-BS1)					Prepared: 05/09/11 14:52		Analyzed: 06/02/11 03:51				
104	2,2',4,6,6'-Pentachlorobiphenyl	49.6	20.0	pg/L	50.000		99	50-150			
105	2,3,3',4,4'-Pentachlorobiphenyl	66.0	20.0	"	50.000		132	50-150			
114	2,3,4,4',5-Pentachlorobiphenyl	50.0	20.0	"	50.000		100	50-150			
118	2,3',4,4',5-Pentachlorobiphenyl	60.4	20.0	"	50.000		121	50-150			
123	2,3',4,4',5'-Pentachlorobiphenyl	48.0	20.0	"	50.000		96	50-150			
126	3,3',4,4',5-Pentachlorobiphenyl	51.2	20.0	"	50.000		102	50-150			
155	2,2',4,4',6,6'-Hexachlorobiphenyl	44.6	20.0	"	50.000		89	50-150			
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	107	20.0	"	100.00		107	50-150			
167	2,3',4,4',5,5'-Hexachlorobiphenyl	47.8	20.0	"	50.000		96	50-150			
169	3,3',4,4',5,5'-Hexachlorobiphenyl	48.6	20.0	"	50.000		97	50-150			
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	49.2	20.0	"	50.000		98	50-150			
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	46.6	20.0	"	50.000		93	50-150			
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	48.0	20.0	"	50.000		96	50-150			
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	48.2	20.0	"	50.000		96	50-150			
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	55.0	20.0	"	50.000		110	50-150			
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	44.8	20.0	"	50.000		90	50-150			
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	53.6	20.0	"	50.000		107	50-150			
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*8.22*		*ng/mL*	*100.00*		*8*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*9.22*		*"*	*100.00*		*9*	*15-150*			*A*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*9.02*		*"*	*100.00*		*9*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*19.4*		*"*	*100.00*		*19*	*25-150*			*A*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*14.9*		*"*	*100.00*		*15*	*25-150*			*A*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*36.1*		*"*	*100.00*		*36*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*26.4*		*"*	*100.00*		*26*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*58.1*		*"*	*100.00*		*58*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*55.8*		*"*	*100.00*		*56*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*23.3*		*"*	*100.00*		*23*	*25-150*			*A*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*50.3*		*"*	*100.00*		*50*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*45.9*		*"*	*100.00*		*46*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*47.0*		*"*	*100.00*		*47*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*49.6*		*"*	*100.00*		*50*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*46.1*		*"*	*100.00*		*46*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*45.5*		*"*	*100.00*		*46*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*93.2*		*"*	*200.00*		*47*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*48.0*		*"*	*100.00*		*48*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*51.9*		*"*	*100.00*		*52*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*54.4*		*"*	*100.00*		*54*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
LCS (BE10403-BS1)					Prepared: 05/09/11 14:52		Analyzed: 06/02/11 03:51				
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*54.8*		*ng/mL*	*100.00*		*55*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*58.6*		*"*	*100.00*		*59*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*55.2*		*"*	*100.00*		*55*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*60.0*		*"*	*100.00*		*60*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*55.5*		*"*	*100.00*		*55*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*54.1*		*"*	*100.00*		*54*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*33.5*		*"*	*100.00*		*34*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*52.0*		*"*	*100.00*		*52*	*30-135*			
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*64.8*		*"*	*100.00*		*65*	*30-135*			
LCS (BE10403-BS2)					Prepared: 05/09/11 14:52		Analyzed: 06/02/11 04:55				
Total PCBs	Total PCBs	179000	20.0	pg/L	200000		90	25-150			
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*11.0*		*ng/mL*	*100.00*		*11*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*11.8*		*"*	*100.00*		*12*	*15-150*			*A*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*11.6*		*"*	*100.00*		*12*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*20.5*		*"*	*100.00*		*20*	*25-150*			*A*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*17.8*		*"*	*100.00*		*18*	*25-150*			*A*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*34.0*		*"*	*100.00*		*34*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*25.2*		*"*	*100.00*		*25*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*51.6*		*"*	*100.00*		*52*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*47.5*		*"*	*100.00*		*47*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*24.4*		*"*	*100.00*		*24*	*25-150*			*A*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*54.5*		*"*	*100.00*		*54*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*48.8*		*"*	*100.00*		*49*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*49.6*		*"*	*100.00*		*50*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*51.9*		*"*	*100.00*		*52*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*51.6*		*"*	*100.00*		*52*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*44.1*		*"*	*100.00*		*44*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*100*		*"*	*200.00*		*50*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*51.4*		*"*	*100.00*		*51*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*56.5*		*"*	*100.00*		*57*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*56.3*		*"*	*100.00*		*56*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*60.3*		*"*	*100.00*		*60*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
LCS (BE10403-BS2)					Prepared: 05/09/11 14:52		Analyzed: 06/02/11 04:55				
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*65.6*		*ng/mL*	*100.00*		*66*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*59.6*		*"*	*100.00*		*60*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*65.8*		*"*	*100.00*		*66*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*61.2*		*"*	*100.00*		*61*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*59.8*		*"*	*100.00*		*60*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*32.6*		*"*	*100.00*		*33*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*52.7*		*"*	*100.00*		*53*	*30-135*			
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*69.3*		*"*	*100.00*		*69*	*30-135*			
Matrix Spike (BE10403-MS1)		**Source: 1104020-10**			Prepared: 05/09/11 14:52		Analyzed: 06/15/11 17:31				
1	2-Monochlorobiphenyl	U	19.6	pg/L	980.39	0.00		50-150			TD
3	4-Monochlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
4	2,2'-Dichlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
15	4,4'-Dichlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
19	2,2',6-Trichlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
37	3,4,4'-Trichlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
54	2,2',6,6'-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
77	3,3',4,4'-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
81	3,4,4',5-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
104	2,2',4,6,6'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
105	2,3,3',4,4'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
114	2,3,4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
118	2,3',4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	118	NR	50-150			TD
123	2,3',4,4',5'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
126	3,3',4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	U	19.6	"	1960.8	0.00		50-150			TD
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	19.6	"	980.39	0.00		50-150			TD
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U	19.6	"	980.39	196	NR	50-150			TD

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Matrix Spike (BE10403-MS1) **Source: 1104020-10** Prepared: 05/09/11 14:52 Analyzed: 06/15/11 17:31

1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*15-150*			*TD*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*0.00*		*"*	*100.00*			*15-150*			*TD*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*0.00*		*"*	*200.00*			*25-150*			*TD*
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
209L	*Surrogate:13C12-Decachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10403 - EPA 3520C PCB Congeners											
Matrix Spike Dup (BE10403-MSD1)		**Source: 1104020-10**			Prepared: 05/09/11 14:52		Analyzed: 06/15/11 17:31				
1	2-Monochlorobiphenyl	U	19.6	pg/L	980.39	0.00		50-150		25	TD
3	4-Monochlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
4	2,2'-Dichlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
15	4,4'-Dichlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
19	2,2',6-Trichlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
37	3,4,4'-Trichlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
54	2,2',6,6'-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
77	3,3',4,4'-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
81	3,4,4',5-Tetrachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
104	2,2',4,6,6'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
105	2,3,3',4,4'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
114	2,3,4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
118	2,3',4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	118	NR	50-150		25	TD
123	2,3',4,4',5'-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
126	3,3',4,4',5-Pentachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	U	19.6	"	1960.8	0.00		50-150		25	TD
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	19.6	"	980.39	0.00		50-150		25	TD
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U	19.6	"	980.39	196	NR	50-150		25	TD
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*15-150*			*TD*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*0.00*		*"*	*100.00*			*15-150*			*TD*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10403 - EPA 3520C PCB Congeners

Matrix Spike Dup (BE10403-MSD1) **Source: 1104020-10** Prepared: 05/09/11 14:52 Analyzed: 06/15/11 17:31

118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*25-150*			*TD*
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*0.00*		*"*	*200.00*			*25-150*			*TD*
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
209L	*Surrogate:13C12-Decachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK1) Prepared: 05/05/11 15:33 Analyzed: 06/01/11 23:34

1	2-Monochlorobiphenyl	U	4.00	pg/g wet							
2	3-Monochlorobiphenyl	U	4.00	"							
3	4-Monochlorobiphenyl	U	4.00	"							
4	2,2'-Dichlorobiphenyl	U	4.00	"							
5	2,3-Dichlorobiphenyl	U	4.00	"							
6	2,3'-Dichlorobiphenyl	U	4.00	"							
7	2,4-Dichlorobiphenyl	U	4.00	"							
8	2,4'-Dichlorobiphenyl	3.92	4.00	"							J
9	2,5-Dichlorobiphenyl	U	4.00	"							
10	2,6-Dichlorobiphenyl	U	4.00	"							
11	3,3'-Dichlorobiphenyl	5.52	4.00	"							
12/13	3,4-DiCB/3,4'-DiCB	U	4.00	"							
14	3,5-Dichlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK1) Prepared: 05/05/11 15:33 Analyzed: 06/01/11 23:34

15	4,4'-Dichlorobiphenyl	2.12	4.00	pg/g wet							J
16/24	2,2',3-TrCB/2,3,6-TrCB	1.88	4.00	"							J
17	2,2',4-Trichlorobiphenyl	1.56	4.00	"							J
18/30	2,2',5-TrCB/2,4,6-TrCB	3.80	4.00	"							J
19	2,2',6-Trichlorobiphenyl	U	4.00	"							
20/28	2,3,3'-TrCB/2,4,4'-TrCB	3.64	4.00	"							J
21/33	2,3,4-TrCB/2,3',4'-TrCB	3.32	4.00	"							J
22	2,3,4'-Trichlorobiphenyl	1.92	4.00	"							J
23	2,3,5-Trichlorobiphenyl	U	4.00	"							
25	2,3',4-Trichlorobiphenyl	U	4.00	"							
26/29	2,3',5-TrCB/2,4,5-TrCB	1.00	4.00	"							J
27	2,3',6-Trichlorobiphenyl	U	4.00	"							
31	2,4',5-Trichlorobiphenyl	5.08	4.00	"							
32	2,4',6-Trichlorobiphenyl	1.60	4.00	"							J
34	2,3',5'-Trichlorobiphenyl	U	4.00	"							
35	3,3',4-Trichlorobiphenyl	U	4.00	"							
36	3,3',5-Trichlorobiphenyl	U	4.00	"							
37	3,4,4'-Trichlorobiphenyl	1.96	4.00	"							J
38	3,4,5-Trichlorobiphenyl	U	4.00	"							
39	3,4',5-Trichlorobiphenyl	U	4.00	"							
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	0.720	4.00	"							J
42	2,2',3,4'-Tetrachlorobiphenyl	U	4.00	"							
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U	4.00	"							
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	2.76	4.00	"							J
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U	4.00	"							
46	2,2',3,6'-Tetrachlorobiphenyl	U	4.00	"							
48	2,2',4,5-Tetrachlorobiphenyl	0.280	4.00	"							J
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	0.760	4.00	"							J
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U	4.00	"							
52	2,2',5,5'-Tetrachlorobiphenyl	1.24	4.00	"							J
54	2,2',6,6'-Tetrachlorobiphenyl	U	4.00	"							
55	2,3,3',4-Tetrachlorobiphenyl	U	4.00	"							
56	2,3,3',4'-Tetrachlorobiphenyl	1.60	4.00	"							J
57	2,3,3',5-Tetrachlorobiphenyl	U	4.00	"							
58	2,3,3',5'-Tetrachlorobiphenyl	U	4.00	"							
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	U	4.00	"							
60	2,3,4,4'-Tetrachlorobiphenyl	U	4.00	"							
61/70/74/76	TeCB-61/70/74/76	2.68	4.00	"							J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK1) Prepared: 05/05/11 15:33 Analyzed: 06/01/11 23:34

63	2,3,4',5-Tetrachlorobiphenyl	U	4.00	pg/g wet							
64	2,3,4',6-Tetrachlorobiphenyl	0.560	4.00	"							J
66	2,3',4,4'-Tetrachlorobiphenyl	1.44	4.00	"							J
67	2,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
68	2,3',4,5'-Tetrachlorobiphenyl	0.760	4.00	"							J
72	2,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							
77	3,3',4,4'-Tetrachlorobiphenyl	1.40	4.00	"							J
78	3,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
79	3,3',4,5'-Tetrachlorobiphenyl	U	4.00	"							
80	3,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							
81	3,4,4',5-Tetrachlorobiphenyl	0.720	4.00	"							J
82	2,2',3,3',4-Pentachlorobiphenyl	U	4.00	"							
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	1.04	4.00	"							J
84	2,2',3,3',6-Pentachlorobiphenyl	0.480	4.00	"							J
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	0.440	4.00	"							J
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	1.68	4.00	"							J
87/115	2,2',3,4,5'-PeCB/2,3,4,4',6-PeCB	U	4.00	"							
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	0.240	4.00	"							EMPC, J
89	2,2',3,4,6'-Pentachlorobiphenyl	U	4.00	"							
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	1.72	4.00	"							J
92	2,2',3,5,5'-Pentachlorobiphenyl	0.400	4.00	"							EMPC, J
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U	4.00	"							
94	2,2',3,5,6'-Pentachlorobiphenyl	U	4.00	"							
95	2,2',3,5',6-Pentachlorobiphenyl	1.12	4.00	"							J
96	2,2',3,6,6'-Pentachlorobiphenyl	U	4.00	"							
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U	4.00	"							
103	2,2',4,5',6-Pentachlorobiphenyl	U	4.00	"							
104	2,2',4,6,6'-Pentachlorobiphenyl	U	4.00	"							
105	2,3,3',4,4'-Pentachlorobiphenyl	4.20	4.00	"							EMPC
106	2,3,3',4,5-Pentachlorobiphenyl	U	4.00	"							
107	2,3,3',4',5-Pentachlorobiphenyl	U	4.00	"							
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U	4.00	"							
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	2.92	4.00	"							J
111	2,3,3',5,5'-Pentachlorobiphenyl	U	4.00	"							
114	2,3,4,4',5-Pentachlorobiphenyl	U	4.00	"							
118	2,3',4,4',5-Pentachlorobiphenyl	2.76	4.00	"							J
120	2,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
121	2,3',4,5',6-Pentachlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK1) Prepared: 05/05/11 15:33 Analyzed: 06/01/11 23:34

122	2,3,3',4',5'-Pentachlorobiphenyl	U	4.00	pg/g wet							
123	2,3',4,4',5'-Pentachlorobiphenyl	U	4.00	"							
126	3,3',4,4',5-Pentachlorobiphenyl	0.760	4.00	"							EMPC, J
127	3,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
128/166	2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB	U	4.00	"							
129/138/163	HxCB-129/138/163	2.76	4.00	"							J
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U	4.00	"							
131	2,2',3,3',4,6-Hexachlorobiphenyl	U	4.00	"							
132	2,2',3,3',4,6'-Hexachlorobiphenyl	0.800	4.00	"							J
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U	4.00	"							
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U	4.00	"							
135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	U	4.00	"							
136	2,2',3,3',6,6'-Hexachlorobiphenyl	U	4.00	"							
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U	4.00	"							
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U	4.00	"							
141	2,2',3,4,5,5'-Hexachlorobiphenyl	U	4.00	"							
142	2,2',3,4,5,6-Hexachlorobiphenyl	U	4.00	"							
144	2,2',3,4,5',6-Hexachlorobiphenyl	U	4.00	"							
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U	4.00	"							
146	2,2',3,4',5,5'-Hexachlorobiphenyl	0.560	4.00	"							J
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	2.04	4.00	"							J
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U	4.00	"							
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U	4.00	"							
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	2.60	4.00	"							J
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	4.00	"							
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	1.00	4.00	"							J
158	2,3,3',4,4',6-Hexachlorobiphenyl	U	4.00	"							
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U	4.00	"							
160	2,3,3',4,5,6-Hexachlorobiphenyl	U	4.00	"							
161	2,3,3',4,5',6-Hexachlorobiphenyl	U	4.00	"							
162	2,3,3',4',5,5'-Hexachlorobiphenyl	0.880	4.00	"							EMPC, J
165	2,3,3',5,5',6-Hexachlorobiphenyl	U	4.00	"							
167	2,3',4,4',5,5'-Hexachlorobiphenyl	0.360	4.00	"							J
169	3,3',4,4',5,5'-Hexachlorobiphenyl	0.440	4.00	"							J
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	1.36	4.00	"							J
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK1) Prepared: 05/05/11 15:33 Analyzed: 06/01/11 23:34

172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U	4.00	pg/g wet							
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	1.08	4.00	"							J
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U	4.00	"							
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U	4.00	"							
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	0.560	4.00	"							J
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U	4.00	"							
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	0.560	4.00	"							J
180/193	2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB	2.28	4.00	"							J
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U	4.00	"							
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U	4.00	"							
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	0.360	4.00	"							J
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U	4.00	"							
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U	4.00	"							
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	1.28	4.00	"							J
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	4.00	"							
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	4.00	"							
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U	4.00	"							
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U	4.00	"							
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	0.600	4.00	"							J
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U	4.00	"							
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	0.360	4.00	"							J
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U	4.00	"							
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	0.520	4.00	"							J
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U	4.00	"							
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	4.00	"							
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	0.400	4.00	"							EMPC, J
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U	4.00	"							
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	4.00	"							
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	4.00	"							
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U	4.00	"							
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	4.00	"							
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	0.640	4.00	"							J
1-3	Total Monochlorobiphenyl	U	4.00	"							
4-15	Total Dichlorobiphenyl	11.6	4.00	"							
16-39	Total Trichlorobiphenyl	25.8	4.00	"							
40-81	Total Tetrachlorobiphenyl	14.9	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Blank (BE10404-BLK1)					Prepared: 05/05/11 15:33			Analyzed: 06/01/11 23:34			
82-127	Total Pentachlorobiphenyl	17.8	4.00	pg/g wet							
128-169	Total Hexachlorobiphenyl	11.4	4.00	"							
170-193	Total Heptachlorobiphenyl	7.48	4.00	"							
194-205	Total Octachlorobiphenyl	1.88	4.00	"							J
206-208	Total Nonachlorobiphenyl	U	4.00	"							
209	Decachlorobiphenyl	0.640	4.00	"							J
Total PCBs	Total PCBs	91.4	4.00	"							
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*9.98*		*ng/mL*	*100.00*		*10*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*14.8*		*"*	*100.00*		*15*	*15-150*			
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*15.6*		*"*	*100.00*		*16*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*38.5*		*"*	*100.00*		*38*	*25-150*			
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*27.7*		*"*	*100.00*		*28*	*25-150*			
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*54.8*		*"*	*100.00*		*55*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*36.4*		*"*	*100.00*		*36*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*69.3*		*"*	*100.00*		*69*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*67.8*		*"*	*100.00*		*68*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*36.1*		*"*	*100.00*		*36*	*25-150*			
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*62.8*		*"*	*100.00*		*63*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*58.8*		*"*	*100.00*		*59*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*60.8*		*"*	*100.00*		*61*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*64.5*		*"*	*100.00*		*65*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*59.3*		*"*	*100.00*		*59*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*59.5*		*"*	*100.00*		*59*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*118*		*"*	*200.00*		*59*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*62.2*		*"*	*100.00*		*62*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*70.0*		*"*	*100.00*		*70*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*67.7*		*"*	*100.00*		*68*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*70.8*		*"*	*100.00*		*71*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*70.1*		*"*	*100.00*		*70*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*65.2*		*"*	*100.00*		*65*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*62.4*		*"*	*100.00*		*62*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*63.9*		*"*	*100.00*		*64*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*54.5*		*"*	*100.00*		*55*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*59.2*		*"*	*100.00*		*59*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*64.9*		*"*	*100.00*		*65*	*30-135*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Blank (BE10404-BLK1)					Prepared: 05/05/11 15:33		Analyzed: 06/01/11 23:34				
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*74.6*		*ng/mL*	*100.00*		*75*	*30-135*			
Blank (BE10404-BLK2)					Prepared: 05/05/11 15:33		Analyzed: 06/02/11 00:39				
1	2-Monochlorobiphenyl	U	4.00	pg/g wet							
2	3-Monochlorobiphenyl	U	4.00	"							
3	4-Monochlorobiphenyl	U	4.00	"							
4	2,2'-Dichlorobiphenyl	U	4.00	"							
5	2,3-Dichlorobiphenyl	U	4.00	"							
6	2,3'-Dichlorobiphenyl	U	4.00	"							
7	2,4-Dichlorobiphenyl	U	4.00	"							
8	2,4'-Dichlorobiphenyl	2.20	4.00	"							J
9	2,5-Dichlorobiphenyl	U	4.00	"							
10	2,6-Dichlorobiphenyl	U	4.00	"							
11	3,3'-Dichlorobiphenyl	4.92	4.00	"							
12/13	3,4-DiCB/3,4'-DiCB	U	4.00	"							
14	3,5-Dichlorobiphenyl	U	4.00	"							
15	4,4'-Dichlorobiphenyl	1.40	4.00	"							EMPC, J
16/24	2,2',3-TrCB/2,3,6-TrCB	1.40	4.00	"							J
17	2,2',4-Trichlorobiphenyl	1.28	4.00	"							J
18/30	2,2',5-TrCB/2,4,6-TrCB	3.08	4.00	"							J
19	2,2',6-Trichlorobiphenyl	0.320	4.00	"							J
20/28	2,3,3'-TrCB/2,4,4'-TrCB	2.96	4.00	"							J
21/33	2,3,4-TrCB/2,3',4'-TrCB	2.20	4.00	"							J
22	2,3,4'-Trichlorobiphenyl	1.52	4.00	"							J
23	2,3,5-Trichlorobiphenyl	U	4.00	"							
25	2,3',4-Trichlorobiphenyl	U	4.00	"							
26/29	2,3',5-TrCB/2,4,5-TrCB	U	4.00	"							
27	2,3',6-Trichlorobiphenyl	U	4.00	"							
31	2,4',5-Trichlorobiphenyl	3.60	4.00	"							J
32	2,4',6-Trichlorobiphenyl	1.12	4.00	"							J
34	2,3',5'-Trichlorobiphenyl	U	4.00	"							
35	3,3',4-Trichlorobiphenyl	U	4.00	"							
36	3,3',5-Trichlorobiphenyl	U	4.00	"							
37	3,4,4'-Trichlorobiphenyl	1.36	4.00	"							J
38	3,4,5-Trichlorobiphenyl	U	4.00	"							
39	3,4',5-Trichlorobiphenyl	U	4.00	"							
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	0.520	4.00	"							J
42	2,2',3,4'-Tetrachlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 00:39

43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U	4.00	pg/g wet							
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	1.64	4.00	"							J
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U	4.00	"							
46	2,2',3,6'-Tetrachlorobiphenyl	U	4.00	"							
48	2,2',4,5-Tetrachlorobiphenyl	U	4.00	"							
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	0.760	4.00	"							J
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U	4.00	"							
52	2,2',5,5'-Tetrachlorobiphenyl	1.04	4.00	"							J
54	2,2',6,6'-Tetrachlorobiphenyl	U	4.00	"							
55	2,3,3',4-Tetrachlorobiphenyl	U	4.00	"							
56	2,3,3',4'-Tetrachlorobiphenyl	1.36	4.00	"							J
57	2,3,3',5-Tetrachlorobiphenyl	U	4.00	"							
58	2,3,3',5'-Tetrachlorobiphenyl	U	4.00	"							
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	0.320	4.00	"							J
60	2,3,4,4'-Tetrachlorobiphenyl	0.440	4.00	"							J
61/70/74/76	TeCB-61/70/74/76	2.20	4.00	"							J
63	2,3,4',5-Tetrachlorobiphenyl	U	4.00	"							
64	2,3,4',6-Tetrachlorobiphenyl	0.400	4.00	"							J
66	2,3',4,4'-Tetrachlorobiphenyl	1.24	4.00	"							J
67	2,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
68	2,3',4,5'-Tetrachlorobiphenyl	0.360	4.00	"							J
72	2,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							
77	3,3',4,4'-Tetrachlorobiphenyl	1.32	4.00	"							J
78	3,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
79	3,3',4,5'-Tetrachlorobiphenyl	U	4.00	"							
80	3,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							
81	3,4,4',5-Tetrachlorobiphenyl	0.520	4.00	"							J
82	2,2',3,3',4-Pentachlorobiphenyl	U	4.00	"							
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	0.760	4.00	"							J
84	2,2',3,3',6-Pentachlorobiphenyl	U	4.00	"							
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	1.48	4.00	"							EMPC, J
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	1.20	4.00	"							J
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	U	4.00	"							
89	2,2',3,4,6'-Pentachlorobiphenyl	U	4.00	"							
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	1.28	4.00	"							J
92	2,2',3,5,5'-Pentachlorobiphenyl	U	4.00	"							
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U	4.00	"							
94	2,2',3,5,6'-Pentachlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 00:39

95	2,2',3,5',6-Pentachlorobiphenyl	0.880	4.00	pg/g wet							J
96	2,2',3,6,6'-Pentachlorobiphenyl	U	4.00	"							
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U	4.00	"							
103	2,2',4,5',6-Pentachlorobiphenyl	U	4.00	"							
104	2,2',4,6,6'-Pentachlorobiphenyl	U	4.00	"							
105	2,3,3',4,4'-Pentachlorobiphenyl	3.00	4.00	"							EMPC, J
106	2,3,3',4,5-Pentachlorobiphenyl	U	4.00	"							
107	2,3,3',4',5-Pentachlorobiphenyl	U	4.00	"							
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U	4.00	"							
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	1.48	4.00	"							EMPC, J
111	2,3,3',5,5'-Pentachlorobiphenyl	U	4.00	"							
114	2,3,4,4',5-Pentachlorobiphenyl	U	4.00	"							
118	2,3',4,4',5-Pentachlorobiphenyl	1.84	4.00	"							J
120	2,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
121	2,3',4,5',6-Pentachlorobiphenyl	U	4.00	"							
122	2,3,3',4',5'-Pentachlorobiphenyl	U	4.00	"							
123	2,3',4,4',5'-Pentachlorobiphenyl	U	4.00	"							
126	3,3',4,4',5-Pentachlorobiphenyl	0.400	4.00	"							EMPC, J
127	3,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
128/166	2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB	0.440	4.00	"							EMPC, J
129/138/163	HxCB-129/138/163	2.24	4.00	"							J
130	2,2',3,3',4,5'-Hexachlorobiphenyl	U	4.00	"							
131	2,2',3,3',4,6-Hexachlorobiphenyl	U	4.00	"							
132	2,2',3,3',4,6'-Hexachlorobiphenyl	0.600	4.00	"							J
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U	4.00	"							
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U	4.00	"							
135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	U	4.00	"							
136	2,2',3,3',6,6'-Hexachlorobiphenyl	0.400	4.00	"							EMPC, J
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U	4.00	"							
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U	4.00	"							
141	2,2',3,4,5,5'-Hexachlorobiphenyl	0.480	4.00	"							J
142	2,2',3,4,5,6-Hexachlorobiphenyl	U	4.00	"							
144	2,2',3,4,5',6-Hexachlorobiphenyl	U	4.00	"							
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U	4.00	"							
146	2,2',3,4',5,5'-Hexachlorobiphenyl	U	4.00	"							
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	1.48	4.00	"							J
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 00:39

152	2,2',3,5,6,6'-Hexachlorobiphenyl	U	4.00	pg/g wet							
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	1.92	4.00	"							J
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	4.00	"							
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	0.760	4.00	"							J
158	2,3,3',4,4',6-Hexachlorobiphenyl	U	4.00	"							
159	2,3,3',4,5,5'-Hexachlorobiphenyl	0.800	4.00	"							EMPC, J
160	2,3,3',4,5,6-Hexachlorobiphenyl	U	4.00	"							
161	2,3,3',4,5',6-Hexachlorobiphenyl	U	4.00	"							
162	2,3,3',4',5,5'-Hexachlorobiphenyl	U	4.00	"							
165	2,3,3',5,5',6-Hexachlorobiphenyl	U	4.00	"							
167	2,3',4,4',5,5'-Hexachlorobiphenyl	0.280	4.00	"							EMPC, J
169	3,3',4,4',5,5'-Hexachlorobiphenyl	0.280	4.00	"							J
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	1.76	4.00	"							EMPC, J
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	U	4.00	"							
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U	4.00	"							
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	0.840	4.00	"							EMPC, J
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U	4.00	"							
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U	4.00	"							
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	U	4.00	"							
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U	4.00	"							
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	U	4.00	"							
180/193	2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB	1.76	4.00	"							J
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U	4.00	"							
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U	4.00	"							
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	0.280	4.00	"							J
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U	4.00	"							
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U	4.00	"							
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	0.680	4.00	"							EMPC, J
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	4.00	"							
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	4.00	"							
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U	4.00	"							
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U	4.00	"							
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	0.680	4.00	"							EMPC, J
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U	4.00	"							
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	0.280	4.00	"							EMPC, J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Blank (BE10404-BLK2)					Prepared: 05/05/11 15:33		Analyzed: 06/02/11 00:39				
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U	4.00	pg/g wet							
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	0.560	4.00	"							EMPC, J
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U	4.00	"							
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	4.00	"							
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	0.400	4.00	"							EMPC, J
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U	4.00	"							
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	4.00	"							
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	0.760	4.00	"							J
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U	4.00	"							
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	4.00	"							
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	0.560	4.00	"							J
1-3	Total Monochlorobiphenyl	U	4.00	"							
4-15	Total Dichlorobiphenyl	8.52	4.00	"							
16-39	Total Trichlorobiphenyl	18.8	4.00	"							
40-81	Total Tetrachlorobiphenyl	12.1	4.00	"							
82-127	Total Pentachlorobiphenyl	12.3	4.00	"							
128-169	Total Hexachlorobiphenyl	9.68	4.00	"							
170-193	Total Heptachlorobiphenyl	5.32	4.00	"							
194-205	Total Octachlorobiphenyl	1.92	4.00	"							J
206-208	Total Nonachlorobiphenyl	0.760	4.00	"							J
209	Decachlorobiphenyl	0.560	4.00	"							J
Total PCBs	Total PCBs	70.0	4.00	"							
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*16.8*		*ng/mL*	*100.00*		*17*	*15-150*			
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*20.8*		*"*	*100.00*		*21*	*15-150*			
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*21.1*		*"*	*100.00*		*21*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*47.5*		*"*	*100.00*		*47*	*25-150*			
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*33.9*		*"*	*100.00*		*34*	*25-150*			
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*68.2*		*"*	*100.00*		*68*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*43.6*		*"*	*100.00*		*44*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*78.4*		*"*	*100.00*		*78*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*76.4*		*"*	*100.00*		*76*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*46.7*		*"*	*100.00*		*47*	*25-150*			
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*80.2*		*"*	*100.00*		*80*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*72.8*		*"*	*100.00*		*73*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*72.5*		*"*	*100.00*		*73*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*77.0*		*"*	*100.00*		*77*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*76.1*		*"*	*100.00*		*76*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*71.4*		*"*	*100.00*		*71*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 00:39

156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*146*		*ng/mL*	*200.00*		*73*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*76.8*		*"*	*100.00*		*77*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*93.1*		*"*	*100.00*		*93*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*75.7*		*"*	*100.00*		*76*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*85.5*		*"*	*100.00*		*86*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*83.1*		*"*	*100.00*		*83*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*74.2*		*"*	*100.00*		*74*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*74.2*		*"*	*100.00*		*74*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*75.6*		*"*	*100.00*		*76*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*64.7*		*"*	*100.00*		*65*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*72.4*		*"*	*100.00*		*72*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*78.2*		*"*	*100.00*		*78*	*30-135*			
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*90.4*		*"*	*100.00*		*90*	*30-135*			

Blank (BE10404-BLK3) Prepared: 05/09/11 17:28 Analyzed: 06/02/11 01:43

1	2-Monochlorobiphenyl	U	4.00	pg/g wet							
2	3-Monochlorobiphenyl	U	4.00	"							
3	4-Monochlorobiphenyl	U	4.00	"							
4	2,2'-Dichlorobiphenyl	U	4.00	"							
5	2,3-Dichlorobiphenyl	U	4.00	"							
6	2,3'-Dichlorobiphenyl	U	4.00	"							
7	2,4-Dichlorobiphenyl	U	4.00	"							
8	2,4'-Dichlorobiphenyl	1.64	4.00	"							EMPC, J
9	2,5-Dichlorobiphenyl	U	4.00	"							
10	2,6-Dichlorobiphenyl	U	4.00	"							
11	3,3'-Dichlorobiphenyl	8.32	4.00	"							
12/13	3,4-DiCB/3,4'-DiCB	U	4.00	"							
14	3,5-Dichlorobiphenyl	U	4.00	"							
15	4,4'-Dichlorobiphenyl	U	4.00	"							
16/24	2,2',3-TrCB/2,3,6-TrCB	0.960	4.00	"							J
17	2,2',4-Trichlorobiphenyl	1.00	4.00	"							J
18/30	2,2',5-TrCB/2,4,6-TrCB	2.44	4.00	"							J
19	2,2',6-Trichlorobiphenyl	U	4.00	"							
20/28	2,3,3'-TrCB/2,4,4'-TrCB	2.76	4.00	"							J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK3) Prepared: 05/09/11 17:28 Analyzed: 06/02/11 01:43

21/33	2,3,4-TrCB/2,3',4'-TrCB	2.40	4.00	pg/g wet							J
22	2,3,4'-Trichlorobiphenyl	1.40	4.00	"							J
23	2,3,5-Trichlorobiphenyl	U	4.00	"							
25	2,3',4-Trichlorobiphenyl	U	4.00	"							
26/29	2,3',5-TrCB/2,4,5-TrCB	0.520	4.00	"							J
27	2,3',6-Trichlorobiphenyl	U	4.00	"							
31	2,4',5-Trichlorobiphenyl	3.16	4.00	"							J
32	2,4',6-Trichlorobiphenyl	1.12	4.00	"							J
34	2,3',5'-Trichlorobiphenyl	U	4.00	"							
35	3,3',4-Trichlorobiphenyl	U	4.00	"							
36	3,3',5-Trichlorobiphenyl	U	4.00	"							
37	3,4,4'-Trichlorobiphenyl	1.40	4.00	"							J
38	3,4,5-Trichlorobiphenyl	U	4.00	"							
39	3,4',5-Trichlorobiphenyl	U	4.00	"							
40/41/71	2,2',3,3'-TeCB/2,2',3,4-TeCB/2,3',4',6-TeCB	0.920	4.00	"							J
42	2,2',3,4'-Tetrachlorobiphenyl	U	4.00	"							
43/73	2,2',3,5-TeCB/2,3',5',6-TeCB	U	4.00	"							
44/47/65	2,2',3,5'-TeCB/2,2',4,4'-TeCB/2,3,5,6-TeCB	3.32	4.00	"							J
45/51	2,2',3,6-TeCB/2,2',4,6'-TeCB	U	4.00	"							
46	2,2',3,6'-Tetrachlorobiphenyl	U	4.00	"							
48	2,2',4,5-Tetrachlorobiphenyl	U	4.00	"							
49/69	2,2',4,5'-TeCB/2,3',4,6-TeCB	1.00	4.00	"							J
50/53	2,2',4,6-TeCB/2,2',5,6'-TeCB	U	4.00	"							
52	2,2',5,5'-Tetrachlorobiphenyl	1.64	4.00	"							J
54	2,2',6,6'-Tetrachlorobiphenyl	U	4.00	"							
55	2,3,3',4-Tetrachlorobiphenyl	U	4.00	"							
56	2,3,3',4'-Tetrachlorobiphenyl	1.68	4.00	"							J
57	2,3,3',5-Tetrachlorobiphenyl	U	4.00	"							
58	2,3,3',5'-Tetrachlorobiphenyl	U	4.00	"							
59/62/75	2,3,3',6-TeCB/2,3,4,6-TeCB/2,4,4',6-TeCB	0.440	4.00	"							J
60	2,3,4,4'-Tetrachlorobiphenyl	0.600	4.00	"							J
61/70/74/76	TeCB-61/70/74/76	4.40	4.00	"							
63	2,3,4',5-Tetrachlorobiphenyl	U	4.00	"							
64	2,3,4',6-Tetrachlorobiphenyl	0.760	4.00	"							J
66	2,3',4,4'-Tetrachlorobiphenyl	1.84	4.00	"							J
67	2,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
68	2,3',4,5'-Tetrachlorobiphenyl	U	4.00	"							
72	2,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK3) Prepared: 05/09/11 17:28 Analyzed: 06/02/11 01:43

77	3,3',4,4'-Tetrachlorobiphenyl	1.04	4.00	pg/g wet							EMPC, J
78	3,3',4,5-Tetrachlorobiphenyl	U	4.00	"							
79	3,3',4,5'-Tetrachlorobiphenyl	U	4.00	"							
80	3,3',5,5'-Tetrachlorobiphenyl	U	4.00	"							
81	3,4,4',5-Tetrachlorobiphenyl	U	4.00	"							
82	2,2',3,3',4-Pentachlorobiphenyl	U	4.00	"							
83/99/112	2,2',3,3',5-PeCB/2,2',4,4',5-PeCB/2,3,3',5,6-PeCB	1.40	4.00	"							J
84	2,2',3,3',6-Pentachlorobiphenyl	0.920	4.00	"							J
85/116/117	2,2',3,4,4'-PeCB/2,3,4,5,6-PeCB/2,3,4',5,6-PeCB	0.600	4.00	"							J
86/87/97/109/119/125	PeCB-86/87/97/109/119/125	2.36	4.00	"							J
88/91	2,2',3,4,6-PeCB/2,2',3,4',6-PeCB	0.360	4.00	"							J
89	2,2',3,4,6'-Pentachlorobiphenyl	U	4.00	"							
90/101/113	2,2',3,4',5-PeCB/2,2',4,5,5'-PeCB/2,3,3',5',6-PeCB	2.52	4.00	"							J
92	2,2',3,5,5'-Pentachlorobiphenyl	0.480	4.00	"							EMPC, J
93/100	2,2',3,5,6-PeCB/2,2',4,4',6-PeCB	U	4.00	"							
94	2,2',3,5,6'-Pentachlorobiphenyl	U	4.00	"							
95	2,2',3,5',6-Pentachlorobiphenyl	1.52	4.00	"							J
96	2,2',3,6,6'-Pentachlorobiphenyl	U	4.00	"							
98/102	2,2',3,4',6'-PeCB/2,2',4,5,6'-PeCB	U	4.00	"							
103	2,2',4,5',6-Pentachlorobiphenyl	U	4.00	"							
104	2,2',4,6,6'-Pentachlorobiphenyl	U	4.00	"							
105	2,3,3',4,4'-Pentachlorobiphenyl	3.16	4.00	"							EMPC, J
106	2,3,3',4,5-Pentachlorobiphenyl	U	4.00	"							
107	2,3,3',4',5-Pentachlorobiphenyl	U	4.00	"							
108/124	2,3,3',4,5'-PeCB/2,3',4',5,5'-PeCB	U	4.00	"							
110/115	2,3,3',4',6-PeCB/2,3,4,4',6-PeCB	3.84	4.00	"							J
111	2,3,3',5,5'-Pentachlorobiphenyl	U	4.00	"							
114	2,3,4,4',5-Pentachlorobiphenyl	U	4.00	"							
118	2,3',4,4',5-Pentachlorobiphenyl	3.52	4.00	"							J
120	2,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
121	2,3',4,5',6-Pentachlorobiphenyl	U	4.00	"							
122	2,3,3',4',5'-Pentachlorobiphenyl	U	4.00	"							
123	2,3',4,4',5'-Pentachlorobiphenyl	U	4.00	"							
126	3,3',4,4',5-Pentachlorobiphenyl	U	4.00	"							
127	3,3',4,5,5'-Pentachlorobiphenyl	U	4.00	"							
128/166	2,2',3,3',4,4'-HxCB/2,3,4,4',5,6-HxCB	0.720	4.00	"							J
129/138/163	HxCB-129/138/163	3.80	4.00	"							J
130	2,2',3,3',4,5'-Hexachlorobiphenyl	0.720	4.00	"							EMPC, J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK3) Prepared: 05/09/11 17:28 Analyzed: 06/02/11 01:43

131	2,2',3,3',4,6-Hexachlorobiphenyl	U	4.00	pg/g wet							
132	2,2',3,3',4,6'-Hexachlorobiphenyl	1.32	4.00	"							J
133	2,2',3,3',5,5'-Hexachlorobiphenyl	U	4.00	"							
134/143	2,2',3,3',5,6-HxCB/2,2',3,4,5,6'-HxCB	U	4.00	"							
135/151	2,2',3,3',5,6'-HxCB/2,2',3,5,5',6-HxCB	1.04	4.00	"							J
136	2,2',3,3',6,6'-Hexachlorobiphenyl	0.640	4.00	"							J
137/164	2,2',3,4,4',5-HxCB/2,3,3',4',5',6-HxCB	U	4.00	"							
139/140	2,2',3,4,4',6-HxCB/2,2',3,4,4',6'-HxCB	U	4.00	"							
141	2,2',3,4,5,5'-Hexachlorobiphenyl	0.760	4.00	"							J
142	2,2',3,4,5,6-Hexachlorobiphenyl	U	4.00	"							
144	2,2',3,4,5',6-Hexachlorobiphenyl	U	4.00	"							
145	2,2',3,4,6,6'-Hexachlorobiphenyl	U	4.00	"							
146	2,2',3,4',5,5'-Hexachlorobiphenyl	0.480	4.00	"							J
147/149	2,2',3,4',5,6-HxCB/2,2',3,4',5',6-HxCB	2.52	4.00	"							J
148	2,2',3,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
150	2,2',3,4',6,6'-Hexachlorobiphenyl	U	4.00	"							
152	2,2',3,5,6,6'-Hexachlorobiphenyl	U	4.00	"							
153/168	2,2',4,4',5,5'-HxCB/2,3',4,4',5',6-HxCB	2.68	4.00	"							J
154	2,2',4,4',5,6'-Hexachlorobiphenyl	U	4.00	"							
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	4.00	"							
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	0.800	4.00	"							EMPC, J
158	2,3,3',4,4',6-Hexachlorobiphenyl	U	4.00	"							
159	2,3,3',4,5,5'-Hexachlorobiphenyl	U	4.00	"							
160	2,3,3',4,5,6-Hexachlorobiphenyl	U	4.00	"							
161	2,3,3',4,5',6-Hexachlorobiphenyl	U	4.00	"							
162	2,3,3',4',5,5'-Hexachlorobiphenyl	0.720	4.00	"							EMPC, J
165	2,3,3',5,5',6-Hexachlorobiphenyl	U	4.00	"							
167	2,3',4,4',5,5'-Hexachlorobiphenyl	0.240	4.00	"							EMPC, J
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U	4.00	"							
170	2,2',3,3',4,4',5-Heptachlorobiphenyl	1.12	4.00	"							J
171/173	2,2',3,3',4,4',6-HpCB/2,2',3,3',4,5,6-HpCB	0.280	4.00	"							J
172	2,2',3,3',4,5,5'-Heptachlorobiphenyl	U	4.00	"							
174	2,2',3,3',4,5,6'-Heptachlorobiphenyl	1.00	4.00	"							J
175	2,2',3,3',4,5',6-Heptachlorobiphenyl	U	4.00	"							
176	2,2',3,3',4,6,6'-Heptachlorobiphenyl	U	4.00	"							
177	2,2',3,3',4,5',6'-Heptachlorobiphenyl	0.600	4.00	"							J
178	2,2',3,3',5,5',6-Heptachlorobiphenyl	U	4.00	"							
179	2,2',3,3',5,6,6'-Heptachlorobiphenyl	0.600	4.00	"							EMPC, J

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Blank (BE10404-BLK3)					Prepared: 05/09/11 17:28	Analyzed: 06/02/11 01:43					
180/193	2,2',3,4,4',5,5'-HpCB/2,3,3',4',5,5',6-HpCB	2.00	4.00	pg/g wet							J
181	2,2',3,4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
182/187	2,2',3,4,4',5,6'-HpCB/2,2',3,4',5,5',6-HpCB	U	4.00	"							
182	2,2',3,4,4',5,6'-Heptachlorobiphenyl	U	4.00	"							
183/185	2,2',3,4,4',5',6-HpCB/2,2',3,4,5,5',6-HpCB	0.360	4.00	"							J
184	2,2',3,4,4',6,6'-Heptachlorobiphenyl	U	4.00	"							
186	2,2',3,4,5,6,6'-Heptachlorobiphenyl	U	4.00	"							
187	2,2',3,4',5,5',6-Heptachlorobiphenyl	0.880	4.00	"							J
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	4.00	"							
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	4.00	"							
190	2,3,3',4,4',5,6-Heptachlorobiphenyl	U	4.00	"							
191	2,3,3',4,4',5',6-Heptachlorobiphenyl	U	4.00	"							
192	2,3,3',4,5,5',6-Heptachlorobiphenyl	U	4.00	"							
194	2,2',3,3',4,4',5,5'-Octachlorobiphenyl	0.640	4.00	"							J
195	2,2',3,3',4,4',5,6-Octachlorobiphenyl	U	4.00	"							
196	2,2',3,3',4,4',5,6'-Octachlorobiphenyl	0.320	4.00	"							J
197/200	2,2',3,3',4,4',6,6'-OcCB/2,2',3,3',4,5,6,6'-OcCB	U	4.00	"							
198/199	2,2',3,3',4,5,5',6-OcCB/2,2',3,3',4,5,5',6'-OcCB	0.520	4.00	"							J
201	2,2',3,3',4,5',6,6'-Octachlorobiphenyl	U	4.00	"							
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	4.00	"							
203	2,2',3,4,4',5,5',6-Octachlorobiphenyl	0.360	4.00	"							J
204	2,2',3,4,4',5,6,6'-Octachlorobiphenyl	U	4.00	"							
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	4.00	"							
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	4.00	"							
207	2,2',3,3',4,4',5,6,6'-Nonachlorobiphenyl	U	4.00	"							
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	4.00	"							
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	0.520	4.00	"							J
1-3	Total Monochlorobiphenyl	U	4.00	"							
4-15	Total Dichlorobiphenyl	9.96	4.00	"							
16-39	Total Trichlorobiphenyl	17.2	4.00	"							
40-81	Total Tetrachlorobiphenyl	17.6	4.00	"							
82-127	Total Pentachlorobiphenyl	20.7	4.00	"							
128-169	Total Hexachlorobiphenyl	16.4	4.00	"							
170-193	Total Heptachlorobiphenyl	6.84	4.00	"							
194-205	Total Octachlorobiphenyl	1.84	4.00	"							J
206-208	Total Nonachlorobiphenyl	U	4.00	"							
209	Decachlorobiphenyl	0.520	4.00	"							J
Total PCBs	Total PCBs	91.1	4.00	"							

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Blank (BE10404-BLK3) Prepared: 05/09/11 17:28 Analyzed: 06/02/11 01:43

1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*19.1*		*ng/mL*	*100.00*		*19*	*15-150*		
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*26.3*		*"*	*100.00*		*26*	*15-150*		
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*25.8*		*"*	*100.00*		*26*	*25-150*		
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*65.4*		*"*	*100.00*		*65*	*25-150*		
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*44.2*		*"*	*100.00*		*44*	*25-150*		
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*98.0*		*"*	*100.00*		*98*	*25-150*		
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*59.3*		*"*	*100.00*		*59*	*25-150*		
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*99.4*		*"*	*100.00*		*99*	*25-150*		
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*99.5*		*"*	*100.00*		*100*	*25-150*		
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*61.0*		*"*	*100.00*		*61*	*25-150*		
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*87.5*		*"*	*100.00*		*88*	*25-150*		
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*82.8*		*"*	*100.00*		*83*	*25-150*		
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*89.8*		*"*	*100.00*		*90*	*25-150*		
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*92.3*		*"*	*100.00*		*92*	*25-150*		
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*85.1*		*"*	*100.00*		*85*	*25-150*		
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*93.9*		*"*	*100.00*		*94*	*25-150*		
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*170*		*"*	*200.00*		*85*	*25-150*		
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*89.8*		*"*	*100.00*		*90*	*25-150*		
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*97.6*		*"*	*100.00*		*98*	*25-150*		
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*94.4*		*"*	*100.00*		*94*	*25-150*		
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*95.6*		*"*	*100.00*		*96*	*25-150*		
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*100*		*"*	*100.00*		*100*	*25-150*		
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*89.1*		*"*	*100.00*		*89*	*25-150*		
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*93.5*		*"*	*100.00*		*94*	*25-150*		
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*89.0*		*"*	*100.00*		*89*	*25-150*		
209L	*Surrogate:13C12-Decachlorobiphenyl*	*88.8*		*"*	*100.00*		*89*	*25-150*		
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*89.6*		*"*	*100.00*		*90*	*30-135*		
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*81.3*		*"*	*100.00*		*81*	*30-135*		
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*94.2*		*"*	*100.00*		*94*	*30-135*		

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

LCS (BE10404-BS1) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 06:00

1	2-Monochlorobiphenyl	9.08	4.00	pg/g wet	10.000		91	50-150			
3	4-Monochlorobiphenyl	11.6	4.00	"	10.000		116	50-150			
4	2,2'-Dichlorobiphenyl	12.0	4.00	"	10.000		120	50-150			
15	4,4'-Dichlorobiphenyl	11.3	4.00	"	10.000		113	50-150			
19	2,2',6-Trichlorobiphenyl	10.1	4.00	"	10.000		101	50-150			
37	3,4,4'-Trichlorobiphenyl	9.52	4.00	"	10.000		95	50-150			
54	2,2',6,6'-Tetrachlorobiphenyl	8.92	4.00	"	10.000		89	50-150			
77	3,3',4,4'-Tetrachlorobiphenyl	10.4	4.00	"	10.000		104	50-150			
81	3,4,4',5-Tetrachlorobiphenyl	9.72	4.00	"	10.000		97	50-150			
104	2,2',4,6,6'-Pentachlorobiphenyl	10.5	4.00	"	10.000		105	50-150			
105	2,3,3',4,4'-Pentachlorobiphenyl	12.8	4.00	"	10.000		128	50-150			
114	2,3,4,4',5-Pentachlorobiphenyl	10.4	4.00	"	10.000		104	50-150			
118	2,3',4,4',5-Pentachlorobiphenyl	12.0	4.00	"	10.000		120	50-150			
123	2,3',4,4',5'-Pentachlorobiphenyl	9.68	4.00	"	10.000		97	50-150			
126	3,3',4,4',5-Pentachlorobiphenyl	10.4	4.00	"	10.000		104	50-150			
155	2,2',4,4',6,6'-Hexachlorobiphenyl	9.20	4.00	"	10.000		92	50-150			
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	21.6	4.00	"	20.000		108	50-150			
167	2,3',4,4',5,5'-Hexachlorobiphenyl	9.92	4.00	"	10.000		99	50-150			
169	3,3',4,4',5,5'-Hexachlorobiphenyl	9.24	4.00	"	10.000		92	50-150			
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	10.3	4.00	"	10.000		103	50-150			
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	9.32	4.00	"	10.000		93	50-150			
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	10.5	4.00	"	10.000		105	50-150			
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	9.96	4.00	"	10.000		100	50-150			
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	11.0	4.00	"	10.000		110	50-150			
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	10.1	4.00	"	10.000		101	50-150			
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	11.1	4.00	"	10.000		111	50-150			
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*9.49*		*ng/mL*	*100.00*		*9*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*14.7*		*"*	*100.00*		*15*	*15-150*			
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*15.8*		*"*	*100.00*		*16*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*41.8*		*"*	*100.00*		*42*	*25-150*			
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*30.4*		*"*	*100.00*		*30*	*25-150*			
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*61.1*		*"*	*100.00*		*61*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*44.7*		*"*	*100.00*		*45*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*80.4*		*"*	*100.00*		*80*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*76.0*		*"*	*100.00*		*76*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*40.9*		*"*	*100.00*		*41*	*25-150*			
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*76.5*		*"*	*100.00*		*76*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*70.9*		*"*	*100.00*		*71*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

LCS (BE10404-BS1) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 06:00

118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*71.2*		*ng/mL*	*100.00*		*71*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*76.5*		*"*	*100.00*		*76*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*71.7*		*"*	*100.00*		*72*	*25-150*			
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*67.0*		*"*	*100.00*		*67*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*131*		*"*	*200.00*		*65*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*68.8*		*"*	*100.00*		*69*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*72.9*		*"*	*100.00*		*73*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*84.6*		*"*	*100.00*		*85*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*78.8*		*"*	*100.00*		*79*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*89.2*		*"*	*100.00*		*89*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*78.1*		*"*	*100.00*		*78*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*83.9*		*"*	*100.00*		*84*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*82.1*		*"*	*100.00*		*82*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*75.9*		*"*	*100.00*		*76*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*70.0*		*"*	*100.00*		*70*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*78.0*		*"*	*100.00*		*78*	*30-135*			
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*91.3*		*"*	*100.00*		*91*	*30-135*			

LCS (BE10404-BS2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 07:04

Total PCBs	Total PCBs	36500	4.00	pg/g wet	40000		91	25-150			
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*4.10*		*ng/mL*	*100.00*		*4*	*15-150*			*A*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*6.07*		*"*	*100.00*		*6*	*15-150*			*A*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*6.55*		*"*	*100.00*		*7*	*25-150*			*A*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*26.8*		*"*	*100.00*		*27*	*25-150*			
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*16.2*		*"*	*100.00*		*16*	*25-150*			*A*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*48.8*		*"*	*100.00*		*49*	*25-150*			
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*27.6*		*"*	*100.00*		*28*	*25-150*			
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*60.0*		*"*	*100.00*		*60*	*25-150*			
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*58.2*		*"*	*100.00*		*58*	*25-150*			
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*33.2*		*"*	*100.00*		*33*	*25-150*			
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*66.9*		*"*	*100.00*		*67*	*25-150*			
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*63.1*		*"*	*100.00*		*63*	*25-150*			
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*60.5*		*"*	*100.00*		*60*	*25-150*			
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*69.6*		*"*	*100.00*		*70*	*25-150*			
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*68.2*		*"*	*100.00*		*68*	*25-150*			

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

LCS (BE10404-BS2) Prepared: 05/05/11 15:33 Analyzed: 06/02/11 07:04

155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*49.1*		*ng/mL*	*100.00*		*49*	*25-150*			
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*98.3*		*"*	*200.00*		*49*	*25-150*			
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*51.9*		*"*	*100.00*		*52*	*25-150*			
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*58.6*		*"*	*100.00*		*59*	*25-150*			
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*68.6*		*"*	*100.00*		*69*	*25-150*			
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*73.4*		*"*	*100.00*		*73*	*25-150*			
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*70.1*		*"*	*100.00*		*70*	*25-150*			
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*63.1*		*"*	*100.00*		*63*	*25-150*			
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*67.7*		*"*	*100.00*		*68*	*25-150*			
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*68.9*		*"*	*100.00*		*69*	*25-150*			
209L	*Surrogate:13C12-Decachlorobiphenyl*	*58.0*		*"*	*100.00*		*58*	*25-150*			
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*49.0*		*"*	*100.00*		*49*	*30-135*			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*63.3*		*"*	*100.00*		*63*	*30-135*			
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*72.0*		*"*	*100.00*		*72*	*30-135*			

Matrix Spike (BE10404-MS1) **Source: 1104020-03** Prepared: 05/05/11 15:33 Analyzed: 06/15/11 17:31

1	2-Monochlorobiphenyl	1.29	1.29	pg/g dry	64.408	6.10	NR	50-150			TD
3	4-Monochlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
4	2,2'-Dichlorobiphenyl	1.29	1.29	"	64.408	76.8	NR	50-150			TD
15	4,4'-Dichlorobiphenyl	1.29	1.29	"	64.408	182	NR	50-150			TD
19	2,2',6-Trichlorobiphenyl	1.29	1.29	"	64.408	57.3	NR	50-150			TD
37	3,4,4'-Trichlorobiphenyl	1.29	1.29	"	64.408	233	NR	50-150			TD
54	2,2',6,6'-Tetrachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
77	3,3',4,4'-Tetrachlorobiphenyl	1.29	1.29	"	64.408	65.3	NR	50-150			TD
81	3,4,4',5-Tetrachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
104	2,2',4,6,6'-Pentachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
105	2,3,3',4,4'-Pentachlorobiphenyl	1.29	1.29	"	64.408	776	NR	50-150			TD
114	2,3,4,4',5-Pentachlorobiphenyl	1.29	1.29	"	64.408	47.6	NR	50-150			TD
118	2,3',4,4',5-Pentachlorobiphenyl	1.29	1.29	"	64.408	1900	NR	50-150			TD
123	2,3',4,4',5'-Pentachlorobiphenyl	1.29	1.29	"	64.408	25.6	NR	50-150			TD
126	3,3',4,4',5-Pentachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
155	2,2',4,4',6,6'-Hexachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	1.29	1.29	"	128.82	417	NR	50-150			TD
167	2,3',4,4',5,5'-Hexachlorobiphenyl	1.29	1.29	"	64.408	115	NR	50-150			TD

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Matrix Spike (BE10404-MS1)		**Source: 1104020-03**			Prepared: 05/05/11 15:33		Analyzed: 06/15/11 17:31				
169	3,3',4,4',5,5'-Hexachlorobiphenyl	1.29	1.29	pg/g dry	64.408	0.00	2	50-150			TD
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	1.29	1.29	"	64.408	0.00	2	50-150			TD
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	1.29	1.29	"	64.408	15.9	NR	50-150			TD
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	1.29	1.29	"	64.408	72.0	NR	50-150			TD
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	1.29	1.29	"	64.408	10.4	NR	50-150			TD
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	1.29	1.29	"	64.408	226	NR	50-150			TD
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	1.29	1.29	"	64.408	64.7	NR	50-150			TD
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	1.29	1.29	"	64.408	55.5	NR	50-150			TD
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*1.00*		*ng/mL*	*100.00*		*1*	*15-150*			*TD*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*15-150*			*TD*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*1.00*		*"*	*200.00*		*0.5*	*25-150*			*TD*
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*1.00*		*"*	*100.00*		*1*	*25-150*			*TD*
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
209L	*Surrogate:13C12-Decachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch BE10404 - EPA 3540C PCB Congeners											
Matrix Spike (BE10404-MS1)		**Source: 1104020-03**			Prepared: 05/05/11 15:33			Analyzed: 06/15/11 17:31			
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*30-135*			*TD*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
Matrix Spike Dup (BE10404-MSD1)		**Source: 1104020-03**			Prepared: 05/05/11 15:33			Analyzed: 06/15/11 17:31			
1	2-Monochlorobiphenyl	U	1.27	pg/g dry	63.465	6.10	NR	50-150	NR	25	TD
3	4-Monochlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
4	2,2'-Dichlorobiphenyl	U	1.27	"	63.465	76.8	NR	50-150	NR	25	TD
15	4,4'-Dichlorobiphenyl	U	1.27	"	63.465	182	NR	50-150	NR	25	TD
19	2,2',6-Trichlorobiphenyl	U	1.27	"	63.465	57.3	NR	50-150	NR	25	TD
37	3,4,4'-Trichlorobiphenyl	U	1.27	"	63.465	233	NR	50-150	NR	25	TD
54	2,2',6,6'-Tetrachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
77	3,3',4,4'-Tetrachlorobiphenyl	U	1.27	"	63.465	65.3	NR	50-150	NR	25	TD
81	3,4,4',5-Tetrachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
104	2,2',4,6,6'-Pentachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
105	2,3,3',4,4'-Pentachlorobiphenyl	U	1.27	"	63.465	776	NR	50-150	NR	25	TD
114	2,3,4,4',5-Pentachlorobiphenyl	U	1.27	"	63.465	47.6	NR	50-150	NR	25	TD
118	2,3',4,4',5-Pentachlorobiphenyl	U	1.27	"	63.465	1900	NR	50-150	NR	25	TD
123	2,3',4,4',5'-Pentachlorobiphenyl	U	1.27	"	63.465	25.6	NR	50-150	NR	25	TD
126	3,3',4,4',5-Pentachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
155	2,2',4,4',6,6'-Hexachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
156/157	2,3,3',4,4',5-HxCB/2,3,3',4,4',5'-HxCB	U	1.27	"	126.93	417	NR	50-150	NR	25	TD
167	2,3',4,4',5,5'-Hexachlorobiphenyl	U	1.27	"	63.465	115	NR	50-150	NR	25	TD
169	3,3',4,4',5,5'-Hexachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
188	2,2',3,4',5,6,6'-Heptachlorobiphenyl	U	1.27	"	63.465	0.00		50-150		25	TD
189	2,3,3',4,4',5,5'-Heptachlorobiphenyl	U	1.27	"	63.465	15.9	NR	50-150	NR	25	TD
202	2,2',3,3',5,5',6,6'-Octachlorobiphenyl	U	1.27	"	63.465	72.0	NR	50-150	NR	25	TD
205	2,3,3',4,4',5,5',6-Octachlorobiphenyl	U	1.27	"	63.465	10.4	NR	50-150	NR	25	TD
206	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	U	1.27	"	63.465	226	NR	50-150	NR	25	TD
208	2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl	U	1.27	"	63.465	64.7	NR	50-150	NR	25	TD
209	2,2',3,3',4,4',5,5',6,6'-Decachlorobiphenyl	U	1.27	"	63.465	55.5	NR	50-150	NR	25	TD
1L	*Surrogate:13C12-2-Monochlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*15-150*			*TD*
3L	*Surrogate:13C12-4-Monochlorobiphenyl*	*0.00*		*"*	*100.00*			*15-150*			*TD*
4L	*Surrogate:13C12-2,2'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
15L	*Surrogate:13C12-4,4'-Dichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
19L	*Surrogate:13C12-2,2',6-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
37L	*Surrogate:13C12-3,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
54L	*Surrogate:13C12-2,2',6,6'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
77L	*Surrogate:13C12-3,3',4,4'-Tetrachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

QC Data
PCB Congeners

Congener Number:	Analyte	Result	Quantitation Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes

Batch BE10404 - EPA 3540C PCB Congeners

Matrix Spike Dup (BE10404-MSD1) **Source: 1104020-03** Prepared: 05/05/11 15:33 Analyzed: 06/15/11 17:31

81L	*Surrogate:13C12-3,4,4',5-Tetrachlorobiphenyl*	*0.00*		*ng/mL*	*100.00*			*25-150*			*TD*
104L	*Surrogate:13C12-2,2',4,6,6'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
105L	*Surrogate:13C12-2,3,3',4,4'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
114 L	*Surrogate:13C12-2,3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
118 L	*Surrogate:13C12-2,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
123L	*Surrogate:13C12-2',3,4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
126L	*Surrogate:13C12-3,3',4,4',5-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
155L	*Surrogate:13C12-2,2',4,4',6,6'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
156L/157L	*Surrogate:13C12-2,3,3',4,4',5-HxCB/13C12-2,3,3',4,4',5'-HxCB*	*0.00*		*"*	*200.00*			*25-150*			*TD*
167L	*Surrogate:13C12-2,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
169L	*Surrogate:13C12-3,3',4,4',5,5'-Hexachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
188L	*Surrogate:13C12-2,2',3,4',5,6,6'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
189L	*Surrogate:13C12-2,3,3',4,4',5,5'-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
202L	*Surrogate:13C12-2,2',3,3',5,5',6,6'-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
205L	*Surrogate:13C12-2,3,3',4,4',5,5',6-Octachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
206L	*Surrogate:13C12-2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
208L	*Surrogate:13C12-2,2',3,3',4,5,5',6,6'-Nonachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
209L	*Surrogate:13C12-Decachlorobiphenyl*	*0.00*		*"*	*100.00*			*25-150*			*TD*
28L	*Surrogate:13C12-2,4,4'-Trichlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
111 L	*Surrogate:13C12-2,3,3',5,5'-Pentachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*
178L	*Surrogate:13C12-2,2',3,3',5,5',6-Heptachlorobiphenyl*	*0.00*		*"*	*100.00*			*30-135*			*TD*

Site Name: Metal Bank of America - State Road Site **Project #: DAS R33687**

Notes and Definitions

U	Analyte included in the analysis, but not detected at or above the quantitation limit.
TD	Spike recovery too dilute for accurate quantitation.
J	The identification of the analyte is acceptable; the reported value is an estimate.
EMPC	The theoretical ion abundance ratio of the two m/z ions do not meet the 25% criteria, and the result is an Estimated Maximum Possible Concentration.
C	See narrative for comments and observations concerning this result.
B	Not detected substantially above (10 times) the level reported in the laboratory or field blanks (including field, trip, rinsate, and equipment blanks).
A	Quality control value is outside acceptance limits.
NR	Not Reported
RPD	Relative Percent Difference
U	Analyte included in the analysis, but not detected at or above the quantitation limit.

Quantitation Limit: The lowest concentration of an analyte that can be reliably measured within specified limits of precision and accuracy for a specific laboratory analytical method and that takes into account analytical adjustments made during sample preparation and analysis.

SOLID SAMPLE RESULTS - REPORTING PROTOCOL: Solid samples where % Solids (percent dry wt at 105 degrees C) has been performed, are analyzed wet and converted to a dry weight result for reporting purposes. This is routine for organics and most inorganic analyses. When metals and mercury analyses are requested, solid samples are routinely analyzed and reported on a dry weight basis. Solid samples for metals/mercury are prepared for analysis by an initial drying at 60 degree C and homogenization before digestion. Oil-type samples will be analyzed and reported on a wet weight basis for all analyses because of the nature of the sample. Any exceptions to the protocol will be noted with a qualifier