		Created Date
DATE	7/25/2017	7/25/2017

NAME	Guardian Environmental - HTC additional fencing
ATTENTION	Kevin Shaver
PHONE	-
FAX	- kshaver@gesoncall.com
CELL	-
RE:	HTC additional fencing

WE ARE PLEASE TO SUBMIT THE FOLLOWING QUOTATION FOR YOUR REVIEW

6+1' high temp fence

Furnish and install approximately 434 LF of top tension wire chain link fence. 2-1/4 x 11-1/2G x 72 galv fabric. 1-5/8" x 9' SS-20 line posts driven 3' deep @ 10' spacing
All terminals 2-1/2" x 11' x SS20 Price & footage includes 2 areas, one
about 345lf & a second about 89lf, no gates
Barb-less barbed wire, 3 strands on 45 degree pressed steel barb arms. No take down labor or material recovery.

LUMP SUM $ 7,697.13 plus tax

Please Note: No allowance for UG or OH obstructions, facilities, debris, rock, soft, wet, unsuitable or "caving" earth or stone fill, etc. or electrical grounding. No borings have been seen. Installation based on standard power equipment to augur holes or drive posts through earth. Grading to be complete within a few inches of FG. No restoration, blacktop patching or landscaping. Layout from legal survey by others, we will layout our fence from your stake-out or at your direction. Excavation spoils left on site in location determined by you or raked into existing grade/grass. No electrical work, grounding or lightning protection of any kind.
No coring of concrete or blacktop slabs (UON). No painting, priming or staining of any kind. Any mowing strips are excluded. No Hazmat.
Prevailing wage, certified payrolls