

#### **Transmittal**

Sent Via:	☐ Messenger	U.S. Mail	Overnight Mail
-----------	-------------	-----------	----------------

cc:

Date: December 15, 2015 From: Daniel Costamagna

To: Lee Hammond Amec Foster Wheeler Environmental Site Remediation Irvine, California

Environmental Site Remediation 1400 Douglas Street, STOP 1030

Omaha, Nebraska 68179

**Project Number:** 0106270030

Project Name: Former Pechiney Cast Plate, Inc. Facility, Vernon, California

#### Item Description

- 1 UPRR Application for Right of Entry Agreement
- 2 Check for Application
- 3 Work Plan for Proposed Sampling

#### Remarks

Enclosed please find the above mentioned subject documents. Please call us at (949) 642-0245 if you have any other questions or concerns.

Sincerely yours, Amec Foster Wheeler

 $\label{local_policy} P:\label{local_policy} $$P:\label{local_policy} $$P:\label{local_policy}$ 

Amec Foster Wheeler Environment & Infrastructure, Inc. 121 Innovation Drive, Suite 200 Irvine, CA USA 92617-3094 Tel (949) 642-0245 Fax (949) 642-4474 www.amecfw.com

### APPLICATION FORM FOR UNION PACIFIC RAILROAD COMPANY ENVIRONMENTAL RIGHT OF ENTRY AGREEMENT

Please fill in as indicated. Please type or print clearly in all capital letters:

	SIBLE PARTY/LICENSEE: Company Name FORMER VECHINEY CAST PLETE, INC.
1	POBox & Street Address 4700 DAYBO FAX BLOK WAY
(	City, State, Zip Code SOUTH JORDAN, UTAH 84095
;	State of Incorporation
•	Contact: (Name / Title) GERRY PEPPER
	(Phone / Fax)
	(email, if possible) gerald . pepper e gmail.com
	EE CONSULTANT (if applicable):  Company Name  AMEC FOSTER WHEELER
1	POBox & Street Address 121 INNO VATION DELUE, STE 200
(	City, State, Zip Code   PUINE, CALIFORNIA 92617
Č	Contact: (Name / Title) LINDA CONLAN
	(Phone / Fax) (949) 642 0245
	(email, if possible) linda. con lan Camectw. com
RAILRO.	CATION (include City / County / State) 3200 FRUITIAND AVENUE VERNOW / LOS ANGELES / CALI FORMIA  AD MILEPOST AND SUBDIVISION  for DOT Crossing Number on nearest railroad/street crossing)  DE AND LONGITUDE (degrees/minutes/seconds)
	THE NAME, ADDRESS, & CONTACT PERSON OF THE GOVERNMENTAL AGENCY ING THIS PROJECT:
NATIL 75 415	HAWTHORNE STREET, SAN FRANCISCO, CA 94105
Please desci	ribe your proposed project:
	PROJECT LEVEL(S):  PHASE I (Non-invasive & non-intrusive visual site inspection and records check only.  No sampling will be involved.)  PHASE II (Site investigation. You must advise specific testing to be performed from the
	list on the next page.) PHASE III (Site remediation.)
	OTHER (Please describe your project in detail only as it pertains to railroad property)  TERM: DATES
From:	To: (Includes removal/lawful closure of facilities and/or monitoring wells)

TYPE OF ENVIRONMENTAL TESTING	NUMBER OF EACH				
Subsurface Soil/Sediment Samples					
Hand Held Auger Borings	12				
Soil Gas Survey Points	MARKAGO MA				
Boring Drilled w/Soil Samples					
Temporary Piezometer Wells					
Temporary Monitor Wells (must be flush-mounted)					
Permanent Monitoring Wells					
Recovery Wells & Associated above Ground Equipment					
Recovery Systems & Above Ground Equipment					
Other (Describe fully)					
SPECIAL PROVISIONS:					
CONFIDENTIALITY (Required for all cases involving sale of Railroad property & in many other cases.)					
RAILROAD FLAGMAN (Required in all Phase II/III cases & many other cases.)					
MONITORING WELL (Required for all monitor wells & piezometers.)					
FURNISH INFORMATION (Required in all cases.)					
PROOF OF FINANCIAL CAPABILITY OR PERFORMANCE BOND (Required for all monitor wells, piezometers, & other facilities.)					
CONTRACTOR INFORMATION: (Must be copied for all contractors that will work under the	his agreement)				
NAME OF CONTRACTOR INTERPHASE ENUIDONM	ENTOL, INC.				
INCORPORATED IN WHAT STATE CALIFORNIA					
FULL MAILING ADDRESS 6200 PEACUTREE					
NAME & TITLE OF CONTRACTOR CONTACT PERSON TES DE LEON					
Ophilograma i produci del del nema mineria del militario d	1∞				
CONTRACTOR FAX NUMBER (323) 278 - 7					
EMAIL ADDRESS office e Interphase - Inc	com				
<ul> <li>( ) COMPLETE AND RETURN THIS APPLICATION FORM, with</li> <li>( ) A \$555.00 CHECK (Payable to Union Pacific Railroad Company), and</li> <li>( ) THE OTHER REQUESTED MATERIAL ON THE CHECKLIST to the appropriate Environmental Access Manager.</li> <li>NOTE: Other fees and charges may be applicable to your request. These charges cannot be determined until your Project is approved.</li> </ul>					



# WORK PLAN PROPOSED SOIL SAMPLES UPRR SEGMENT

Former Pechiney Cast Plate, Inc. Facility
3200 Fruitland Avenue
Vernon, California

Prepared for:

Pechiney Cast Plate, Inc.

Prepared by:

Amec Foster Wheeler Environment & Infrastructure, Inc.

121 Innovation Drive, Suite 200 Irvine, California 92617-3094 (949) 642-0245

December 15, 2015

Project No. 0106270030



WORK PLAN
PROPOSED SOIL SAMPLES UPRR SEGMENT
Former Pechiney Cast Plate, Inc. Facility
3200 Fruitland Avenue
Vernon, California

December 15, 2015 Project 0106270030

This work plan was prepared by the staff of Amec Foster Wheeler Environment & Infrastructure, Inc., under the supervision of the Engineer(s) and/or Geologist(s) whose seal(s) and signature(s) appear hereon.

The findings, recommendations, specifications, or professional opinions are presented within the limits described by the client, in accordance with generally accepted professional engineering and geologic practice. No warranty is expressed or implied.

CHANGE GEORGE COSTAMAGNA

No. GEO 9007

SP | 51 | 2-016

Daniel G. Costamagna, PG No. 9007 Senior Geologist

Kimberly HChominsky

No. 7033 (SK) Exp. 1/31/17

Kimberly Holland-Chominsky, PG No. 7033

Senior Associate Geologist

# WORK PLAN PROPOSED SOIL SAMPLES UPRR SEGMENT

Former Pechiney Cast Plate, Inc. Facility Vernon, California

#### 1.0 INTRODUCTION AND AGENCY DIRECTIVE

Amec Foster Wheeler Environment & Infrastructure, Inc. (Amec Foster Wheeler) has prepared this work plan (WP) on behalf of Pechiney Cast Plate, Inc. (Pechiney), for the former Pechiney property located at 3200 Fruitland Avenue, in Vernon, California (the site; Figure 1) and at the direction of the United States Environmental Protection Agency (U.S. EPA) for additional characterization of polychlorinated biphenyls (PCBs) that may be encountered in soils.

The WP is intended to be a plan that describes the protocols for handling, managing and sampling soil. Depending on the analytical results obtained from the soil samples, additional samples may be collected.

Mr. Nathan Dadap of the U.S. EPA has directed Pechiney to conduct the PCB sampling activities. His contact information is as follows.

Nathan Dadap
U.S. EPA Region 9
Land Division, RCRA Branch
75 Hawthorne Street
San Francisco, CA 94105
415-972-3654

#### 2.0 SCOPE OF WORK

This section provides procedures for soil sampling, equipment decontamination, managing and characterization of soil with residual chemicals of potential concern (COCs) remaining at concentrations below or above the site-specific remediation goals for the Pechiney site (Table 1).

#### 2.1 SOIL CONTAINING PCBs AND OTHER COCS

PCBs were detected above the site-specific remediation goals at three locations (W-1, W-2, SWO-6-N and SWO-6-S) as shown on Figure 2. In addition, arsenic was detected above the site-specific remediation goal in two soil samples (W-24 and W-25). Soil samples will be collected at 1, 3, and 5 feet below native grade at the locations shown on Figure 2. Based on data already collected, U.S. EPA is requiring samples to be collected within 25 feet of the

Amec Foster Wheeler Environment & Infrastructure, Inc.

active rail line shown on Figure 2. Locations where sampling occurs shall be documented and surveyed.

Soils generated during sampling shall be containerized in 55-gallon drums and relocated to the Pechiney site for waste characterization and disposal.

#### 2.2 SOIL TESTING AND EQUIPMENT DECONTAMINATION

Soil sampling and analysis for PCBs and arsenic shall be conducted to assess the presence of these COCs at concentrations above the remediation goals (Table 1).

The number of, and the methods used to collect the soil samples and the analyses to be performed shall be selected in the field by the supervising Professional Geologist (PG) or Professional Engineer (PE). The analytical suite shall be selected based on field observations, and may include the following test methods:

- PCBs using EPA Method 8082 (using soxhlet extraction method 3540C);
- Arsenic using EPA Methods 6010B

Samples shall be collected in glass jars, which shall be sealed, uniquely labeled, and stored in an ice-chilled cooler. The samples shall be shipped to an analytical laboratory using chain of custody procedures.

Re-useable sampling equipment (hand augers, shovels, etc.) will be decontaminated using the following steps to reduce the potential for cross-contamination.

- 1. wash and scrub in non-phosphate detergent and potable water;
- 2. rinse in potable water; and
- 3. rinse in hexane and air dried

Investigation derived waste, including decontamination water, shall be managed and stored at the Pechiney site in accordance with regulatory requirements.

#### 2.3 WASTE MANAGEMENT

The soil shall be profiled for disposal. Waste profiling shall consist of collecting soil samples (from hand auger) for laboratory analyses. Sampling shall be conducted in conformance with the procedures stipulated by the supervising PG or PE. Soil samples shall be analyzed for COCs specified above.

Other analyses may be required contingent on waste profiling requirements, receiving facility requirements, or other regulatory directives.

Amec Foster Wheeler Environment & Infrastructure, Inc.

#### 3.0 HEALTH & SAFETY AND INSURANCE REQUIREMENTS

Project personnel shall comply with all applicable federal, state, and local regulations, as well as Occupational Safety and Health Administration (OSHA) regulations specified in 29 Code of Federal Regulations 1910.120 and Code of California Regulations Title 8, Section 5192. A site-specific health and safety plan shall be prepared prior to the start of sampling.

Railroad protective liability insurance will be obtained prior to the start of work. All required insurance certificates will be included with the executed agreement for access.

#### 4.0 REFERENCE

AMEC, 2012, Feasibility Study, Former Pechiney Cast Plate, Inc., Facility, Vernon, California, May 7.



## **TABLE**

#### TABLE 1

### SITE-SPECIFIC REMEDIATION GOALS PCBs AND ARSENIC IN SOIL

#### Pechiney Cast Plate, Inc. Facility - UPRR Segmest

3200 Fruitland Avenue Vernon, California

Compound	Remediation Goal (mg/kg)	Explanation			
PCBs in Soil					
Aroclor-1254	2.0	Noncarcinogenic RBSL <sup>1</sup> for construction workers. Also protective of commercial/industrial worker exposure.			
Total Aroclors For soil that may be left exposed at the surface (0 to 5 feet bgs)	3.5	Based on the regression analysis for dioxin-like PCB congeners versus total Aroclors in combined soil and concrete presented in Appendix E of the FS (AMEC, 2012a), the total Aroclor concentration that would result in a maximum dioxin TEQ concentration of 81 pg/g. Protective of cumulative commercial/industrial worker exposure, and cumulative construction worker exposure, to PCBs.			
Total Aroclors  For subsurface soil (5 to 15 feet bgs) that only construction workers may come into contact with during excavation, grading, etc. (and that would remain at 5 to 15 feet bgs)	23	Based on the regression analysis for dioxin-like PCB congeners versus total Aroclors in combined soil and concrete presented in Appendix E of the FS (AMEC, 2012), the total Aroclor concentration that would result in a maximum dioxin TEQ concentration of 530 pg/g. <sup>3</sup> Protective of cumulative construction worker exposure to PCBs.			
Arsenic in Soil					
Arsenic	10	Site-Specific Background Concentration in Soil, established as described in Appendix B of the FS (AMEC, 2012).			

#### Notes

- Developed based on the methodology described in Appendix C of the FS (AMEC, 2012a),
   RBSLs were used to conduct the screening-level human health risk assessment for the Site.
- Based on the carcinogenic RBSL for dioxin-like PCB congeners for outdoor commercial/industrial workers (8.1 pg/g TEQ), adjusted to a target cancer risk of 10-5.
- 3. Based on the carcinogenic RBSL for dioxin-like PCB congeners for construction workers (53 pg/g TEQ), adjusted to a target cancer risk of 10-5.

#### Abbreviations

bgs = below ground surface
FS = Feasibility Study
mg/kg = milligrams per kilogram
PCBs = polychlorinated biphenyls
pg/g = picograms/gram

RBSL = risk-based screening level TEQ = toxic equivalent



## **FIGURES**



