

Message

From: Rykaczewski, Dave A. [Dave.Rykaczewski@wsp.com]
Sent: 5/9/2018 5:44:43 PM
To: Santos, Carmen [Santos.Carmen@epa.gov]
CC: Russ.Cepko@cbs.com
Subject: Additional Information - Former Westinghouse Apparatus Repair facility
Attachments: Entrance to office area from warehouse.JPG; Entrance from warehouse to western offices.JPG; Lunch room.JPG; Offices-cubicals.JPG; Typical office.JPG; Conference room.JPG; Cubicals.JPG

Carmen,

Below and attached are additional information related to the Former Westinghouse Apparatus Repair Facility that we discussed during last week's call:

- Western Office Area – Attached are some photographs of the western office area. Note that the pictures are from 2013 when the space was subleased to a third party firm. The space is no longer sublet, and only 2 employees from Southern Counties Express use the space.
- Transformer Pit Concrete Wall samples – The rectangular pit measures approximately 69 feet by 11 feet. A total of 6 bulk samples were collected from the walls, 2 along each long wall and 1 on each short wall. The heights of each sample ranged from 1.2 feet to 7.5 feet above the base of the pit floor.
- Transformer Pit Sump - We have not been able to verify the dimensions of the sump in the northwest corner of the transformer pit. The sump has a grate over it that could not be removed. No inlet or outlet pipes were observed below the grate.

We can discuss these conditions further during the call today. Russ will not be able to join today.

Thanks,
Dave

Dave Rykaczewski, PE

Senior Technical Manager
Water & Environment



11 Stanwix Street, Suite 950, Pittsburgh, PA 15222

Direct: +1-412-375-0282

Main: +1-412-604-1040

Mobile: +1-412-418-0140

Please note I have a new address.

www.wsp.com/usa