Message

From: Ramanauskas, Peter [ramanauskas.peter@epa.gov]
Sent: 12/12/2016 4:07:05 PM
To: Mannix, John [mannixj@monroe.wednet.edu]; Mullin, Michelle [Mullin.Michelle@epa.gov]; Moore, Kendall [moore.kendall@epa.gov]
CC: Peachey, Robert [peachey.robert@epa.gov]; Deka Smith [smithf@monroe.wednet.edu]; piplicd@monroe.wednet.edu
Subject: RE: Sky Valley Remedial Completion Report Status

Hello John,

We have some comments on the closeout report.

1) The Pod/Library Building section on page 6 states: "Caulking remains behind the unit ventilators in each of the twenty Pod Classrooms. The caulking fills the gap between the metal window frame and CAB transition in each of Classrooms #1 through #20 – 1,040 lf." Just for clarification, please confirm that 1,040 lf of caulking have been removed from the window frame/CAB transition and only limited caulking remains behind the unit ventilators.

2) It seems that some pre-abatement wipe sample lab data is missing (e.g. Table 10 identifies a > 500 ug Room D wipe sample). This sample is notes as "100-PCB-W" in Table 10 on page 203, but does not appear in the data packages. The Figure on page 208 shows the Room D sample to be 046 Vinyl Floor. Please clarify and confirm all data is correctly presented in the report.

3) With respect to the soil data presented in the report, SVEC needs to better identify which soil samples are the "post-abatement" samples. Soil is reported to exceed 1 ppm in samples 41373-12, -14, -16 -18, and -22. How were these soil areas remediated and confirmed to be < 1 ppm? There does not appear to be any information on disposal or removal of PCB impacted soils in this report.

4) Does the Clean Harbors manifest #010003598FLE identified as PAINT CHIPS/DUST/SANDBLAST MEDIA on the last page of the report include the removed caulk?

5) For the air and wipe sampling to yet be collected, SVEC should identify whether the locations and quantities of future sampling will be in the same locations as the "post-abatement" samples identified in this report.

Please provide responses to the above comments.

Regards,
Peter

From: Mannix, John [mailto:mannixj@monroe.wednet.edu]
Sent: Thursday, December 01, 2016 6:57 PM
To: Mullin, Michelle <Mullin.Michelle@epa.gov>; Moore, Kendall <moore.kendall@epa.gov>
Cc: Ramanauskas, Peter <ramanauskas.peter@epa.gov>; Peachey, Robert <peachey.robert@epa.gov>; Deka Smith <smithf@monroe.wednet.edu>; piplicd@monroe.wednet.edu
Subject: Re: Sky Valley Remedial Completion Report Status

Michelle, Kendall, Robert, and Peter,

Attached is a cover memo and the Final Closeout Report for the PCB Remediation project at Sky Valley Education Center. The report is just barely under 20 MB, so if it as not

passed along by your email server please let me know and I can share it as a Google Doc.

Respectfully,

John Mannix
Assistant Superintendent, Operations

D 360.804.2579 | T 360.804.2570
200 E. Fremont St. Monroe, WA 98272

On Wed, Nov 30, 2016 at 11:07 AM, Mannix, John <mannixj@monroe.wednet.edu> wrote:

Peter, et al.,

Devlin, Gregg Middaugh (of PBS Environmental) and I were working on the draft close out report yesterday. We had finally received the certified waste handling documentation from NorthStar (our abatement contractor, who had been waiting to receive it from Clean Harbors, their hazardous materials disposal subcontractor) to include in the report.

I have a final version of the closeout report in hand and am working on the cover memo which will cover a couple of the items you had requested during our most recent telephone conference. I will hopefully have it to you later today, but given how busy things are these days, and how my workload is greatly impacted by my need to react to issues as they arise, it may take me another couple days if there are significant interruptions.

Regards,
John

John Mannix
Assistant Superintendent, Operations

D 360.804.2579 | T 360.804.2570
200 E. Fremont St. Monroe, WA 98272

On Wed, Nov 30, 2016 at 6:19 AM, Ramanauskas, Peter <ramanauskas.peter@epa.gov> wrote:

Hello John/Devlin,

Writing in to check on the status of the remedial completion report we discussed earlier this month. Please let us know when we can expect to receive that.

Thank you,

Peter

Any dissemination or use of this information by a person other than the intended recipient is unauthorized and may be illegal. If you have received this e-mail in error, please immediately notify us by return e-mail. All email to and from this domain is archived as a public record in compliance with federal and state requirements. As such they may be both discoverable in a legal action and available through a public records request.