

Project: Hopi HAMP Compared to Treatment System Option

Prepared by: Mike Luecker

Date: 8/31/17

Treatment - Improved Distribution System with Meters Includes Valve/Meters and Storage/Boosters 2nd Mesa				
	FMCV	2nd Mesa	Shungopovi	TOTAL
Construction Costs	\$3,187,000	\$2,852,000	\$1,548,000	\$7,587,000
Non-Construction Costs	\$1,236,000	\$1,085,000	\$601,000	\$2,922,000
Total Estimated Capital Cost	\$4,423,000	\$3,937,000	\$2,149,000	\$10,509,000

Treatment - Unimproved Distribution System & No Meters Comparison to HAMP (no distribution system improvements)				
	FMCV	2nd Mesa	Shungopovi	TOTAL
Construction Costs	\$1,541,000	\$2,223,000	\$913,000	\$4,677,000
Non-Construction Costs	\$623,000	\$850,000	\$364,000	\$1,837,000
Total Estimated Capital Cost	\$2,164,000	\$3,073,000	\$1,277,000	\$6,514,000

Project: FMCV Treatment System w/Existing Distribution System Upgrades (Meters & Valve replacements)

Prepared by: Mike Luecker

Date: 8/31/17

Construction Costs				Includes System Upgrades	Compare to HAMP
ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED COST	TOTAL ESTIMATED COST
Arsenic Treatment Facility, ATF (w/ metal building, site work, site piping, valves, flow meters, de-sander, power drop, telemetry and back-up generator)	EA	2	\$600,000	\$1,200,000	\$1,200,000
Start up assistance (Provided by Contractor/ Equipment Supplier)	LS	1	\$25,000	\$25,000	\$25,000
6" Main from Existing 'Refurbished' Well to ATF & Connect to Existing System	LF	400	\$40	\$16,000	\$16,000
Refurbish Existing Wells	LS	2	\$150,000	\$300,000	\$300,000
Misc System Improvements (Water Tank Rehab, Waterline replacements, disinfection, electrical, etc)	LS	1	\$1,000,000	\$1,000,000	\$0 - See Notes
Add/Replace existing valves throughout system	EA	100	\$1,500	\$150,000	\$0 - See Notes
Water Meters w/Box - Residential & Commercial	EA	620	\$800	\$496,000	\$0 - See Notes
Construction Costs				\$3,187,000	\$1,541,000

Non-Construction Cost

Contingency (15%) =	\$478,000	\$231,000
Engineering - PER & Env doc (2%) =	\$64,000	\$31,000
Engineering - Detailed Design (8%) =	\$255,000	\$123,000
Engineering - Construction Mgmt. (10%) =	\$319,000	\$154,000
Legal and Administrative (2%) =	\$64,000	\$31,000
Equipment - O&M Support for ATF (Minor items outside Treatment contract) =	\$50,000	\$50,000
Sub-total	\$1,230,000	\$620,000
Tero/Tribal Tax (0.5%)	\$6,000	\$3,000
Non-Construction Costs	\$1,236,000	\$623,000

Total Estimated Capital Cost	\$4,423,000	\$2,164,000
------------------------------	-------------	-------------

Notes:

Construction costs and all Non-Construction Costs rounded to \$1,000

Increase 6" from \$30 (as shown in PER) to \$40 to account for gate/air valves and some pavement replacement.

Comparison to HAMP - Remove improvements to existing system.

Water Meters - Assume \$800 since there are no existing meters, so will require more time/\$ as compared to replacing existing.

Add/replace valves throughout system - This is assumption and may also cover other minor system improvements (air valves/PRV/etc)

Project: 2nd Mesa Treatment System w/Existing System Upgrades (Meters & Valve replacements, plus Booster & Storage)
 Prepared by: Mike Luecker
 Date: 8/31/17

Construction Costs				Includes System Upgrades	Compare to HAMP
ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED COST	TOTAL ESTIMATED COST
Arsenic Treatment Facility, ATF (w/ metal building, site work, site piping, valves, flow meters, de-sander, power drop, telemetry and back-up generator)	EA	1	\$600,000	\$600,000	\$600,000
Start up assistance (Provided by Contractor/ Equipment Supplier)	LS	1	\$25,000	\$25,000	\$25,000
6" Main from 'Existing' Well to ATF & connect to existing	LF	200	\$40	\$8,000	\$8,000
6" Main from 'New' Well to ATF	LF	5500	\$40	\$220,000	\$220,000
6" Main from 8" to upper tank	LF	8000	\$40	\$320,000	\$320,000
Refurbish Existing Well as back-up	LS	1	\$150,000	\$150,000	\$150,000
New' Well as primary	LS	1	\$500,000	\$500,000	\$500,000
Booster Station (from 8" to upper existing tank w/power drop, site work/pipring & telemetry to upper tank)	LS	1	\$250,000	\$250,000	\$250,000
Water Storage - 75,000 gal (includes site piping/valves)	LS	1	\$150,000	\$150,000	\$150,000
Misc System Improvements (Water Tank Rehab, Waterline replacements, disinfection, electrical, etc)	LS	1	\$500,000	\$500,000	\$0 - See Notes
Add/Replace existing valves throughout system	EA	50	\$1,500	\$75,000	\$0 - See Notes
Water Meters w/Box - Residential & Commercial	EA	135	\$400	\$54,000	\$0 - See Notes
Construction Costs				\$2,852,000	\$2,223,000
Non-Construction Cost					
Contingency (15%) =				\$428,000	\$333,000
Engineering - PER & Env doc (2%) =				\$57,000	\$44,000
Engineering - Detailed Design (8%) =				\$228,000	\$178,000
Engineering - Construction Mgmt. (10%) =				\$285,000	\$222,000
Legal and Administrative (2%) =				\$57,000	\$44,000
Equipment - O&M Support for ATF (Minor items outside Treatment contract) =				\$25,000	\$25,000
Sub-total				\$1,080,000	\$846,000
Tero/Tribal Tax (0.5%)				\$5,000	\$4,000
Non-Construction Costs				\$1,085,000	\$850,000
Total Estimated Capital Cost				\$3,937,000	\$3,073,000

Notes:

Construction costs and all Non-Construction Costs rounded to \$1,000

Increase 6" from \$30 (as shown in PER) to \$40 to account for gate/air valves and some pavement replacement.

Comparison to HAMP - Remove improvements to existing system.

Water Meters - While meters exist, assume they may need to be replaced or need new ones elsewhere. Assumed cost is avg.

Add/replace valves throughout system - This is assumption and may also cover other minor system improvements (air valves/PRV/etc)

Project: Shungopovi Treatment System w/Existing Distribution System Upgrades (Meters & Valve replacements)
 Prepared by: Mike Luecker
 Date: 8/31/17

Construction Costs				Includes System Upgrades	Compare to HAMP
ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED COST	TOTAL ESTIMATED COST
Arsenic Treatment Facility, ATF (w/ metal building, site work, site piping, valves, flow meters, de-sander, power drop, telemetry and back-up generator)	EA	1	\$600,000	\$600,000	\$600,000
Start up assistance (Provided by Contractor/ Equipment Supplier)	LS	1	\$25,000	\$25,000	\$25,000
6" Main from Existing 'New' Well to ATF & Connect to Existing System	LF	200	\$40	\$8,000	\$8,000
6" Main from 'Existing' Back up Well to ATF	LF	2000	\$40	\$80,000	\$80,000
Refurbish Existing Well as back-up	LS	1	\$150,000	\$150,000	\$150,000
Refurbish 'New' Well as primary	LS	1	\$50,000	\$50,000	\$50,000
Misc System Improvements (Water Tank Rehab, Waterline replacements, disinfection, electrical, etc)	LS	1	\$500,000	\$500,000	\$0 - See Notes
Add/Replace existing valves throughout system	EA	50	\$1,500	\$75,000	\$0 - See Notes
Water Meters w/Box - Residential & Commercial	EA	150	\$400	\$60,000	\$0 - See Notes
Construction Costs				\$1,548,000	\$913,000

Non-Construction Cost

Contingency (15%) =	\$232,000	\$137,000
Engineering - PER & Env doc (2%) =	\$31,000	\$18,000
Engineering - Detailed Design (8%) =	\$124,000	\$73,000
Engineering - Construction Mgmt. (10%) =	\$155,000	\$91,000
Legal and Administrative (2%) =	\$31,000	\$18,000
Equipment - O&M Support for ATF (Minor items outside Treatment contract) =	\$25,000	\$25,000
Sub-total	\$598,000	\$362,000
Tero/Tribal Tax (0.5%)	\$3,000	\$2,000
Non-Construction Costs	\$601,000	\$364,000

Total Estimated Capital Cost	\$2,149,000	\$1,277,000
-------------------------------------	--------------------	--------------------

Notes:

Construction costs and all Non-Construction Costs rounded to \$1,000

Increase 6" from \$30 (as shown in PER) to \$40 to account for gate/air valves and some pavement replacement.

Comparison to HAMP - Remove improvements to existing system.

Water Meters - While meters exist, assume they may need to be replaced or need new ones elsewhere. Assumed cost is avg.

Add/replace valves throughout system - This is assumption and may also cover other minor system improvements (air valves/PRV/etc)