

APPENDIX B BASIS OF COST ESTIMATE

This appendix provides details of the estimated implementation costs for the remedial alternatives subject to detailed screening in Section 6 of the Feasibility Study Report. Costs include both capital costs for implementation as well as long-term operation and maintenance (O&M) costs, including engineering, administration, and contingencies. Following is a brief overview of the general cost estimating approach and assumptions common to many of the alternatives.

Intended Accuracy of Estimates

Per the USEPA Remedial Investigation/Feasibility Study (RI/FS) guidance, the accuracy of FS cost estimates is intended to be in the range of -30 to +50 percent.

Basis of Costs/Unit Rates

Costs are based on published unit rates, such as R.S. Means, technology review documents, recent actual cost data and supplier quotes for other projects of a similar nature, and professional judgement. Where appropriate and unless otherwise indicated, estimated rates and costs include contractor labor, equipment, materials, expenses, and third- party services (such as waste transportation and disposal), commensurate with the intended accuracy of the estimate. Material costs include procurement, delivery, placement, and compaction, as appropriate. Waste disposal costs include approvals, loading, hauling, and disposal fees.

Construction Cost Index

The most recent Engineering News Record Construction Cost Index is 11392 (as of January 2020). As appropriate, the cost index may be used to update older cost information (for example, the cost index has increased approximately 14 percent since January 2015).

Present Worth

The present worth was calculated for the estimated capital and O&M costs based on the anticipated construction and operations schedule for project implementation (refer to Table 6-3 of the FS). It was assumed that pre-construction activities will occur in 2021, and implementation of the alternative will occur in 2022. The O&M period was assumed to be 30 years. Per USEPA guidance, a 7 percent discount factor was used to determine the present worth.

Capital Costs

Capital costs for each alternative are broken down by direct implementation costs and indirect costs.

Direct Implementation Costs

Direct costs for implementing each alternative are remediation contractor costs broken down by significant components of each remedy. Quantities are based on the volumes and areas described in Section 5 where appropriate. As noted above, unit rates are estimated and include contractor labor, equipment, materials, expenses, and third-party services.

Indirect Costs

Indirect costs are broken into several categories, and represent ancillary costs necessary for, but not directly associated with, implementation of each remedy. While these costs are generally estimated as a fixed percentage of the estimated direct costs, adjustments may be made to more accurately reflect anticipated costs. For example, no construction management costs would be incurred if a remedy consists of the filing of deed notices and other institutional controls.

• **Investigations:** Lump sum costs have been included for several investigations based on the relative complexity of the remedy and requirements for the design. Depending on the alternative, investigations may include predesign investigations, soil delineation, treatability studies, and/or geotechnical investigations.

- Remedial/Geotechnical Design: Preparation of design documents needed for contractor procurement and implementation of the remedy. Generally estimated as 10 percent of direct costs. Based on the relative complexity of the remedy Alternative SW-2 was assumed as a lump sum of \$5,000 and Alternative SG-2 was adjusted to 5% of the direct costs.
- **Mobilization/Miscellaneous Site Preparation:** Includes mobilization and demobilization of contractor resources to/from the Site, along with miscellaneous costs such as work trailer setup, establishment of electric service, restroom facilities, etc. Generally estimated as 5 percent of direct costs. Alternative SG-2 does not include construction, therefore, it does not require mobilization or site preparation.
- **Site Administration:** Costs borne by the responsible party for internal administration of the Site and management of design and remediation contractors. Generally estimated as 5 percent of direct costs. Alternative SG-2 does not include construction; therefore, site administration costs were adjusted to 1 percent of direct costs.
- Permitting/Legal Costs: Costs associated with applying for and obtaining any local permits necessary for the work, as well as any legal/filing fees commonly associated with institutional controls. Generally estimated as 2 percent of direct costs.
- Construction Management/Oversight: Costs associated with the management and oversight of the remedial
 action contractor during implementation of the remedy, including labor, expenses, and third-party services,
 such as laboratory analysis or surveying, not otherwise included in the direct costs. Generally estimated as 10
 percent of direct costs. Alternative SG-2 does not include construction, therefore, it does not require
 construction management or oversight.

Material Quantities

Common quantity assumptions were based the following:

Conversion from in-place cubic yards to tons for disposal = 1.65 tons/cubic yard Percentage of excavated soil/fill assumed to require handling as hazardous = 100%

Assumed quantities for the alternatives are summarized as follows:

Waste Alternatives

ltem	Quantity	Unit
Footprint of NAPL Impacted Soil	6,850	SF
Depth of Excavation	13	FT
Number of 8'x30' USTs	6	~
Estimated Soil Removal Volume	3,500	CY

Soil/Fill Alternatives

ltem		Qı	uantity		Unit
iteiii	SF-2	SF-3	SF-4	SF-5	Unit
Footprint of Additional NAPL Impacted Soil		1	1,200		SF
Depth of Additional NAPL Impacted Soil			7		FT
Volume of NAPL Impacted Soil			310		CY
Asphalt Cap Footprint	-		27,200		SY
New Bulkhead Walls	-		800		FT
Footprint of Targeted Excavation	-	-	22,856	-	SF
Depth of Targeted Excavation	-	-	6	-	FT
Volume of Targeted Excavation	-	-	5,100	-	CY
Untreated Area - Lot 67/69	-	-	-	9,200	SF
S/S Treatment Footprint	-			137,100	SF
S/S Treatment Volume	-	-	-	30,500	CY

Groundwater Alternatives

H		Qua	intity		11
ltem	GW-2	GW-3	GW-4	GW-5	Unit
Sheet Pile Containment	70,000		-	70,000	SF
Fill Between Old and New Wall	975	~	-	975	CY
Length of Conveyance Trenching/Fill	2,500	-	2,500	-	FT
Width of Conveyance Trenching/Fill, multiple pipes in trench	10	-	10	-	FT
Piping, conduit, wiring, instrumentation, all lines homerun to treatment plant	30,000	-	30,000	-	FT
Footprint of Treatment Building	7,500	~	7,500	-	SF
Length of Discharge Line	500	-	500	-	FT
Initial Injection – inorganic (reagent)	-	1.954 M	-	196,643	LB
Initial Injection – organic (reagent)	-	1.622 M	-	65,548	LB
Days in field	-	300	-	53	Day
Second Round	-	67% initial costs		67% initial costs	LS
Third Round	-	33% initial costs	-	33% initial costs	LS

Sewer Alternatives

ltem	Quantity	Unit
Length of 4-inch Sewer Pipe	125	FT
Volume of Liquid Waste in Sewer Pipe	90	GAL
Volume of Liquid Waste in 4x4 Manhole	720	GAL
Total Liquid Waste (Manhole + Sewer Pipe) – flush 3 times	2,500	GAL
Number of Drums for Solid Waste	2	e s

Soil Gas Alternatives

la	Quar	Unit	
Item	SG-2	SG-3	Unit
Amount of Chemical Treatment for Organics		570,322	LB

Operation and Maintenance Costs

O&M costs are those costs required to continue implementation of the remedy after the capital construction period has been completed. Typical components include site inspections, routine monitoring, and continued O&M of remediation systems. Additionally, costs are included for National Contingency Plan (NCP)-required five-year reviews where contaminants remain in place following remediation. Costs for five-year reviews include document review, site inspections, and coordination with agency personnel. For the purposes of this FS, these costs have been distributed between the soil and groundwater alternatives at an estimated annual cost of \$5000. Costs for O&M items are presented on an annual cost basis.

Costs for groundwater monitoring assumed annual sampling of up to 25 monitoring wells for volatile organic compounds, semi-volatile organic compounds, and metals, and include costs for labor, equipment, analysis, reporting, and purge water disposal. Classification exception area (CEA) monitoring assumes collection of additional parameters once per year.

Contingency

A contingency of 25 percent is added to both capital and O&M costs to account for unforeseen costs which may be incurred during implementation and O&M of the remedy, such as increases in media quantities required to be addressed beyond that assumed for the FS.

Net Present Value Factor																			
	70%																		
Discessor Rate	7%																		
Inflation Rate	495																 	 	<u> </u>
TUDDING BASE																			
18.08	COSTP	263.6	2033	79.7	10.	2014	10.5	3006	9627	10.75	10.0	36.9	3011	30.0	283	2003	1935	38.6	100
Waste - Alternative 2, Removal and Off-Site Disposal																			
TOTAL PRESENT VALUE			\$ 1,798,211																
Capital Costs	\$ 1,580,700	s -	\$ 163,474	\$ 1,634,738	s -	s -	S -	\$ -	\$ -	s -	s -	S -	S -	S -	\$ -	\$ -	S -	S	\$ -
Pre-construction Activities	\$ 152,800	\$ -	\$ 163,474	\$ -	\$ -	\$ -													
Mobilization and Demobilization	\$ 59,500	s -	\$ -	\$ 68,114	s -	s -	s -	\$ -	s -	s -	s -	\$ -	s -	s -	\$ -	\$ -	s -	s -	\$ -
Direct Implentation Costs	\$ 1,189,900	٠ .	s -	\$ 1,362,281		s -	٠ .	\$		ς .		s .	\$ -	٩ .			s -		s -
				\$ 204,342		s -													
Other Indirect Costs	\$ 178,500	5 -	\$ -	\$ 204,342	S -	3 -	\$ -	5 -	5 -	5 -	S -	3 -	3 -	\$ -	\$ -	5 -	-	\$ -	
O&M Costs Soil/Fill - Alternative 2, Institutional Controls and	s -	S -	S -	S -	S -	S -	S -	S -	s -	<u>s</u> -	S -	S -	S -	S -	\$ -	\$ -	S -	\$ -	S -
LNAPL Removal																			
TOTAL PRESENT VALUE	\$ 356,100																		
																			<u> </u>
Capital Costs			\$ 50,302		S -	s -	S -	S -	S -	s -	S -	S -	S -	S -	S -	S -	S	S	S -
Pre-construction Activities	\$ 47,000	\$ -	\$ 50,302	\$ -	\$ -	\$ -													ļ
Mobilization and Demobilization	\$ 9,200	s -	\$ -	\$ 10,543	\$ -	\$ -	s -	\$ -	\$ -	s -	\$ -	\$ -	\$ -	s -	\$ -	\$ -	s -	s -	\$ -
Direct Implentation Costs	\$ 184,200	š -	\$ -	\$ 210,850	s -	s -	s -	s -	s -	s -	s -	\$ -	s -	s -	s -	s -	s -	\$ -	s -
						\$ -			\$ -		s -	s -	\$.						1.
Other Indirect Costs			\$ -	\$ 31,628	3 -		3 -	-	<u> </u>	٠ -	-	-		b -	3 -	3 -	5 -	- 1	3 -
O&M Costs Soil/Fill - Alternative 3 Institutional Controls,	\$ 88,100	s -	s -	S -	S 8,125	\$ 8,125	\$ 8,125	\$ 8,125	\$ 8,125	\$ 8,125	S 8,125	\$ 8,125	\$ 8,125	S 8,125	\$ 8,125	\$ 8,125	S 8,125	\$ 8,125	\$ 8,125
Engineering Controls (Cap, Sheet Pile) and LNAPL Removal																			
TOTAL PRESENT VALUE	S 10,450,900																		
Capital Costs	\$ 9,638,000	s -	£ 1346855	\$ 9,793,550	e _	s -	e _		\$ -	s -	e _	s .	s -	s -	e _	s .		e _	
			\$ 1,346,855	3 2,723,330		s -	3	9	9										1
Pre-construction Activities	\$ 1,258,700		1	S -	5 -			ļ					ļ			ļ	 	 	
Mobilization and Demobilization	\$ 349,100	s -	\$ -	\$ 399,731	s -	\$ -	s -	\$ -	\$ -	s -	s -	\$ -	\$ -	S -	\$ -	\$ -	S -	\$ -	\$ -
Direct Implentation Costs	\$ 6,982,800	s -	\$ -	\$ 7,994,625	s -	\$ -	s -	\$ -	s -	s -	s -	\$ -	\$ -	s -	\$ -	\$ -	s -	s -	\$ -
Other Indirect Costs	\$ 1,047,400	s -	s -	\$ 1,199,194	s -	\$ -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -
Diamond Alkali OU2 Contingency			\$ -	\$ 200,000		s -													
· ·		3 -		\$ 200,000	3 -	-	3 -	3 -	3 -		3 -	3 -	3 -	3 -	3 -	5 -	3 -	3 -	3 -
O&M Costs Soil/Fill - Alternative 4, Institutional Controls,	S 812,900	S -	S -	S -	S 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	S 75,000	\$ 75,000	\$ 75,000	S 75,000	\$ 75,000	\$ 75,000	S 75,000	\$ 75,000	\$ 75,000
Engineering Centrols (Cap, Sheet Pile), Focused Removal, and I NAPI. Removal																			
TOTAL PRESENT VALUE																			
	S 12,633,300																		
		c	\$ 1572568	\$ 12,050,600	5	c	ę	2	c	c	9	s	c	s	\$		9	e	c
Capital Costs	S 11,820,400			\$ 12,050,600	S -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -
Capital Costs Pre-construction Activities	\$ 11,820,400 \$ 1,469,700	s -	\$ 1,572,560 \$ 1,572,560	\$ -	S - S -	s - s -	S -	S -	s -	s -	S -	s -	S -	s -	s -	s -	s -	s -	s -
Capital Costs	\$ 11,820,400 \$ 1,469,700	s -			S - S - S -	s - s -	s - s -	\$ -	s - s -	s - s -	S -	s - s -	s - s -	S -	s -	\$ -	S -	S -	\$ - \$ -
Capital Costs Pre-construction Activities	\$ 11,820,400 \$ 1,469,700	s -		\$ -	S - S - S -		s - s -	\$ - \$ - \$ -	s - s - s -	s - s -	S - S - S -	\$ - \$ - \$ -	\$ - \$ - \$ -	s - s - s -	s - s - s -	\$ - \$ -	S - S - S -	S - S - S -	\$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs	\$ 11,826,400 \$ 1,469,700 \$ 431,300	s -	\$ 1,572,560 \$ -	\$ - \$ 493,775	s -	s -	s - s - s -	\$ - \$ - \$ -	s - s - s -	s - s - s -	S - S - S -	s - s - s -	s - s - s -	s - s - s -	s - s - s -	\$ - \$ - \$ -	S - S - S -	\$ - \$ - \$ -	\$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800	s - s - s -	\$ 1,572,560 \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325	s - s -	\$ - \$ -		†	\$ - \$ - \$ -	S - S - S -			- 	\$ - \$ - \$ -	\$ - \$ - \$ -	\$ - \$ - \$ -	S - S - S -	S - S - S -	\$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700	s - s - s - s -	\$ 1,572,560 \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500	s - s - s -	\$ - \$ - \$ -	s - s -	\$ - \$ -	\$ -	\$ -	s - s -	\$ - \$ -	\$ - \$ -	s -	\$ - \$ - \$ - \$ -	\$ -	s -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700	s - s - s - s -	\$ 1,572,560 \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325	s - s -	\$ - \$ - \$ - \$ -	s - s -	\$ - \$ -	\$ - \$ - \$ - \$ - \$ 5	\$ -	s - s -	\$ - \$ -	- 	s -	\$ - \$ - \$ - \$ - \$ -	\$ -	s -	S - S - S - S - S - S -	\$ - \$ - \$ - \$ - \$ 5
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700	s - s - s - s -	\$ 1,572,560 \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325	s - s - s -	\$ - \$ - \$ -	s - s -	\$ - \$ -	\$ -	\$ -	s - s -	\$ - \$ -	\$ - \$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ -	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ 5	\$ - \$ - \$ - \$ - \$ 5
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency SoftFill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Star Remediation,	\$ 11,826,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900	s - s - s - s -	\$ 1,572,560 \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325	s - s - s -	\$ - \$ - \$ -	s - s -	\$ - \$ -	\$ -	\$ -	s - s -	\$ - \$ -	\$ - \$ -	s -	\$ - \$ - \$ - \$ - \$ -	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ 5	\$ - \$ - \$ - \$ - \$ 5
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soli/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI Remeval	\$ 11,826,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900	s - s - s - s -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -	s - s - s -	\$ - \$ - \$ - \$ - \$ 5 - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ 75,000	\$ -	s - s -	\$ - \$ -	\$ - \$ - \$ 75,000	s -	\$ - \$ - \$ - \$ - \$ - \$ -	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ 5	\$ - \$ - \$ - \$ - \$ - \$ 75,000
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soli/Fill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and UNAPI Remeval TOTAL PRESENT VALUE Capital Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300	s - s - s - s -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -	s - s - s -	\$ - \$ - \$ - \$ - \$ 75,000	s - s -	\$ - \$ -	\$ -	\$ -	s - s -	\$ - \$ -	\$ - \$ -	s -	\$ - \$ - \$ - \$ - \$ 75,000	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency Diamond Alkali OU2 Contingency O&M Costs SoftFill: Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600	s - s - s - s -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ - \$ 13,504,550	s - s - s -	\$ - \$ - \$ - \$ - \$ 5 - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ 75,000	\$ -	s - s -	\$ - \$ -	\$ - \$ - \$ 75,000	s -	\$ - \$ - \$ - \$ - \$ 5 - \$ 5 - \$ 75,000	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soli/Fill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and UNAPI Remeval TOTAL PRESENT VALUE Capital Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300	s - s - s - s -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -	s - s - s -	\$ - \$ - \$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ 75,000	\$ -	s - s -	\$ - \$ -	\$ - \$ - \$ 75,000	s -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -	s -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs SoftFill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and INAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ - \$ 13,504,550	s - s - s -	\$ - \$ - \$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ - \$ 75,000	\$ - \$ 75,000	\$ -	s - s -	\$ - \$ -	\$ - \$ - \$ 75,000	s -	\$ - \$ - \$ - \$ - \$ 75,000	\$ -	s -	\$ - \$ - \$ - \$ 75,000	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soli/Fill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and LNAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implemention Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,990 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,550 \$ -0 \$ 554,356 \$ 11,087,125	\$ - \$ - \$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ -	\$ - \$ - \$ - \$ - \$ 75,000	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and INAPI Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,850 \$ -0 \$ 554,356 \$ 11,087,125 \$ 1,663,069	\$ - \$ - \$ - \$ 75,000	\$ - \$ - \$ - \$ 75,000	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000	\$ - \$ 75,000 \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	s -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ 75,000	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI Remeval TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,550 \$ -0 \$ 554,356 \$ 11,087,125	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), Is-Shir Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,850 \$ -0 \$ 554,356 \$ 11,087,125 \$ 1,663,069	\$ - \$ - \$ - \$ 75,000	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Engineering Controls (Sheet Pile), In-Situ Remediation, and J NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil Gas - Alternative 2, Institutional Controls,	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,850 \$ -0 \$ 554,356 \$ 11,087,125 \$ 1,663,069	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), Is-Shir Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,850 \$ -0 \$ 554,356 \$ 11,087,125 \$ 1,663,069	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Slitt Remediation, and I. NAPI. Remeable TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Centrols, and Site-Wide Engineering Controls	\$ 11,826,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700 \$ 745,100	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,850 \$ -0 \$ 554,356 \$ 11,087,125 \$ 1,663,069	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soll/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency Soll Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Centrols, and Site-Wide Engineering Controls TOTAL PRESENT VALUE	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 745,100	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,985 \$ 1,717,955 \$ - \$ - \$ -	\$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ \$ 13,504,550 \$ - \$ 554,356 \$ 11,087,125 \$ 1,663,069 \$ 200,000	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ \$ - \$ \$ - \$ \$ 68,750	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Soil Gas - Alternative 2, Institutional Controls, Monitoring Engineering Controls, and Site-Wide Engineering Controls TOTAL PRESENT VALUE Capital Costs VALUE Capital Costs Oom Costs Other Indirect Costs Total Present Value Costs Total PRESENT VALUE Capital Costs Capital Costs Capital Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 1,452,600 \$ 745,100 \$ 745,100	\$ - \$ - \$ - \$ - \$ 5 - \$ - \$ 5	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,955 \$ 1,717,955 \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,550 \$ -0 \$ 11,087,125 \$ 1,663,069 \$ -0 \$ 11,15519	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soll/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency Soll Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Centrols, and Site-Wide Engineering Controls TOTAL PRESENT VALUE	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700 \$ 745,100 \$ 449,800 \$ 108,400	\$ - \$ - \$ - \$ - \$ 5 - \$ - \$ 5	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,985 \$ 1,717,955 \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,550 \$ -0 \$ 11,087,125 \$ 1,663,069 \$ -0 \$ 11,15519	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ \$ - \$ \$ - \$ \$ 68,750	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Soil Gas - Alternative 2, Institutional Controls, Monitoring Engineering Controls, and Site-Wide Engineering Controls TOTAL PRESENT VALUE Capital Costs VALUE Capital Costs Oom Costs Other Indirect Costs Total Present Value Costs Total PRESENT VALUE Capital Costs Capital Costs Capital Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,660 \$ 174,700 \$ 745,100 \$ 449,800 \$ 108,400 \$ 7,500	\$ - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,955 \$ 1,717,955 \$ - \$ - \$ - \$ -	\$ -0 \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ -0 \$ 13,504,550 \$ -0 \$ 11,087,125 \$ 1,663,069 \$ -0 \$ 11,15519	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ \$ - \$ \$ - \$ \$ 68,750	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ -	S - S - S - S - S - S - S - S - S - S -	S - S - S - S -	\$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative S, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation, and LNAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Cost. Soil Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Controls, and Site-Wide Engineering Controls TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,900 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 9,683,900 \$ 1,452,600 \$ 174,700 \$ 745,100 \$ 108,400 \$ 7,500 \$ -	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,955 \$ 1,717,955 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ \$ 13,504,550 \$ \$ 554,356 \$ 11,087,125 \$ 200,000 \$ \$ 1,663,069 \$ \$ 1,663,069 \$ \$ 1,663,069 \$	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ 5 - \$	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ 5 -	S - S - S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5	\$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ \$ - \$ \$ - \$ \$ - \$ \$ - \$ \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ 5 - \$ \$ - \$ \$ \$ 68,750	S - S - S - S -	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soll/Fill - Alternative S, Institutional Controls, Engineering Controls, (Sheet Pile), In-Situ Remediation, and LNAPL Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Controls, and Site-Wide Engineering Controls TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,990 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 9,683,900 \$ 1,452,600 \$ 174,700 \$ 745,100 \$ 108,400 \$ 9,900	S - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,955 \$ 1,717,955 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ \$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ \$ 13,504,550 \$ \$ 554,356 \$ 11,087,125 \$ 200,000 \$ \$ 115,519 \$ \$ 1,4375	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ 5 - \$ - \$ 5 - \$ - \$ 5 - \$ - \$ 5 - \$	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ 5 - \$ - \$ 5	\$ - S 75,000 S S - S - S - S - S - S - S - S - S	\$ - S 75,000 S - 75,000 S S - S - S - S - S - S - S - S -	\$ - \$ 75,000 \$ \$ 75,00	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 5	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ - \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5 \$ 5	\$ - \$ - \$ - \$ - \$ - \$ 68,750	\$ - \$ 75,000 \$ - \$ - \$ 5 - \$	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ 5	S - S - S - S -	\$ - \$ - \$ - \$ - \$ 68,750
Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Costs Soil/Fill - Alternative S, Institutional Controls, Engineering Centrols (Sheet Pile), In-Situ Remediation, and I NAPI. Removal TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Direct Implentation Costs Other Indirect Costs Diamond Alkali OU2 Contingency O&M Cost. Soil Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Centrols, and Site-Wide Engineering Controls TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization Diamond Alkali OU2 Contingency O&M Costs Soil Gas - Alternative 2, Institutional Controls, Monitoring/Engineering Centrols TOTAL PRESENT VALUE Capital Costs Pre-construction Activities Mobilization and Demobilization	\$ 11,820,400 \$ 1,469,700 \$ 431,300 \$ 8,625,600 \$ 1,293,800 \$ 174,700 \$ 812,990 \$ 13,971,400 \$ 13,226,300 \$ 1,605,600 \$ 484,200 \$ 7,45,100 \$ 745,100 \$ 108,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400 \$ 1,800,400	\$ - S - S - S - S - S - S - S - S - S -	\$ 1,572,560 \$ - \$ - \$ - \$ - \$ - \$ - \$ 1,717,955 \$ 1,717,955 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ 493,775 \$ 9,875,500 \$ 1,481,325 \$ 200,000 \$ \$ 13,504,550 \$ \$ 554,356 \$ 11,087,125 \$ 200,000 \$ \$ 1,663,069 \$ \$ 1,663,069 \$ \$ 1,663,069 \$	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ - \$ 75,000 \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 68,750 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ 5 -	\$ - S - C - C	\$ - \$ 75,000 \$ \$ 75,00	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ - \$ 68,750 \$ - \$ 5 - \$ 68,750	\$ - \$ 75,000 \$ 75,000 \$ - \$ - \$ - \$ 68,750 \$ - \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ - \$ - \$ 68,750 \$ - \$ 5 - \$ 68,750	\$ - \$ - \$ - \$ - \$ 68,750 \$ - \$ - \$ -	\$ - \$ 75,000 \$ - \$ - \$ 5 - \$	\$ - \$ 75,000 \$ - \$ - \$ 5 - \$ \$ - \$ \$ - \$ \$ - \$ \$ 5 - \$ \$ 5 - \$ \$ 68,750	S - S - S - S - S - S - S - S - S - S -	\$ - \$ - \$ - \$ - \$ 68,750

								arue Anarys										
Net Process Value Factor																		
Discourt Rate																		
Inflates Bate																		
TEST	1944			2646	100	3945	284	2044	2045	3946		2645	2049	3350		2652	3653	3884
Waste - Alternative 2, Removal and Off-Site Disposal																		
					+	-									-			
TOTAL PRESENT VALUE					 		-				-							
Capital Costs	<u>s</u> -	S							-								-	
Pre-construction Activities						<u> </u>	-						ļ				ļ	
Mobilization and Demobilization	s -																	
Direct Implentation Costs	s -																	
Other Indirect Costs																		
O&M Costs	s -	s	-	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -		
Soil/Fill - Alternative 2, Institutional Controls and																		
LNAPL Removal TOTAL PRESENT VALUE																		
		-			+		-	-	-	-					+		 	
Capital Costs	<u>s</u> -	S			-		-	-	 	<u></u>	-						 	
Pre-construction Activities					 	 	-		-				 					
Mobilization and Demobilization	\$ -				-			<u> </u>	 	<u> </u>	ļ		ļ				 	
Direct Implentation Costs	\$ -	1			1	1		1							-			
Other Indirect Costs		1																
O&M Costs	\$ 8,125	s	8,125	S 8,125	S 8,12	5 S 8,125	\$ 8,125	\$ 8,125	S 8,125	\$ 8,125	S 8,125	\$ 8,125	S 8,125	S 8,125	S 8,12	5 8 8,12		
Soil/Fill - Alternative 3 Institutional Controls, Engineering Controls (Cap, Sheet Pile) and LNAPL Removal																		
TOTAL PRESENT VALUE																		
Capital Costs	s -	s	_															
Pre-construction Activities																		
Mobilization and Demobilization	¢	1			1	1			†	·			 				1	
							-										·	
Direct Implentation Costs	· -								<u> </u>	·	 		 		·		 	
Other Indirect Costs					-	-										+		
Diamond Alkali OU2 Contingency					-	1									-			
O&M Costs Soil/Fill - Alternative 4, Institutional Controls,	\$ 75,000	S	75,000	\$ 75,000	\$ 75,00	0 \$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	S 75,000	\$ 75,000	\$ 75,00	0 \$ 75,00		
Engineering Centrols (Cap, Sheet Pile), Fecused																		
Removal, and I NAPI. Removal																	1	
TOTAL PRESENT VALUE						1												
Capital Costs	<u>s</u> -	S	-		1	1									+	+	1	
Pre-construction Activities						-										+		
Mobilization and Demobilization	<u>\$</u> -	_				<u> </u>			 	<u></u>			ļ			_	 	
Direct Implentation Costs	\$ -																ļ	
Other Indirect Costs																		
Diamond Alkali OU2 Contingency																		
O&M Costs	\$ 75,000	s	75,000	\$ 75,000	\$ 75,00	0 \$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,000	s 75,000	\$ 75,000	\$ 75,000	\$ 75,000	\$ 75,00	0 \$ 75,000		
Seil/Fill - Alternative 5, Institutional Controls, Engineering Controls (Sheet Pile), In-Situ Remediation,																		
and I.NAPI. Removal						1	1	1		1					1		1	
TOTAL PRESENT VALUE																		
Capital Costs	s -	s	-					1										
Pre-construction Activities																		
Mobilization and Demobilization	\$ <u>-</u>																	
Direct Implentation Costs	s -																	
Other Indirect Costs																		
Diamond Alkali OU2 Contingency																		
O&M Costs	\$ 68,750		68,750	g 20750	S 2075	0 8 60 756	g 2075n	C 20 750	g 20750	S 20 750	\$ 68,750	C 60750	S 68,750	\$ 68.756	\$ 68,75	0 \$ 68,75		
Soil Gas - Alternative 2, Institutional Controls,	<u>a 98,/30</u>	,	u6,/30	a 08,/30	2 98,/3	5 68,/5t	<u> </u>	5 08,/50	a 95,/5U	a 66,/50	a 95,/30	a 00,/30	3 95,/30	a 66,/30	5 65,/3	3 08,/3	1	
Monitoring/Engineering Centrols, and Site-Wide Engineering Controls						1												
Engineering Controls TOTAL PRESENT VALUE					1					***************************************					1		-	
		+			+	1	-		+	+	 			 	+		-	
Capital Costs	s -	S			+		-	+	+	-	-		 	 	+		+	
Pre-construction Activities						 	+	-	-	-	-				+			
																		1
Mobilization and Demobilization	s -														-	_	-	
Mobilization and Demobilization																	8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8	

S - S S - S S - S S - S	S - S S - S S - S S - S	-	S -	s -
S - S S - S S - S S - S	\$ - \$ \$ - \$ \$ - \$	-	S -	s -
S - S S - S S - S S - S	\$ - \$ \$ - \$ \$ - \$ \$ - \$	- - -	s -	s -
\$ - \$ \$ - \$ \$ - \$ \$ - \$	\$ - \$ \$ - \$ \$ - \$ \$ - \$	-	S -	s -
\$ - \$ \$ - \$ \$ - \$ \$ - \$	\$ - \$ \$ - \$ \$ - \$	-	\$ -	
\$ - \$ \$ - \$ \$ - \$ \$ - \$	\$ - \$ \$ - \$ \$ - \$	-	\$ -	
\$ - \$ \$ - \$ \$ - \$	\$ - \$ \$ - \$	-		\$ -
\$ - \$ \$ - \$	s - s		\$ -	\$ -
s - s	8 8	-	s -	\$ -
	12	-	s -	s -
s - s	s - s	_	s -	s -
s - s	s - s	_	s -	\$ -
s - s	s - s	_	\$ -	s -
s - s	s - s	-	s -	s -
s - s	s - c	_	s -	s -
		101000000000000000000000000000000000000		
s - s	s - s	-	s -	s -
s - s	s - s	-	\$ -	s -
s - s	s - s		s -	\$ -
\$. \$	\$ - \$		\$.	15
s . s	\$. \$		\$.	1,
0 5 1 125 000 5	\$ 1 125 000 \$	1 125 000	\$ 1 125 000	\$ 1.125.000
\$ 3,469,998 \$	s - s	-	s -	s -
s - s	s - s	-	s -	s -
\$ 3,469,998 \$	s - s	_	s -	s -
s - s	s - s	-	s -	s -
0 S 131,250 S	S 131,250 S	131,250	S 131,250	\$ 131,250
s - s	s - s	_	s -	s -
s - s	s - s	-	s -	\$ -
s - s	s - s	-	s -	s -
s - s	\$ - S	-	s -	\$ -
0 \$ 1,500,000 \$	\$ 1,500.000 S	1,500.000	\$ 1,500,000	\$ 1,500,000
7,7,7,7	,,,,,,			
\$ 283,539 \$	s - s	-	\$ -	\$ -
\$ - \$	s - s	-	\$ -	\$ -
\$ 283,539 \$	s - s	-	\$ -	\$ -
\$ - \$	s - s	-	\$ -	\$ -
0 \$ 131,250 \$	\$ 131.250 S	131 250	\$ 131 250	\$ 131,250
00	\$ 3,469,998 \$ - \$ 3,469,998 \$ - \$ 131,250 \$ - \$ - \$ - \$ 1,500,000 \$ 283,539 \$ - \$ 283,539	\$ - \$ - \$ \$ 1,125,000 \$ \$ 1,125,000 \$ \$ 1,125,000 \$ \$ 3,469,998 \$ - \$ \$ - \$ - \$ \$ 3,469,998 \$ - \$ \$ 5 - \$ - \$ \$ 131,250 \$ 131,250 \$ \$ - \$ - \$ \$ - \$ - \$ \$ - \$ - \$ \$ 131,250 \$ 131,250 \$ \$ - \$ - \$ \$ - \$ - \$ \$ - \$ - \$ \$ - \$ -	\$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000 \$ 1,125,000,000 \$ 1,12	\$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ - \$ 5

					***************************************	***************************************	***************************************	***************	*****************	***************************************							
STAR T		2010	1040	2847	7647	7045	2844	1015	2016	2042	2045	2040	2000	705	385	- 85	2054
Soil Gas - Alternative 3, Institutional Controls, Site- Wide Engineering Controls, and In-Situ Remediation																	
TOTAL PRESENT VALUE																	
Capital Costs S	S																
Pre-construction Activities																	
Mobilization and Demobilization \$	-																
Direct Implentation Costs \$	-																
Other Indirect Costs																	
O&M Costs \$	- 5		s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -	s -		
Sewer Water - Alternative 2, Removal and Off Site Disposal																	
TOTAL PRESENT VALUE																	
Capital Costs \$	- S				·									<u> </u>	1	<u> </u>	1
Pre-construction Activities																	
Mobilization and Demobilization \$																	
Direct Implentation Costs \$																	
Other Indirect Costs																	
O&M Costs S	_ 5		s -	s -	e _	s -	s -	s _	\$ -	s -	s -	s _	s -	\$ -	s -	İ	
Groundwater Alternative 2, Institutional Controls, Containment at River, and Pump and Treat						*	9				,	-	-		\ <u>\</u>		
TOTAL PRESENT VALUE																	
Capital Costs \$	- S	-															
Pre-construction Activities				-										-		-	
Mobilization and Demobilization \$				-	l									-	 	-	
Direct Implentation Costs \$	-			 										-		<u> </u>	
Other Indirect Costs																	
Diamond Alkali OU2 Contingency \$	225 000 6	1,125,000		\$1,125,000	0.1.135.000	01.125.000	C4 445 000	0.1.125.000	0.1.125.000	01.125.000	\$ 1,125,000	01.125.000	0.1.125.000	01.125.000	\$ 1,125,000	DA 125 000	0.4.425.00
O&M Costs S 1,3 Groundwater - Alternative 3, Institutional Controls and In-Situ Remediation	125,900 8	1,125,000	5 1,125,000	51,125,000	5 1,125,000	51,125,000	51,125,000	\$1,125,000	\$ 1,125,000	\$1,125,000	51,125,000	51,125,000	\$1,125,000	51,125,000	\$ 1,125,000	51,125,000	\$ 1,125,000
																<u> </u>	
TOTAL PRESENT VALUE				-										 	 	-	+
Capital Costs \$	- S	<u> </u>		 										+		 	
Pre-construction Activities																1	
Mobilization and Demobilization \$	- S																
			\$ -														
Direct Implentation Costs \$	- S		\$ - \$ -														
Other Indirect Costs \$	- s	- -	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In-	- S	- -	\$ - \$ - \$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation	- s	- -	\$ - \$ - \$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,259	\$ 131,250	S 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,256
Other Indirect Costs 5 O&M Costs 5 Geomdwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE	- \$ - \$ 131,259 \$; - ; - 3 131,250	\$ - \$ - \$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,256
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$	- s	; - ; - 3 131,250	\$ - \$ - \$ 131,250	\$ 131,250	S 131,259	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	S 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,25
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities	- \$ 131,259 \$ - \$	5 131,250		\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$	- \$ - \$ 131,259 \$	5 131,250	\$ - \$ - \$ 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,256	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ O&M Costs \$ Sommon Controls, Targeted Pringip and Treat, and Targeted Periodic Institutional Controls, ToTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implentation Costs \$	- \$ 131,259 \$ - \$	5 131,250		\$ 131,250	S 131,259	\$ 131,250	\$ 131,250	\$ 131,250	S 131,250	S 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250	\$ 131,250
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ Groundwater Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic Institutional Costs \$ TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implentation Costs \$ Other Indirect Costs \$	- \$ \$ 131,250 \$ \$ - \$ \$ - \$ \$ - \$ \$	3 - 131,250	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implentation Costs \$ O&M Costs \$ 1, Groundwater - Alternative 5, Institutional Controls, Site	- \$ \$ 131,250 \$ \$ - \$ \$ - \$ \$ - \$ \$	3 - 131,250	\$ - \$ -			\$ 131,250					\$ 131,250						
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 5, institutional Controls, Site Containment at River Edgs and In-Situ Remediation	- \$ \$ 131,250 \$ \$ - \$ \$ - \$ \$ - \$ \$	3 - 131,250	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implentation Costs \$ O&M Costs \$ Groundwater - Alternative 5, Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE	- \$ \$ - \$ \$ - \$ \$ - \$ \$ 599,990 \$	131,250 131,250	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ Groundwater Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Other Indirect Costs \$ O&M Costs \$ 1.6 Groundwater -Alternative 5, Institutional Controls, 8te Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ 3.1.6	- \$ \$ 131,250 \$ \$ - \$ \$ - \$ \$ - \$ \$	131,250 131,250	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implentation Costs \$ O&M Costs \$ Groundwater - Alternative 5, Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities	- \$ 131,250 \$ 131,250 \$ - \$ 5 - \$ 5 500,000 \$ 5	; - ; 131,250	\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ O&M Costs \$ Groundwater - Alternative 5, Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Solution of the Indirect Costs \$ Cost Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Solution of the Indirect Costs \$ Pre-construction Activities Mobilization and Demobilization \$ \$ Solution of the Indirect Costs \$ Pre-construction Activities Mobilization and Demobilization \$ \$ Solution of the Indirect Costs \$ Pre-construction Activities \$ Mobilization and Demobilization \$ \$ Solution of the Indirect Costs \$ Pre-construction Activities \$ Mobilization and Demobilization \$ \$ Solution of the Indirect Costs \$ Pre-construction Activities \$ Mobilization and Demobilization \$ Solution of the Indirect Costs \$ Solution of the Indirect Costs \$ Pre-construction Activities \$ Solution of the Indirect Costs \$ Soluti	- S 131,250 S 131,250 S - S - S - S - S - S - S - S - S - S -	; - ; - ; 131,250	\$ - \$ - \$ 1,500,600														
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Other Indirect Costs \$ Other Indirect Costs \$ Control Pump And Treat Alternative 5, Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implementation Costs \$ \$ Pre-construction Activities Mobilization and Demobilization \$ Direct Implementation Costs \$	- \$ 131,250 \$ 131,250 \$ 5 131,		\$ - \$ -														
Other Indirect Costs \$ O&M Costs \$ Groundwater - Alternative 4, Institutional Controls, Targeted Pump and Treat, and Targeted Periodic In- Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Other Indirect Costs \$ Groundwater - Alternative 5, Institutional Controls, Site Containment at River Edge and In-Situ Remediation TOTAL PRESENT VALUE Capital Costs \$ Pre-construction Activities Mobilization and Demobilization \$ Pre-construction Activities Mobilization and Demobilization \$ Other Indirect Costs \$	- S 131,250 S 131,250 S - S - S - S - S - S - S - S - S - S -	3 1,500,000	\$ - \$	\$1,500,000	\$1,500,000		\$1,500,000	\$1,590,000	\$1,590,000	\$1,500,000		\$1,500,000	\$1,500,000	\$1,500,000		\$1,500,000	\$1,500,00

SUMMARY TABLE

Component		otal Capital Costs	1	otal Annual D&M Costs	Pr	Total Net esent Worth
Waste			<u> </u>		<u> </u>	
Alternative 1 - No Action	\$	-	\$	-	\$	-
Alternative 2 - Removal and Off-Site Disposal	\$	1,798,211	\$	-	\$	1,580,700
Soil/Fill						
Alternative 1 - No Action	\$	-	\$	-	\$	-
Alternative 2 - Institutional Controls and NAPL Removal	\$	303,322	\$	8,125	\$	356,100
Alternative 3 - Institutional Controls, Engineering Controls, and NAPL Removal	\$	11,140,405	\$	75,000	\$	10,450,900
Alternative 4 - Institutional Controls, Engineering Controls, Focused Removal with Off-Site Disposal of Lead, and NAPL Removal	\$	13,623,160	\$	75,000	\$	12,633,300
Alternative 5 - Institutional Controls, In-Situ Remediation, Engineering Controls, and NAPL Removal	\$	15,222,505	\$	68,750	\$	13,971,400
<u>Groundwater</u>						
Alternative 1 - No Action	\$	-	\$	-	\$	-
Alternative 2 - Institutional Controls, Site Containment at River Edge, and Pump and Treat	\$	30,590,844	\$	1,125,000	\$	34,258,600
Alternative 3 - Institutional Controls and In-Situ Remediation	\$	28,459,770	\$	131,250	\$	20,844,800
Alternative 4 - Institutional Controls, Pump and Treat, and Targeted Periodic In- Situ Remediation	\$	12,831,750	\$	1,500,000	\$	24,234,400
Alternative 5 - Institutional Controls, Site Containment at River Edge and In- Situ Remediation	\$	20,811,881	\$	131,250	\$	17,193,900
Sewer Water	X					
Alternative 1 - No Action	\$	-	\$	-	\$	-
Alternative 2 - Removal and Off-Site Disposal	\$	27,981	\$	-	\$	24,900
Soil Gas						
Alternative 1 - No Action	\$	-	\$	-	\$	-
Alternative 2 - Institutional Controls, Air Monitoring or Engineering Controls (existing occupied buildings) and Site-Wide Engineering Controls (future buildings)	\$	123,525	\$	31,500	\$	449,800
Alternative 3 - Institutional Controls, Site-Wide Engineering Controls (future buildings), and Air Monitoring or Engineering Controls and In-Situ Remediation of Soil/Fill (existing occupied buildings)	\$	4,591,968	\$	-	\$	4,050,800

TABLE B-W1 - PRELIMINARY COST ESTIMATE WASTE - ALTERNATIVE 1 NO ACTION

Component	Estimated Quantity	Unit	Estimated Unit Cost	Estimated Capital Cost	Estimated Annual O&M Cost
Capital Costs					
Direct Implementation Costs				\$ -	
		Subt	otal - Direct Costs	\$ -	
Indirect Costs					
Remedial Design	(10% of Direct Cost	:s)	\$ -	
Mobilization/Misc. Site Prep	(5% of Direct Costs	5)	\$ -	
Site Administration	(5% of Direct Costs	;)	\$ -	
Permitting/Legal Costs	(2% of Direct Costs	;)	\$ -	
Construction Management/Oversight	(:	10% of Direct Cost	s)	\$ -	
		Subtot	al - Indirect Costs	\$ -	
	Contingen	cy - 25% of Direct	and Indirect Costs	\$ -	
		Т	otal Capital Costs	\$ -	
Operation and Maintenance Costs					
					\$ -
		Sub	total - O&M Costs		\$ -
	Contir	ngency Reserve - 2	5% of O&M Costs		\$ -
		Total A		\$ -	
	Net Pr	esent Worth of A	\$ -		
Total Net Present	: Worth of Alterna	ative		\$ -	

TABLE B-W2 - PRELIMINARY COST ESTIMATE WASTE - ALTERNATIVE 2 REMOVAL AND OFF-SITE DISPOSAL

Component	Estimated Quantity	Unit	Est	timated Unit Cost	Esti	mated Capital Cost	Estimated Annual O&M Cost
<u>Capital Costs</u>							
Direct Implementation Costs	THE PROPERTY OF THE PROPERTY O						
Consolidation/Containerization of Wastes	1	LS	\$	25,000	\$	25,000	
UST Removal/Disposal	6	Ea	\$	15,000	\$	90,000	
Impacted Soil Removal at USTs	3,500	СУ	\$	22	\$	77,000	
Clean Backfill (provide/place/compact)	5,600	Ton	\$	60	\$	336,000	
6" Gravel Surface at NAPL Footprint	800	SY	\$	18	\$	14,400	
Waste Disposal, UST Soil (T&D)	5,800	Ton	\$	75	\$	435,000	
Waste Disposal, Non-haz liquids (T&D)	34,700	Gal	\$	0.25	\$	8,675	
Waste Disposal, LNAPLs (T&D)	4,500	Gal	\$	1	\$	4,500	
Waste Disposal, Non-haz solids/tanks (T&D)	30	Ton	\$	75	\$	2,250	
Soil Treatment for Disposal	880	Ton	\$	25	\$	22,000	
Water Management/Disposal	1	LS	\$	55,000	\$	55,000	
UST Closure Sampling/Reporting	1	LS	\$	20,000	\$	20,000	
		Sub	total	- Direct Costs	\$	1,089,825	
Indirect Costs							
Remedial/Geotechnical Design	(:	10% of Direct Cos	ts)		\$	108,983	
Mobilization/Misc. Site Prep	(5% of Direct Cos	ts)		\$	54,491	
Site Administration	(5% of Direct Cos	ts)		\$	54,491	
Permitting/Legal Costs	(2% of Direct Cos	ts)		\$	21,797	
Construction Management/Oversight	(:	10% of Direct Cos	ts)		\$	108,983	
		Subto	tal - I	ndirect Costs	\$	348,744	
	Contingend	cy - 25% of Direct	and I	ndirect Costs	\$	359,642	
		-	Γotal	Capital Costs	\$	1,798,211	
Operation and Maintenance Costs							
							\$ -
		Suk	total	- O&M Costs			\$ -
			\$ -				
		Total A	Annua	l O&M Costs			\$ -
	Net Present Worth of Annual O&M Costs						
Total Net Present Wor	th of Alternative				\$	1,580,700	

TABLE B-SF1 - PRELIMINARY COST ESTIMATE SOIL/FILL - ALTERNATIVE 1 NO ACTION

Component	Estimated Quantity	Unit	Estimated Unit Cost	Estimated Capital Cost	Estimated Annual O&M Cost
Capital Costs					
Direct Implementation Costs					
		Subt	otal - Direct Costs	\$ -	
Indirect Costs					
Remedial Design	(:	10% of Direct Cost	s)	\$ -	
Mobilization/Misc. Site Prep	(5% of Direct Costs	5)	\$ -	
Site Administration	(5% of Direct Costs	5)	\$ -	
Permitting/Legal Costs	(2% of Direct Costs	5)	\$ -	
Construction Management/Oversight	(:	10% of Direct Cost	s)	\$ -	
		Subtot	al - Indirect Costs	\$ -	
	Contingenc	y - 25% of Direct a	and Indirect Costs	\$ -	
		T	otal Capital Costs	\$ -	
Operation and Maintenance Costs					
Site Inspections/Maintenance					\$ -
Five-Year Reviews					\$ -
		Subt		\$ -	
	Contin	igency Reserve - 2		\$ -	
		Total A	nnual O&M Costs		\$ -
	Net Pr	esent Worth of A	\$ -		
Total Net Prese	ent Worth of Alte	rnative		\$ -	

TABLE B-SF2 - PRELIMINARY COST ESTIMATE SOIL/FILL - ALTERNATIVE 2 INSTITUTIONAL CONTROLS AND NAPL REMOVAL

Component	Estimated Quantity	Unit	Est	imated Unit Cost	Estir	nated Capital Cost	Estima Annual O	
Capital Costs								
Direct Implementation Costs								
Deed Restrictions (legal/filing)	15	Lots	\$	4,000	\$	60,000		
Fencing Enhancements	1,000	LF	\$	20	\$	20,000		
NAPL Removal		•						
Excavate/Load Soil/Fill	310	CY	\$	15	\$	4,650		
Waste Disposal, Petroleum-impacted (T&D)	510	Ton	\$	75	\$	38,250		
Soil Treatment	510	Ton	\$	25	\$	12,750		
Clean Backfill (provide/place/compact)	510	Ton	\$	60	\$	30,600		
6" Gravel Surface at NAPL Footprint	135	SY	\$	18	\$	2,430		
		Sub	total	- Direct Costs	\$	168,680		
Indirect Costs								
Predesign Investigation		Lump Sum			\$	20,000		
Remedial Design	(10% of Direct Cos	ts)		\$	16,868		
Mobilization/Misc. Site Prep		(5% of Direct Cost	s)		\$	8,434		
Site Administration		(5% of Direct Cost	s)		\$	8,434		
Permitting/Legal Costs		(2% of Direct Cost	:s)		\$	3,374		
Construction Management/Oversight	(10% of Direct Cos	ts)		\$	16,868		
	·	Subto	tal - I	ndirect Costs	\$	73,978		
	Contingen	cy - 25% of Direct	and I	ndirect Costs	\$	60,664		
		7	Fotal	Capital Costs	\$	303,322		
Operation and Maintenance Costs								
Site Inspections/Maintenance	1	Annual	\$	1,500			\$	1,500
Five-Year Reviews	1	Annualized	\$	5,000			\$	5,000
	б ологияния на пология н	Sub	total	- O&M Costs		***************************************	\$	6,500
	Contir			\$	1,625			
Total Annual O&M Costs							\$	8,125
	Net Present Worth of Annual O&M Costs							
Total Net Present Wort	n of Alternative				\$	356,100		

TABLE B-SF3 - PRELIMINARY COST ESTIMATE SOIL/FILL - ALTERNATIVE 3 INSTITUTIONAL CONTROLS, ENGINEERING CONTROLS, AND NAPL REMOVAL

Component	Estimated Quantity	Unit	Esti	mated Unit Cost	Estimated Capital Cos	- 1	Estimated Annual O&M Cos
Capital Costs							
Direct Implementation Costs							
Deed Restrictions (legal/filing)	15	Lots	\$	4,000	\$ 60,0	00	
Fencing Enhancements	1,000	LF	\$	20	\$ 20,0	00	
Site Preparation			•				
Clear Vegetation	0.5	Ac	\$	1,500	\$ 7	50	
Asphalt and Debris Removal	1	LS	\$	25,000	\$ 25,0	00	
Asphalt and Debris Disposal (T&D)	7500	Ton	\$	75	\$ 562,5	00	
Asphalt Cap			•				
Regrade as needed to level surface	2000	CY	\$	20	\$ 40,0	00	
Base gravel - 6"	27,200	SY	\$	18	\$ 489,6	00	
Bituminous concrete - 6"	27,200	SY	\$	48	\$ 1,305,6	00	
Seal coating	27,200	SY	\$	1.25	\$ 34,0	00	
NAPL Removal			'				
Excavate/Load Soil/Fill	310	CY	\$	15	\$ 4,6	50	
Waste Disposal, Petroleum-impacted (T&D)	510	Ton	\$	75	\$ 38,2		
Soil Treatment	510	Ton	\$	25	\$ 12,7	50	
Clean Backfill (provide/place/compact)	510	Ton	\$	60	\$ 30,6	00	
Vertical Barrier	'		ı				
Temporary Silt Screens in river	1 1	LS	\$	25,000	\$ 25,0	00	
Old Wall Excavation (non soil/fill debris)	240	CY	\$	50	\$ 12,0		
Decontamination and Disposal of Old Wall (non-	400	T			·		
soil/fill debris, T&D)	400	Ton	\$	250	\$ 100,0	וטט	
Sheet Pile Installation (800' x 30')	24,000	SF	\$	150	\$ 3,600,0	00	
Seal inactive wall pipes	1	LS	\$	35,000	\$ 35,0	00	
		Sub	total -	Direct Costs	\$ 6,395,7	00	
Indirect Costs							
Geotechnical Investigation		Lump Sum			\$ 60,0	00	
Predesign Investigation/Soil Delineation		Lump Sum			\$ 250,0	00	
Remedial/Geotechnical Design	(1	.0% of Direct Co	sts)		\$ 639,5	70	
Mobilization/Misc. Site Prep	(!	5% of Direct Cos	ts)		\$ 319,7	85	
Site Administration	(!	5% of Direct Cos	ts)		\$ 319,7	85	
Permitting/Legal Costs	(:	2% of Direct Cos	ts)		\$ 127,9	14	
Construction Management/Oversight	(1	.0% of Direct Co	sts)		\$ 639,5	70	
		Subt	otal - Ir	ndirect Costs	\$ 2,356,6	24	
		Diamond Alka	li OU2	Contingency	\$ 200,0	00	
	Contingenc	y - 25% of Direc	and Ir	ndirect Costs	\$ 2,188,0	81	
			Total C	Capital Costs	\$ 11,140,4	05	
peration and Maintenance Costs							
Site Inspections/Maintenance	4	Qtr	\$	5,000			\$ 20,00
Renew Top Coat every 10 yrs (annualized cost)	1	annualized	\$	35,000			\$ 35,00
Five-Year Reviews	1	annualized	\$	5,000			\$ 5,00
		Su	ototal -	O&M Costs			\$ 60,00
	Contin	gency Reserve -	25% of	O&M Costs			\$ 15,00
		Total	Annual	O&M Costs			\$ 75,00
	Net Pro	esent Worth of	Annual	O&M Costs	\$ 812,9	00	,
Tabal Nick Day and Mile	th of Alternative				\$ 10,450,9		

TABLE B-SF4 - PRELIMINARY COST ESTIMATE SOIL/FILL - ALTERNATIVE 4 INSTITUTIONAL CONTROLS, ENGINEERING CONTROLS, FOCUSED REMOVAL WITH OFF-SITE DISPOSAL OF LEAD, AND NAPL REMOVAL

	Estimated Quantity	Unit	Esti	mated Unit Cost	Estimated Capital Cost	Estimated Annual O&M Co
apital Costs						
Direct Implementation Costs						
Deed Restrictions (legal/filing)	15	Lots	\$	4,000	\$ 60,000	
Fencing Enhancements	1,000	LF	\$	20	\$ 20,000	
Site Preparation	'		'			
Clear Vegetation	0.5	Ac	\$	1,500	\$ 750	
Asphalt and Debris Removal	1	LS	\$	25,000	\$ 25,000	
Asphalt and Debris Disposal (T&D)	7500	Ton	\$	75	\$ 562,500	
Asphalt Cap			•			
Regrade as needed to level surface	2000	CY	\$	20	\$ 40,000	
Base gravel - 6"	27,200	SY	\$	18	\$ 489,600	
Bituminous concrete - 6"	24,800	SY	\$	48	\$ 1,190,400	
Seal coating	24,800	SY	\$	1.25	\$ 31,000	
NAPL Removal			'			
Excavate/Load Soil/Fill	310	CY	\$	15	\$ 4,650	
Waste Disposal, Petroleum-impacted (T&D)	510	Ton	\$	75	\$ 38,250	
Soil Treatment	510	Ton	\$	25	\$ 12,750	
Clean Backfill (provide/place/compact)	510	Ton	\$	60	\$ 30,600	
Vertical Barrier	'		'			
Temporary Silt Screens in river	1	LS	\$	25,000	\$ 25,000	
Old Wall Excavation (non soil/fill debris)	240	CY	\$	50	\$ 12,000	
Decontamination and Disposal of Old Wall (non-soil/fill debris, T&D)	400	Ton	\$	250	\$ 100,000	
Sheet Pile Installation (800' x 30')	24,000	SF	\$	150	\$ 3,600,000	
Seal inactive wall pipes	1	LS	\$	35,000	\$ 35,000	
Limited Excavation/Disposal			•			
Foundation Protection During Excavation	1	LS	\$	200,000	\$ 200,000	
Excavate/load soils	5,100	CY	\$	15	\$ 76,500	
Disposal of soils (non-haz, T&D)	8,415	Ton	\$	75	\$ 631,125	
Soil Treatment for Disposal	8,415	Ton	\$	25	\$ 210,375	
Clean Backfill (provide/place/compact)	8,415	Ton	\$	60	\$ 504,900	
		St	ıbtotal -	Direct Costs	\$ 7,900,400	
Indirect Costs						
Geotechnical Investigation		Lump Sum			\$ 60,000	
Predesign Investigation/Soil Delineation		Lump Sum			\$ 250,000	
Remedial Design	(1	0% of Direct C	osts)		\$ 790,040	
Mobilization/Misc. Site Prep	(:	5% of Direct Co	osts)		\$ 395,020	
Site Administration	(5% of Direct Co	osts)		\$ 395,020	
Permitting/Legal Costs	(2	2% of Direct Co	osts)		\$ 158,008	
Oversight/Post-Ex Sampling	(1	0% of Direct C	osts)		\$ 790,040	
		Sub	total - Ir	ndirect Costs	\$ 2,838,128	
		Diamond Alk	ali OU2	Contingency	\$ 200,000	
	Contingenc	y - 25% o f Dire	ct and Ir	ndirect Costs	\$ 2,684,632	
			Total (Capital Costs	\$ 13,623,160	
peration and Maintenance Costs						
Site Inspections/Maintenance	4	Qtr	\$	5,000		\$ 20,00
Renew Top Coat every 10 yrs (annualized cost)	1	annualized	\$	35,000		\$ 35,00
Five-Year Reviews	1	annualized	\$	5,000		\$ 5,00
		S	ubtotal	- O&M Costs		\$ 60,00
	Contin	gency Reserve	- 25% o	f O&M Costs		\$ 15,00
		Tota	l Annua	O&M Costs		\$ 75,00
	Net Pre	esent Worth o	f Annua	I O&M Costs	\$ 812,900	
Total Net Present Wo	orth of Alternative	***************************************			\$ 12,633,300	

TABLE B-SF5 - PRELIMINARY COST ESTIMATE SOIL/FILL - ALTERNATIVE 5 INSTITUTIONAL CONTROLS, IN-SITU REMEDIATION, ENGINEERING CONTROLS, AND NAPL REMOVAL

Component	Estimated Quantity	Unit	Esti	mated Unit Cost	ı	timated pital Cost	Estimated O&M 0	
Capital Costs		<u> </u>	<u> </u>					
Direct Implementation Costs								
Deed Restrictions (legal/filing)	15	Lots	\$	4,000	\$	60,000		
Fencing Enhancements	1,000	LF	\$	20	\$	20,000		
Site Preparation		•	•					
Clear Vegetation	0.5	Ac	\$	1,500	\$	750		
Asphalt and Debris Removal	1	LS	\$	25,000	\$	25,000		
Asphalt and Debris Disposal (T&D)	7500	Ton	\$	75	\$	562,500		
NAPL Removal								
Excavate/Load Soil/Fill	310	CY	\$	15	\$	4,650		
Waste Disposal, Petroleum-impacted (T&D)	510	Ton	\$	75	\$	38,250		
Soil Treatment	510	Ton	\$	25	\$	12,750		
Clean Backfill (provide/place/compact)	510	Ton	\$	60	\$	30,600		
Vertical Barrier		•	•					
Temporary Silt Screens in river	1	LS	\$	25,000	\$	25,000		
Old Wall Excavation (non soil/fill debris)	240	CY	\$	50	\$	12,000		
Decontamination and Disposal of Old Wall (non- soil/fill debris, T&D)	400	Ton	\$	250	\$	100,000		
Sheet Pile Installation (800' x 30')	24,000	SF	\$	150	\$	3,600,000		
Seal inactive wall pipes	1	LS	\$	35,000	\$	35,000		
In-Situ Treatment		•	•					
Excavate top 18"	5100	CY	\$	15	\$	76,500		
Dispose top 18" (T&D)	8,420	Ton	\$	75	\$	631,500		
Regrade as needed to level surface	500	CY	\$	20	\$	10,000		
Insitu Solidification and Stabilization	30,500	CY	\$	60	\$	1,830,000		
Base gravel - 6"	27,200	SY	\$	18	s	489,600		
Bituminous concrete - 6"	27,200	SY	\$	48	\$	1,305,600		
	d	Sub	total -	Direct Costs	\$	8,869,700		
Indirect Costs								
Geotechnical Investigation		Lump Sum			\$	60,000		
Predesign Investigation/Soil Delineation		Lump Sum			\$	250,000		
Remedial Design, incl. treatability testing	(10% of Direct Cos	sts)		\$	886,970		
Mobilization/Misc. Site Prep		5% of Direct Cos	ts)		\$	443,485		
Site Administration		5% of Direct Cos	ts)		\$	443,485		
Permitting/Legal Costs		2% of Direct Cos	ts)		\$	177,394		
Constr. Mgmt/Oversight/Post-Ex Sampling	(10% of Direct Cos	its)		\$	886,970		
		Subto	tal - In	direct Costs	\$	3,148,304		
		Diamond Alkal	i OU2	Contingency	\$	200,000		
	Contingend	cy - 25% of Direct	and In	direct Costs	\$	3,004,501		
			Total C	Capital Costs	\$	15,222,505		
Operation and Maintenance Costs					l			
Site Inspections/Maintenance	4	Qtr	\$	3,750			\$	15,000
Renew Top Coat every 10 yrs	1	annualized	\$	35,000			\$	35,000
Five-Year Reviews	1	annualized	\$	5,000			\$	5,000
		Sul	total -	- O&M Costs			\$	55,000
	Contir	ngency Reserve -	25% of	O&M Costs			\$	13,750
		Total /	Annual	O&M Costs			\$	68,750
	Net Pr	esent Worth of	Annual	O&M Costs	\$	745,100		
Total Net Present Wort	h of Alternative				\$	13,971,400		

TABLE B-GW1 - PRELIMINARY COST ESTIMATE GROUNDWATER - ALTERNATIVE 1 NO ACTION

Component	Estimated Quantity	Unit	Estimated Unit Cost	Estimated Capita Cost	Estimated Annual O&M Cost
Capital Costs					
Direct Implementation Costs				\$ -	
		Subt	otal - Direct Costs	\$ -	
Indirect Costs					
Remedial Design	(10% of Direct Cost	ts)	\$ -	
Mobilization/Misc. Site Prep		(5% of Direct Cost	s)	\$ -	
Site Administration		(5% of Direct Cost	\$ -		
Permitting/Legal Costs		(2% of Direct Cost	\$ -		
Construction Management/Oversight	(10% of Direct Cost	ts)	\$ -	
		Subto	tal - Indirect Costs	\$ -	
	Contingen	cy - 25% of Direct	and Indirect Costs	\$ -	
		Т	otal Capital Costs	\$ -	
Operation and Maintenance Costs					
Site Inspections/Maintenance					\$ -
Five-year Reviews (annualized cost)					\$ -
	-	Sub	total - O&M Costs		\$ -
	Conti	ngency Reserve - 2	.5% of O&M Costs		\$ -
		Total A	nnual O&M Costs		\$ -
	Net Pr	esent Worth of A	nnual O&M Costs	\$ -	
Total Net Present Wort	h of Alternative			\$ -	

TABLE B-GW2 - PRELIMINARY COST ESTIMATE GROUNDWATER - ALTERNATIVE 2 INSTITUTIONAL CONTROLS, CONTAINMENT AT RIVER AT RIVER EDGE, AND PUMP AND TREAT

Component	Estimated Quantity	Unit	Esti	mated Unit Cost	Esti	mated Capital Cost		nated Annua 0&M Cost
apital Costs								
Direct Implementation Costs								
CEA/WRA Submissions	1	LS	\$	75,000	\$	75,000		
Year 1 Groundwater Monitoring	4	LS	\$	45,000	\$	180,000		
Sheet Pile Containment Installation	70,000	SF	\$	150	\$	10,500,000		
Fill Between Old and New Wall	975	СУ	\$	125	\$	121,875		
Extraction Well, pump, riser, well head, pump	20	EA	\$	2,500	\$	50,000		
Conveyance Trenching/Fill	2,500	LF	\$	40	\$	100,000		
Piping, conduit, wiring, instrumentation	30,000	LF	\$	37	\$	1,110,000		
Treatment Building, Pad, Utilities	7,500	SF	\$	250	\$	1,875,000		
Utilities (sewer, water, electrical)	1	LS	\$	100,000	\$	100,000		
Discharge line	500	LF	\$	150	\$	75,000		
200 gpm Treatment System (includes equipment, installation, labor)								
Process Water Tanks	1	LS	\$	150,000	\$	150,000		
Oxidation System	1	LS	\$	500,000	\$	500,000		
Filtration Units	1	LS	\$	400,000	\$	400,000		
Metals Precipitaion System	1	LS	\$	275,000	\$	275,000		
Sludge Processing	1	LS	\$	150,000	\$	150,000		
Carbon Adsorption Units	1	LS	\$	250,000	\$	250,000		
Pumps and Piping	1	LS	\$	150,000	\$	150,000		
Electrical, Instrumentation, Controls	1	LS	\$	1,500,000	\$	1,500,000		
Chemical Feed System	1	LS	\$	175,000	\$	175,000		
	·····	Sub	total -	Direct Costs	\$	17,736,875		
Indirect Costs								
Predesign Investigation		Lump Sum			\$	750,000		
Geotechnical Investigation		Lump Sum			\$	150,000		
Remedial Design		(10% of Direct Cos	sts)		\$	1,773,688		
Mobilization/Misc. Site Prep		(5% of Direct Cost	ts)		\$	886,844		
Site Administration		(5% of Direct Cost	ts)		\$	886,844		
Permitting/Legal Costs		(2% of Direct Cost	ts)		\$	354,738		
Construction Management/Oversight		(10% of Direct Cos	sts)		\$	1,773,688		
		Subto	tal - Ir	direct Costs	\$	6,575,800		
		Diamond Alkal	i OU2	Contingency	\$	200,000		
	Contingen	cy - 25% of Direct	and Ir	direct Costs	\$	6,078,169		
			Total C	Capital Costs	\$	30,590,844		
peration and Maintenance Costs								
Routine Groundwater Monitoring	2	event	\$	45,000			\$	90,00
Biennial Sampling Per CEA (annualized costs)	1	event	\$	10,000			\$	10,00
Treatment System		1	ـ ا	450			_	4=0.5-
Utilities	1	LS	\$	150,000			\$	150,00
Chemicals (oxidant, pH adjustment, etc.)	1	LS	\$	50,000			\$	50,00
Carbon Changeout	1	LS	\$	50,000			\$	50,00
Sludge/Waste Management	1	LS	\$	50,000			\$	50,00
Routine O&M (staffed 40 hrs per wk)	1	LS	\$	320,000			\$	320,00
Non Routine Maintenance	1	LS	\$	25,000			\$	25,00
Performance Sampling	1	LS	\$	150,000			\$	150,00
Five-Year Reviews	1	annualized	\$	5,000			\$	5,00
				O&M Costs			\$	900,00
	Conti	ngency Reserve - :					\$	225,00
				O&M Costs			\$	1,125,00
	Net P	resent Worth of A	Innual	O&M Costs	\$	10,650,100	l	

TABLE B-GW3 - PRELIMINARY COST ESTIMATE GROUNDWATER - ALTERNATIVE 3 INSTITUTIONAL CONTROLS AND IN-SITU REMEDIATION

Component	Estimated Quantity	Unit	Es	timated Unit Cost	Estim	ated Capital Cost	į.	ted Annual M Cost
Capital Costs								
Direct Implementation Costs								
CEA/WRA Submissions	1	LS	\$	75,000	\$	75,000		
1st Year Groundwater Monitoring	4	Event	\$	45,000	\$	180,000		
Initial Chemical Treatment (organics)	1,622,250	LB	\$	1.75	\$	2,838,938		
Initial Chemical Treatment (inorganics)	1,954,500	LB	\$	2.25	\$	4,397,625		
Inject labor/equipment	300	Day	\$	3,500	\$	1,050,000		
Round 2 Injections (67% , chemicals and labor)	1	LS	\$	5,551,997	\$	5,551,997		
Round 3 Injections (33% , chemicals and labor)	1	LS	\$	2,775,998	\$	2,775,998		
		Subt	otal	- Direct Costs		\$16,869,558		
Indirect Costs								
Predesign Investigation		Lump Sum			\$	500,000		
Remedial Design	(10% of Direct Cost	ts)		\$	1,686,956		
Mobilization/Misc. Site Prep	1	(5% of Direct Cost	s)		\$	843,478		
Site Administration		(5% of Direct Cost	s)		\$	843,478		
Permitting/Legal Costs		(2% of Direct Cost	s)		\$	337,391		
Construction Management/Oversight	(10% of Direct Cost	ts)		\$	1,686,956		
		Subto	tal -	Indirect Costs	\$	5,898,259		
	Contingen	cy - 25% of Direct	and	Indirect Costs	\$	5,691,954		
	***************************************	T	otal	Capital Costs	\$	28,459,770		
Operation and Maintenance Costs								
Routine Groundwater Monitoring	2	Event	\$	45,000			\$	90,000
Biennial Sampling per CEA (annualized cost)	1	Event	\$	10,000			\$	10,000
Five-year Reviews (annualized cost)	1	(annualized)	\$	5,000			\$	5,000
				\$	105,000			
	Contin			\$	26,250			
Total Annual O&M Costs							\$	131,250
Net Present Worth of Annual O&M Costs						1,242,500		
Total Net Present Worth	n of Alternative				\$	20,844,800		

TABLE B-GW4 - PRELIMINARY COST ESTIMATE GROUNDWATER - ALTERNATIVE 4 INSTITUTIONAL CONTROLS, PUMP AND TREAT, AND TARGETED PERIODIC IN-SITU REMEDIATION

Component	Estimated Quantity	Unit	Estir	nated Unit Cost	Estim	nated Capital Cost	1	ted Annua M Cost
Capital Costs			***************************************	******************				***************************************
Direct Implementation Costs								
CEA/WRA Submissions	1	LS	\$	75,000	\$	75,000		
Year 1 Groundwater Monitoring	4	LS	\$	45,000	\$	180,000		
Extraction Well, pump, riser, well head, pump	20	EA	\$	1,500	\$	30,000		
Conveyance Trenching/Fill	2,500	CY	\$	40	\$	100,000		
Piping, conduit, wiring, instrumentation	30,000	LF	\$	37	\$	1,110,000		
Treatment Building, Pad, Utilities	7,500	SF	\$	250	\$	1,875,000		
Utilities (sewer, water, electrical)	1	LS	\$	100,000	\$	100,000		
Discharge line	500	LF	\$	150	\$	75,000		
200 gpm Treatment System, includes equipment, installation, labor								
Process Water Tanks	1	LS	\$	150,000	\$	150,000		
Oxidation System	1	LS	\$	500,000	\$	500,000		
Filtration Units	1	LS	\$	400,000	\$	400,000		
Metals Precipitaion System	1	LS	\$	275,000	\$	275,000		
Sludge Processing	1	LS	\$	150,000	\$	150,000		
Carbon Adsorption Units	1	LS	\$	250,000	\$	250,000		
Pumps and Piping	1	LS	\$	150,000	\$	150,000		
Electrical, Instrumentation, Controls	1	LS	\$	1,500,000	\$	1,500,000		
Chemical Feed System	1	LS	\$	175,000	\$	175,000		
		Sub	total -	Direct Costs		\$7,095,000		
Indirect Costs								
Predesign Investigation		Lump Sum			\$	750,000		
Geotechnical Investigation	·	Lump Sum			\$	150,000		
Remedial Design	(10% of Direct Cos	ts)		\$	709,500		
Mobilization/Misc. Site Prep		(5% of Direct Cost	ts)		\$	354,750		
Site Administration		(5% of Direct Cost	ts)		\$	354,750		
Permitting/Legal Costs		(2% of Direct Cost	ts)		\$	141,900		
Construction Management/Oversight	(10% of Direct Cos	ts)		\$	709,500		
		Subto	tal - In	direct Costs	\$	3,170,400		
	Contingen	cy - 25% of Direct	and In	direct Costs	\$	2,566,350		
		T	Total C	apital Costs	\$	12,831,750		
Operation and Maintenance Costs								
Routine Groundwater Monitoring	2	event	\$	45,000			\$	90,00
Biennial Sampling Per CEA (annualized costs)	1	event	\$	10,000			\$	10,00
Treatment System								
Utilities	1	LS	\$	150,000			\$	150,00
Chemicals (oxidant, pH adjustment, etc.)	1	LS	\$	50,000			\$	50,00
Carbon Changeout	1	LS	\$	50,000			\$	50,00
Sludge/Waste Management	1	LS	\$	50,000			\$	50,00
Routine O&M (staffed 40 hrs per wk)	1	LS	\$	320,000			\$	320,00
Non Routine Maintenance	1	LS	\$	25,000			\$	25,00
Performance Sampling In-Situ argetted reatment for Selected	1	LS LS	\$	150,000 300,000			\$ \$	150,00 300,00
Contaminants Five-year Reviews	1	annualized	\$	5,000			\$	
, , , , , , , , , , , , , , , , , , ,		<u> </u>	<u> </u>	O&M Costs	<u> </u>		\$	1,200,00
	Conti	ngency Reserve - 2	25% of	O&M Costs			\$	300,00
		Total A	nnual	O&M Costs	 		\$	1,500,00
	Net Pi	resent Worth of A	nnual	O&M Costs	\$	14,200,200		
Total Net Present Wo	orth of Alternative				Ś	24,234,400		

TABLE B-GW5 - PRELIMINARY COST ESTIMATE GROUNDWATER - ALTERNATIVE 5 INSTITUTIONAL CONTROLS, SITE CONTAINMENT AT RIVER EDGE AND FOCUSED IN-SITU REMEDIATION

Component	Estimated Quantity	Unit	Esti	mated Unit Cost	Esti	imated Capital Cost	ited Annual &M Cost
Capital Costs							
Direct Implementation Costs							
CEA/WRA Submissions	1	LS	\$	75,000	\$	75,000	
1st Year Groundwater Monitoring	4	Event	\$	45,000	\$	180,000	
Sheet Pile Containment Installation	70,000	SF	\$	150	\$	10,500,000	
Fill Between Old and New Wall	975	CY	\$	125	\$	121,875	
Initial Chemical Treatment (organics)	196,643	LB	\$	1.75	\$	344,124	
Initial Chemical Treatment (inorganics)	65,548	LB	\$	2.25	\$	147,482	
Inject labor/equipment	53	Day	\$	3,500	\$	185,500	
Round 2 Injections (67% , chemicals and labor)	1	LS	\$	453,661	\$	453,661	
Round 3 Injections (33% , chemicals and labor)	1	LS	\$	226,831	\$	226,831	
		Subt	otal -	Direct Costs		\$12,234,473	
Indirect Costs							
Predesign Investigation		Lump Sum			\$	350,000	
Geotechnical Investigation		Lump Sum			\$	150,000	
Remedial Design	(10% of Direct Cost	ts)		\$	1,223,447	
Mobilization/Misc. Site Prep		(5% of Direct Cost	s)		\$	611,724	
Site Administration		5% of Direct Cost	s)		\$	611,724	
Permitting/Legal Costs		2% of Direct Cost	s)		\$	244,689	
Construction Management/Oversight	(10% of Direct Cost	ts)		\$	1,223,447	
		Subto	tal - Ir	ndirect Costs	\$	4,415,031	
	Contingend	cy - 25% of Direct	and I	ndirect Costs	\$	4,162,376	
		Т	otal (Capital Costs	\$	20,811,881	
Operation and Maintenance Costs							
Routine Groundwater Monitoring	2	Event	\$	45,000			\$ 90,000
Biennial Sampling per CEA (annualized cost)	1	Event	\$	10,000			\$ 10,000
Five-year Reviews (annualized cost)	1	(annualized)	\$	5,000			\$ 5,000
				\$ 105,000			
	Contingency Reserve - 25% of O&M Costs						\$ 26,250
Total Annual O&M Costs							\$ 131,250
	Net Present Worth of Annual O&M Costs						
Total Net Present Worth	of Alternative	***************************************			Ş	17,193,900	

TABLE B-SW1 - PRELIMINARY COST ESTIMATE SEWER WATER - ALTERNATIVE 1 NO ACTION

Component	Estimated Quantity	Unit	Unit Estimated Unit E		ed Capital Cost	Estimated Annual O&M Cost
<u>Capital Costs</u>						
Direct Implementation Costs						
		Subtot	al - Direct Costs	\$	-	
Indirect Costs						
Remedial Design	(:	10% of Direct Cost	s)	\$	-	
Mobilization/Misc. Site Prep	(5% of Direct Costs	;)	\$	-	
Site Administration	(5% of Direct Costs	5)	\$	-	
Permitting/Legal Costs	(2% of Direct Costs	\$	-		
Construction Management/Oversight	(:	10% of Direct Cost	s)	\$	-	
		Subtotal	- Indirect Costs	\$	-	
	Contingency	- 25% of Direct an	d Indirect Costs	\$	-	
		Tot	al Capital Costs	\$	-	
Operation and Maintenance Costs						
						\$ -
		Sub	total - O&M Costs			\$ -
	Contir	igency Reserve - 2	5% of O&M Costs			\$ -
		Total A	nual O&M Costs			\$ -
	Net Pr	esent Worth of A	nnual O&M Costs	\$	-	
Total Net Present V	Vorth of Alternat	ive		\$	-	

TABLE B-SW2 - PRELIMINARY COST ESTIMATE SEWER WATER - ALTERNATIVE 2 REMOVAL AND OFF-SITE DISPOSAL

Component	Estimated Quantity	Unit	Est	imated Unit Cost	Esti	mated Capital Cost	Estimated Annual O&M Cost
Capital Costs							
Direct Implementation Costs							
Removal of Liquids/Solids	1	LS	\$	5,000			
Pressure Wash Manhole	1	LS	\$	3,000	\$	3,000	
Waste Disposal (liquids, non-haz, T&D)	2,500	Gallons	\$	0.30	\$	750	
Waste Disposal (solids, non-haz, T&D)	2	Drums	\$	250	\$	500	
Disconnect and Grout Pipe and Manhole	1 LS \$ 5,000 \$					5,000	
		Sul	ototal	- Direct Costs	\$	14,250	
Indirect Costs							
Remedial Design		Lump Sum			\$	5,000	
Mobilization/Misc. Site Prep		(5% of Direct Cos	ts)		\$	713	
Site Administration		(5% of Direct Cos	ts)		\$	713	
Permitting/Legal Costs		(2% of Direct Cos	ts)		\$	285	
Construction Management/Overisght	(10% of Direct Co	sts)		\$	1,425	
		Subt	otal -	Indirect Costs	\$	8,135	
	Contingen	cy - 25% of Direc	t and I	Indirect Costs	\$	5,596	
			Total	Capital Costs	\$	27,981	
Operation and Maintenance Costs							
					\$ -		
		Su			\$ -		
			\$ -				
Total Annual O&M Costs							\$ -
	Net Pr	esent Worth of	Annua	I O&M Costs	\$	-	
Total Net Present Wor	th of Alternative				\$	24,900	

TABLE B-SG1 - PRELIMINARY COST ESTIMATE SOIL GAS - ALTERNATIVE 1 NO ACTION

Component	Estimated Quantity	Unit Estimated Unit Cost		Estimated Capital Cost		Estimated Annual O&M Cost	
Capital Costs							
Direct Implementation Costs							
	\$	-					
Indirect Costs							
Remedial Design	(:	\$	-				
Mobilization/Misc. Site Prep	(\$	-				
Site Administration	(\$	-				
Permitting/Legal Costs	(2% of Direct Costs	\$	-			
Construction Management/Oversight	(:	10% of Direct Cost	\$	-			
	\$	-					
Contingency - 25% of Direct and Indirect Costs					-		
Total Capital Costs					-		
Operation and Maintenance Costs							
						\$ -	
Contingency Reserve - 25% of O&M Costs						\$ -	
Total Annual O&M Costs						\$ -	
Net Present Worth of Annual O&M Costs					-		

TABLE B-SG2 - PRELIMINARY COST ESTIMATE SOIL GAS - ALTERNATIVE 2 INSTITUTIONAL CONTROLS, AIR MONITORING/ENGINEERING CONTROLS, AND SITE-WIDE ENGINEERING CONTROLS

Component	Estimated Quantity	Unit	Es	Estimated Unit Cost		Estimated Capital Cost		mated Annual O&M Cost
Capital Costs								
Direct Implementation Costs								
Deed Restrictions/CEAs	15	Lots	\$	4,000	\$	60,000		
Initial Round of Indoor Air Monitoring (3/bldg)	21	Sample	\$	1,500	\$	31,500		
Subtotal - Direct Costs						91,500		
Indirect Costs								
Remedial Design	(5% of Direct Costs)				\$	4,575		
Site Administration	(1% of Direct Costs)				\$	915		
Permitting/Legal Costs	(1% of Direct Costs)				\$	1,830		
Subtotal - Indirect Costs					\$	7,320		
Contingency - 25% of Direct and Indirect Costs					\$	24,705		
Total Capital Costs					\$	123,525		
Operation and Maintenance Costs								
Indoor Air Monitoring	21	Sample	\$	1,500			\$	31,500
Subtotal - O&M Costs						***************************************	\$	31,500
Contingency - 25% of O&M Costs							\$	31,500
Net Present Worth of Annual O&M Costs				\$	341,400			
Total Net Present Worth of Alternative				\$	449,800			

TABLE B-SG3 - PRELIMINARY COST ESTIMATE SOIL GAS - ALTERNATIVE 3 INSTITUTIONAL CONTROLS, SITE-WIDE ENGINEERING CONTROLS, AND IN-SITU REMEDIATION

Component	Estimated Unit Estimated Unit Cost		Estimated Capital Cost		Estimated Annual O&M Cost		
Capital Costs							
Direct Implementation Costs							
Deed Restrictions/CEAs	15	Lots	5	4,000	\$	60,000	
In-Situ Treatment		•	•				
Initial Chemical Treatment (organics)	570,322	LB	9	\$ 1.75	\$	998,064	
Inject labor/equipment	90	Day	1	\$ 3,500	\$	315,000	
Round 2 Injections (67% , chemicals and labor)	1	LS	1	\$ 879,753	\$	879,753	
Round 3 Injections (33% , chemicals and labor)	1	LS	9	\$ 439,876	\$	439,876	
		Subto	otal	- Direct Costs	\$	2,692,693	
Indirect Costs							
Delineation/Treatability Study	Lump Sum				\$	200,000	
Remedial Design	(10% of Direct Costs)				\$	269,269	
Mobilization/Misc. Site Prep	(5% of Direct Costs)				\$	134,635	
Site Administration	(2% of Direct Costs)				\$	53,854	
Permitting/Legal Costs	(2% of Direct Costs)				\$	53,854	
Construction Management/Oversight	(10% of Direct Costs)				\$	269,269	
Subtotal - Indirect Costs						980,881	
Contingency - 25% of Direct and Indirect Costs						918,394	
Total Capital Costs						4,591,968	
Operation and Maintenance Costs				***************************************			
	40000						\$ -
Subtotal - O&M Costs							\$ -
Contingency Reserve - 25% of O&M Costs							\$ -
Total Annual O&M Costs							\$ -
Net Present Worth of Annual O&M Costs					\$	-	
Total Net Present Worth of Alternative					\$	4,050,800	