TO: CP

June 24, 1968.

Mr. Raymond T. Wachob, Plant Engineer
Crouse-Hinds Company
7th North and Wolf Streets
Syracuse, New York

Dear Mr. Wachob:

In response to your request for description of DPW proposed work on the 7th North Street landfill site, the Department of Public Works proposes to construct an all-weather access road on parcel "A" from 7th North Street into the actual landfill area (flowage parcel 6003) as indicated on map.

This all-weather, all-purpose road will be what is commonly known as a 'penetration' job; which includes at least five inches of stone base penetrated with a liquid bituminous material, rolled.... and a seal-coat of liquid bituminous material applied with cover stone and rolled.

However, we propose to landfill parcel 'A' approximately 12 to 18 inches below grade..... constructing the road on top of this landfill.

Very truly yours,

Raymond H. Dodge
Commissioner of Public Works

RHD:AcE
cc: Wm. Burrows, Corp.Counsel

ED_006185_00000744-00001