

Sampling and Analysis Plan, Investigation and Remediation of Releases and Groundwater Protection and Evaluation, Red Hill Bulk Fuel Storage Facility JOINT BASE PEARL HARBOR-HICKAM, O'AHU, HAWAI'I

Administrative Order on Consent in the Matter of Red Hill Bulk Fuel Storage Facility, EPA Docket Number RCRA 7003-R9-2015-01 and DOH Docket Number 15-UST-EA-01, Attachment A, Statement of Work Section 6.2, Section 7.1.2, Section 7.2.2, and Section 7.3.2

January DD, 2017



**Comprehensive Long-Term Environmental Action Navy
Contract Number N62742-12-D-1829, CTO 0053**

DRAFT

1 **Sampling and Analysis Plan,**
2 **Investigation and Remediation of**
3 **Releases and Groundwater**
4 **Protection and Evaluation,**
5 **Red Hill Bulk Fuel Storage Facility**
6 **JOINT BASE PEARL HARBOR-HICKAM, O'AHU, HAWAI'I**

7 **Administrative Order on Consent in the Matter of Red Hill Bulk Fuel Storage**
8 **Facility, EPA Docket Number RCRA 7003-R9-2015-01 and**
9 **DOH Docket Number 15-UST-EA-01, Attachment A, Statement of Work Section**
10 **6.2, Section 7.1.2, Section 7.2.2, and Section 7.3.2**

11 **January DD, 2017**
12

13 Prepared for:

14 **Defense Logistics Agency Energy**
15 **8725 John J Kingman Rd Suite 4950**
16 **Fort Belvoir, VA 22060-6222**

17 Prepared by:

18 **AECOM Technical Services, Inc.**
19 **1001 Bishop Street, Suite 1600**
20 **Honolulu, HI 96813-3698**

21 Prepared under:



22 **Comprehensive Long-Term Environmental Action Navy**
23 **Contract Number N62742-12-D-1829, CTO 0053**
24

DRAFT

CONTENTS

Acronyms and Abbreviations	vii
1. Introduction	1-1
2. Background	2-1
2.1 Site or Sampling Area Description	2-1
2.2 Operational History	2-2
2.3 Previous Investigations	2-2
2.3.1 Oily Waste Disposal Facility Remedial Investigation (DON 1996, 2000)	2-2
2.3.2 Facility Site Characterization and Investigation (DON 1999, 2002)	2-3
2.3.3 Technical Report (DON 2007)	2-3
2.3.4 Tank 17 Removal Action Report (DON 2008)	2-4
2.3.5 Type 1 Letter Report (DON 2010a)	2-4
2.4 Ongoing Activities	2-5
2.4.1 Groundwater Protection Plan (DON 2014)	2-5
2.4.2 Tank 5 Release Response Reports (DON 2014–2016)	2-6
2.4.3 Groundwater Monitoring Program (DON 2005–2016)	2-6
2.4.4 Soil Vapor Monitoring Program (DON 2008–2016)	2-7
2.5 Regulatory Involvement	2-7
2.6 Geological Information	2-7
2.6.1 Geology and Soils	2-7
2.6.2 Groundwater	2-9
3. Project Field Tasks	3-1
4. Sampling Rationale	4-1
4.1 COPCs	4-1
4.2 Groundwater Screening Criteria	4-8
4.3 Natural Attenuation	4-10
4.4 Current Groundwater Monitoring Network	4-11
5. Field Methods and Procedures	5-1
5.1 Field Equipment	5-1
5.1.1 List of Equipment Needed	5-1
5.1.2 Inspection, Maintenance, and Calibration of Field Equipment	5-2
5.2 Geological Mapping	5-2
5.3 High-Precision Land Survey	5-2
5.4 Water Level Monitoring Study	5-3
5.5 Groundwater Sampling	5-3
5.5.1 Groundwater Sampling Procedures	5-4
5.5.2 Field QC	5-5
5.5.3 Groundwater Sample Containers and Preservation	5-6
5.5.4 Sample Custody Requirements	5-8
5.6 Decontamination Procedures	5-10
5.7 Disposal of Residual Materials	5-10
5.8 Field Variances	5-11
5.9 Documentation of Field Activities	5-11

Discussion Purposes Only, Subject to Change

SAP, Investigation and Remediation of Releases
and Groundwater Protection and Evaluation

January DD, 2017

Red Hill Bulk Fuel Storage Facility, JBPHH, O'ahu, HI

Contents

1	6.	Analytical Program	6-1
2		6.1 Reference Limits and Evaluation	6-3
3		6.2 Laboratory Analytical Methods	6-5
4		6.3 Laboratory Quality Control	6-6
5		6.4 Laboratory Analytical Detection Limits	6-7
6		6.5 Laboratory Equipment Testing, Inspection, and Maintenance	6-7
7		6.6 Laboratory Instrument Calibration and Frequency	6-7
8	7.	Assessment and Oversight	7-1
9		7.1 Assessment and Response Actions	7-1
10		7.1.1 Field Activity Assessment	7-2
11		7.1.2 Laboratory Activity and Data Assessment	7-2
12		7.2 Quality Reports to Management	7-4
13	8.	Data Validation, Management, and Usability	8-1
14		8.1 Data Review, Verification, and Validation	8-1
15		8.1.1 Field Activity and Data Verification Summary	8-1
16		8.1.2 Data Validation and Data Quality Assessment Process	8-1
17		8.1.3 Interpreting Exceedances of PALs	8-3
18		8.2 Data Management	8-4
19		8.2.1 Laboratory Subcontractor Requirements	8-4
20		8.2.2 Validation Subcontractor Requirements	8-4
21		8.2.3 Data Recording	8-5
22		8.2.4 Data Reporting	8-6
23		8.3 Reconciliation with User Requirements	8-7
24	9.	References	9-1
25		APPENDIXES	
26	A	NAVFAC Pacific Environmental Restoration Program Project Procedures	
27		(DON 2015b)	
28	B	Field Forms	
29	C	Analytical Data Package Requirements	
30	D	Field Sampling, Analytical, and Quality Management Reference Tables	
31		D-1 Location-Specific Sampling Methods/SOP Requirements	
32		D-2 Preparation and Analytical Requirements for Groundwater and QC	
33		Water	
34		D-3 Analytical Services	
35		D-4 Analytical SOP References	
36		D-5 Laboratory QC Samples	
37		D-6 Analytical Instrument and Equipment Maintenance, Testing, and	
38		Inspection	
39		D-7 Analytical Instrument Calibration	
40		D-8 Data Verification and Validation (Steps I and IIa/IIb) Process	

Discussion Purposes Only, Subject to Change

SAP, Investigation and Remediation of Releases
and Groundwater Protection and Evaluation

January DD, 2017

Red Hill Bulk Fuel Storage Facility, JBPHH, O'ahu, HI

Contents

1	FIGURES	
2	1-1 Current Study Area	1-3
3	1-2 Project Organizational Chart for Sections 6 and 7	1-5
4	TABLES	
5	1-1 Key Project Personnel and Responsibilities	1-2
6	4-1 Fuels Currently Stored at the Facility	4-1
7	4-2 Groundwater COPC Recommendations and Rationales	4-3
8	4-3 COPC List	4-8
9	4-4 Summary of Models and Approaches to Develop DOH Groundwater Tier 1	
10	EALs	4-9
11	4-5 Groundwater Screening Criteria	4-10
12	4-6 Current Groundwater Monitoring Well Network	4-11
13	5-1 Measurement Performance Criteria – Field QC Samples	5-5
14	5-2 Summary of Field QC Samples for Groundwater	5-6
15	5-3 Sample Containers, Preservatives, and Holding Times	5-7
16	5-4 Study Area Identifiers	5-9
17	5-3 Sample Type and Matrix Identifiers	5-9
18	5-4 Field QC Sample Type Identifiers	5-9
19	5-5 Sample Handling System	5-10
20	6-1 Current Groundwater Sample Analysis and Screening Criteria Summary	6-1
21	6-2 Expected Maximum Number of Field Samples per Groundwater Sampling	
22	Event	6-2
23	6-3 Reference Limits and Evaluation for Groundwater	6-4
24	7-1 Planned Project Assessments Table	7-1
25	7-2 Assessment Findings and Corrective Action Responses	7-1
26	7-3 Quality Assurance Management Reports	7-4
27	8-1 Project Documents and Records	8-5

DRAFT