quasar energy group DOVETAIL BIOENERGY ANAEROBIC DIGESTION FACILITY

February, 2014 1146 Herr Road Fairborn, Ohio 45324

PROJECT LOCATION



INDEX	
PAGE#	PAGE TITTLE
cs	COVER SHEET
G-1	PROCESS FLOW DIAGRAM EFFLUENT STORAGE TANK
G-2	PLANT SLUDGE HYDRAULIC PROCESS FLOW
SD-1	SITE DIMENSION PLAN
S-1	STRUCTURAL STORAGE TANK PLAN AND SECTION
S-2	STRUCTURAL TANK DETAILS
S-3	STRUCTURAL TANK DETAILS
1-1	EFFLUENT PUMPING
1-2	EFFLUENT STORAGE TANK



OWNER/ DEVELOPER

Dovetail Bioenergy 7624 Riverview Road Cleveland, OH 44131

SITE INFORMATION

Dovetail Bioenergy 1146 Herr Road Fairborn, Ohio 45324

PROFESSIONAL ENGINEER

Alan R. Johnson, P.E. Vice President, Project Management quasar energy group 5755 Granger Road, Suite 320 Cleveland, OH 44131

DESIGN ENGINEER

Randy A. Minor II
Design Engineer
quasar energy group
1363 Gerlaugh Drive
Wooster, OH 44691
Cell: (216)-386-7019

PROCESS ENGINEER

Ned Mast Vice President, Engineering quasar energy group 1363 Gerlaugh Drive Wooster, OH 44691


SITE ENGINEER


Stone Environmental 748-A Green Crest Drive, Westerville, OH 43081


TANK ENGINEER


Engineering Associate Inc. 1935 Eagle Pass Wooster, OH 44691











STRUCTURAL NOTES

DESIGN SPECIFICATIONS
STRUCTURAL CONCRETE DESIGN CONFORMS TO THE MOST RECENT EDITIONS OF
ACI PUBLICATIONS 318 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL
CONCRETE" AND 350 "CODE REQUIREMENTS FOR ENVIRONMENTAL ENGINEERING

€S-1

DESIGN STRENGTHS

CONCRETE fc' = 4,000 PSI (28 DAY COMPRESSIVE STRENGTH)

REINFORCING STEEL fy = 60,000 PSI A615 OR A996 GRADE 60 BARS

<u>DESIGN LOADING</u>
DIGESTER EFFLUENT LOADING (INSIDE): 65 PSF/FT
ALLOWABLE FOUNDATION BEARING CAPACITY: 3,000 PSF

CONCRETE CONSTRUCTION
ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL BE IN ACCORDANCE WITH ACI 301 AND 318 REQUIREMENTS. IN ADDITION TO ACI 301 AND 318, APPLICABLE DESIGN MIX AND PROPORTIONING REQUIREMENTS OF ODOT (OHIO DEPARTMENT OF TRANSPORATION) CONSTRUCTION AND MATERIAL SPECIFICATION FOR CONCRETE CLASS OCT CONTAINED IN 499 AND 511 SHALL APPLY.

ALL CONCRETE SURFACES EXPOSED TO AIR, UNLESS OTHERWISE NOTED IN SPECIFICATIONS, SHALL BE TREATED WITH AN APPROPRIATE CURING COMPOUND AS SOON AS CONCRETE FINISHING IS COMPLETED OR FORMS ARE REMOVED.

OUTSIDE CORNERS OF EXPOSED CONCRETE SHALL BE FINISHED WITH A $3/4\mbox{"}$ CHAMFER.

CONCRETE DELIVERED TO THE SITE SHOULD MEET TEMPERATURE REQUIREMENTS OF ASTM C94. CONCRETE SHOULD NOT BE PLACED UPON FROZEN SOILS OR SOILS WHICH CONTAIN FROZEN MATERIAL. CONCRETE SHOULD BE PROTECTED FROM FREEZING UNTIL THE NECESSARY STRENGTH IS ACHIEVED. FROST SHOULD NOT BE PERMITTED TO PENETRATE BELOW FOOTINGS BEARING ON FROST SUSCEPTIBLE SOIL SINCE SUCH FREEZING COULD HEAVE AND CRACK THE FOOTINGS

UNLESS NOTED OTHERWISE ON THE DRAWINGS, REINFORCING STEEL SPLICE LENGTHS SHALL BE AS FOLLOWS:

#5 BARS: 2'-0' #6 BARS: 2'-8'

#7 BARS: 3'-5

#8 BARS: 4'-0'

CONSTRUCTION JOINTS JOINT LOCATIONS SHALL BE AS SHOWN IN THE PLANS. NO HORIZONTAL JOINTS SHALL BE PERMITTED IN THE SLAB. APPROVAL OF THE ENGINEER MUST BE OBTAINED PRIOR TO ADDING ANY JOINTS NOT SHOWN IN THE PLANS.

CONCRETE POURS IN THE FOUNDATION SLAB AND WALLS SEPARATED BY CONSTRUCTION JOINTS SHOWN ON THE DRAWINGS SHALL BE ALTERNATELY PLACED SUCH THAT A MINIMUM OF 48 HOURS HAS PASSED FROM THE TIME OF THE FIRST POUR UNTIL THE TIME OF THE PLACEMENT OF THE ADJACENT SECOND POUR. THE PURPOSE OF THIS PLACEMENT RESTRICTION IS TO ALLOW SHRINKAGE THAT IS TYPICALLY PRESENT DURING THE INITIAL CURING PROCESS TO OCCUR BEFORE THE ADJACENT POUR IS PLACED, AND THEREBY REDUCING STREESES IN THE WALL CALLED BY SUBJECTED. STRESSES IN THE WALL CAUSED BY SHRINKAGE FORCES.

PROVIDE A ROUGHENED SURFACE AT CONSTRUCTION JOINT LOCATIONS BY EITHER ROUGHENING THE SURFACE IMMEDIATELY AFTER THE CONCRETE IS PLACED OR BY SANDBLASTING OR AIR—WATER CUTTING AFTER THE CONCRETE

WHERE REQUIRED, HOT APPLIED JOINT SEALER SHALL MEET THE REQUIREMENTS OF ASTM D 6690, TYPE II.


WHERE REQUIRED, COLD APPLIED JOINT SEALER SHALL BE COMPOSED OF A HOMOGENEOUS BLEND OF ASPHALT, RUBBER, INERT FILLER AND A SUITABLE SOLVENT OR SOLVENTS. THE MATERIAL SHALL BE CAPABLE OF BEING INSTALLED BY A HEAVY DUTY AIR OPERATED PUMP OR OTHER DEVICE CAPABLE OF CONTINUOUSLY FEEDING THE COMPOUND UNDER PRESSURE

GEOTECHNICAL REPORT REPARED BY PROFESSIONAL SERVICE INDUSTRIES, INC. DATED 4-24-2013. INTERPRETATION OF THE CONTENTS OF THE REPORT IS THE CONTRACTOR'S RESPONSIBILITY.

REMOVE ALL TOPSOIL AND ROOT ZONE FROM THE TANK AREA. EXCAVATE TO THE DEPTH SHOWN ON THE SITE PLAN BASED ON RECOMMENDATIONS IN THE GEOTECHNICAL REPORT. IT IS RECOMMENDED THAT THE SUBGRADE BE EVALUATED BY A GEOTECHNICAL ENGINEER TO ASSESS THE SUITABILITY OF THE SOIL LEFT IN PLACE PRIOR TO CONSTRUCTION OF THE TANK FOUNDATION. THE GEOTECHNICAL ENGINEER SHALL PERFORM TESTING TO VERIFY THAT THE ASSUMED ALLOWABLE BEARING CAPACITY LISTED UNDER "DESIGN LOADING"

BACKFILL OR FILL SHALL BE PLACED IN LIFTS AND COMPACTED IN ACCORDANCE WITH THE RECOMMENDATIONS CONTAINED IN THE GEOTECHNICAL REPORT.

A SAND OR FINE STONE CUSHION AT LEAST 3° IN THICKNESS SHALL BE PLACED UNDER THE TANK FOUNDATION SLAB PRIOR TO CONSTRUCTION OF THE TANK FOUNDATION.





1935 Eagle Pass

Wooster, Ohio 44691 ENGINEERING Phone: (330) 345-6556 ASSOCIATES Fax: (330) 345-8077

QUASAR ENERGY GROUP DIGESTER EFFLUENT STORAGE TANK

BDH

REP

STRUCTURAL STORAGE TANK PLAN AND SECTION

FAIRBORN, OH FACILITY

