To: Egan, Robert[egan.robert@epa.gov]

From: Hanson, Kristen

Sent: Thur 2/25/2016 6:12:15 PM

Subject: RE: Tower Standard Hydraulic Conductivity Testing

Hi Bob,

Do you know what Chris is referring to regarding my comments on slug tests.

Kristen

From: Saari, Christopher A - DNR [mailto:Christopher.Saari@wisconsin.gov]

Sent: Thursday, February 11, 2016 1:28 PM

To: Egan, Robert

Cc: Hanson, Kristen; Robinson, John H - DNR

Subject: RE: Tower Standard Hydraulic Conductivity Testing

Bob, I'll get you something when I receive it from REI. I think they were looking for feedback from EPA and LDF before finalizing, so I will pass on Kristen's comments re: slug tests.

I terms of previous testing, I found the attached in REI's May 1999 Phase II Site Investigation Report. Using the Hazen Method, they estimated hydraulic conductivity at their MW2 at 16.3 ft/day (5.76 x 10⁻³ cm/sec).

We are committed to service excellence.

Visit our survey at http://dnr.wi.gov/customersurvey to evaluate how I did.

Chris Saari

Phone: (715) 685-2920

Christopher.Saari@Wi.gov

From: Egan, Robert [mailto:egan.robert@epa.gov] Sent: Thursday, February 11, 2016 12:56 PM To: Saari, Christopher A - DNR Cc: KHanson@ldftribe.com; Robinson, John H - DNR Subject: RE: Tower Standard Hydraulic Conductivity Testing Chris, Please send the work plan (or analogous document) to me and to LDF when it becomes available. We should have comments for you soon. Do you know whether any conductivity values are in the files from the work performed in the 1990s/2000s? They would be good for comparison to new data. Thank you. Bob Egan Corrective Action Manager **Underground Storage Tanks Section** RCRA Branch EPA Region 5 (312) 886-6212 (312) 692-2911 (fax)

From: Saari, Christopher A - DNR [mailto:Christopher.Saari@wisconsin.gov]

Sent: Thursday, February 11, 2016 8:55 AM

EPA-R5-2017-010506 0001560

To: Egan, Robert < <u>egan.robert@epa.gov</u>>

Cc: Robinson, John H - DNR < John.Robinson@wisconsin.gov >; Fassbender, Judy L - DNR

<<u>Judy.Fassbender@wisconsin.gov</u>>

Subject: Tower Standard Hydraulic Conductivity Testing

Hi Bob:

I received a cost proposal from REI to perform the hydraulic conductivity measurements that we discussed in Madison last week, and I wanted to run the concept by you to make sure it will meet the needs of EPA and LDF. In a nutshell, REI has proposed:

- Complete hydraulic conductivity calculations at all 17 wells (assume 2 hours per test)
- Data interpretation: download well specific data and conduct hydraulic conductivity calculation. Data to be presented will include copy of data download graph and conductivity calculation
- Datalogger charge: REI will be using InSitu Level Troll 500 loggers. The loggers will be atmospherically vented and will automatically compensate for barometric pressure fluctuations. REI will also use a water level indicator to collect manual measurements to ensure data is calibrated.

REI indicated that typically they run slug tests (introduce stainless slug and allow water levels to stabilize and pull the slug and measure recovery). Per Dave Larsen, some of the wells probably will recover too soon for this method and Larsen want to make sure that all parties are on board with these methods.

I should be available today if you want to discuss this, but I'll be out tomorrow. Otherwise next week would be fine, too. Thanks.

We are committed to service excellence.

Visit our survey at http://dnr.wi.gov/customersurvey to evaluate how I did.

Chris Saari

Hydrogeologist – Remediation and Redevelopment Program Wisconsin Department of Natural Resources

Phone: (715) 685-2920 Fax: (715) 685-2909 Christopher.Saari@Wi.gov

