Larsen[dlarsen@reiengineering.com] From: Egan, Robert Sent: Thur 6/16/2016 12:02:45 PM Subject: Details on wells for Tower Standard Chris and Dave, Thank you for looking into the possibility of installing the 2 wells next month. My task order has been moving more slowly than I expected and we don't expect to be able to get everything in place and a driller scheduled by the week of July 18, and I realize it may be very difficult for Dave to do the same at this stage. The two locations are at MW-16 screened just above bedrock, assumed to be a total depth of 60 feet. The other is at the MW-21 location, screened at the 1550 elevation, about 25 feet in depth. I planned for 5 foot screens, no plans for sampling soils. If water is used during drilling, as expected, we would like to have at least an equal amount removed during development. Having the 3 wells at these locations will help USGS in its modeling effort. I am still assuming we can contract the sampling, especially since LDF would like some additional parameters to compare to the lake bed samples. We can also have the surveying done, and we will recheck the elevations of the well nest location where we noticed the bentonite had swelled over the well cap. Thanks again. I much appreciate your efforts to schedule this work. Bob Bob Egan

Christopher A Saari[Christopher.Saari@Wisconsin.gov]; Dave

To:

Corrective Action Manager

Underground Storage Tanks Section

RCRA Branch

EPA Region 5

(312) 886-6212

(312) 692-2911 (fax)