VOC Emissions and TTE Evaluation Test Protocol

Container Life Cycle Management LLC
Temporary Total Enclosure (TTE),
Scrubber Inlet and Outlet,
Paint Bake-Off Oven Stack, and
Overspray Filter Exhaust
3950 South Pennsylvania Avenue
St. Francis, Wisconsin 53235
Protocol No. M173801

VOC Emissions and TTE Evaluation Test Protocol

Container Life Cycle Management LLC
Temporary Total Enclosure (TTE),
Scrubber Inlet and Outlet,
Paint Bake-Off Oven Stack, and Overspray Filter Exhaust
3950 South Pennsylvania Avenue
St. Francis, Wisconsin 53235

Protocol Submittal Date July 21, 2017 revised August 4, 2017

Submitted By

Chris Jensen Senior Project Manager (630) 993-2100 Phone cjensen@mp-mail.com, Email

Prepared for Container Life Cycle Management LLC

© Copyright 2017 All rights reserved in Mostardi Platt

Protocol No. M173801

TABLE OF CONTENTS

| 1.0 INTRODUCTION | 1 |
|--|-------------|
| 2.0 PROCESS DESCRIPTION | |
| 3.0 TEST REQUIREMENTS | |
| 4.0 SPECIFIC TEST PROCEDURES | |
| 5.0 TEST PROGRAM SCHEDULE | |
| 6.0 PROJECT PERSONNEL | |
| 8.0 TEST PROCEDURES Volumetric Flowrate Determination Oxygen (O ₂)/Carbon Dioxide (CO ₂) Determination Moisture (H ₂ O) Determination Methane (CH ₄) Determination | 5 5 6 |
| Total Organic Concentration Determination Enclosure Evaluation Determination Natural Draft Openings (NDO) Distance to Emitting Point Exhaust Point Distance from NDO Total NDO Area Velocity of Air Flow through NDOs | 7 7 7 |
| Direction of Air Flow through the NDO. | 7 |
| 9.0 QUALITY ASSURANCE PROCEDURES | ٤٤ |

GENERAL INFORMATION APPENDED:

Sample Point Location Diagrams
Test Train Diagrams
Data Sheets
Calculation and Nomenclature Sheets
Calibration Data

1.0 INTRODUCTION

The test protocol is an emission test program to determine the volatile organic compounds (VOC) emission rate from the Container Life Cycle Management LLC facility in St. Francis, Wisconsin while all connected processes are being operated in a manner that is consistent with normal operations.

As discussed with representatives of USEPA Region 5, all testing will be performed as described in the Code of Federal Regulations, Title 40, Part 60, Appendix A (40CFR60), Methods 1, 2, 3, 18 (methane only, if applicable), 25A, and Methods 204 and 204F, 40CFR, Part 51, Appendix M, and ASTM E337-02 and the latest revisions thereof. Where applicable, the Quality Assurance Handbook for Air Pollution Measurement Systems, Volume III, Stationary Source Specific Methods, USEPA 600/4-77-027b will be used to determine the precise procedures.

Testing will be performed simultaneously at the inlet and outlet of the wet scrubber/mist eliminator (C10), Paint Bake-Off Oven Stack, and Overspray Filter Exhaust to determine of total VOC emissions to atmosphere as well as to determine the effectiveness of the scrubber as a VOC removal device.

| | Project Contact Information | |
|--------------------------|-------------------------------------|--------------------------|
| Location | Address | Contact |
| Technical Representative | 366 Greif Parkway | Mr. Geoff Westphal |
| · | Delaware, Ohio 43015 | EHS Manager-N.A. |
| | | Work: 740-657-6616 |
| | | geoff.westphal@greif.com |
| Facility Representative | Container Life Cycle Management LLC | Mr. Mark Furgason |
| | 3950 South Pennsylvania Avenue | Plant Manager |
| | St. Francis, Wisconsin 53235 | Work: 414-483-8801 |
| | | mfurgason@masdinc.com |
| Testing Company | Mostardi Platt | Chris Jensen |
| Representative | 888 Industrial Drive | Senior Project Manager |
| , | Elmhurst, Illinois 60126 | (630) 993-2100 (phone) |
| | | cjensen@mp-mail.com |

2.0 PROCESS DESCRIPTION

The CLCM facility located at 3950 South Pennsylvania Avenue in St. Francis, Wisconsin reconditions both steel and plastic drums. USEPA Region 5 has requested certain information related to process conditions on the days of testing as follows:

- a. VOC emissions should be influenced most heavily by two factors drum processing rate and the characteristics of the residual material in the drums. During the actual test runs the facility will endeavor to maximize throughput of drums on each of the two lines (poly and steel).Based on historical operations maximum expected throughput will be approximately 220 drums per hour (steel drums) and 100 drums per hour (poly). The increased scrutiny and recordkeeping during testing could slow the process rates.
- b. Because the St. Francis facility does not receive a steady and predictable supply of drums, for purposes of the September 2017 testing, the facility will pre-stage as many chemical drums as possible. The testing will likely be conducted across two days to avoid running out of drums during a test run. Each test run (three total) will be one hour

- in duration and the chemical drums will be staged ahead of each run. Before, after and between runs the facility may revert to non-chemical drums to maintain production.
- c. A sample of the scrubber water taken during each test run and distilled to separate the volatile fraction. The distillate will be used to prepare a known standard for analysis by flame ionization detector (FID), calibrated against propane, to determine the response factor (RF) of the FID to the liquid inputs used and sampled during testing. Total hydrocarbon emissions will be determined in accordance with USEPA Method 25A, 40CFR60 with VOC emissions determined as ppm propane. Method 204 F is used for determining the input of VOCs as a segment of liquid/gas protocols for determining VOC. The amount of VOCs introduced to the process (L) is the sum of the weight (W) of each VOC containing liquid used and its VOC content (V), corrected for RF. The Scrubber water samples will be analyzed for Response Factor determinations by USEPA Method 204F, 40CFR51, Appendix M.
- d. During testing drums entering the process will be counted and photographed. The counts will be used to verify line speed and the photographs will be used – after the testing – to verify the nature of the drums original contents or origin. The processing rate for each test run and a summary of the drum information for each test run will be provided in the test report.
- e. Drums shipped to the CLCM facilities are accompanied by "RCRA Empty" certifications from the suppliers. For the drums shipped directly to the St. Francis facility the certification sheets will be available on site. The small percentage of drums which are initially shipped to the Oak Creek facility and evaluated may come from multiple inbound loads where multiple certifications apply. For the drums intended for processing during testing, copies of all the applicable certifications will accompany the load. EPA is not requesting copies of these certifications be included in the stack test report the copies will be available for inspection during testing.

3.0 TEST REQUIREMENTS

The following table presents a list of the pollutants to be tested at each emission source and the applicable rules or regulations for each emission test:

| Test Locations | Test Parameter | Method/Regulation Citation |
|--------------------------|----------------|--|
| Scrubber Inlet | | |
| Scrubber Outlet | | USEPA Methods 1, 2, 3, 18 (methane only, if applicable), and |
| Paint Bake-Off Oven | VOC | 25A, 40CFR60, Appendix A; and ASTM Method E37-02 |
| Stack | | |
| Overspray Filter Exhaust | | |
| Building | TTE | USEPA Method 204, 40CFR51, Appendix M |

4.0 SPECIFIC TEST PROCEDURES

Detailed test procedures are appended. Three complete test runs will be performed for each parameter in accordance with the following USEPA methods.

- 1. Volumetric flow will be determined utilizing USEPA Methods 1 and 2, 40CFR60 in conjunction with each emission test. A pretest and post-test volumetric flow will be performed and averaged for each VOC gaseous test run.
- 2. Oxygen (O_2) and carbon dioxide (CO_2) content of the gases will be determined by USEPA Method 3, 40CFR60 during each test run.
- 3. Moisture content of the gases will be determined using ASTM E337-02 during each volumetric flow test run.
- 4. Total hydrocarbon emissions will be determined in accordance with USEPA Method 25A, 40CFR60. Each test will be one hour long for VOC emissions with the emissions determined as ppm propane.
- 5. The Building Temporary Building Enclosure (TTE) will be evaluated to verify that it meets the criteria of USEPA Method 204, 40CFR51, Appendix M. The Scrubber Outlet, Paint Bake-Off Oven Stack, and the Overspray Filter Exhaust will be the only Building exhausts.
- 6. The Scrubber water samples will be analyzed for Response Factor determinations by USEPA Method 204F, 40CFR51, Appendix M.
- 7. Plant VOC emission rates will be determined from the combined Scrubber Outlet, Paint Bake-Off Oven exhaust, and Overspray Filter Exhaust measurements. Separately, the Scrubber will be evaluated for VOC control efficiency.
- 8. Where applicable, the *Quality Assurance Handbook for Air Pollution Measurement Systems*, Volume III, Stationary Source Specific Methods, USEPA 600/4-77-027b is used to determine the precise procedures.

5.0 TEST PROGRAM SCHEDULE

Refer to plant submittals for specific dates.

| Day | Task | On-Site Hours |
|-----|---|---------------|
| 1 | Travel to plant, set up equipment, and evaluate TTE | 8 |
| 2 | Perform VOC emissions tests | 8 |

All project days are considered weekdays and are scheduled between the hours of 7:00 a.m. and 6:00 p.m., unless otherwise stated.

6.0 PROJECT PERSONNEL

- 1 Senior Project Manager
- 1 Test Supervisor
- 2 Test Engineers
- 2 Test Technicians

7.0 PLANT REQUIREMENTS

Mostardi Platt must be supplied with the following items in order to complete this test program:

- 1. Safe access to test positions.
- 2. A minimum of two separate 110 V, 15 A circuits at each test location.
- 3. Two-inch test ports cleaned and loose prior to arrival of test crew.
- 4. Any scaffolding required to perform the tests.
- 5. Sufficient lighting at the test site.
- 6. Safety belts, if required.
- 7. Plant or pollution control equipment-operating data, if required for report.
- 8. Washroom facilities for use by members of the test crew.
- 9. Steady load during test period.
- 10. Communication between the test location and plant operations.
- 11. Parking location to place Mostardi Platt mobile trailer within 200 feet of sampling locations with access to multiple 110 V, 15 amp, 60-cycle, 220 V, 50 amp, 60-cycle circuits, or a 480 V welding receptacle.
- 12. Pre- and post-test scrubber water and coating samples and exact usage during each test run for emissions determinations.

8.0 TEST PROCEDURES

All testing, sampling, analytical, and calibration procedures used for this test program will be performed as described in the Title 40, *Code of Federal Regulations*, Part 60, Appendix A (40CFR60), Methods 1, 2, 3, 18 (methane only, if applicable), 25A, and, 40CFR51, Appendix M, Method 204, and ASTM E337-02 and the latest revisions thereof. Where applicable, the *Quality Assurance Handbook for Air Pollution Measurement Systems*, Volume III, Stationary Source

Specific Methods, United States Environmental Protection Agency (USEPA) 600/R-94/038c, September 1994 was used to supplement procedures.

Volumetric Flowrate Determination

In order to determine emission rates on a lb/hr basis, the gas velocities and volumetric flowrates are determined using reference Method 2.

Velocity pressures are determined by traversing the test locations with S-type pitot tubes. Temperatures are measured using a K-type thermocouple with a calibrated digital temperature indicator. The molecular weight and moisture content of the gases are determined to permit the calculation of the volumetric flowrate. Sampling points utilized are determined using Method 1, 40CFR60.

Oxygen (O₂)/Carbon Dioxide (CO₂) Determination

 O_2 and CO_2 gas content are determined at the test locations in accordance with Method 3, 40CFR60. This method collects samples in a grab or integrated manner and analyzes the samples using a Fyrite gas analyzer. Several passes of the gas are made during each run to ensure a stable reading. Mandatory leak checks are performed prior to and following each use. Chemicals are changed frequently and inspected for reactivity prior to each use.

Moisture (H₂O) Determination

Determining the moisture content in the gas stream is necessary to calculate the stack gas volumetric air flow on a dry basis and the emission rate in lbs/hr. For this purpose, Mostardi Platt will use American Standard Testing Method (ASTM) Method E337-02.

American Standard Testing Method (ASTM) Method E337-02 reapproved 2002, wet bulb/dry bulb measurements will be made at the test locations during each VOC sampling run and the water vapor content is calculated as follows:

Bws =
$$e' - AP(t - t')$$

where: P

e' = saturated vapor pressure of water, in. Hg, at the wet bulb temperature, t'

 $A = 3.67 \times 10^{-4} [1 + 0.00064(t' - 32)]$

P = absolute pressure, in. Hg, in duct

t = dry bulb temperature, °F

t' = wet bulb temperature. °F

Methane (CH₄) Determination

The Method 18, 40CFR60, sampling and measurement system meets the requirements for stack sampling of gaseous organic compounds set forth by the United States Environmental Protection Agency (USEPA). In particular, it meets the requirements of USEPA Reference Method 18, "Determination of Gaseous Organic Compound Emissions by Gas Chromatography," 40CFR60, Appendix A. This method applies to the analysis of approximately 90% of the total gaseous organics emitted from an industrial source. The major organic components of a gas mixture are separated by gas chromatography, and methane is quantified by a flame ionization detector.

The gas chromatograph to be used during this program is a VIG 200 with a flame ionization detector. This instrument is calibrated using ultra-zero air, methane (CH₄) in nitrogen certified standards. The calibrations are performed before and after sampling with calibration checks performed each day. Sample times and locations are logged on integrator printouts.

Total Organic Concentration Determination

The Method 25A sampling and measurement system meets the requirements for stack sampling of volatile organic compounds (VOCs) set forth by the United States Environmental Protection Agency (USEPA). In particular, it meets the requirements of USEPA Reference Method 25A, "Determination of Total Gaseous Organic Concentration Using a Flame Ionization Analyzer," 40CFR60, Appendix A. This method applies to the measurement of total gaseous organic concentration of hydrocarbons. With this method, gas samples are extracted from the sample locations through heated Teflon sample lines to the analyzers.

The flame ionization detectors (FIDs) to be used during this program are VIG High-Temperature Total Hydrocarbon Analyzers. They are highly sensitive FIDs that provide a direct reading of total organic vapor concentrations with linear ranges of 0-10, 100, 1000, and 10,000 ppm by volume. The instruments are calibrated using ultra-zero air and propane in air EPA Protocol standards. The calibrations are performed before and after sampling with calibration checks performed between each test run. Sample times and locations are logged simultaneously on data loggers.

Calculations are performed by computer or by hand. An explanation of the nomenclature and calculations along with the complete test results is included in the appendix. Also appended are calibration data and copies of the raw field data sheets.

Enclosure Evaluation Determination

A 100% Temporary Building Enclosure (TBE) must meet five (5) specific engineering criteria. The criteria are described in USEPA Method 204, 40CFR51, Appendix M. A summary of these items and the evaluation technique used are described below.

Natural Draft Openings (NDO) Distance to Emitting Point

Criteria: All NDOs such as open doorways, windows, etc. must be at least four equivalent

NDO diameters from the nearest potential VOC emission point.

Technique: The dimensions of all NDOs and potential emission points are measured. The

calculated NDO equivalent diameters are compared to the emission point

distances measured.

Exhaust Point Distance from NDO

Criteria: Any exhaust point from the enclosure must be at least four equivalent hood or

duct diameters from all NDOs.

Technique: The dimensions of all NDOs and potential emission points are measured. The

calculated NDO equivalent diameters are compared to the exhaust point

distances measured.

Total NDO Area

Criteria: The area of all NDOs divided by the total area of all walls, floor and ceilings in the

enclosure (called the "NEAR" ratio in the procedure) must not exceed 0.05.

Technique: Actual measurements are used to determine a composite surface area of the

room and the NDOs and the NEAR ratio is determined.

Velocity of Air Flow through NDOs

<u>Criteria</u>: The calculated face velocity through the NDOs must be greater than 200 fpm.

This is defined as the total exhaust volume (in scfm), less make up air, divided by

the area of all NDOs (in square feet).

Technique: The composite area of the NDOs (as determined above) is used along with the

measured net exhaust volume, as determined by USEPA Method 2, 40CFR60, Appendix A, of the enclosure to calculate the face velocity or alternately, the static pressure of the enclosure is measured to determine if it meets the ≥ 0.007

inches H₂O criteria.

Direction of Air Flow through the NDO

Criteria: The direction of air flow through all NDOs must be into the enclosure.

Technique: Smoke tubes or paper streamers are used at each NDO to measure the direction

of the air flow. A record of this data will be included on the scale drawing

9.0 QUALITY ASSURANCE PROCEDURES

Mostardi Platt recognizes the previously described reference methods to be very techniqueoriented and attempts to minimize all factors which can increase error by implementing its Quality Assurance Program into every segment of its testing activities.


Shelf life of chemical reagents prepared at the Mostardi Platt laboratory or at the jobsite does not exceed those specified in the above mentioned methods. In addition, those reagents having a shelf life of one week are prepared daily at the jobsite. When on-site analyses are required, the same person performing the analysis performs all reagent standardization daily.

Dry and wet test meters are calibrated according to methods described in the *Quality Assurance Handbook for Air Pollution Measurement Systems*, Sections 3.3.2, 3.4.2 and 3.5.2. Percent error for the wet test meter according to the methods is less than the allowable error of 1.0%. The dry test meters measure the test sample volumes to within 2% at the flowrate and conditions encountered during sampling.

Calibration gases are EPA Protocol gases.

APPENDIX

EQUAL AREA TRAVERSE FOR ROUND DUCTS



Container Life Cycle Management LLC St. Francis, Wisconsin Job:

Date: TBD

Test Locations: Scrubber Inlet


Scrubber Outlet

Paint Bake Off Oven Exhaust Overspray Filter Exhaust


Stack Diameter: **TBD**

Stack Area: TBD

USEPA Method 2 - S-Type Pitot Tube Diagram




USEPA Method 3 - Integrated Oxygen/Carbon Dioxide Sample Train Diagram utilizing Fyrite Gas Analyzer




Moisture Determination


ASTM Method E337-02, Reapproved 2002



USEPA Method 25A -Total Gaseous Organic Compound Sample Train



USEPA Method 18 - Methane Using an Integrated Bag Sample



| Volumetric F | low Rate | Determination | r Field Data Sheet | | |
|--|----------------------|--|---|----------------|-----------|
| Project Number: | | | Date: | | |
| Client: | | | Test Number: | | |
| Test Location: | | | Start Time: | | |
| Source Condition: | | | End Time: | | |
| Test Engineer: | | | Test Tech: | , | , |
| Duct Diamet Flue Area Port Length P _{bar} <i>"</i> | | ft ft ² CO ₂ % | Upstream Disturbance, Diameters Downstream Disturbance, Diameter Pitot ID Pitot Coefficie Wet Bulb Temp | | — Leak |
| Checks Static Static | ″H₂O _ ″Hg 'Hg | O ₂ % N ₂ % Meter No | Dry Bulb Temp B _{ws} | Pre Pos | |

| Port- Point # | ΔΡ | Temp. °F | $\sqrt{\Delta P}$ | Null Point Angle, Degrees | Port- Point # | ΔΡ | Temp. °F | $\sqrt{\Delta P}$ | Null Point Angle, Degrees |
|------------------|----|-------------|-------------------|------------------------------------|------------------|----|-------------|-------------------|------------------------------------|
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Average | | | | | | | | | |

Method 25A Field Data Sheet

| Project: | Operator: | | |
|-----------|-----------|----|--|
| Client: | Source: | 1. | |
| Location: | | 2. | |
| Date: | | 3. | |
| | | | |

| Parameters | Location 1 | Location 2 | Location 3 |
|-----------------------|------------|------------|------------|
| Test 1 | | | |
| Time | | | |
| VOC ppmv as | | | |
| Air flow, scfm | | | |
| VOC lbs/hr as | | | |
| Removal Efficiency, % | | | |
| | | | |
| Test 2 | | | |
| Time | | | |
| VOC ppmv as | | | |
| Air flow, scfm | | | |
| VOC lbs/hr as | | | |
| Removal Efficiency, % | | | |
| | | | |
| Test 3 | | | |
| Time | | | |
| VOC ppmv as | | | |
| Air flow, scfm | | | |
| VOC lbs/hr as | | | |
| Removal Efficiency, % | | | |
| | | | |

METHOD 204 ENCLOSURE DATA SHEET

| roject: _ ocation: ate: | | | | \ | | ission po | oints on | cts, NDOs accompar | | | |
|-------------------------------|-----------------------------------|------------------------|-----------------|--------------|---------------------|---------------|----------|-----------------------|----------|--------|----------------|
| nclosure De ontrol Devic | | | | | Proce | ess(es)E | nclosed | d: | | | |
| DO to VC | OC Emission P | 'oint | | | | | | | | | |
| | | | | | | | | Distanc | es | | |
| NDO | Dimension | ns Area | Equiva Diame | lent eter | VO Emiss Poir | sion | Minir | mum | Actı | ual | Pass/ Fail? |
| | | | <u> </u> | | | | | | | | |
| | | _ | | | | | | + | | | |
| | + | | | | | | | | | | |
| | | | | | | | | | | | |
| Minimum 2 | ivalent diamete Allowed Distan | nce = 4 × Equ | • | iameter | r (NDC |)) | | | | | |
| | 100000 | | | | | | | C | istand | es | |
| Exhaust Point | Dimensions | Equivalent Diameter | NDO | Dimen | nsions | Equiv Diam | | Minimu | ım | Actual | Pass/ Fail? |
| | | | | | | | | | | | |
| | | <u> </u> | | | | | | | \dashv | | |
| | | | | | | | | | + | | |
| | | | | | | | | | _ | | |

Equivalent diameter = $\begin{bmatrix} 4 \times \text{area} \\ \pi \end{bmatrix}^{0.5}$

Minimum Allowed Distance = 4 × Equivalent Diameter (NDO or Exhaust Point)

METHOD 204 ENCLOSURE DATA SHEET (cont.)

Near Ratio [NDO Area/Total Enclosure Area]

| NDO | Surface Area (FT²) | Wall, Ceiling, or Floor Section | Surface Area (FT²) | |
|-------------|-----------------------|------------------------------------|-----------------------|----------------|
| | | | | |
| | | | | NEAR ratio: |
| | | | | |
| | | | | NDOArea = |
| | | | | EnclosureA rea |
| | | | | |
| | | | | Pass/Fail? |
| TOTAL NDO A | REA= | TOTAL ENCLOSURE | AREA= | |

Velocity of Air through NDO (Volumetric Flow Method)

| | Exhausted | Air | Make | Up Air | | |
|------------------|-----------|-----------------------|------------------|--------|--|-----|
| Exhaust Point | SCFM | Controlled? (Y/N?) | Make up point | SCFM | | |
| | | | | | total NDO area ft² | |
| | | | | | Exhaust sofm - 1 make up sofm = NDO area (ft²) | fpm |
| | | | | | fpm should be ≥ 200 | |
| | | | | | pass/fail? | |
| TOTAL | | | TOTAL | | | |

| IOTAL | IOIAL |
|---|-------------------------|
| Or, Velocity of Air through NDO (Pressu | re Differential Method) |
| Pressure Differential across the enclosu Pressure difference > 0.007 inches H ₂ O pass/fail? | |

METHOD 204 ENCLOSURE DATA SHEET (cont.)

Direction of Air through NDO

Checked by Smoke Tubes

| | Normally | | Direction of Air Flow | | | | | Direction of Air Flow (One Hour Verification) | | | | | |
|-----|----------|--------|-----------------------|---------------------|---------|--|-----------------|--|-----------------|-----------------|-----------------|-----------------|-----------------|
| NDO | | | | | | NDO | Initial: | 10 min: | 20 min: | 30 min: | 40 min: | 50 min: | 60 min: |
| No. | Open | Closed | Into Enclosure | Out of Enclosure | Swirled | Required to be Normally Closed? | Actual Time: | Actual Time: | Actual Time: | Actual Time: | Actual Time: | Actual Time: | Actual Time: |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | _ | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

^{*}Check to verify that airflow was checked at top, bottom, middle, and both sides of enclosure.

Status of doors and windows

| Are all access doors and windows whose | e areas are not included a | s NDOs closed during | normal operation? |
|--|----------------------------|----------------------|-------------------|
| □ Yes □ No | | | |

Capture of VOC Emissions

| Does all exhaust ductwork go | o control (for PTE) | or to a point where it | can be measured (fo | or TTE). |
|------------------------------|---------------------|------------------------|---------------------|----------|
| □ Yes □ No | | | | |

MOSTARDI PLATT

Volumetric Air Flow Calculations (Wet Bulb/ Dry Bulb)

$$Bws = \frac{\Box e' - AP(t - t')\Box}{P}$$

e' = saturated vapor presssure of water, in. Hg,

at the wet bulb temperature, t

$$A = 3.67 \times 10^{-4} \left[1 + 0.00064 (t' - 32) \right]$$

P = pressure, inches mercury, in the duct

 $t = dry bulb temperature, ^{\sqcap}F$

 $t' = wet bulb temperature, ^F$

Bws = water vapor in gas stream proportion

by volume

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + [0.28 \times (100 - \%CO_2 - \%O_2)]$$

$$MS = Md \times (1 - Bws) + (18 \times Bws)$$

$$V_S = \sqrt{\frac{(T_S + 460)}{M_S \times P_S}} \times \sqrt{DP} \times Cp \times 85.49$$

 $Acfm = Vs \times Area (of stack or duct) \times 60$

Dscfm = Acfm × 17.647 ×
$$\Box$$
 Ps \Box × (1 - Bws)

$$Scfm = Acfm \times 17.647 \times \frac{\square}{\cdot (460 + Ts)} \frac{Ps}{\square}$$

$$Scfh = Scfm \times 60 \frac{min}{hr}$$

scfm = standard cubic feet per minute Ms = molecular weight of gas (lb/lb mole) scfh = standard cubic feet per hour Md = dry molecular weight of gas

(lb/lb mole)

MOSTARDI PLATT

ppmv to lb/hr Conversion Calculations

1.
$$ppm SO_{2} \times 1.660 \times 10^{-7} = \frac{lbs/SO_{2}}{scf}$$
$$\frac{lbs SO_{2}}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs SO_{2}}{hr}$$

2. ppm NO_x × 1.194 × 10⁻⁷ =
$$\frac{lbs/NO_x}{scf}$$

$$\frac{lbs NO_x}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs NO_x}{hr}$$

3. ppm CO × 7.266 ×
$$10^{-8} = \frac{\text{lbs/CO}}{\text{scf}}$$

$$\frac{\text{lbs CO}}{\text{scf}} \times \frac{\text{scf}}{\text{min}} \times \frac{60 \text{ min}}{\text{hr}} = \frac{\text{lbs CO}}{\text{hr}}$$

4.
$$\operatorname{ppm} C_{3}H_{8} \times 1.142 \times 10^{-7} = \frac{\operatorname{lbs}C_{3}H_{8}}{\operatorname{scf}}$$
$$\frac{\operatorname{lbs} C_{3}H_{8}}{\operatorname{scf}} \times \frac{\operatorname{scf}}{\min} \times \frac{60 \min}{\operatorname{hr}} = \frac{\operatorname{lbs} C_{3}H_{8}}{\operatorname{hr}}$$

5.
$$ppm CH_4 \times 4.164 \times 10^{-8} = \frac{lbsCH_4}{scf}$$
$$\frac{lbs CH_4}{scf} \times \frac{scf}{min} \times \frac{60 min}{hr} = \frac{lbs CH_4}{hr}$$

MOSTARDI PLATT

Procedures for Calibration

Temperature Sensing Devices


The potentiometer and thermocouples are calibrated utilizing a NBS traceable millivolt source.


Pitot Tubes


The pitot tubes utilized during this test program are manufactured according to the specification described and illustrated in the *Code of Federal Regulations*, Title 40, Part 60, Appendix A, Methods 1 and 2. The pitot tubes comply with the alignment specifications in Method 2, Section 4; and the pitot tube assemblies are in compliance with specifications in the same section.


S TYPE PITOT TUBE INSPECTION FORM


 Pitot Tube Nc
 1
 Date:
 10/10/2011
 Inspectors Name:
 DTEM



















Pitot tube assembly level? ___x__yes ___

Pitot tube openings damaged? ______yes (explain below) ____x __no

$$a_1 = 1$$
 ° (<10°), $a_2 = 1$ ° (<10°)

$$b_1 = 0$$
 ° (<5°), $b_2 = 2$ ° (<5°)

$$z = A \sin g = \frac{0.008 \text{ (in.); (<0.125 in.)}}{2.008 \text{ (in.); (<0.125 in.)}}$$

$$w = A \sin q = \frac{0.025}{(in.)}$$
 (<0.03125 in.)

Calibration required? yes x no

Stack Temperature Sensor Calibration

Meter Box #: CM1 Name: BWH

Ambient Temperature: 59 °F Date: December 28, 2011

Calibrator Model # : CL23A

Serial # : T-276953

Date Of Certification: January 11, 2011

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

| Reference | Test | |
|-------------------|-------------------|--------------|
| Source | Thermometer | Temperature |
| Temperature (° F) | Temperature (° F) | Difference % |
| 0 | 0 | 0.0 |
| 250 | 249 | 0.0 |
| 600 | 599 | 0.0 |
| 1200 | 1201 | 0.0 |

(Ref. Temp., °F + 460) - (Test Them. Temp., °F + 460) * $_{100} <= 1.5 \%$ Ref. Temp., °F + 460

Method 25A Calibration Summary

| Project: | Date: | |
|-----------|-----------------|--|
| Client: | Operator: | |
| Location: | Analyzer ID: | |
| | Analyzer Range: | |
| | | |

| Cal Run | Cal Level | Test Location | Cylinder ID Serial Number | Cal Gas Type | Cal Time | Expected Cal Value | Actual Response | Difference (% of cal value) | Drift (% of span) | Cylinder Pressure |
|-------------|--------------|------------------|---------------------------------|--------------------|-------------|-----------------------|--------------------|-----------------------------------|-------------------------|----------------------|
| Pre 1 | Zero | | | | | | | | N/A | |
| | Low | | | | | | | | N/A | |
| | Mid | | | | | | | | N/A | |
| | High | | | | | | | | N/A | |
| | Zero | | | | | | | | | |
| Post | Low | | | | | | | | | |
| 1/ Pre 2 | Mid | | | | | | | | | |
| | High | | | | | | | | | |
| | Zero | | | | | | | | | |
| Post | Low | | | | | | | | | |
| 2/ Pre 3 | Mid | | | | | | | | | |
| | High | | | | | | | | | |
| | Zero | | | | | | | | | |
| Post 3 | Low | | | | | | | | | |
| | Mid | | | | | | | | | |
| | High | | | | | | | | | |
| | Zero | | | | | | | | | |
| | Low | | | | | | | | | |
| | Mid | | | | | | | | | |
| | High | | | | | | | | | |
| | Zero | | | | | | | | | |
| | Low | | | | | | | | | |
| | Mid | | | | | | | | | |
| | High | | | | | | | | | |