



Anticipated elevation with current FS remedy alternative 2B

- 479,000 CY (plus 20% given the in-place volume estimate) over approximately 35 acres (not sure how the estimate was built) -- (11 ft waste plus 4 ft cover) = 15 ft height
- Landfill top elevation = 817 (subgrade elevation) + 15 = **832 ft**
- We should be able to create a "flat top" surface here as well

FIGURE X
Existing Elevation Conceptual Site Model
Allied Paper OU-1
Kalamazoo River Superfund Site
Kalamazoo, Michigan