TABLE 7

Detailed Cost Estimate of Selected Remedy, Alternative 2D

Allied Paper, Inc./Portage Creek/Kalamazoo River Superfund Site

| No.<br>. CAPI |   | Estimated       |              | (Labor and                              |                      |
|---------------|---|-----------------|--------------|---|----------------------|
|               | Description   | Quantity        | Unit         | Materials)                              | Estimated Cost       |
|               | ITAL COSTS  | Quartery        |              |   | Estimated cost       |
| ite Pr        | reparation  |                 |              |   |                      |
| 1             | Pre-construction Field Survey                                     | 1               | LS           | \$5,300                                 | \$5,300              |
| 2             | Air Monitoring Program  | 420             | DAY          | \$1,600                                 | \$672,000            |
| 3             | Temporary Fencing   | 1               | LS           | \$16,000                                | \$16,000             |
| 4             | Decontamination Area  | 1               | EA           | \$37,000                                | \$37,000             |
| 5             | Temporary Construction Access Roads                               | 1               | LS           | \$85,000                                | \$85,000             |
| 6             | Clearing & Grubbing   | 20              | AC           | \$13,000                                | \$260,000            |
| _             | Temporary Steel Sheeting (Drive, Extract and Salvage: Means 31 41 |                 |              | <b>,</b> ,                              | ,,                   |
| 7             | 16.10 0100)   | 564             | TON          | \$2,200                                 | \$1,240,800          |
| 8             | Utility Protection / Relocation                                   | 1               | LS           | \$106,000                               | \$106,000            |
| 9             | Temporary Stormwater Management and Erosion and Sediment          | 1               | LS           | \$265,000                               | \$265,000            |
| 10            | Well Abandonment  | 100             | EA           | \$640                                   | \$64,000             |
|               |   |                 | Site Prepa   | ration Subtotal:                        | \$2,751,10           |
| xcava         | ation and Consolidation   |                 |              |   |                      |
| 11            | Survey  | 10              | WK           | \$5,300                                 | \$53,000             |
| 12            | Soil Removal and Consolidation                                    | 920000          | CY           | \$13                                    | \$12,190,000         |
| 12a           | Construction Water Treatment System                               | 300             | days         | \$11,000                                | \$3,300,000          |
| 13            | Confirmation Sampling   | 660             | EA           | \$530                                   | \$349,800            |
| 14            | Remove Sheet Pile Wall  | 2600            | LF           | \$120                                   | \$312,000            |
| 15            | Soil Removal and Consolidation (setback from creek)               | 0               | CY           | \$13                                    | \$0                  |
|               |   | Excavation      | \$16,204,800 |   |                      |
| inal C        | Cover System  | EXCAVACION      | and conson   | uation Subtotal.                        | \$10,204,00          |
| 16            | Grade Verification Surveys  | 8               | WK           | \$5,000                                 | \$40,000             |
| 17            | Soil Grading Layer (Select Fill)                                  | 22,900          | CY           | \$20                                    | \$458,000            |
| 18            | Geotextile Separation Layer (8-oz/sy)                             | 10,000          | SY           | \$3                                     | \$25,000             |
| 19            | Gas Venting Layer (Sand)  | 44,000          | CY           | \$21                                    | \$924,000            |
| 20            | Active Gas Venting System   | 28              | EA           | \$95,000                                | \$2,696,90           |
| 21            | 30-mil PVC Liner (or equivalent)                                  | 160,000         | SY           | \$8                                     | \$1,280,000          |
| 22            | Geotextile Cushion Layer (16-oz/sy)                               | 160,000         | SY           | \$5                                     | \$800,000            |
| 23            | Soil Protection / Drainage Layer (Sand)                           | 91,000          | CY           | \$21                                    | \$1,911,000          |
| 24            | Topsoil Layer   | 22,900          | CY           | \$32                                    | \$732,800            |
| 25            | Seed & Mulch  | 28              | AC           | \$2,200                                 | \$62,45              |
| 23            | Seed & Mulch  |                 |              | عجرystem Subtotal:                      | \$8,930,15           |
| erma          | nent Stormwater Management  |                 |              | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | <del>+0,000,00</del> |
| 28            | Vegetated Swales  | 16,000          | LF           | \$16                                    | \$256,000            |
| 29            | Riprap-lined Swales   | 6,000           | LF           | \$110                                   | \$660,000            |
| 30            | Riprap Slope Protection   | 1               | LS           | \$636,000                               | \$636,000            |
| 31            | Culverts  | 1,600           | LF           | \$32                                    | \$51,200             |
| 32            | Subsurface Drain Piping   | 8,000           | LF           | \$48                                    | \$384,000            |
| 33            | Stormwater Basins   | 2               | EA           | \$84,800                                | \$169,600            |
| 33            |   | ermanent Stormw |              |   | \$2,156,800          |
| Restor        | ration  |                 | ater manag   |   | <b>42,230,00</b>     |
| 34            | As-built Survey   | 6               | WK           | \$5,300                                 | \$31,800             |
| 35            | Backfill  | 400,000         | CY           | \$21                                    | \$8,400,000          |
| 36            | Topsoil   | 31,000          | CY           | ,<br>\$32                               | \$992,000            |
| 37            | Seed & Mulch  | 38              | AC           | \$2,200                                 | \$83,600             |
| 38            | Permanent Gravel Access Roads                                     | 1               | LS           | \$265,000                               | \$265,000            |
| 55            |   | -               |              | ration Subtotal:                        | \$9,772,400          |
| ost-c         | losure Monitoring Features Installation                           |                 |              |   |                      |
| 39            | Installation of Permanent Gas Monitoring Probes                   | 0               | EA           | \$5,300                                 | \$0                  |
| 40            | Installation of Perimeter Gas Venting Trenches                    | 0               | SF           | \$21                                    | \$0                  |
| 41            | Installation of Post-closure Groundwater Monitoring Well Network  | 20              | EA           | \$6,400                                 | \$128,000            |
|               | Post-closure Monitoring Features Installation Subtotal:           |                 |              |   |                      |
|               |   | -               |              |   | \$128,000            |
|               |   |                 | CAPITAL C    | OST SUBTOTAL:                           | \$39,943,25          |

ES072413073057MKE 1 of 3

2 of 3

TABLE 7

Cost Estimate for Remedial Alternative 2D

|   | <u> </u>  | reek, kalamazoo mver saperjana site  |                                   |  | Unit Cost         |                              |  |
|---|---|--|-----------------------------------|--|-------------------|------------------------------|--|
| Item                                      |   |  | Estimated                         |  | (Labor and        |                              |  |
| No.                                       |   | Description  | Quantity                          | Unit   | Materials)        | Estimated Cost<br>\$798,86   |  |
|   |   | Subcontractor Performance and Payment Bonds (2% of Subtotal Capital Cost): |                                   |  |                   |                              |  |
|   | Mobilization/Demobilization (5% of Subtotal Capital Cost):                            |  |                                   |  |                   |                              |  |
|   | Administration, Design, and Construction Oversight:                                   |  |                                   |  |                   |                              |  |
|   | Independent Construction Quality Assurance (10% of Final Cover System Capital Costs): |  |                                   |  |                   |                              |  |
|   |   |  | Contingency (20%                  |  |                   | \$7,988,651<br>\$56,620,950  |  |
|   |   | TOTAL CAPITAL COST:  |                                   |  |                   |                              |  |
| II. OPERATION AND MAINTENANCE (O&M) COSTS |   |  | *********                         | Discount Rate                                    | 1.9%              |                              |  |
| Post-c                                    | losure Inspections &  | Maintenance  | Current Annual Cost               |  | NPV Factor        | NPV                          |  |
| 42  | Years 1-5   |  | \$150,000                         | YR   | 4.73              | \$709,070                    |  |
| 43  | Years 6-30  |  | \$75,000                          | YR   | 17.98             | \$1,348,52                   |  |
|   |   |  | Post-closure Inspections 8        | Post-closure Inspections & Maintenance Subtotal: |                   |                              |  |
| Post-c                                    | losure Landfill Gas N   | Ionitoring & Reporting   |                                   |  |                   |                              |  |
| 44  | Years 1-5   |  | \$4,000                           | YR   | 4.73              | \$18,90                      |  |
| 45  | Years 6-30  |  | \$2,000                           | YR   | 17.98             | \$35,96                      |  |
|   |   | P  | ost-closure Landfill Gas Monitori | ng & Re  | porting Subtotal: | \$54,86                      |  |
| Post-c                                    | losure Groundwater  | Sampling & Reporting   |                                   |  |                   |                              |  |
| 46  | Years 1-5   |  | \$200,000                         | YR   | 4.73              | \$945,43                     |  |
| 47  | Years 6-30  |  | \$100,000                         | YR   | 17.98             | \$1,798,03                   |  |
|   |   | F  | ost-closure Groundwater Sampli    | ng & Re  | porting Subtotal: | \$2,743,46                   |  |
|   |   |  |                                   | O&M COST SUBTOTAL:                               |                   |                              |  |
|   |   |  | Contingency (20%                  | Contingency (20% of Subtotal O&M Cost):          |                   |                              |  |
|   |   |  |                                   | TOTAL O&M COST:                                  |                   |                              |  |
| III. PERIODIC COSTS                       |   |  |                                   | Discount Rate<br>Discount                        | 1.9%              |                              |  |
| 5-Year Reviews                            |   | Annual Cos   | t                                 | Factor   | Net Present Value |                              |  |
| 48  | Year 5  |  | \$25,000                          | YR   | 0.91              | \$22,75                      |  |
| 49  | Year 10   |  | \$25,000                          | YR   | 0.83              | \$20,71                      |  |
| 50  | Year 15   |  | \$25,000                          | YR   | 0.75              | \$18,85                      |  |
| 51  | Year 20   |  | \$25,000                          | YR   | 0.69              | \$17,15                      |  |
| 52  | Year 25   |  | \$25,000                          | YR   | 0.62              | \$15,61                      |  |
| 53  | Year 30   |  | \$25,000                          | YR   | 0.57              | \$14,21                      |  |
|   |   |  | , ,                               |  | L PERIODIC COST:  | \$109,30                     |  |
|   |   |  | 7                                 | TOTAL ESTIMATED COST:                            |                   |                              |  |
|   |   |  |                                   |  | ROUNDED TO:       | \$62,557,377<br>\$63,000,000 |  |

This estimate has been prepared for the purposes of comparing potential remedial alternatives. The information in this cost estimate is based on the available information regarding the site investigation and the anticipated scope of the remedial alternative. Changes in cost elements are likely to occur as a result of new information and data collected during the engineering design of the remedial alternative. This cost estimate is expected to be within -30% to +50% of the projected cost.

Unit prices are based on 2015 dollars.

All volumes represent in-place measures.

Where not otherwise noted, unit cost is based on past project experience.

Mobilization/Demobilization includes, but is not necessary limited to, transportation of personnel, equipment, and materials to and from the OU, temporary utilities and services (i.e., electrical, water, telephone, sanitary), construction trailers, etc., that is with winter shutdown.

CY = Cubic Yard; LF = Linear Feet; LS = Lump Sum; SY = Square Yard; AC = Acre; EA = Each; TN = Ton; WK = Week; MO = Month.

## Item Notes (where applicable):

- 1. Pre-construction survey includes costs associated with performing an aerial survey, supplemental field survey, in-field property boundary delineations, field marking OU features to be protected (e.g., monitoring wells), and cross sections within Portage Creek prior to
- 2. Air monitoring unit cost assumes that monitoring activities are required during COC-containing material handling only (e.g., excavation, consolidation, subgrade preparation).
- 6. Clearing and grubbing unit cost is based on cutting and chipping of medium to heavily forested area and grubbing of stumps and other miscellaneous debris within the areas subject to consolidation and final cover system.
- 7. Temporary steel sheeting cost estimate is based on the assumption that approximately 1,200 linear feet of 15-foot long steel sheeting will be installed to facilitate earthwork activities along the bank of Portage Creek adjacent to the Monarch HRDL.

ES072413073057MKE

## TABLE 7

## Cost Estimate for Remedial Alternative 2D

Allied Paper, Inc./Portage Creek/Kalamazoo River Superfund Site

|      |             |           |      | Unit Cost  | •                     |
|------|-------------|-----------|------|------------|-----------------------|
| item |             | Estimated |      | (Labor and |                       |
| No.  | Description |           | Unit | Materials) | <b>Estimated Cost</b> |

- Soil removal and consolidation quantity represents the total quantity of in-situ material requiring excavation prior to consolidation within the Former Type III Landfill, Western Disposal Area, and Monarch HRDL consolidation areas. Soil removal and consolidation cost includes excavation and loading of COC-containing materials, onsite transport to placement area within the consolidation areas, and placement and compaction in 12-inch lifts within the consolidation areas. Estimated quantities are based on removal and consolidation of approximately 190,000 cubic yards of material along the peripheral areas of the Former Type III Landfill and the Western Disposal Area (including the Panelyte Property, Panelyte Marsh, and Conrail Property), approximately 170,000 cubic yards from the Monarch HRDL, and approximately 99,500 cubic yards of material from outlying areas.
- 13 Confirmation sample quantity assumes that all soil removal areas will be sampled on a 50-foot by 50-foot grid to confirm removal of COC-containing material.
- 14 Estimated quantity and cost is not based on calculation, rather it is an estimate based on site topography and the potential for sheet pile removal based on slope stability considerations. Lineal footage and costs to be determined during design phase.
- 15 Estimated quantity is based on a setback 30-foot-wide along a linear distance of 2,100 feet along Bryant HRDL/FRDLs and Portage Creek. Estimated excavation depth is 8 feet based on nearby borings.
- 16 Final cover quantities are based on the following estimated areas: Former Type III Landfill 10 acres, Western Disposal Area 12 acres, and
   25 Bryant HRDLs/FRDLs 20.7 acres.
- 17 Soil grading layer cost estimate is based on an assumed 6-inch-thick layer of select fill covering the entire consolidation/cover system areas and is the first layer of the earthen cover system.
- 18 Geotextile separation layer cost estimate assumes utilizing a non-woven geotextile covering the entire cover system areas, and includes an additional 20% material quantity to account for overlap and wrinkles. Unit cost is based on information provided by geotextile
- 23 Soil protection/drainage layer consists of a 2-foot-thick layer of sand covering the entire cover system area.
- 24 Topsoil layer consists of a 6-inch-thick layer of topsoil covering the entire cover system areas.
- 25 Seed and mulch cost estimate is based on seeding and mulching the entire area subject to consolidation/final cover system.
- 26 Slurry wall costs include all components of design and construction. Groundwater collection and treatment (Contingency 2) not costed here as the slurry wall cost will be higher.
- 28 Total length of the vegetated swale is based on a conceptual cover system layout prepared for cost estimating purposes only.
- 29 Total length of the riprap-lined swale is based on a conceptual cover system layout prepared for cost estimating purposes only.
- 31 Total length of culvert piping is based on a conceptual cover system layout prepared for cost estimating purposes only.
- 32 It is anticipated that subsurface drainage would be installed at the interface between the consolidation area and the existing Bryant HRDLs and FRDLs liner system. Liner system grades at the interface are assumed to slope downward on a 4 on 1 slope forming a v-notch channel containing the subsurface drainage piping.
- 33 Stormwater basin unit cost represents an average per basin cost, which was developed from a conceptual stormwater basin configuration.
- 34 Restoration quantity assumes approximately 22 acres of soil removal area, located outside the limits of capping, as specified in the
- 38 following: Former Type III Landfill 3.6 acres, Western Disposal Area 3.6 acres, Bryant HRDL/RDL 1.4 acres, Monarch HRDL 6.8 acres, commercial properties 5.3 acres and Residential/MHLLC-Owned properties including Golden Age) 1.5 acres.
- 35 Estimated backfill quantities are based on the volume of clean fill material that will be required to backfill the peripheral soil removal areas located outside the limits of capping to appropriate subgrade elevation. An estimated 50,000 cubic yards will be used to backfill the Monarch HRDL. Actual quantities will be determined during the design.
- **36** Topsoil quantity is based on covering approximately 42 acres of soil removal area, located outside the limits of capping, with 6 inches of topsoil.
- 37 Seed and mulch quantity is based on covering the 42 acres of topsoil placed over the outlying soil removal areas, as necessary to promote vegetative growth.
- Permanent access road quantity based on an assumed 8,000 linear feet of newly constructed road that will be required to access various portions of the cover system area for maintenance purposes.
- 47 Net present value (NPV) factors calculated using the following equation:

$$NPV = I_0 + \frac{I_1}{1+r} + \frac{I_2}{(1+r)^2} + ... + \frac{I_n}{(1+r)^n}$$

- r = Discount rate (expressed as decimal)
- n = Number of years from present

ES072413073057MKE

42 -