


JOB NUMBER 88119		DATE: 10/9/05	
FILE NO. 88119-C-7		DRAWING NO. C-7	
DESIGNED BY DMW, RMA	CHECKED BY REB	APPROVED BY —	
SCALE: 1" = 40'		SHEET 10 OF 16	



INTERIM ON-SITE DRAINAGE MEASURES
WAIMANALO GULCH LANDFILL

SITE PLAN



NOT FOR CONSTRUCTION

- NOTE:**
1. FIBER ROLLS SHALL BE PLACED ON GRADED SLOPES PER DETAIL 4/C-10 @ 50' O.C. ±. TO CORRESPOND ON SITES SURVEY INDICATED IN CONSTRUCTION. SITES SURVEY HAS MARKED APPROPRIATE CONTOUR LINES IN THE FIELD, OR AS DIRECTED BY THE OWNER OR OWNER'S REPRESENTATIVE.
 2. THE CONTRACTOR SHALL POTHOLE ALONG ALL ASH OR MSW CELL LOCATIONS WHERE GRADING OR EXCAVATION OPERATIONS MAY OCCUR TO VERIFY LINER EDGE PRIOR TO ANY CONSTRUCTION OPERATIONS.

