



JERSEY CITY MUNICIPAL UTILITIES AUTHORITY

555 ROUTE #440 · JERSEY CITY, NEW JERSEY 07305 · TEL: (201) 432-1150 · FAX: (201) 432-1576

DANIEL F. BECHT, ESQ
EXECUTIVE DIRECTOR

JOHN D. FOLK, C.P.A.
DIRECTOR OF FINANCE

BOARD OF COMMISSIONERS

EILEEN GAUGHAN
CHAIRPERSON

DONALD BROWN
VICE CHAIRPERSON

WILLIAM MACCHI
SECRETARY

LEWIS W. MATTHIAS
TREASURER

WILLIAM CHOPEK, JR
COMMISSIONER

July 26, 2013

Roger McCready, CPG
Project Manager
CH2M Hill
Fifth Third Center, Suite 1100
One South Main St
Dayton, OH. 45402

**RE: Dredging of Passaic River near Jersey City Aqueduct
Lower Passaic River RM 10.9, Lyndhurst NJ**

Dear Mr. McCready,

The Jersey City Municipal Utilities Authority (JCMUA) has reviewed your letter dated June 18, 2013 and report by Ocean Surveys Inc. dated June 13, 2013. As per the above report, the magnetometer survey shows the mains off by as much as 15 FT from the as-built plans. Therefore, in the worst case scenario we could be left with only 15 FT offset if the mains are in fact the way they are shown on the as-builts.

Given the above I would like you to use the following offsets from the two 72 inch diameter steel mains buried under the river when conducting dredging operations: 30 FT away from the west main as shown on the as-built and 30 FT away from the east main as surveyed by the magnetometer.

Please contact me at 201-432-1150 if you have any questions regarding this matter.

Very truly yours

A handwritten signature in black ink, appearing to read "Rajiv Prakash".

Rajiv Prakash, PE
Staff Engineer

cc: Daniel Becht, Esq., Executive Director
Richard Haytas, Senior Engineer
John Hroncich, PE, Project Manager, UWJC
Mike Leahy, T&D Manager, UWJC
Steve White, Aqueduct Supervisor, UWJC