




**STEPHANIE
RAWLINGS-BLAKE
MAYOR**

CITY OF BALTIMORE
Stephanie Rawlings-Blake
Mayor

DEPARTMENT OF PUBLIC WORKS
David E. Scott, P.E.
Director



**BUREAU OF WATER AND WASTEWATER
WATER & WASTEWATER ENGINEERING DIVISION**

**Gwynns Falls Sewershed Evaluation Study Plan
Project 1032**

**Sewershed Study and Plan Report
Sanitary Sewer Overflow Consent Decree
Civil Action No. JFM-02-1524**

June 2010

**Kishia L. Powell, P.E. Head
Bureau of Water & Wastewater**

**Wazir Qadri, Acting Chief
Water & Wastewater Engineering Division**



TABLE OF CONTENTS

GWYNNS FALLS SEWERSHED STUDY AND PLAN

TABLE OF CONTENTS

Executive Summary

- 1.0 Project Description
 - 1.1 Project Background
 - 1.2 Previous Study
 - 1.3 Purpose of Sewershed Study
 - 1.4 Description of the Sewershed and Sub-Basins
 - 1.5 Collection System Components and Attributes
- 2.0 Effectiveness of Paragraph 8 Construction Projects
 - 2.1 Engineered SSO Locations
 - 2.2 Construction Projects
 - 2.3 Pre- and Post-Construction Flow Monitoring
 - 2.4 Hydraulic Model Simulations
 - 2.5 Conclusions
- 3.0 Flow Monitoring Program
 - 3.1 Overall Description
 - 3.2 Metering Network Within the Gwynns Falls Sewershed
 - 3.3 Rainfall Measurement
 - 3.4 Dopplar Radar Analysis
 - 3.5 Data Flow Summary and Quality Assurance/Quality Control Processes
 - 3.6 Dry Weather Analysis
 - 3.6.1 Base Infiltration Rates and Severity
 - 3.6.2 Correlation with Completed Sewer CCTV and Manhole Inspections
 - 3.6.3 Influence of Groundwater Table on Infiltration Rates
 - 3.6.4 Base Infiltration from Baltimore County
 - 3.7 Wet Weather Analysis
 - 3.7.1 Observed Peak Flows
 - 3.7.2 Rain Dependent Infiltration/Inflow Rates and Severity
 - 3.7.3 Correlation with Completed CCTV and Manhole Inspections
 - 3.7.4 RDII From Baltimore County
 - 3.7.5 Smoke Testing Recommendations
 - 3.8 Gwynns Falls Sewershed Infiltration and Inflow Evaluation Report
- 4.0 Sewer System Evaluation Study
 - 4.1 Overview
 - 4.2 Manhole Inspections
 - 4.3 Sewer Cleaning and Closed Circuit Television Inspection
 - 4.3.1 Structural/Operational Defects and Ratings
 - 4.4 Smoke Testing
 - 4.5 Dyed-Water Testing
 - 4.6 Emergency Repairs/Rehabilitation
 - 4.7 Southwest Diversion Isolated Inspections
 - 4.8 Westport Pump Station Force Main Inspection
 - 4.9 Quality Assurance/Quality Control Protocols
 - 4.9.1 Manhole Inspection Protocols
 - 4.9.2 Sewer CCTV Inspection Protocols
 - 4.9.3 Sonar/CCTV Inspection Protocol
 - 4.9.4 Smoke Testing Protocol
 - 4.9.5 Dye-Water Testing

TABLE OF CONTENTS

GWYNNNS FALLS SEWERSHED STUDY AND PLAN

5.0	Hydraulic Modeling
5.1	Model Network
5.2	Model Calibration
5.3	Baseline Analysis and Capacity Assessment
5.3.1	Design Storms
5.3.2	Definition of Deficiency
5.3.3	Storm Simulations (All Storms)
5.3.4	Identification of Hydraulic Deficiencies (All Storms)
5.4	Alternative Analysis (1-Year and Larger Storms)
6.0	Geographic Information System
6.1	Overview of GIS
6.2	Field Data and GIS Integration
6.2.1	Manhole Inspections
6.2.2	GPS Manhole Surveys
6.2.4	Smoke and Dyed Water Testing
6.3	Office Research and GIS Updates
6.4	QA/QC Review and Procedures
6.5	GIS Certification
7.0	Recommendations
7.1	Decision Making Criteria
7.2	Proposed Improvements
7.2.1	Sanitary Sewer Overflow Structure Identification and Elimination
7.2.2	Structural Deficiencies Identified
7.2.3	Proposed Gwynns Falls Collection System Hydraulic Improvements
7.3	Proposed Improvement Implementation Schedule
7.4	Estimated Costs of the Proposed Improvement Projects
7.4.1	Estimated Improvement Budget
7.5	Sewershed Re-Inspection Program
7.5.1	Re-Inspection Prioritization Scheme
7.5.2	CCTV and Manhole Inspections
7.6	Future Data Collection and Evaluation Services
7.6.1	Long-Term Flow Monitoring Plan
7.6.2	Sewer Cleaning Program
7.6.3	CCTV and Manhole Inspection Programs
7.6.4	Root Control Program
7.6.5	Fats, Oils and Grease Control Programs
7.6.6	Re-Inspection Prioritization Scheme

TABLE OF CONTENTS

GWYNNS FALLS SEWERSHED STUDY AND PLAN

List of Tables

Table ES-1 – Proposed Improvement Projects Summary
Table 2.2.1 - Paragraph 8 Projects in the Gwynns Falls Sewershed
Table 2.4.1 – Pre- and Post-Construction Hydraulic Model SSO Reductions
Table 3.2.1 – Gwynns Falls Flow Meter Purpose and Operational History
Table 3.4.1 – Storms Selected for Doppler Radar Analysis
Table 3.6.1 – Dry Weather Analysis Table
Table 3.7.1 – Wet-Weather Analysis Table
Table 4.2.1 – Manhole Condition Summary
Table 4.2.2 – Manhole Defect Location Summary
Table 4.2.3 – Manhole Infiltration Location Summary
Table 4.3.1 – CCTV Defect Observation Summary
Table 4.3.2 – Sewer Structural Pipe Rating Summary
Table 4.3.3 – Sewer O&M Pipe Rating Summary
Table 4.4.1 – Smoke Testing Defect Summary
Table 4.5.1 – Dyed Water Testing Defect Summary
Table 5.4.1 – Total Estimated Improvement Costs for Gwynns Falls
Table 7.1.1 – Condition and Criticality Factors
Table 7.1.2 – Criticality Factor Relative Importance Values
Table 7.2.2.1 – Condition Ratings – Manholes by Sub-Sewershed
Table 7.2.2.2 – Manhole MACP Condition ratings 4 & 5
Table 7.2.2.3 – Sanitary Sewers in the Gwynns Falls Sewershed
Table 7.3.1 – Manhole Rehabilitation Implementation Schedule
Table 7.3.2 – Sanitary Sewer Rehabilitation Implementation Schedule (First & Second Priority) and Further Inspection
Table 7.3.3 – Hydraulic Improvements Schedule
Table 7.4.1 – Estimated Manhole Rehabilitation and Replacement Improvement Budget
Table 7.4.2 – Estimated Sewer Rehabilitation and Replacement Improvement Budget
Table 7.4.3 - Estimated Hydraulic Improvement Budget
Table 7.5.1 – Sewershed Re-Inspection Implementation Schedule

List of Figures

Figure ES-1 – Condition and Criticality Matrix
Figure 1.4.1 – Location Map
Figure 1.4.2 – Sub-sewershed Boundaries with Interceptors
Figure 1.4.3 – Future Contracts
Figure 2.1.1 – Location of Engineered SSOs in the Gwynns Falls Sewershed
Figure 2.3.1 – Pre and Post-Construction Scattergraphs for SSO #119
Figure 3.2.1 – Flow Meter Schematic
Figure 3.3.1 – Rain Gauge Network
Figure 4.4.1 – Smoke Test Locations
Figure 4.5.1 – Dye Flood Configuration
Figure 4.5.2 – Downspout Test Configuration
Figure 4.6.1 - Emergency Repair/Rehabilitation Locations
Figure 6.1.1 – GIS Feature Group Summary
Figure 7.1.1 – Condition/Criticality Matrix
Figure 7.6.1 – Root Control Analysis

TABLE OF CONTENTS

GWYNNS FALLS SEWERSHED STUDY AND PLAN

List of Maps

- Map 1.4.1A – Gwynns Falls Sewershed Major Sewers and Pump Stations
- Map 1.4.1B – Gwynns Falls Sewershed Major Sewers and Pump Stations
- Map 2.0.1 – Gwynns Falls Sewershed Paragraph 8 Construction Projects
- Map 3.2.1A – Gwynns Falls Flow Monitoring and Rain Gauge Network
- Map 3.2.1B – Gwynns Falls Flow Monitoring and Rain Gauge Network
- Map 3.6.1 – Gwynns Falls Base Infiltration Severity Map
- Map 3.7.1 – Gwynns Falls RDII Severity Map
- Map 5.1.1A – Gwynns Falls Sewershed Modeled Network
- Map 5.1.1B – Gwynns Falls Sewershed Modeled Network
- Map 5.3.3A – Gwynns Falls Storm Simulation Results (All Storms), Map 1 of 5
- Map 5.3.3B – Gwynns Falls Storm Simulation Results (All Storms), Map 2 of 5
- Map 5.3.3C – Gwynns Falls Storm Simulation Results (All Storms), Map 3 of 5
- Map 5.4.2 – Gwynns Falls Alternative Analysis (2-yr Storm)
- Map 5.4.3 – Gwynns Falls Alternative Analysis (5-yr Storm)
- Map 5.4.4 – Gwynns Falls Alternative Analysis (10-yr Storm)
- Map 5.4.5 – Gwynns Falls Alternative Analysis (15-yr Storm)
- Map 5.4.6 – Gwynns Falls Alternative Analysis (20-yr Storm)
- Map 7.2.3 – Gwynns Falls Recommended Hydraulic Improvements

List of Attachments

- Attachment 3.2.1 – Flow Meter Confirmation Log
- Attachment 3.8.1 – Gwynns Falls Sewershed Inflow and Infiltration Report
- Attachment 4.2.1 – Manhole Inspection Database
- Attachment 4.3.1 – CCTV Inspection Database
- Attachment 4.4.1 – Smoke Test Database
- Attachment 4.5.1 – Dye Flood Database
- Attachment 4.7.1 – Westport Avenue Force Main Assessment Report
- Attachment 4.8.1 – Gwynns Falls Manhole Inspection QAQC Manual
- Attachment 4.8.2 – Gwynns Falls CCTV Inspection QAQC Manual
- Attachment 4.8.3 – Gwynns Falls Smoke Testing QAQC Manual
- Attachment 4.8.4 – Gwynns Falls Dyed Water Testing QAQC Manual
- Attachment 5.2.1 – Gwynns Falls Model Calibration Report
- Attachment 5.3.1 – Gwynns Falls Baseline Assessment and Capacity Analysis Report
- Attachment 5.4.1 – Gwynns Falls Alternative Analysis Report

PROJECT DESCRIPTION
GWYNNS FALLS SEWERSHED STUDY AND PLAN

Executive Summary

On September 30, 2002, the City of Baltimore (City) entered into a Consent Decree with the United States Environmental Protection Agency (EPA), the State of Maryland Department of the Environment (MDE) and the Department of Justice (DOJ). The objective of Paragraph 9 of the Consent Decree is to complete a series of "Collection System Evaluation and Sewershed Plans". This Sewershed Study and Plan details the evaluation of the Gwynns Falls Sewershed.

Gwynns Falls is one of eight sewersheds located within the City. The sewershed study included the inspection or cataloguing of approximately 980,000 linear feet (lf) of gravity sewer ranging from 6- to 102-inches in diameter, approximately 5,200 public sector manholes, six sets of inverted siphons, the Westport Wastewater Pumping Station and 200-lf of associated existing force main, the Maidens Choice Pressure Sewer, and the Southwest Diversion Pressure Sewer.

Of the assets identified under the Gwynns Falls Sewershed, approximately 920,000-lf of gravity sewers and 5,100 of the public sector manholes are located within the sewershed. The remaining 60,000-lf of gravity sewers and 100 public sector manholes are located outside of the main Gwynns Falls sewershed in the Maidens Choice Pressure Sewer service area, the PA-13 basin, and the Southwest Diversion Pressure Sewer service area. These assets were included as part of the Gwynns Falls Sewershed Study, despite not being located within the sewershed boundaries, because they convey sanitary sewer flow exclusively from the Gwynns Falls sewershed to the Patapsco Wastewater Treatment Plant (WWTP).

Much of the sewershed's collection system was constructed in the 1920s and 1930s. The collection system is comprised of four conveyance sub-systems. These sub-systems can be identified as: Upper Gwynns Falls, Lower Gwynns Falls, Maidens Choice, and PA-13. Upper Gwynns Falls conveys flow from the northern part of the sewershed through the Forest Park, Powder Mill, and Walbrook interceptors into the main Gwynns Falls Interceptor. Lower Gwynns Falls conveys flow from the southern part of the sewershed through the Dead Run interceptor and other smaller tributaries into the main Gwynns Falls interceptor. Maidens Choice also conveys flow from the southern part of the sewershed through the Maidens Choice interceptor directly into the Southwest Diversion via the Maidens Choice Pressure Sewer or into the Low Level Sewershed through the Primson Avenue diversion chamber. Moreover, Maidens Choice conveys sanitary sewer flows generated by Baltimore County that enter the City boundary at the south west of the Gwynns Falls sewershed. PA-13 is a sub-basin within the Patapsco sewershed which is pumped to the Southwest Diversion by the Westport Pump Station.

The Gwynns Falls interceptor conveys the majority of the sanitary sewer flow in the sewershed, aside from that conveyed by the Maidens Choice interceptor to the Southwest Diversion. The Southwest Diversion, in turn, discharges to the Patapsco WWTP. This interceptor also conveys the sanitary sewer flow generated by the Baltimore County Gwynns Falls sewershed. Under normal operating conditions all the flow generated within the Gwynns Falls sewershed is discharged to the Patapsco WWTP; however, flow can be diverted to the High Level interceptor for treatment at the Back River WWTP via the Baltimore Street diversion structure or diverted to the Low Level sewershed via the Primson Avenue diversion chamber. It should be noted that during normal system operation, flows are not diverted to the Back River WWTP service area.

PROJECT DESCRIPTION

GWYNNS FALLS SEWERSHED STUDY AND PLAN

In accordance with the Consent Decree, the following items have been completed for the Gwynns Falls Sewershed Study and Plan:

- Evaluation of the effectiveness of the construction projects completed pursuant to Paragraph 8 of the Consent Decree using rainfall and flow monitoring data, as well as the hydraulic model developed in accordance with Paragraph 12 of the Consent Decree. Based on a comparison of pre- and post-flow monitoring data, there has been a significant volume reduction in Sanitary Sewer Overflows (SSOs) in the sewershed since the Paragraph 8 projects were completed.
- Presentation of the results of the rainfall and flow monitoring, as well as smoke and dyed water testing, conducted in the sewershed.
- Identification of deficiencies discovered during the collection system inspections, which included inspection of all gravity sewers having a diameter of eight inches or greater using closed circuit television (CCTV) inspection and inspection of all manholes and other appurtenances within the sewershed.
- Identification of rehabilitation and other corrective actions taken, or proposed to be taken, to address the deficiencies identified during the evaluation of the sewershed.
- Description of the decision-making criteria used to select future corrective action.
- Proposal of a plan and schedule for future evaluation of the collection system within the sewershed.
- Proposal of a plan and schedule for implementing rehabilitation and other corrective actions deemed necessary either to correct deficiencies identified during the collection system evaluation or to ensure operation of the collection system.
- Proposal of a plan and schedule for eliminating those identified physical connections between the sanitary sewer collection system and the storm water collection system.
- Determination of the range of storm events for which the collection system in its existing condition can convey peak flows without the occurrences of SSOs.
- Prediction of the range of storm events for which the collection system will be able to convey peak flows without the occurrence of SSOs assuming completion of the Paragraph 8 construction projects and completion of the proposed rehabilitation and other corrective action projects recommended in this Sewershed Plan
- Certification of the Geographic Information System (GIS) described in Paragraph 14 of the Consent Decree.

As required by the Consent Decree, the Sewershed Plan identifies specific improvements or other corrective actions needed to address structural deficiencies, reduce rainfall dependent inflow and infiltration (RDII) contributing to SSOs, address hydraulic deficiencies identified during the hydraulic analyses, and address other deficiencies that contribute to SSOs.

As part of the sewershed study, the City developed a condition and criticality protocol that provides the framework for a rehabilitation strategy based on criticality (consequences of failure) and condition (probability of failure) ratings of 1 through 5. Assets whose failures can impact the community or environment and whose condition is the poorest received a higher rating and will receive attention sooner. Assets that receive a lower rating will receive some level of regular monitoring but no immediate action or rehabilitation. Five levels of

PROJECT DESCRIPTION
GWYNNS FALLS SEWERSHED STUDY AND PLAN

prioritization were developed based on the combination of condition and criticality as shown in the matrix in Figure ES-1:

		Criticality				
		1	2	3	4	5
Condition	5	First Priority Rehab Program				
	4					
	3	Frequent Assessment				
	2	Low Priority			Regular Monitoring	
	1					

Figure ES-1: Condition and Criticality Matrix

Prioritization of asset rehabilitation projects and other corrective actions were developed with the consideration that all proposed improvements required to eliminate SSO's must be completed before January 1, 2016, as stipulated in the Consent Decree. The proposed improvements include the study of suspected SSO structures, rehabilitation of manholes and sanitary sewers that received a condition rating of 4 or 5, cleaning and rehabilitation of a siphon vault, further inspection of the Maidens Choice Pressure Sewer, and completion of the required hydraulic improvements. The proposed improvement projects and the estimated costs to complete these repairs are summarized in the following table:

Table ES-1: Proposed Improvement Projects Summary (cost in millions of 2008 dollars)

First and Second Priority Sewer Rehabilitation			
Rehabilitation Item	Quantity		Est. Cost
Manhole Rehabilitation/Replacement	73	Ea	\$0.39
Cured-In-Place-Pipe Lining	15,533	LF	\$1.14
Sewer Point Repair (10' Repair)	3,040	LF	\$1.64
Sewer Replacement (> 10' Repair)	3,410	LF	\$1.64
Sewer Point Repair & Cured-In-Place-Pipe Lining	1,032	LF	\$0.16
Sewer Replacement & Cured-In-Place-Pipe Lining	2,054	LF	\$0.20
Siphon Vault Rehabilitation and Cleaning	1	Ea	\$0.19
Maidens Choice Pressure Sewer Inspection	1	Ea	\$0.19
Sub-Total Estimated Cost:			\$5.55
Hydraulic Improvements			
Rehabilitation Item	Quantity		Est. Cost
6" to 24" Cured-In-Place-Pipe Lining	100,199	LF	\$7.34
12" to 36" Pipe Replacement	17,675	LF	\$24.87
Manhole Sealing	28	Ea	\$0.03
Manhole Rehabilitation/Replacement	603	Ea	\$3.18
Equalization Tanks	2.45	MG	\$20.87
Sub-Total Estimated Cost:			\$56.30
Total Estimated Cost:			\$61.85

PROJECT DESCRIPTION

GWYNNNS FALLS SEWERSHED STUDY AND PLAN

Inspection data for those manholes and sewers that received condition rating of 1, 2, or 3 were reviewed to determine whether corrective actions were required. Those deficiencies that require corrective actions were recommended for inclusion in the First and Second Priority corrective action plan. These repairs include the rehabilitation or replacement of 73 manhole structures, installation of approximately 15,533-lf of cured-in-place-pipe (CIPP) liner, approximately 3,040-lf of point repairs, approximately 3,410-lf of sewer replacement and various quantities of point repair/CIPP and sewer replacement/CIPP combinations for deteriorated sewer located through the sewershed.

The recommended hydraulic improvements include miscellaneous 12 to 36-inch diameter sewer upgrades in the Powder Mill, Forrest Park, Dead Run, Maidens Choice, and Gwynns Falls sub-sewersheds. Two storage tanks are recommended for the Maidens Choice sub-sewershed totaling 2.45 million gallons. Miscellaneous manhole rehabilitation/replacement is also recommended for the Powder Mill, Forrest Park, Dead Run, Maidens Choice, and Gwynns Falls sub-sewersheds.

Baltimore County is currently developing hydraulic models for the contributing upstream County portions of the Gwynns Fall Sewershed. The combination of the City and County hydraulic models would result in a regional model capable of providing more realistic results and recommendations. This Plan provides recommended improvements that should be implemented by the City in accordance with the schedule provided. However, the Plan should not be considered final and may require amendment once the system-wide regional hydraulic model is completed and simulations are performed.

As required by Paragraph 9.C.xii of the Consent Decree, as well as under other contracts, the City will also implement continuous operation and maintenance enhancement efforts within the sewershed. These programs will be comprehensive, system-wide initiatives that will include a long-term flow monitoring plan, a sewer cleaning program, CCTV and manhole inspection programs, and root and grease control programs.