A testing tolerance equal to the mutually agreed measurement uncertainty shall be applied to the measured HP section wheel power or the measured HP capacity depending on the guarantee, taking into full consideration the calibration and inspection status of the condensate flow nozzle and other test instrumentation. The minimum testing tolerance on HP shaft power is expected to be 0.5% subject to the use of test accuracy flow metering.