

test probes located at the boiler outlet (16 probes with 4 points each), bubblers, chillers, knockout bottles, desicant filters vacuum pumps, plumbing and fittings.

Coal samples will be taken at each individual coal feeder plus fly ash, bottom ash and air heater ash samples will be collected and analyzed.

IPSC will conduct the acceptance testing and tuning, provide test setup, provide test procedures, publish test results, recommendations and final report.