| Hazard   | Safety Equipment Required  |
|--|--|
| Hazardous noise  | Earplugs and/or earmuffs   |
| Toxic fumes and/or vapors from welding, grinding, or solvent type cleaning | Preparing for proper working atmosphere in and around the boiler requires specific preparation by Contractor |
| Head injuries from falling material or bumps                               | Hardhats   |
| Burns from welding and cutting   | Gloves, long sleeve shirts, and welding leathers   |
| Foot injuries from dropped tools or equipment                              | Steel-toed boots   |
| Eye and face injuries  | Safety glasses and face shields  |

## 8. Quality Assurance/Quality Control:

- a. IPSC reserves full access rights for quality assurance (QA) inspections of ongoing Work. A nonbinding schedule identifying the anticipated approximate number of random QA inspections in each area shall be prepared by IPSC and included within the approved installation plan.
- b. Contractor shall provide, within the proposed installation plan, a quality control plan, identifying the procedures and acceptance criteria to govern the Work. The Work specific quality control plan shall detail the number and type of examinations to be performed during installation to ensure the long-term integrity of all pressure boundaries and structural connections.
- c. The successful bidder shall provide all required nondestructive examination (NDE) personnel in support of Contractor's R Stamp Program and as detailed in the approved installation plan. These personnel shall be trained and certified in accordance with ASNT standards, with at least five (5) years in the applicable technique.
- d. Contractor shall provide to IPSC a copy of all code documentation required, including, but not limited to:
  - (1) NDE Certifications
  - (2) R Forms
  - (3) Repair Plans