

DIVISION F2

DETAILED REQUIREMENTS

- e. IPSC will provide general fire protection and first aid services. Provisions for local fire extinguishing, such as weld slag induced fires, shall be provided by Contractor. All workplace injuries shall be reported to IPSC's First Aid Clinic and the Contract Administrator.
- g. IPSC will not provide office or administrative space or off-site telephone service to Contractor; however, IPSC will make an on-site telephone line available to Contractor at a specific, office-trailer-ready location, if requested. Contractor shall make its own arrangements for off-site and long distance telephone service.

10. Shipping, Receiving, Handling, and Storing:

- a. Shipping: The Contractor shall ensure that all materials and equipment are securely prepared for shipment to prevent damage and or deterioration. All pressure parts shall be coated with a light color rust inhibiting coating prior to shipment to allow for ready identification and correction of damaged material.

Tube ends shall be fully prepared for installation prior to shipment and shall be capped or otherwise protected from damage during shipment. Tubing shall be shipped and stored with means for preventing oxidation/corrosion of internal and external surfaces.
- b. Receiving: Upon arrival at IPP plant site, Contractor shall examine all shipments for shortages, discrepancies, or damage. Contractor shall prepare a report itemizing the material received and submit the report to the Contract Administrator.
- c. Handling: Contractor shall be responsible for any damage to equipment and materials until final acceptance of the Work. Contractor shall be responsible for arranging the unloading of all carriers promptly and shall pay any demurrage incurred. Materials shall be handled with due care to prevent damage or loss.
- d. Storage: All materials, equipment, and supplies not immediately incorporated in the Work shall be placed in storage. Storage areas will be allocated and assigned by the Contract Administrator and will be in the general area of the Work. The storage areas shall be kept clean and orderly at all times.

Contractor shall temporarily connect the motor space heaters for the fan motors to a 120 volt source while in storage and construction until a permanent source is available.

11. Performance Guarantees: Contractor guarantees the following performance when operating in accordance with the parameters identified in Article 12 of this Section: