

## DIVISION F2

## DETAILED REQUIREMENTS

---

include 5 days for installation of the boiler internal scaffolding and 4 days for removal of the same.

- c. A bid evaluation credit of \$100,000 per day shall be applied to each bid for each full day less than the longest schedule bid in the proposed Installation Plan. Bid evaluation credit shall not apply to the longest schedule bid. This is a bid evaluation credit only and shall not modify or supersede any part of the submitted bid package.
  - d. Work not requiring the unit to be off-line, such as mobilization, staging, boiler enclosure structural access work, demobilization etc. shall be clearly identified on the proposed Installation Plan and can be coordinated outside this outage window, with approval of the Contract Administrator.
  - e. The bidders shall provide a schedule of costs associated with an IPSC scheduled delay of the outage start date in one week increments up to a one month. These costs shall be based on notification from IPSC 1 month prior to the scheduled outage start dates and a second schedule based on notification from IPSC 1 week prior to the scheduled outage start dates.
  - f. Unless otherwise noted in these Specifications, IPSC facilities and equipment shall not be used in support of this work. To prevent delays, caused by equipment breakdown, the Contractor shall provide spare tools and equipment at the jobsite in reasonable quantities in anticipation of equipment failures.
4. Installation : Each bidder shall prepare and provide, with each bid package, a proposed Installation Plan showing project progress on a daily basis beginning with initial equipment delivery and ending with site clean up and exit.
- a. The proposed Installation Plan, submitted with the bid package, shall be the basis for development of the approved Installation Plan forming a part of the eventual contract governing this work. The approved Installation Plan shall be used as the basis for instituting mid-outage resource corrections and for calculating any penalties associated with completion of the work scope.
  - b. The proposed Installation Plan shall include detailed information regarding each task within the contract scope, including:
    - Equipment and Material Delivery
    - Equipment Mobilization and Assembly
    - Manpower Loading Throughout the Contract
    - Scaffold Installation Plan
      - Scaffold Erected - Guaranteed Date
      - Scaffold Removed - Guaranteed Date
    - Boiler Pendant Split Ring Casting Replacement
    - Platen Loop Removal and Extension