

DIVISION F2

DETAILED REQUIREMENTS

-
- e. The Contractor shall submit certified weld procedures and welder qualification records for each welder employed, to the IPSC Contract Administrator prior to beginning work.
 - f. A substandard weld shall be defined as any weld declared substandard in the opinion of the IPSC Contract Administrator or designee. The ASME and AWS codes will form the basis of the acceptability determination.
 - g. Completed welds shall be smooth and free of undercutting, cavities, depressions, cracks, surface porosity, weld craters, overlaps, and abrupt ridges. All welds shall meet the specifications of the applicable sections of AWS and ASME Section I.
10. Available On-Site Services: Unless otherwise arranged, in writing, with the Contract Administrator, on-site services shall be provided in accordance with this section. Services not covered in this section shall be provided by the Contractor.
- a. IPSC will make potable water, compressed air (small volume only), and electricity available at 460V and 120V. Connections to IPSC electric or water systems shall be made only by IPSC employees unless approved otherwise in writing for each specific location. The Contractor shall coordinate all service connection needs with the Contract Administrator prior to mobilization.
 - b. The Contractor shall provide enough sanitary facilities for its employees. Contractor employees are prohibited from using the permanent restroom facilities at the site.
 - c. The Contractor may utilize the open areas next to the east and west sides of the Unit 1 Generation Building and Baghouse for staging of equipment and supplies. Staging and access requirements of the Contractor shall be detailed within the Bidders Installation Plan. Actual placement of materials and equipment shall be coordinated with the Contract Administrator.
 - d. The Contractor shall maintain a clean work space. The Contractor shall clean the work site at least daily. This includes, but is not limited to, picking up trash, sweeping, and washing the area as necessary, straightening cords and hoses, organizing tools and equipment, and emptying trash receptacles. IPSC will provide trash collection containers (dumpsters) for the Contractor's use, outside the generation building at ground level. IPSC will empty these containers as needed.
 - e. IPSC will provide general fire protection and first aid services. Provisions for local fire extinguishing, such as weld slag induced fires, shall be provided by the Contractor. All workplace injuries shall be reported to the IPSC First Aid Clinic and the Contract Administrator.