Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S102 A1
Client Sample No. JEB-H1-1FD-101004
Description
Analysis Date 11/23/2004
Analyst JH

Volume (L) 1306.8
No. of Grid Openings 21
Filter Area (mm2) 385
Area Analyzed (mm2) 0.304
Analytical Sens. (struc/cc) 0.000968
Dectection Limit. (struc/cc) 0.00289

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.00289	0.00 - 0.00289	0
Total Asbestos Structures	0.0	<0.00289	0.00 - 0.00289	0
Asbestos Structures > 5um	0.0	<0.00289	0.00 - 0.00289	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00289	0.00 - 0.00289	0
PCM Equivalent Fibers-US	0.0	<0.00289	0.00 - 0.00289	0
PCM Equivalent Structures-US	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL ASB STRUCS >10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00289	0.00 - 0.00289	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00289	0.00 - 0.00289	0
AHERA-like Total Structures 3:1	0.0	<0.00289	0.00 - 0.00289	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00289	0.00 - 0.00289	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00289	0.00 - 0.00289	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00289	0.00 - 0.00289	0
Total Other Amphibole Strucs 3:1	0.0	<0.00289	0.00 - 0.00289	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00289	0.00 - 0.00289	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00289	0.00 - 0.00289	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00289	0.00 - 0.00289	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S103 A1
Client Sample No. JEB-H1-2FD-101004
Description
Analysis Date 11/21/2004
Analyst TM

Volume (L) 1222.8
No. of Grid Openings 22
Filter Area (mm2) 385
Area Analyzed (mm2) 0.319
Analytical Sens. (struc/cc) 0.000988
Dectection Limit. (struc/cc) 0.00295

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	6.3	0.00198	0.00 - 0.00622	2
Total Asbestos Structures	6.3	0.00198	0.00 - 0.00622	2
Asbestos Structures > 5um	0.0	<0.00295	0.00 - 0.00295	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00295	0.00 - 0.00295	0
PCM Equivalent Fibers-US	0.0	<0.00295	0.00 - 0.00295	0
PCM Equivalent Structures-US	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL ASB STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00295	0.00 - 0.00295	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00295	0.00 - 0.00295	0
AHERA-like Total Structures 3:1	6.3	0.00198	0.00 - 0.00622	2
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
Total Other Amphibole Strucs 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00295	0.00 - 0.00295	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S105 A1
Client Sample No. JEB-H2-4FD-101004
Description
Analysis Date 11/22/2004
Analyst DW

Volume (L) 1186.62
No. of Grid Openings 23
Filter Area (mm2) 385
Area Analyzed (mm2) 0.333
Analytical Sens. (struc/cc) 0.000974
Dectection Limit. (struc/cc) 0.00291

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	3.0	0.000974	0.00 - 0.00461	1
Total Asbestos Structures	3.0	0.000974	0.00 - 0.00461	1
Asbestos Structures > 5um	0.0	<0.00291	0.00 - 0.00291	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00291	0.00 - 0.00291	0
PCM Equivalent Fibers-US	0.0	<0.00291	0.00 - 0.00291	0
PCM Equivalent Structures-US	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL ASB STRUCS >10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00291	0.00 - 0.00291	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00291	0.00 - 0.00291	0
AHERA-like Total Structures 3:1	3.0	0.000974	0.00 - 0.00461	1
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00291	0.00 - 0.00291	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00291	0.00 - 0.00291	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00291	0.00 - 0.00291	0
Total Other Amphibole Strucs 3:1	0.0	<0.00291	0.00 - 0.00291	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00291	0.00 - 0.00291	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00291	0.00 - 0.00291	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00291	0.00 - 0.00291	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S41 A1
Client Sample No. JEB-H1-6FD-101004
Description
Analysis Date 10/29/2004
Analyst TM

Volume (L) 1216.8
No. of Grid Openings 22
Filter Area (mm2) 385
Area Analyzed (mm2) 0.319
Analytical Sens. (struc/cc) 0.000993
Dectection Limit. (struc/cc) 0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	31.4	0.00993	0.00476 - 0.0183	10
Total Asbestos Structures	31.4	0.00993	0.00476 - 0.0183	10
Asbestos Structures > 5um	28.2	0.00893	0.00408 - 0.0170	9
Asbestos Fibers and Bundles > 5um	25.1	0.00794	0.00343 - 0.0156	8
PCM Equivalent Fibers-US	22.0	0.00695	0.00279 - 0.0143	7
PCM Equivalent Structures-US	18.8	0.00596	0.00219 - 0.0130	6
PROTOCOL ASB STRUCS 5-10	3.1	0.000993	0.00 - 0.00470	1
PROTOCOL ASB STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS TOTAL	3.1	0.000993	0.00 - 0.00470	1
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS 5-10	3.1	0.000993	0.00 - 0.00470	1
PROTOCOL AMPH STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS TOTAL	3.1	0.000993	0.00 - 0.00470	1
AHERA-like Total Structures 3:1	31.4	0.00993	0.00476 - 0.0183	10
AHERA-like Asb Strucs >5 and 3:1	28.2	0.00893	0.00408 - 0.0170	9
AHERA-like Asb Strucs 5 - 10 and 3:1	12.5	0.00397	0.00108 - 0.0102	4
AHERA-like Asb Strucs >10 and 3:1	15.7	0.00496	0.00161 - 0.0116	5
Total Other Amphibole Strucs 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4763 S30 A1	**Volume (L)**	1216.8
Client Sample No.	JEB-H1-6FD-101004	**No. of Grid Openings**	22
Description	Duplicate Analysis of 041191-41 - Reprep	**Filter Area (mm2)**	385
Analysis Date	12/6/2004	**Area Analyzed (mm2)**	0.319
Analyst	KM	**Analytical Sens. (struc/cc)**	0.000993
		Dectection Limit. (struc/cc)	0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	18.8	0.00596	0.00219 - 0.0130	6

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S42 A1
Client Sample No. JEB-H1-7FD-101004
Description
Analysis Date 10/30/2004
Analyst KM

Volume (L) 609
No. of Grid Openings 45
Filter Area (mm2) 385
Area Analyzed (mm2) 0.652
Analytical Sens. (struc/cc) 0.000970
Dectection Limit. (struc/cc) 0.00290

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	4.6	0.00291	0.00 - 0.00751	3
Total Asbestos Structures	4.6	0.00291	0.00 - 0.00751	3
Asbestos Structures > 5um	1.5	0.000970	0.00 - 0.00460	1
Asbestos Fibers and Bundles > 5um	1.5	0.000970	0.00 - 0.00460	1
PCM Equivalent Fibers-US	1.5	0.000970	0.00 - 0.00460	1
PCM Equivalent Structures-US	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL ASB STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
AHERA-like Total Structures 3:1	4.6	0.00291	0.00 - 0.00751	3
AHERA-like Asb Strucs >5 and 3:1	1.5	0.000970	0.00 - 0.00460	1
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
AHERA-like Asb Strucs >10 and 3:1	1.5	0.000970	0.00 - 0.00460	1
Total Other Amphibole Strucs 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S106 A1
Client Sample No. JEB-H2-5EFD-101004
Description
Analysis Date 11/22/2004
Analyst DW

Volume (L) 615
No. of Grid Openings 44
Filter Area (mm2) 385
Area Analyzed (mm2) 0.638
Analytical Sens. (struc/cc) 0.000982
Dectection Limit. (struc/cc) 0.00294

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	3.1	0.00196	0.00 - 0.00619	2
Total Asbestos Structures	3.1	0.00196	0.00 - 0.00619	2
Asbestos Structures > 5um	3.1	0.00196	0.00 - 0.00619	2
Asbestos Fibers and Bundles > 5um	3.1	0.00196	0.00 - 0.00619	2
PCM Equivalent Fibers-US	3.1	0.00196	0.00 - 0.00619	2
PCM Equivalent Structures-US	3.1	0.00196	0.00 - 0.00619	2
PROTOCOL ASB STRUCS 5-10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL ASB STRUCS >10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00294	0.00 - 0.00294	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00294	0.00 - 0.00294	0
AHERA-like Total Structures 3:1	3.1	0.00196	0.00 - 0.00619	2
AHERA-like Asb Strucs >5 and 3:1	3.1	0.00196	0.00 - 0.00619	2
AHERA-like Asb Strucs 5 - 10 and 3:1	1.6	0.000982	0.00 - 0.00465	1
AHERA-like Asb Strucs >10 and 3:1	1.6	0.000982	0.00 - 0.00465	1
Total Other Amphibole Strucs 3:1	0.0	<0.00294	0.00 - 0.00294	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00294	0.00 - 0.00294	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00294	0.00 - 0.00294	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00294	0.00 - 0.00294	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S107 A1
Client Sample No. JEB-H2-5WFD-101004
Description
Analysis Date 11/22/2004
Analyst DW

Volume (L) 622.2
No. of Grid Openings 44
Filter Area (mm2) 385
Area Analyzed (mm2) 0.638
Analytical Sens. (struc/cc) 0.000971
Dectection Limit. (struc/cc) 0.00290

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	3.1	0.00194	0.00 - 0.00611	2
Total Asbestos Structures	3.1	0.00194	0.00 - 0.00611	2
Asbestos Structures > 5um	1.6	0.000971	0.00 - 0.00460	1
Asbestos Fibers and Bundles > 5um	1.6	0.000971	0.00 - 0.00460	1
PCM Equivalent Fibers-US	1.6	0.000971	0.00 - 0.00460	1
PCM Equivalent Structures-US	1.6	0.000971	0.00 - 0.00460	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL ASB STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00290	0.00 - 0.00290	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00290	0.00 - 0.00290	0
AHERA-like Total Structures 3:1	3.1	0.00194	0.00 - 0.00611	2
AHERA-like Asb Strucs >5 and 3:1	1.6	0.000971	0.00 - 0.00460	1
AHERA-like Asb Strucs 5 - 10 and 3:1	1.6	0.000971	0.00 - 0.00460	1
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
Total Other Amphibole Strucs 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00290	0.00 - 0.00290	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S43 A1
Client Sample No. JEB-L2-1CH-101004
Description
Analysis Date 10/30/2004
Analyst KM

Volume (L) 313.2
No. of Grid Openings 85
Filter Area (mm2) 385
Area Analyzed (mm2) 1.23
Analytical Sens. (struc/cc) 0.000998
Dectection Limit. (struc/cc) 0.00298

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	4.9	0.00599	0.00220 - 0.0130	6
Total Asbestos Structures	4.9	0.00599	0.00220 - 0.0130	6
Asbestos Structures > 5um	3.2	0.00399	0.00109 - 0.0102	4
Asbestos Fibers and Bundles > 5um	3.2	0.00399	0.00109 - 0.0102	4
PCM Equivalent Fibers-US	3.2	0.00399	0.00109 - 0.0102	4
PCM Equivalent Structures-US	3.2	0.00399	0.00109 - 0.0102	4
PROTOCOL ASB STRUCS 5-10	0.8	0.000998	0.00 - 0.00473	1
PROTOCOL ASB STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS TOTAL	0.8	0.000998	0.00 - 0.00473	1
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS 5-10	0.8	0.000998	0.00 - 0.00473	1
PROTOCOL AMPH STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS TOTAL	0.8	0.000998	0.00 - 0.00473	1
AHERA-like Total Structures 3:1	4.9	0.00599	0.00220 - 0.0130	6
AHERA-like Asb Strucs >5 and 3:1	3.2	0.00399	0.00109 - 0.0102	4
AHERA-like Asb Strucs 5 - 10 and 3:1	2.4	0.00299	0.00 - 0.00773	3
AHERA-like Asb Strucs >10 and 3:1	0.8	0.000998	0.00 - 0.00473	1
Total Other Amphibole Strucs 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S45 A1
Client Sample No. JEB-L2-2CH-101004
Description
Analysis Date 10/30/2004
Analyst TM

Volume (L) 307.92
No. of Grid Openings 87
Filter Area (mm2) 385
Area Analyzed (mm2) 1.26
Analytical Sens. (struc/cc) 0.000992
Dectection Limit. (struc/cc) 0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	6.3	0.00793	0.00343 - 0.0156	8
Total Asbestos Structures	6.3	0.00793	0.00343 - 0.0156	8
Asbestos Structures > 5um	1.6	0.00198	0.00 - 0.00625	2
Asbestos Fibers and Bundles > 5um	1.6	0.00198	0.00 - 0.00625	2
PCM Equivalent Fibers-US	1.6	0.00198	0.00 - 0.00625	2
PCM Equivalent Structures-US	0.8	0.000992	0.00 - 0.00470	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Total Structures 3:1	6.3	0.00793	0.00343 - 0.0156	8
AHERA-like Asb Strucs >5 and 3:1	1.6	0.00198	0.00 - 0.00625	2
AHERA-like Asb Strucs 5 - 10 and 3:1	0.8	0.000992	0.00 - 0.00470	1
AHERA-like Asb Strucs >10 and 3:1	0.8	0.000992	0.00 - 0.00470	1
Total Other Amphibole Strucs 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S46 A1
Client Sample No. JEB-L2-3CH-101004
Description
Analysis Date 10/31/2004
Analyst KM

Volume (L) 307.44
No. of Grid Openings 87
Filter Area (mm2) 385
Area Analyzed (mm2) 1.26
Analytical Sens. (struc/cc) 0.000993
Dectection Limit. (struc/cc) 0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	5.6	0.00695	0.00280 - 0.0143	7
Total Asbestos Structures	5.6	0.00695	0.00280 - 0.0143	7
Asbestos Structures > 5um	2.4	0.00298	0.00 - 0.00770	3
Asbestos Fibers and Bundles > 5um	0.0	<0.00297	0.00 - 0.00297	0
PCM Equivalent Fibers-US	0.8	0.000993	0.00 - 0.00471	1
PCM Equivalent Structures-US	0.8	0.000993	0.00 - 0.00471	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Total Structures 3:1	5.6	0.00695	0.00280 - 0.0143	7
AHERA-like Asb Strucs >5 and 3:1	2.4	0.00298	0.00 - 0.00770	3
AHERA-like Asb Strucs 5 - 10 and 3:1	2.4	0.00298	0.00 - 0.00770	3
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Total Other Amphibole Strucs 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S47 A1
Client Sample No. JEB-L2-4CH-101004
Description
Analysis Date 10/31/2004
Analyst TM

Volume (L) 309.72
No. of Grid Openings 86
Filter Area (mm2) 385
Area Analyzed (mm2) 1.25
Analytical Sens. (struc/cc) 0.000998
Dectection Limit. (struc/cc) 0.00298

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	5.6	0.00698	0.00281 - 0.0144	7
Total Asbestos Structures	5.6	0.00698	0.00281 - 0.0144	7
Asbestos Structures > 5um	2.4	0.00299	0.00 - 0.00773	3
Asbestos Fibers and Bundles > 5um	0.0	<0.00298	0.00 - 0.00298	0
PCM Equivalent Fibers-US	0.0	<0.00298	0.00 - 0.00298	0
PCM Equivalent Structures-US	0.8	0.000998	0.00 - 0.00473	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00298	0.00 - 0.00298	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00298	0.00 - 0.00298	0
AHERA-like Total Structures 3:1	5.6	0.00698	0.00281 - 0.0144	7
AHERA-like Asb Strucs >5 and 3:1	2.4	0.00299	0.00 - 0.00773	3
AHERA-like Asb Strucs 5 - 10 and 3:1	2.4	0.00299	0.00 - 0.00773	3
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Total Other Amphibole Strucs 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00298	0.00 - 0.00298	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S48 A1
Client Sample No. JEB-L2-5CH-101004
Description
Analysis Date 10/31/2004
Analyst KM

Volume (L) 318.84
No. of Grid Openings 87
Filter Area (mm2) 385
Area Analyzed (mm2) 1.26
Analytical Sens. (struc/cc) 0.000958
Dectection Limit. (struc/cc) 0.00286

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	7.9	0.00958	0.00459 - 0.0176	10
Total Asbestos Structures	7.9	0.00958	0.00459 - 0.0176	10
Asbestos Structures > 5um	5.6	0.00670	0.00270 - 0.0138	7
Asbestos Fibers and Bundles > 5um	4.8	0.00575	0.00211 - 0.0125	6
PCM Equivalent Fibers-US	4.0	0.00479	0.00156 - 0.0112	5
PCM Equivalent Structures-US	4.8	0.00575	0.00211 - 0.0125	6
PROTOCOL ASB STRUCS 5-10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL ASB STRUCS >10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00286	0.00 - 0.00286	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00286	0.00 - 0.00286	0
AHERA-like Total Structures 3:1	7.9	0.00958	0.00459 - 0.0176	10
AHERA-like Asb Strucs >5 and 3:1	5.6	0.00670	0.00270 - 0.0138	7
AHERA-like Asb Strucs 5 - 10 and 3:1	4.8	0.00575	0.00211 - 0.0125	6
AHERA-like Asb Strucs >10 and 3:1	0.8	0.000958	0.00 - 0.00454	1
Total Other Amphibole Strucs 3:1	0.0	<0.00286	0.00 - 0.00286	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00286	0.00 - 0.00286	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00286	0.00 - 0.00286	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00286	0.00 - 0.00286	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S44 A1
Client Sample No. JEB-L2-1NA-101004
Description
Analysis Date 10/30/2004
Analyst JH

Volume (L) 316.56
No. of Grid Openings 84
Filter Area (mm2) 385
Area Analyzed (mm2) 1.22
Analytical Sens. (struc/cc) 0.000999
Dectection Limit. (struc/cc) 0.00299

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.00299	0.00 - 0.00299	0
Total Asbestos Structures	0.0	<0.00299	0.00 - 0.00299	0
Asbestos Structures > 5um	0.0	<0.00299	0.00 - 0.00299	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00299	0.00 - 0.00299	0
PCM Equivalent Fibers-US	0.0	<0.00299	0.00 - 0.00299	0
PCM Equivalent Structures-US	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00299	0.00 - 0.00299	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00299	0.00 - 0.00299	0
AHERA-like Total Structures 3:1	0.0	<0.00299	0.00 - 0.00299	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Total Other Amphibole Strucs 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00299	0.00 - 0.00299	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S75 A1
Client Sample No. JEB-L2-1ZP-101004
Description
Analysis Date 11/18/2004
Analyst JH

Volume (L) 299.89
No. of Grid Openings 8
Filter Area (mm2) 385
Area Analyzed (mm2) 0.116
Analytical Sens. (struc/cc) 0.0111
Dectection Limit. (struc/cc) 0.0331

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	948.9	1.22	1.00 - 1.47 (Poisson)	110
Total Asbestos Structures	1035.2	1.33	1.10 - 1.59 (Poisson)	120
Asbestos Structures > 5um	103.5	0.133	0.0687 - 0.232	12
Asbestos Fibers and Bundles > 5um	86.3	0.111	0.0531 - 0.204	10
PCM Equivalent Fibers-US	69.0	0.0886	0.0383 - 0.175	8
PCM Equivalent Structures-US	60.4	0.0775	0.0312 - 0.160	7
PROTOCOL ASB STRUCS 5-10	25.9	0.0332	0.00 - 0.0858	3
PROTOCOL ASB STRUCS >10	25.9	0.0332	0.00 - 0.0858	3
PROTOCOL ASB STRUCS TOTAL	51.8	0.0664	0.0244 - 0.145	6
PROTOCOL CHRYS STRUCS 5-10	17.3	0.0221	0.00 - 0.0698	2
PROTOCOL CHRYS STRUCS >10	8.6	0.0111	0.00 - 0.0525	1
PROTOCOL CHRYS STRUCS TOTAL	25.9	0.0332	0.00 - 0.0858	3
PROTOCOL AMPH STRUCS 5-10	8.6	0.0111	0.00 - 0.0525	1
PROTOCOL AMPH STRUCS >10	17.3	0.0221	0.00 - 0.0698	2
PROTOCOL AMPH STRUCS TOTAL	25.9	0.0332	0.00 - 0.0858	3
AHERA-like Total Structures 3:1	940.3	1.21	0.901 - 1.35 (Poisson)	109
AHERA-like Asb Strucs >5 and 3:1	103.5	0.133	0.0687 - 0.232	12
AHERA-like Asb Strucs 5 - 10 and 3:1	51.8	0.0664	0.0244 - 0.145	6
AHERA-like Asb Strucs >10 and 3:1	51.8	0.0664	0.0244 - 0.145	6
Total Other Amphibole Strucs 3:1	0.0	<0.0331	0.00 - 0.0331	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.0331	0.00 - 0.0331	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.0331	0.00 - 0.0331	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.0331	0.00 - 0.0331	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S38 A1
Client Sample No. CC9-L6-1CC-101004
Description
Analysis Date 10/28/2004
Analyst JH

Volume (L) 923.4
No. of Grid Openings 29
Filter Area (mm2) 385
Area Analyzed (mm2) 0.420
Analytical Sens. (struc/cc) 0.000992
Dectection Limit. (struc/cc) 0.00297

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	2.4	0.000992	0.00 - 0.00470	1
Total Asbestos Structures	2.4	0.000992	0.00 - 0.00470	1
Asbestos Structures > 5um	0.0	<0.00297	0.00 - 0.00297	0
Asbestos Fibers and Bundles > 5um	0.0	<0.00297	0.00 - 0.00297	0
PCM Equivalent Fibers-US	0.0	<0.00297	0.00 - 0.00297	0
PCM Equivalent Structures-US	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00297	0.00 - 0.00297	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Total Structures 3:1	2.4	0.000992	0.00 - 0.00470	1
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Total Other Amphibole Strucs 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00297	0.00 - 0.00297	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-1FD-101004 *Lab/Cor Sample No.:* B4773 S102 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A2		NSD									
A	2	A31		NSD									
A	3	B32		NSD									
A	4	B1		NSD									
A	5	C3		NSD									
A	6	C22		NSD									
A	7	D30		NSD									
A	8	D42		NSD									
A	9	D22		NSD									
B	10	A21		NSD									
B	11	A40		NSD									
B	12	B11		NSD									
B	13	C3		NSD									
B	14	C11		NSD									
B	15	C30		NSD									
B	16	D41		NSD									
B	17	D23		NSD									
B	18	D1		NSD									
B	19	A3		NSD									
B	20	A24		NSD									
B	21	A30		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-2FD-101004 *Lab/Cor Sample No.:* B4773 S103 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	CDQ	1	1	F	1.1	0.05	22	1067	15399	Mg, Si Chrysotile Verified - JH	TAS_AHRA
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	C43		NSD									
A	7	C23		NSD									
A	8	C3		NSD									
A	9	B13		NSD									
A	10	B33		NSD									
A	11	B42		NSD									
B	12	B44		NSD									
B	13	B24	AZQ	2	2	F	3	0.9	3.3	1078	15400	Mg, Si, Ca, Fe Actinolite Zone Axis [1 1 1] - JH	TAS_AHRA
B	14	B4		NSD									
B	15	C14		NSD									
B	16	C34		NSD									
B	17	C43		NSD									
B	18	C23		NSD									
B	19	C3		NSD									
B	20	B13		NSD									
B	21	B33		NSD									
B	22	B42		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H2-4FD-101004 *Lab/Cor Sample No.:* B4773 S105 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B34		NSD									
A	3	B14		NSD									
A	4	B4		NSD									
A	5	C4		NSD									
A	6	C14		NSD									
A	7	C44		NSD									
A	8	C32		NSD									
A	9	C12		NSD									
A	10	C1		NSD									
A	11	B11		NSD									
A	12	A10		NSD									
B	13	A20		NSD									
B	14	A40		NSD									
B	15	A1		NSD									
B	16	D11	AZQ	1	1	B	2.5	2	1.2	1068	15408	Mg, Si, Ca, Fe Actinolite Zone Axis [1 0 2] - JH	TAS_AHRA
B	17	D30		NSD									
B	18	C41		NSD									
B	19	C21		NSD									
B	20	C11		NSD									
B	21	B1		NSD									
B	22	B21		NSD									
B	23	B41		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-6FD-101004 *Lab/Cor Sample No.:* B4773 S41 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B34		NSD									
A	2	B12	AQ	1	1	F	9.5	1.75	5.4		15268	Mg, Al, Si, Ca, Fe Actinolite Intersects left grid bar	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	C24		NSD									
A	4	C22		NSD									
A	5	D40	AZQ	2	2	B	4.5	1.25	3.6	5367	15269	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [3.1.1] - KM	TAS_AHRA
A	6	D33		NSD									
A	7	A42		NSD									
A	8	A2	AQ	3		MD1-1	15.5	10	1.5			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	8	A2	AQ		3	MF	5.25	0.45	12			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT
A	8	A2	AQ	4	4	F	11.5	3.5	3.3			Mg, Al, Si, Ca, Fe Actinolite Ferri-actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	8	A2	AQ	5	5	F	14.5	2.25	6.4			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	9	A22	AQ	6	6	F	15.25	3	5.1			Mg, Al, Si, Ca, Fe Actinolite Ferri-actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	10	C4	AQ	7	7	F	9	1.5	6.0			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	11	D21	AQ	8		MD1-0	9.5	6	1.6			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	11	D21	AQ		8	MF	1.8	0.4	4.5			Mg, Al, Si, Ca, Fe Actinolite	
B	12	B44		NSD									
B	13	B12	AQ	9		MD1-1	8	2	4.0			Actinolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	13	B12	AQ		9	MF	8	1.25	6.4			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	13	B12	AQ	10	10	F	14	1.25	11			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	14	C20		NSD									
B	15	C1		NSD									
B	16	D41		NSD									
B	17	D2		NSD									
B	18	A33		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-6FD-101004 *Lab/Cor Sample No.:* B4773 S41 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	19	A20		NSD									
B	20	C23		NSD									
B	21	D11		NSD									
B	22	A20		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-6FD-101004 *Lab/Cor Sample No.:* B4763 S30 A1

Descripiton: Duplicate Analysis of 041191-41 - Reprep

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B43		NSD									
A	2	B23	AQ	1	1	F	6	2	3.0			Mg, Si, Ca, Fe Actinolite	
A	3	B3		NSD									
A	4	C13		NSD									
A	5	C33		NSD									
A	6	B41		NSD									
A	7	B21		NSD									
A	8	C1		NSD									
A	9	C31		NSD									
A	10	A41		NSD									
A	11	A11	ADQ	2	2	F	8.5	0.9	9.4			Mg, Si, Ca, Fe Actinolite	
B	12	B33		NSD									
B	13	B13		NSD									
B	14	C3	ADQ	3	3	F	6	1.8	3.3			Mg, Si, Ca, Fe Actinolite	
B	14	C3	CD	4	4	F	0.6	0.1	6.0			Mg, Si Chrysotile	
B	15	B31		NSD									
B	16	B11		NSD									
B	17	C1		NSD									
B	18	A41		NSD									
B	19	A21		NSD									
B	20	A1		NSD									
B	21	A40		NSD									
B	22	A20	ADQ	5	5	F	14	4.5	3.1			Mg, Si, Ca, Fe Actinolite	
B	22	A20	ADQ	6	6	F	1.3	0.35	3.7			Mg, Si, Ca, Fe Actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-7FD-101004 *Lab/Cor Sample No.:* B4773 S42 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B34		NSD									
A	2	B14		NSD									
A	3	B43		NSD									
A	4	B23		NSD									
A	5	B3		NSD									
A	6	B32		NSD									
A	7	B12		NSD									
A	8	B41		NSD									
A	9	B21		NSD									
A	10	B1		NSD									
A	11	B40		NSD									
A	12	A31		NSD									
A	13	A21		NSD									
A	14	A30	AQ	1		MD1-1	11	10	1.1			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	14	A30	AQ		1	MF	10	0.8	12		694	Mg,Al,Si,Ca,Fe Actinolite fiber too dense for diffraction	AFB>5, PCMEF-US
A	15	A40		NSD									
B	16	B43		NSD									
B	17	B23		NSD									
B	18	B3		NSD									
B	19	C13		NSD									
B	20	C33		NSD									
B	21	B31		NSD									
B	22	B11		NSD									
B	23	C1		NSD									
B	24	C21		NSD									
B	25	C41	AZQ	2	2	F	4.5	1	4.5	956	695	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [5 1 6] - KM	TAS_AHRA
B	26	A41		NSD									
B	27	A21		NSD									
B	28	A1		NSD									
B	29	D11		NSD									
B	30	D31		NSD									
C	31	B23		NSD									
C	32	B3		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H1-7FD-101004 *Lab/Cor Sample No.:* B4773 S42 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	33	C13		NSD									
C	34	C33	AQ	3	3	F	4.7	1.5	3.1			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	35	B31		NSD									
C	36	B11		NSD									
C	37	C1		NSD									
C	38	C21		NSD									
C	39	C41		NSD									
C	40	A41		NSD									
C	41	A21		NSD									
C	42	A1		NSD									
C	43	D11		NSD									
C	44	D21		NSD									
C	45	D41		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H2-5EFD-101004 *Lab/Cor Sample No.:* B4773 S106 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B34		NSD									
A	3	B24		NSD									
A	4	B14		NSD									
A	5	B4	AZQ	1	1	F	7.5	2	3.8	1080	15415	Mg, Si, Ca, Fe Actinolite Zone Axis [4 0 3] - JH	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	C4		NSD									
A	7	C14		NSD									
A	8	C24		NSD									
A	9	C34		NSD									
A	10	C44		NSD									
A	11	C43		NSD									
A	12	C42		NSD									
A	13	C32		NSD									
A	14	C22		NSD									
A	15	C12		NSD									
A	16	C2		NSD									
A	17	B2		NSD									
A	18	B12		NSD									
A	19	B22		NSD									
A	20	B32		NSD									
A	21	B42		NSD									
A	22	B41		NSD									
A	23	B21		NSD									
A	24	B1		NSD									
B	25	B44		NSD									
B	26	B34		NSD									
B	27	B24		NSD									
B	28	B14		NSD									
B	29	B4		NSD									
B	30	C4		NSD									
B	31	C14		NSD									
B	32	C24		NSD									
B	33	C34		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H2-5EFD-101004 *Lab/Cor Sample No.:* B4773 S106 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	34	C44	AQ	2	2	F	13	2.5	5.2			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	35	C42		NSD									
B	36	C32		NSD									
B	37	C22		NSD									
B	38	C2		NSD									
B	39	B2		NSD									
B	40	B12		NSD									
B	41	B22		NSD									
B	42	B32		NSD									
B	43	B42		NSD									
B	44	B40		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H2-5WFD-101004 *Lab/Cor Sample No.:* B4773 S107 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B34		NSD									
A	3	B24		NSD									
A	4	B14		NSD									
A	5	B4		NSD									
A	6	C4		NSD									
A	7	C14		NSD									
A	8	C24		NSD									
A	9	C34		NSD									
A	10	C44		NSD									
A	11	C42		NSD									
A	12	C32		NSD									
A	13	C22		NSD									
A	14	C12		NSD									
A	15	C2		NSD									
A	16	B2	AZQ	1	1	F	9	0.85	11	1081	15417	Mg, Si, Ca, Fe Actinolite Zone Axis [2 0 1] - JH	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	17	B12		NSD									
A	18	B22		NSD									
A	19	B32		NSD									
A	20	B42		NSD									
A	21	B40		NSD									
A	22	B30		NSD									
A	23	B20		NSD									
B	24	B41		NSD									
B	25	B31		NSD									
B	26	B21		NSD									
B	27	B11		NSD									
B	28	B1		NSD									
B	29	C1		NSD									
B	30	C11		NSD									
B	31	C21	AQ	2	2	F	2.5	0.5	5.0		15418	Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	32	C31		NSD									
B	33	C41		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-H2-5WFD-101004 *Lab/Cor Sample No.:* B4773 S107 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	34	C43		NSD									
B	35	C33		NSD									
B	36	C23		NSD									
B	37	C13		NSD									
B	38	C3		NSD									
B	39	B3		NSD									
B	40	B13		NSD									
B	41	B23		NSD									
B	42	B33		NSD									
B	43	B43		NSD									
B	44	B34		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1CH-101004 *Lab/Cor Sample No.:* B4773 S43 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	B33		NSD									
A	7	B13		NSD									
A	8	C3		NSD									
A	9	C23		NSD									
A	10	C43	AZQ	1	1	F	3.5	0.8	4.4	957	696	Mg, Al, Si, Ca, Fe Actinolite Alumino-actinolite - Zone Axis [5 1 4] - KM	TAS_AHRA
A	10	C43	AQ	2	2	F	7.5	1.2	6.2			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	11	B42		NSD									
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C43		NSD									
A	16	B31		NSD									
A	17	B11		NSD									
A	18	C1		NSD									
A	19	C21		NSD									
A	20	C41		NSD									
A	21	A41		NSD									
A	22	A21		NSD									
A	23	A1		NSD									
A	24	D11		NSD									
A	25	D31		NSD									
A	26	A31		NSD									
A	27	A11		NSD									
A	28	D1		NSD									
A	29	D21		NSD									
B	30	B44		NSD									
B	31	B24		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1CH-101004 *Lab/Cor Sample No.:* B4773 S43 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	32	B14		NSD									
B	33	C4		NSD									
B	34	C24		NSD									
B	35	C44		NSD									
B	36	B33		NSD									
B	37	B13		NSD									
B	38	C3		NSD									
B	39	C23		NSD									
B	40	C43		NSD									
B	41	B32		NSD									
B	42	B12		NSD									
B	43	C2		NSD									
B	44	C22		NSD									
B	45	C42		NSD									
B	46	B41	AQ	3	3	F	13	3	4.3			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	47	B21		NSD									
B	48	B1		NSD									
B	49	C11		NSD									
B	50	C31		NSD									
B	51	A31		NSD									
B	52	A11		NSD									
B	53	D21		NSD									
B	54	D31		NSD									
B	55	D41		NSD									
B	56	A42		NSD									
B	57	D22		NSD									
C	58	B43		NSD									
C	59	B23		NSD									
C	60	B3		NSD									
C	61	C13		NSD									
C	62	C33		NSD									
C	63	C43		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1CH-101004 *Lab/Cor Sample No.:* B4773 S43 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	64	C41	ADQ	4	4	F	6	0.3	20			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	65	C21		NSD									
C	66	C1		NSD									
C	67	B11		NSD									
C	68	B31		NSD									
C	69	B41	AQ	5	5	F	4.9	0.8	6.1			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	70	A30		NSD									
C	71	A10		NSD									
C	72	D10		NSD									
C	73	D30		NSD									
C	74	D40		NSD									
C	75	D42		NSD									
C	76	D22		NSD									
C	77	D2		NSD									
C	78	A12		NSD									
C	79	A32		NSD									
C	80	A42	AQ	6	6	F	9.8	2.7	3.6			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	81	A44		NSD									
C	82	A14		NSD									
C	83	D4		NSD									
C	84	D2		NSD									
C	85	D22		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-2CH-101004 *Lab/Cor Sample No.:* B4773 S45 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B24		NSD									
A	2	B4		NSD									
A	3	C14		NSD									
A	4	C34		NSD									
A	5	C33		NSD									
A	6	C13		NSD									
A	7	B13		NSD									
A	8	B33		NSD									
A	9	B32		NSD									
A	10	B12		NSD									
A	11	C2		NSD									
A	12	C22		NSD									
A	13	C41		NSD									
A	14	C21		NSD									
A	15	C1		NSD									
A	16	B11		NSD									
A	17	B31		NSD									
A	18	B40		NSD									
A	19	B20		NSD									
A	20	C10		NSD									
A	21	C30		NSD									
A	22	D20		NSD									
A	23	A20		NSD									
A	24	A40		NSD									
A	25	A41	CDQ	1	1	B	1.75	0.25	7.0	5368	15270	Mg, Si, Fe Chrysotile Verified - KM	TAS_AHRA
A	26	A21		NSD									
A	27	A1		NSD									
A	28	A12		NSD									
A	29	A32		NSD									
B	30	B44		NSD									
B	31	B24		NSD									
B	32	B4	CD	2		MD1-0	2	1	2.0			Chrysotile	TAS_AHRA
B	32	B4	CD		2	MF	1.2	0.05	24			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-2CH-101004 *Lab/Cor Sample No.:* B4773 S45 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	33	C14		NSD									
B	34	C13		NSD									
B	35	B3		NSD									
B	36	B23		NSD									
B	37	B43		NSD									
B	38	B42		NSD									
B	39	B22		NSD									
B	40	C2	AQ	3	3	F	3	0.6	5.0			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
B	41	C22	AZQ	4	4	F	2.6	0.45	5.8	5369	15271	Mg, Si, Ca, Fe Actinolite Zone Axis [9 1 6] - KM	TAS_AHRA
B	42	C41		NSD									
B	43	C21		NSD									
B	44	C1	AQ	5		MD1-1	11	4	2.8			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	44	C1	AQ		5	MF	9.5	1.2	7.9			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	45	B11		NSD									
B	46	B31		NSD									
B	47	B40	AQ	6	6	F	6.25	2	3.1			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	48	B20		NSD									
B	49	C10		NSD									
B	50	C30		NSD									
B	51	D40		NSD									
B	52	D20		NSD									
B	53	A10		NSD									
B	54	A30		NSD									
B	55	A41		NSD									
B	56	A21		NSD									
B	57	A1		NSD									
B	58	D11		NSD									
C	59	B44		NSD									
C	60	B24		NSD									
C	61	B4		NSD									
C	62	C14		NSD									
C	63	C34		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-2CH-101004 *Lab/Cor Sample No.:* B4773 S45 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	64	C43		NSD									
C	65	C23		NSD									
C	66	C3		NSD									
C	67	B13	AQ	7	7	F	1.25	0.25	5.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	67	B13	AQ	8	8	F	1.75	0.35	5.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	68	B33		NSD									
C	69	B42		NSD									
C	70	B22		NSD									
C	71	B2		NSD									
C	72	C12		NSD									
C	73	C32		NSD									
C	74	C41		NSD									
C	75	C21		NSD									
C	76	C1		NSD									
C	77	B11		NSD									
C	78	B31		NSD									
C	79	B40		NSD									
C	80	B20		NSD									
C	81	C10		NSD									
C	82	C30		NSD									
C	83	D40		NSD									
C	84	D20		NSD									
C	85	A10		NSD									
C	86	A30		NSD									
C	87	A41		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-3CH-101004 *Lab/Cor Sample No.:* B4773 S46 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B34		NSD									
A	2	B14		NSD									
A	3	C4		NSD									
A	4	B43		NSD									
A	5	B23	AZQ	1	1	F	3.5	1	3.5	966	698	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [3 1 0] - KM	TAS_AHRA
A	6	B3	AZQ	2		MD1-0	9.5	6	1.6			Tremolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	B3	AZQ		2	MF	2	0.3	6.7	967	699	Mg, Al, Si, Ca, Fe Tremolite Zone Axis [5 -1 0] - KM	
A	7	C13		NSD									
A	8	B32		NSD									
A	9	B12		NSD									
A	10	C2		NSD									
A	11	C22		NSD									
A	12	B41		NSD									
A	13	B31		NSD									
A	14	B11		NSD									
A	15	C1		NSD									
A	16	C21		NSD									
A	17	A41		NSD									
A	18	A21		NSD									
A	19	A1		NSD									
A	20	D11		NSD									
A	21	D31	ADQ	3	3	F	4.2	0.7	6.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	22	A32		NSD									
A	23	A12		NSD									
A	24	D2		NSD									
A	25	D22		NSD									
A	26	D42		NSD									
A	27	B40		NSD									
A	28	B20		NSD									
A	29	A10		NSD									
B	30	B24		NSD									
B	31	B14		NSD									
B	32	B4		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-3CH-101004 *Lab/Cor Sample No.:* B4773 S46 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	33	C14	CD	4		MD1-0	6	6	1.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	33	C14	CD		4	MB	1.1	0.15	7.3	968		Chrysotile tilts into matrix - Verified - KM	
B	34	C34		NSD									
B	35	B43		NSD									
B	36	B13		NSD									
B	37	C3		NSD									
B	38	C23		NSD									
B	39	C43		NSD									
B	40	B42		NSD									
B	41	B22		NSD									
B	42	B2		NSD									
B	43	C12		NSD									
B	44	C32		NSD									
B	45	B31		NSD									
B	46	B11		NSD									
B	47	C1		NSD									
B	48	C21		NSD									
B	49	C41		NSD									
B	50	A41		NSD									
B	51	A21		NSD									
B	52	A1		NSD									
B	53	D11		NSD									
B	54	A42		NSD									
B	55	A32		NSD									
B	56	A12		NSD									
B	57	D2		NSD									
B	58	B10		NSD									
C	59	B34		NSD									
C	60	B14		NSD									
C	61	C4		NSD									
C	62	C24	ADQ	5	5	B	5.2	1.2	4.3			Mg, Al, Si, Ca, Fe Actinolite	AS>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	63	C44		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-3CH-101004 *Lab/Cor Sample No.:* B4773 S46 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	64	B43		NSD									
C	65	B23		NSD									
C	66	B3		NSD									
C	67	C13		NSD									
C	68	C33		NSD									
C	69	B32		NSD									
C	70	B12		NSD									
C	71	C2		NSD									
C	72	C22		NSD									
C	73	C42		NSD									
C	74	B41		NSD									
C	75	B21		NSD									
C	76	B2		NSD									
C	77	C12		NSD									
C	78	C32		NSD									
C	79	A31		NSD									
C	80	A11	AQ	6	6	F	2.5	0.6	4.2			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	80	A11	AQ	7	7	B	1.8	0.5	3.6			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	81	D1		NSD									
C	82	D21		NSD									
C	83	D41		NSD									
C	84	A32		NSD									
C	85	A22		NSD									
C	86	A2		NSD									
C	87	D12		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-4CH-101004 *Lab/Cor Sample No.:* B4773 S47 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14		NSD									
A	5	C34		NSD									
A	6	C33		NSD									
A	7	C13	AZQ	1	1	F	3	0.6	5.0	5371	15272	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [5 1 0] - KM	TAS_AHRA
A	7	C13	CDQ	2		MD1-0	5.75	3	1.9			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	7	C13	CDQ		2	MF	1.75	0.05	35	5372	15273	Mg, Si, Fe Chrysotile Verified - KM	
A	8	B3	AQ	3	3	F	4	0.75	5.3			Actinolite	TAS_AHRA
A	9	B23		NSD									
A	10	B43		NSD									
A	11	B42		NSD									
A	12	B22		NSD									
A	13	B2		NSD									
A	14	C12		NSD									
A	15	C32		NSD									
A	16	C41		NSD									
A	17	C21		NSD									
A	18	C1		NSD									
A	19	B11		NSD									
A	20	B31		NSD									
A	21	B40	AQ	4		MD1-0	7	4.75	1.5			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	21	B40	AQ		4	MF	3	0.25	12			Mg, Al, Si, Ca, Fe Actinolite	
A	22	B20		NSD									
A	23	C10		NSD									
A	24	C30		NSD									
A	25	D40		NSD									
A	26	D20		NSD									
A	27	A10		NSD									
A	28	A30		NSD									
A	29	A41		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-4CH-101004 *Lab/Cor Sample No.:* B4773 S47 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	30	B34		NSD									
B	31	B14		NSD									
B	32	C4		NSD									
B	33	C24		NSD									
B	34	C44		NSD									
B	35	C43		NSD									
B	36	C23		NSD									
B	37	C3	AQ	5		MD1-1	8.25	2.75	3.0			Actinolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	37	C3	AQ		5	MF	5	0.75	6.7			Mg, Al, Si, Ca, Fe Actinolite	
B	38	B13		NSD									
B	39	B33		NSD									
B	40	B42		NSD									
B	41	B22		NSD									
B	42	B2		NSD									
B	43	C12		NSD									
B	44	C32		NSD									
B	45	C41		NSD									
B	46	C21		NSD									
B	47	C1		NSD									
B	48	B11		NSD									
B	49	B31		NSD									
B	50	B41		NSD									
B	51	A40		NSD									
B	52	A20	AQ	6	6	F	4.5	0.65	6.9		710	Mg, Al, Si, Ca, Fe Actinolite Ferrianactinolite	TAS_AHRA
B	53	A10		NSD									
B	54	D10		NSD									
B	55	D30		NSD									
B	56	D40		NSD									
B	57	D42		NSD									
B	58	D22		NSD									
B	59	D2		NSD									
B	60	A12		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-4CH-101004 *Lab/Cor Sample No.:* B4773 S47 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	61	A44		NSD									
C	62	A24		NSD									
C	63	A4		NSD									
C	64	D14		NSD									
C	65	D34		NSD									
C	66	D44		NSD									
C	67	D42		NSD									
C	68	D22		NSD									
C	69	D2		NSD									
C	70	A12		NSD									
C	71	A42		NSD									
C	72	A40		NSD									
C	73	A20		NSD									
C	74	A10		NSD									
C	75	D10		NSD									
C	76	C21		NSD									
C	77	C1		NSD									
C	78	B11		NSD									
C	79	B31		NSD									
C	80	B41	AQ	7	7	F	1.7	0.4	4.2			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	81	B43		NSD									
C	82	B23		NSD									
C	83	B3		NSD									
C	84	C13		NSD									
C	85	C33		NSD									
C	86	C43		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-5CH-101004 *Lab/Cor Sample No.:* B4773 S48 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B34		NSD									
A	3	B24		NSD									
A	4	B14		NSD									
A	5	B4	AZQ	1	1	F	6.2	0.6	10	969	700	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [1 3 4] - KM	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	B43	CDQ	2	2	F	1	0.1	10	970	701	Mg, Si Chrysotile Verified - KM	TAS_AHRA
A	7	B33		NSD									
A	8	B23		NSD									
A	9	B13		NSD									
A	10	B3		NSD									
A	11	B42		NSD									
A	12	B32		NSD									
A	13	B22		NSD									
A	14	B12		NSD									
A	15	B2		NSD									
A	16	B41		NSD									
A	17	B31		NSD									
A	18	B21	ADQ	3	3	F	4	0.6	6.7			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	19	B11		NSD									
A	20	B1		NSD									
A	21	A41		NSD									
A	22	A31		NSD									
A	23	A21		NSD									
A	24	A11		NSD									
A	25	A1		NSD									
A	26	A42		NSD									
A	27	A22		NSD									
A	28	A12		NSD									
B	29	B34		NSD									
B	30	B24		NSD									
B	31	B14		NSD									
B	32	B4		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-5CH-101004 *Lab/Cor Sample No.:* B4773 S48 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	33	C14	AQ	4	4	F	9	1.2	7.5			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	34	C24		NSD									
B	35	C34		NSD									
B	36	C44		NSD									
B	37	C33		NSD									
B	38	C23		NSD									
B	39	C13		NSD									
B	40	C3		NSD									
B	41	B3	AQ	5		MD1-0	6	1.5	4.0			Mg, Al, Si, Ca, Fe Actinolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	41	B3	AQ		5	MF	5	0.75	6.7			Mg, Al, Si, Ca, Fe Actinolite	
B	42	B13		NSD									
B	43	B23		NSD									
B	44	B33		NSD									
B	45	B42	AQ	6	6	F	20	4.5	4.4			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	46	B22		NSD									
B	47	B12	AQ	7	7	F	7.5	1.5	5.0			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	47	B12	AQ	8		MD1-1	7.5	2	3.8			Actinolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	47	B12	AQ		8	MF	7.5	1.2	6.2			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	48	B2		NSD									
B	49	C12		NSD									
B	50	C22		NSD									
B	51	C42		NSD									
B	52	C31		NSD									
B	53	C21		NSD									
B	54	C11		NSD									
B	55	C1		NSD									
B	56	B11		NSD									
C	57	B43		NSD									
C	58	B33		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-5CH-101004 *Lab/Cor Sample No.:* B4773 S48 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	59	B23		NSD									
C	60	B13		NSD									
C	61	B3		NSD									
C	62	C3		NSD									
C	63	C13		NSD									
C	64	C23		NSD									
C	65	C33		NSD									
C	66	C43		NSD									
C	67	B42	AZQ	9	9	F	6	1	6.0	5374	15275	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [1 -1 2] - KM	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	68	B32		NSD									
C	69	B22		NSD									
C	70	B12		NSD									
C	71	B2		NSD									
C	72	C2		NSD									
C	73	C12		NSD									
C	74	C22		NSD									
C	75	C32		NSD									
C	76	C42		NSD									
C	77	C41		NSD									
C	78	C31		NSD									
C	79	C21		NSD									
C	80	C11		NSD									
C	81	C1		NSD									
C	82	B1	AQ	10	10	F	4.5	1.2	3.7			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	83	B11		NSD									
C	84	B21		NSD									
C	85	B31		NSD									
C	86	B41		NSD									
C	87	B40		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1NA-101004 *Lab/Cor Sample No.:* B4773 S44 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A43		NSD									
A	2	A23		NSD									
A	3	A3		NSD									
A	4	D13		NSD									
A	5	D33		NSD									
A	6	D43		NSD									
A	7	D41		NSD									
A	8	D21		NSD									
A	9	D1		NSD									
A	10	A11		NSD									
A	11	A31		NSD									
A	12	A41		NSD									
A	13	B40		NSD									
A	14	B20		NSD									
A	15	B10		NSD									
A	16	C10		NSD									
A	17	C30		NSD									
A	18	C40		NSD									
A	19	C42		NSD									
A	20	C22		NSD									
A	21	C2		NSD									
A	22	B12		NSD									
A	23	B32		NSD									
A	24	B42		NSD									
A	25	B44		NSD									
A	26	B24		NSD									
A	27	B14		NSD									
A	28	C24		NSD									
B	29	A44		NSD									
B	30	A24		NSD									
B	31	A4		NSD									
B	32	D14		NSD									
B	33	D34		NSD									
B	34	D42		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1NA-101004 *Lab/Cor Sample No.:* B4773 S44 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	35	D22		NSD									
B	36	D2		NSD									
B	37	A12		NSD									
B	38	A32		NSD									
B	39	A42		NSD									
B	40	A40		NSD									
B	41	A20		NSD									
B	42	A10		NSD									
B	43	D10		NSD									
B	44	D30		NSD									
B	45	D40		NSD									
B	46	C41		NSD									
B	47	C21		NSD									
B	48	C1		NSD									
B	49	B11		NSD									
B	50	B31		NSD									
B	51	B41		NSD									
B	52	B43		NSD									
B	53	B23		NSD									
B	54	B3		NSD									
B	55	C13		NSD									
B	56	C23		NSD									
C	57	A43		NSD									
C	58	A23		NSD									
C	59	A3		NSD									
C	60	D13		NSD									
C	61	D43		NSD									
C	62	D41		NSD									
C	63	D21		NSD									
C	64	D1		NSD									
C	65	A11		NSD									
C	66	A31		NSD									
C	67	A41		NSD									
C	68	B40		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1NA-101004 *Lab/Cor Sample No.:* B4773 S44 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	69	B30		NSD									
C	70	B10		NSD									
C	71	C10		NSD									
C	72	C30		NSD									
C	73	C42		NSD									
C	74	C22		NSD									
C	75	C2		NSD									
C	76	B12		NSD									
C	77	B32		NSD									
C	78	B42		NSD									
C	79	B44		NSD									
C	80	B24		NSD									
C	81	B4		NSD									
C	82	C14		NSD									
C	83	C34		NSD									
C	84	C43		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1ZP-101004 *Lab/Cor Sample No.:* B4773 S75 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A22	CDQ	1	1	B	1.4	0.1	14	1065	771	Mg, Si Chrysotile Verified - DW	TAS_AHRA
A	1	A22	AZQ	2	2	F	1.7	0.5	3.4	5559	15432	Mg, Si, Ca, Fe Actinolite Zone Axis - [1 0 0] - DW	TAS_AHRA
A	1	A22	AQ	3	3	F	1.2	0.3	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	1	A22	AQ	4	4	F	2.8	0.5	5.6			Mg, Si, Ca Tremolite	TAS_AHRA
A	1	A22	CD	5	5	F	2.5	0.05	50			Chrysotile	TAS_AHRA
A	1	A22	AQ	6	6	F	2.7	0.4	6.8			Mg, Si, Ca Tremolite	TAS_AHRA
A	1	A22	AQ	7	7	F	6.5	0.7	9.3			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	A22	CD	8	8	F	2.2	0.05	44			Chrysotile	TAS_AHRA
A	1	A22	CD	9	9	B	4	0.25	16			Chrysotile	TAS_AHRA
A	1	A22	CD	10		MD2-0	1.1	1	1.1			Chrysotile	TAS_AHRA
A	1	A22	CD		10	MF	1.1	0.04	28			Chrysotile	
A	1	A22	CD		11	MB	1	0.08	12			Chrysotile	
A	1	A22	AQ	11	12	F	8	0.3	27			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	A22	AQ	12	13	F	1.2	0.25	4.8			Tremolite	TAS_AHRA
A	1	A22	CMQ	13	14	F	4	0.05	80			Mg, Si Chrysotile	TAS_AHRA
A	1	A22	CD	14	15	F	1.7	0.05	34			Chrysotile	TAS_AHRA
A	1	A22	AQ	15	16	F	1.1	0.25	4.4			Mg, Si, Ca Tremolite	TAS_AHRA
A	1	A22	AQ	16	17	F	1.5	0.4	3.8			Mg, Si, Ca Tremolite	TAS_AHRA
A	1	A22	AQ	17	18	F	5.5	0.7	7.9			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	A22	AQ	18	19	F	5	0.2	25			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AZQ	19	20	F	3.6	0.5	7.2	5560	15433	Mg, Si, Ca Tremolite Zone Axis - [3 1 0] - DW	TAS_AHRA
A	2	B2	AQ	20	21	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	21	22	F	1.5	0.3	5.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	CDQ	22	23	B	2.4	0.3	8.0			Mg, Si Chrysotile	TAS_AHRA
A	2	B2	AQ	23	24	F	2.8	0.7	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	24	25	B	4.9	0.7	7.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	25	26	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	26	27	F	2.7	0.4	6.8			Mg, Si, Ca Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1ZP-101004 *Lab/Cor Sample No.:* B4773 S75 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	2	B2	CDQ	27		CD3-0	1	0.8	1.2			Chrysotile	TAS_AHRA
A	2	B2	CDQ		28	CB	1	0.4	2.5			Mg, Si Chrysotile	
A	2	B2	CDQ		29	CF	1	0.05	20			Mg, Si Chrysotile	
A	2	B2	CDQ		30	CF	0.8	0.05	16			Mg, Si Chrysotile	
A	2	B2	AQ	28	31	F	4	0.4	10			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	29	32	F	2.4	0.2	12			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	B2	AQ	30	33	F	1.5	0.4	3.8			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	CDQ	31	34	B	18	11	1.6			Mg, Si Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	3	C30	AQ	32	35	F	2.4	0.45	5.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	AQ	33	36	F	2.4	0.3	8.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	CDQ	34	37	F	1.5	0.05	30			Mg, Si Chrysotile	TAS_AHRA
B	3	C30	AQ	35	38	F	1	0.2	5.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	AQ	36	39	F	0.7	0.2	3.5			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	AQ	37	40	B	2.6	0.5	5.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	AQ	38	41	F	3	0.6	5.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	C30	AQ	39	42	B	4.8	0.4	12			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	CDQ	40	43	CC5-0	1	0.8	1.2			Mg, Si Chrysotile	
B	4	D12	AQ	41	44	B	2.6	0.4	6.5			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	42	45	F	2.6	0.6	4.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	43	46	B	2.7	0.4	6.8			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	CDQ	44	47	B	2.3	0.07	33			Mg, Si Chrysotile	TAS_AHRA
B	4	D12	AQ	45	48	F	0.8	0.25	3.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	46	49	F	2.7	0.6	4.5			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	47	50	F	2.5	0.6	4.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	CDQ	48	51	F	3.5	0.04	88			Mg, Si Chrysotile	TAS_AHRA
B	4	D12	AQ	49	52	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	50	53	F	2.5	0.3	8.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	51	54	F	16	0.4	40			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS >10, PSAS TOT, PSAM >10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	4	D12	AQ	52	55	F	1.6	0.4	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	53	56	F	2.6	0.3	8.7			Mg, Si, Ca Tremolite	TAS_AHRA
B	4	D12	AQ	54	57	F	2.3	0.7	3.3			Mg, Si, Ca Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1ZP-101004 *Lab/Cor Sample No.:* B4773 S75 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	4	D12	CDQ	55	58	F	1.5	0.05	30			Mg, Si Chrysotile	TAS_AHRA
B	5	A10	AQ	56	59	F	2.5	0.6	4.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	5	A10	CDQ	57	60	F	0.6	0.05	12			Mg, Si Chrysotile	TAS_AHRA
B	5	A10	CDQ	58	61	F	0.55	0.05	11			Mg, Si Chrysotile	TAS_AHRA
B	5	A10	CDQ	59	62	F	0.5	0.05	10			Mg, Si Chrysotile	TAS_AHRA
B	5	A10	AQ	60	63	B	8	2.5	3.2			Mg, Si, Ca Tremolite	AS>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	5	A10	AQ	61	64	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	5	A10	AQ	62	65	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	5	A10	CDQ	63		MD3-0	5	2	2.5			Chrysotile	TAS_AHRA
B	5	A10	CDQ		66	MF	5	0.05	100			Mg, Si Chrysotile	
B	5	A10	CDQ		67	MB	2.3	1.5	1.5			Mg, Si Chrysotile	
B	5	A10	CDQ		68	MF	1.1	0.05	22			Mg, Si Chrysotile	
B	5	A10	AQ	64	69	F	1.2	0.4	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	AQ	65	70	F	1	0.3	3.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	AQ	66	71	F	1.3	0.4	3.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	CD	67		CD3-1	5.2	3	1.7			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	6	B23	CD		72	CB	5.2	0.1	52			Chrysotile	AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
B	6	B23	CD		73	CB	4.5	0.1	45			Chrysotile	
B	6	B23	CD		74	CF	0.6	0.05	12			Chrysotile	
B	6	B23	CDQ	68	75	F	4.8	0.05	96			Chrysotile	TAS_AHRA
B	6	B23	AQ	69	76	F	2.7	0.7	3.9			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	CD	70	77	F	2.3	0.06	38			Chrysotile	TAS_AHRA
B	6	B23	AQ	71	78	B	2.5	0.6	4.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	AQ	72	79	F	2	0.5	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	AQ	73	80	B	1.5	0.4	3.8			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	CD	74	81	F	2.6	0.06	43			Chrysotile	TAS_AHRA
B	6	B23	CD	75	82	F	1.5	0.06	25			Chrysotile	TAS_AHRA
B	6	B23	CD	76	83	B	1.1	0.15	7.3			Chrysotile	TAS_AHRA
B	6	B23	AQ	77	84	F	1	0.25	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	6	B23	AQ	78	85	B	4	0.8	5.0			Mg, Si, Ca Tremolite	TAS_AHRA
C	7	B43	AQ	79	86	F	4	0.35	11			Mg, Si, Ca Tremolite	TAS_AHRA
C	7	B43	AQ	80	87	F	1.5	0.2	7.5			Mg, Si, Ca Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1ZP-101004 *Lab/Cor Sample No.:* B4773 S75 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	7	B43	CDQ	81	88	B	2.5	0.2	12			Mg,Si Chrysotile	TAS_AHRA
C	7	B43	AQ	82		MD2-1	16	2.5	6.4			Tremolite	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	B43	AQ		89	MF	16	0.75	21			Mg, Si, Ca Tremolite	AFB>5, PCMEF-US
C	7	B43	CD		90	MF	3	0.1	30			Chrysotile	
C	7	B43	CD	83	91	B	4.5	0.4	11			Chrysotile	TAS_AHRA
C	7	B43	AQ	84	92	F	1.2	0.2	6.0			Tremolite	TAS_AHRA
C	7	B43	AQ	85	93	F	4	1	4.0			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	CD	86	94	F	3.5	0.1	35			Chrysotile	TAS_AHRA
C	7	B43	AQ	87		MD3-1	37	12	3.1			Tremolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	B43	AQ		95	MF	37	1.5	25			Mg,Si,Ca Tremolite	AFB>5, PCMEF-US
C	7	B43	CD		96	MF	4.5	0.1	45			Chrysotile	
C	7	B43	AQ		97	MF	3.5	0.3	12			Mg,Si,Ca Tremolite	
C	7	B43	AQ	88	98	F	2.75	0.3	9.2			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	CD	89	99	F	2	0.1	20			Chrysotile	TAS_AHRA
C	7	B43	CD	90	100	F	1	0.1	10			Chrysotile	TAS_AHRA
C	7	B43	AQ	91	101	F	4.5	1	4.5			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	AQ	92	102	F	2	0.3	6.7			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	AQ	93	103	F	5	1.2	4.2			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	CD	94	104	F	4	0.05	80			Chrysotile	TAS_AHRA
C	7	B43	CD	95	105	F	20	0.1	200			Chrysotile	AS>5, AFB>5, PSAS >10, PSAS TOT, PCAS >10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	B43	CD	96	106	F	6	0.1	60			Chrysotile	AS>5, AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	7	B43	CD	97	107	F	3	0.1	30			Chrysotile	TAS_AHRA
C	7	B43	AQ	98	108	F	5	0.35	14			Mg,Si,Ca Tremolite	TAS_AHRA
C	7	B43	AQ	99	109	F	4	1	4.0			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	AQ	100	110	F	5	0.75	6.7			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	AQ	101	111	F	2.75	0.35	7.9			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	CD	102	112	F	3.5	0.1	35			Chrysotile	TAS_AHRA
C	8	B11	CD	103	113	B	2.5	0.3	8.3			Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: JEB-L2-1ZP-101004 *Lab/Cor Sample No.:* B4773 S75 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	8	B11	AQ	104	114	F	13	0.4	32			Mg,Si,Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS >10, PSAS TOT, PSAM >10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	8	B11	AQ	105	115	F	2.5	0.8	3.1			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	AQ	106	116	F	4	0.6	6.7			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	AQ	107	117	F	1.5	0.5	3.0			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	CD	108	118	F	1	0.1	10			Chrysotile	TAS_AHRA
C	8	B11	AQ	109	119	F	5	1	5.0			Mg,Si,Ca Tremolite	TAS_AHRA
C	8	B11	AQ	110	120	F	1.5	0.4	3.8			Mg,Si,Ca Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC9-L6-1CC-101004 *Lab/Cor Sample No.:* B4773 S38 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	D24		NSD									
A	2	D22		NSD									
A	3	D20		NSD									
A	4	C20		NSD									
A	5	C22		NSD									
A	6	C44	AZQ	1	1	F	2.5	0.7	3.6	952	693	Mg, Al, Si, Ca, Fe Actinolite Alumino-actinolite - Zone Axis [7 1 6] - KM	TAS_AHRA
A	7	C42		NSD									
A	8	C40		NSD									
A	9	D41		NSD									
A	10	D43		NSD									
A	11	D44		NSD									
A	12	D42		NSD									
A	13	C10		NSD									
A	14	C12		NSD									
A	15	C14		NSD									
B	16	C10		NSD									
B	17	C20		NSD									
B	18	C40		NSD									
B	19	C42		NSD									
B	20	C22		NSD									
B	21	C2		NSD									
B	22	C4		NSD									
B	23	B4		NSD									
B	24	B14		NSD									
B	25	B24		NSD									
B	26	B34		NSD									
B	27	B44		NSD									
B	28	B32		NSD									
B	29	B42		NSD									