



Land Conservation Department

Plan Package

 STORAGE STR. 1999


AS BUILT DOCUMENTATION ON SHEETS 2, 6, & 7

CONSTRUCTION PLAN

Practice: WASTE STORAGE FACILITY-313
 Owner: [REDACTED] Phone: 920-336-7919 OR 983-1061
 Address: 3870 DICKINSON ROAD DEPERE, WI. 54115
 Township: LEDGE VIEW County: BROWN
 Section: 33 Township: 23 N Range: 21 E
 Fld. Off: GREEN BAY Off. Phone: 391-4620

Sh Plan Index
Contents

- 1 - LOCATION MAP
- 2 - USGS MAP
- 3 - QUANTITIES
- 4 - CONSTRUCTION NOTES
- 5 - CONCRETE - SPEC-4
- 6 - STRUCTURE PLAN VIEW
- 7 - STRUCTURE LAYOUT PLAN
- 8 - STRUCTURE SECTION A-A
- 9 - 4' WALL DETAIL
- 10 - 6' WALL DETAIL
- 11 - 8' WALL DETAIL
- 12 - 4' WALL CORNER DETAIL
- 13 - 6' & 8' WALL CORNER DETAIL
- 14 - LIQUID TIGHT SLAB JOINTS
- 15 - LIQUID TIGHT WALL JOINTS
- 16 - REVEGETATION DETAIL




**** NOTICE TO LANDOWNERS AND CONTRACTORS REGARDING UTILITIES ****
 No representation is made by the Brown County Land Conservation department as to the existence or nonexistence of underground hazards. Prior to the start of construction the owners of utilities must be notified of the pending construction. You will be liable for damages resulting from construction activities!

CONSTRUCTION DRAWINGS AND SPECIFICATIONS ACCEPTANCE
 I/we have reviewed and do accept the attached plans. I/we agree to have this project constructed in accordance with these plans and specifications and to notify all affected utility companies.
 I/we agree that any changes made during construction will be pre-approved by an authorized Land Conservation agent.

SIGNED: _____
 DESIGNED: [Signature]
 CHECKED: [Signature]
 APPROVED: [Signature] PROJECT TECH.
 APPROVED: _____

DATE: _____
 DATE: 3/99 Feb-98
 DATE: 5/23/99
 DATE: 5/24/99
 DATE: _____




ESTIMATED QUANTITIES

ITEM	UNIT	QUANTITY	SHEET NUMBER	WI. CONSTRUCTION SPEC. OR JOB SHEET NO.
CONCRETE				
1. 8"-WALL	CU. YDS.	109	4 THRU 11	
2. 5"-FLOOR	CU. YDS.	166	4, 5, 8, & 14	
TOTAL CONCRETE	CU. YDS.	275		
HYDROFLEX WATERSTOP	LN FT	220	15	
6" PVC RIBBED WATERSTOP	LN FT	88	14	
SAND/GRAVEL FILL	CU YDS	730	4 & 8	
WHITE CURING COMPOUND	GALLONS	80	14, 1	
REINFORCING STEEL				
#5 IN WALLS	LN FT	5100	9 THRU 15	
#4 IN WALLS	LN FT	7626	9 THRU 15	
#4 IN FLOOR	LN FT	15,740	9 THRU 15	

ESTIMATED QUANTITIES

OWNER

BROWN LCC, WI
COUNTYDesigned: 449 Checked:SHEET 3 OF



5/90
RWCONCRETE SPEC 4 - SUMMARYPART I. FURNISHING CONCRETE

3,500 psi

Fly ash - Type C or F

Superplasticizers O.K. (Slump 3" Pre, 8" Post)

Retarders O.K. if temperature is over 80° F

Calcium chloride not allowed

Accelerators not allowed

Entrained Air - 4-8%

Slump - 2-5"

Concrete may be supplied in either of two methods:

1. Using fly ash and/or superplasticizer - Job mix must be preapproved or supplied before pouring.
 - Must have test results to show 28 day strength.
 - If mix uses superplasticizer but no fly ash, 6 bags of cement (564 lb.) must be used.
 - If fly ash is used it must be 10-20% of the mix by volume. Minimum cement content is 5 bags (470 lb.)
2. 6 bags cement (564 lb.)
6 gal. water bag of cement is maximum permitted. This includes water in aggregate.

Batch ticket info:

Company name	Purchaser name
Date	Truck no.
Amount delivered	Time loaded
Water added at plant	Type & amount of cement*
Admixtures*	Weights of aggregates*
% moisture or weight of water in aggregates	

Contractor or Inspector add:

Water added at site
Time concrete arrived
Time concrete unloaded

* Materials info that will remain constant can be submitted with the job mix and need not be on the batch tickets.

RW
5/90CONCRETE - SPEC 4 - SUMMARYPART II. - CONCRETE INSTALLATION

Expansion joint material - 1/2" min.

Rebars - Grade 40 or 60; Must be tied in place before pouring starts.
Bar splicing - 30 diameters.

Waterstops - 6", center bulb, 3/16" rib min. unless shown on drawings. Use split rib in slabs. Cement or weld joints.

Subgrade - firm and damp

Form release agent (not oil) shall be applied before forms are set.

Placing - Must be within 1 1/2 hr.
No cold joints permitted. Vibrate all walls 4' or higher.
Vertical drop - 5' max. (12' with superplasticizer)FORM REMOVAL AND FINISHING

Finish slabs with ribbed bull float or coarse broom. Sawn joints to be cut as soon as possible and not later than 24 hrs. after pouring.

Forms - Walls - 24 hrs. minimum; can't backfill for 7 days
Tank covers - 7 days min.Form ties - Non-liquid tight walls - flush with surface
Liquid tight walls - 1/2" with cavity patched
with grout, mortar mix or epoxy sealer.CURING - Use white curing compound; 200 sq. ft/gal. maximum; apply as soon as slab can be walked on or when wall forms are removed. Don't spray on construction joints.HOT WEATHER (>80 F, and/or low humidity, and/or high wind)
Use set retarder or place within 45 minutes.
In extreme conditions restrict pouring to late in day.COLD WEATHER (Ave. temp is <40 for 3 days)Daily min. Temp. For Insulation

Slabs -	20	6" straw or hay
	10	12" straw or hay
Walls: Above ground	30	plastic cover or tarp
	20	insulating blankets
		or 1" styrofoam
Below ground	20	plastic cover or tarp
	10	1" styrofoam or
		insulating blankets

SH-5

75

76

77.1 17

118 718

79

80

81

82

83

84

85

86

87

88

89.0 Hvac

125

TBM-1.1 ELEV=99.05
IS THE TOP NE CORNER
OF EXISTING STR.

90.0

93.5

91.7
1.3

91.7 BED
138

91.7 Cl
141

EXISTING

STRUCTURE
(1995)

78.3'

93.4
139

93.2 CL
140

95.4
99.05

97.3
6.25

35'

94.8 LOW
147

97.3 E
144

35'

97.7
99.05

97.0
124

97.2 NW
179

88.8
126

89

90

91.1 6.7
128

87.3

127

90.2 Edg
129

84.1 Cl
130

89.6
131

91

99.05
94.25

91.7
137

8' WALL
(SEE DRWG #74)

80'

AS

BUILT

STRUCTURE

(MAY-1999)

92.9
136

90.5 Bed
135

88.4 Cl
131

92.2 Fe

99.05

147.8'

94.5 1.0
144

8' WALL
(SEE DRWG #74)

6' WALL
SEE DRWG #68

4' WALL
SEE DRWG #64

RAMP

21'

32 1/2'

97.7 Fe
149

97

97.5

33'

5.2

93.9

99.1


98.6 NE
160

97.3 Cl
181

93.1 Cl
182

STRUCTURE PLAN VIEW


SHEET-6



$$CAPACITY = \left(\frac{7.32 + 5.2}{2} \right) \left(\frac{148}{1} \right) \left(\frac{78.3}{1} \right) = 72,543.4 \text{ FT}^3$$

$$RAMP DISPLACEMENT = \left(\frac{0 + 5.6}{2} \right) \left(\frac{58}{1} \right) \left(\frac{32 \text{ WIDE}}{1} \right) = 5197 \text{ FT}^3$$

$$\text{THEN } 72,543 - 5197 = 67,346 \text{ FT}^3$$



PERMIT - ENTER CHART WITH 117 A.U. AND READ \$ 250.00

SECTION A-A

40

80

120

OWNER	
BROWN LCC, WI	
COUNTY	
Designed: KXQ	Checked:
SHEET 8 OF	


DESIGN VALUES

MANURE - 60 PCF, EQUIVALENT FLUID PRESS.
 WARTH BACKFILL - 85 PCF, EQUIVALENT FLUID PRESS.
 110 PCF, WEIGHT

WORKING STRESS DES.: $f_c = 1400$ psi $f_s = 20,000$ psi

CONDITIONS OF USE

BACKFILL - 3 - 4 FT.
 TRACTOR SURCHARGE



TYPICAL SECTION

MATERIALS

CONCRETE: SPEC. 4
 STEEL: 40 GRADE REBARS

QUANTITIES: (WALL & FOOTING ONLY)

CONCRETE (.216 CU.YD. PER LIN. FT.) 6 1/2 CU. YD.

STEEL: #4 (21.08 FT. PER LIN. FT.)* 632 FT.

* INCLUDES OVERLAP

TYPE 2

R

LINEAL FT. OF WALL : 30 FT.

STEEL SCHEDULE

MARK	SIZE	AM'T	TYPE	R	S	LENGTH	TOTAL LENGTH
A	#4		STR	—	—	20'-0"	369
B	#4	30	STR	—	—	3'-10"	115.0
C	#4	30	2	1'-8"	2'-0"	3'-8"	110.0
D	#4	30	STR	—	—	2'-11"	87.5
E	#4	5	2	2'-0"	2'-0"	4'-0"	20.0

4 FT. WALL WITH SURCHARGE

OWNER

DESIGNED:

CHECKED:

SHEET 9 OF

DESIGN VALUES

MANURE - 60 PCF, EQUIVALENT FLUID PRESS.
 EARTH BACKFILL - 60 PCF, EQUIVALENT FLUID PRESS.
 110 PCF, WEIGHT


WORKING STRESS DES.: $f_c = 1400$ psi $f_s = 20,000$ psi

CONDITIONS OF USE

BACKFILL - 0 - 4 FT.

NO SURCHARGE

SLAB MUST BE POURED WITH FOOTING



TYPICAL SECTION

MATERIALS

CONCRETE: SPEC. 4

STEEL: 40 GRADE REBARS

QUANTITIES: (WALL & FOOTING ONLY)

CONCRETE (.289 CU.YD. PER LIN. FT.) 30.3 CU. YD.

STEEL: #4 (23.27 FT. PER LIN. FT.)* 2444 FT.

#5 (5 FT. PER LIN. FT.)* 525 FT.

* INCLUDES OVERLAP

STEEL SCHEDULE

TYPE 2

R

S

LINEAL FT. OF WALL : 105 FT.

MARK	SIZE	AM'T	TYPE	R	S	LENGTH	TOTAL LENGTH
A	#4		STR	—	—	20'-0"	
B	#4		STR	—	—	5'-0"	
C	#5		2	2'-6"	2'-6"	5'-0"	
D	#4		STR	—	—	3'-4"	
E	#4		2	2'-0"	2'-0"	4'-0"	

6 FT. WALL

OWNER

DESIGNED:

CHECKED:

SHEET 10 OF

DESIGN VALUES

MANURE - 80 PCF, EQUIVALENT FLUID PRESS.
 EARTH BACKFILL - 80 PCF, EQUIVALENT FLUID PRESS.
 110 PCF, WEIGHT


WORKING STRESS DES.: $f_c = 1400$ psi $f_s = 20,000$ psi

CONDITIONS OF USE

BACKFILL - 0 - 5 FT.

NO SURCHARGE

SLAB MUST BE POURED WITH FOOTING

TYPICAL SECTIONMATERIALS

CONCRETE: SPEC. 4

STEEL: 40 GRADE REBARS

QUANTITIES: (WALL & FOOTING ONLY)

CONCRETE (.385 CU. YD. PER LIN. FT.) 72.4 CU. YD.

STEEL: #4 (24.20 FT. PER LIN. FT.)* 4550 FT.

#5 (24.34 FT. PER LIN. FT.)* 4575 FT.

* INCLUDES OVERLAP

STEEL SCHEDULE

LINEAL FT. OF WALL : 188 FT.

MARK	SIZE	AM'T	TYPE	R	S	LENGTH	TOTAL LENGTH
A	#4		STR	—	—	20'-0"	
B	#4		STR	—	—	5'-0"	
C	#5		2	4'-5"	3'-4"	7'-9"	
D	#5		STR	—	—	4'-5"	
E	#4		2	2'-0"	2'-0"	4'-0"	

TYPE 2

R

S

8 FT. CONCRETE WALL

OWNER


DESIGNED:

CHECKED:

SHEET 11 OF 11

NOTES FOR CONCRETE WALLS

1. SURFACE DRAINAGE MUST BE AWAY FROM WALL.
2. THE SLAB REINFORCEMENT MUST EXTEND INTO THE FOOTING AND OVERLAP FOOTING STEEL 12" MIN.
3. MINIMUM CLEARANCE BETWEEN NEAREST EDGE OF STEEL AND NEAREST SURFACE OF CONCRETE IS 2 IN. FOR FORMED SURFACES AND 3 IN. FOR UNFORMED SURFACES



PLAN VIEW

NOTE: TO BE USED WITH DRAWING
#s 64, 69, 70, 75, & 76.

STANDARDIZED DESIGN; MUST BE ADAPTED TO THE SPECIFIC SITE
DESIGN FOLDER IS IN APPLETON OFFICE:
1011 N. LYNNDAL DRIVE
APPLETON, 54914-3091; (414) 734-2061

CORNER DETAIL,
STEEL ON OUTSIDE


OWNER

Designed: _____ Checked: _____

SHEET 12 OF _____

NOTES FOR CONCRETE WALLS

1. SURFACE DRAINAGE MUST BE AWAY FROM WALL. 2 FT OF BACKFILL IS RECOMMENDED.
2. THE SLAB REINFORCEMENT MUST EXTEND INTO THE FOOTING AND OVERLAP FOOTING STEEL 12" MIN.
3. MINIMUM CLEARANCE BETWEEN NEAREST EDGE OF STEEL AND NEAREST SURFACE OF CONCRETE IS 2 IN. FOR FORMED SURFACES AND 3 IN. FOR UNFORMED SURFACES



PLAN VIEW

NOTE: TO BE USED WITH DRAWING
#'s 68, 71, & 74.

STANDARDIZED DESIGN; MUST BE ADAPTED TO THE SPECIFIC SITE
DESIGN FOLDER IS IN APPLETON OFFICE:

1011 N. LYNNDAL DRIVE


APPLETON, 54914-3091; (414) 734-2061

CORNER DETAIL, STEEL ON INSIDE


OWNER _____

Designed: _____ Checked: _____


SHEET 13 OF _____



ISOLATION
CONSTRUCTION
CONTROL




CONSTRUCTION
CONTROL



NOTE: JOINT C1 SAW CUT
BACKER ROD TO BE 1/8" LARGER THAN WIDTH OF SAW CUT. SEALANT DEPTH TO BE 1/4" OR SLIGHTLY LESS THAN JOINT WIDTH WHICH EVER GOVERNS.

CONTROL



NOTE: JOINT C2 JOINT FORMER STRIP
REMOVE JOINT FORMER STRIP AND TREAT AS INDICATED FOR JOINT C1.

CONTROL

CROSS SECTIONS

SEE REVERSE SIDE FOR
ADDITIONAL INFORMATION

JOINT B ESTIMATED LENGTH 80 LIN. FT.

JOINT C ESTIMATED LENGTH 212 LIN. FT.

JOINT _____ ESTIMATED LENGTH _____ LIN. FT.


NOTE: THE MOST COMMON JOINT PURPOSE IS UNDERLINED.

LIQUID TIGHT SLAB JOINTS

OWNER

Designed: _____ Checked: _____

SHEET 14 OF _____



TYPICAL SECTION

GENERAL CONSTRUCTION NOTES:

1. CONCRETE IS TO BE MIXED AND PLACED ACCORDING TO WIS. SPEC. 4.
2. JOINTS ARE TO BE SPACED ~~30~~⁷⁸ OR LESS EACH WAY, SEE SHEET 15.1.
3. WHITE CURING COMPOUND SHALL BE APPLIED TO CONCRETE AS SOON AS THE CONCRETE CAN BE WALKED ON.
4. SITE PREPARATION: REMOVE ALL ORGANIC AND UNCOMPACTED MATERIAL BEFORE PLACING SAND/GRAVEL SUBBASE.
5. ANY BARNYARD SLABS OR RAMPS ARE TO BE GROOVED.
GROOVES: 1/2" x 1/2" - 4 INCHES APART; AT ANGLE TO EQUIPMENT TRAVEL
6. SAND/GRAVEL IS TO BE CLEAN PIT-RUN MATERIAL WITH LESS THAN 10% FINES. COMPACT IN 4" LAYERS WITH VIBRATING COMPACTOR. DAMPEN THE SAND/GRAVEL BEFORE THE CONCRETE IS POURED.

QUANTITIES:

CONCRETE SLAB 166 CU.YD.
(WALL FOOTINGS NOT INCLUDED)

SAND/GRAVEL 730 CU.YD.
(CLEAN, LESS THAN 10% FINES)

REBARS: ~~#4~~^{#4} @ 18" O.C. BOTH WAYS) 15,740 LIN.FT.
(1.40 LIN.FT. PER SQ. FT.)

WHITE CURING COMPOUND 16,000 SQ.FT.
(ASTM C-309, TYPE 2)

JOINTS: SEE JOINT DRAWINGS FOR TYPES AND LENGTHS.





CONCRETE SLAB WITH REBARS

OWNER

DESIGNED:

CHECKED:

SHEET 4.1 OF

JOINT-PISOLATION
CONSTRUCTION
CONTROLJOINT QCONSTRUCTION
CONTROLJOINT-RCONTROL
CONSTRUCTIONJOINT S

NOTE: BACKER ROD TO BE 1/8" LARGER THAN WIDTH OF THE JOINT.
NOTCH FOR THE SEALANT TO BE FORMED IN EITHER THE FIRST OR SECOND POUR CONCRETE.

CONTROL
CONSTRUCTIONPLAN VIEWSJOINT R ESTIMATED LENGTH 8 LIN. FT.JOINT Q ESTIMATED LENGTH 220 LIN. FT.

JOINT _____ ESTIMATED LENGTH _____ LIN. FT.

NOTE: THE MOST COMMON JOINT PURPOSE IS UNDERLINED.

LIQUID TIGHT WALL JOINTS

OWNER

Designed: _____ Checked: _____

SHEET 15 OF _____

MAXIMUM DISTANCE BETWEEN CONTROL JOINTS FOR A 5-INCH SLAB

Reinforcement	A_s sq. in./ft.	f_y psi	L ft.
6 x 6 - W1.4 x W1.4 (10 Gage)	.028	65,000	27
6 x 6 - W2.0 x W2.0 (8 Gage)	.040	65,000	38
6 x 6 - W2.9 x W2.9 (6 Gage)	.058	65,000	56
#3 @ 18" C to C	.073	40,000	43
#3 @ 15" C to C	.088	40,000	52
#4 @ 18" C to C	.131	40,000	78
#4 @ 15" C to C	.157	40,000	93
#3 @ 18" C to C	.073	60,000	65
#3 @ 15" C to C	.088	60,000	78
#4 @ 18" C to C	.131	60,000	117
#4 @ 15" C to C	.157	60,000	140

It is absolutely essential for the reinforcing steel to be in the proper position to provide any advantages from its use. THE PROPER POSITION IS AT OR ABOVE THE MID-DEPTH OF THE SLAB.

A common practice is to specify that the steel be placed 1.5 to 2 inches below the top surface of the concrete slab.

Since positioning is critical, support devices are essential. The steel must be supported with devices spaced to maintain the steel in the correct position during concrete placement.

BROWN COUNTY
LAND CONSERVATION DEPARTMENT
ESTABLISHING AND MAINTAINING VEGETATION

1. Make plans for seeding after construction! Seed within 24 hours after construction.
2. Obtain needed materials.
 - a. Lime. If needed, apply lime as recommended by soil test.
 - b. Fertilizer. In lieu of a soil test, apply 400-600 lbs/acre of 20-10-10.
 - c. Seed. Always check the label and seed in pure live seed rates.
 - d. Mulch materials. Mulch with straw or hay that is reasonably free from grain or weed seed.
3. Prepare the seedbed with a disk or harrow. After applying fertilizer, work the soil to a depth of 3 inches. On small areas, handwork may be necessary. Failure will result if seedbed is not prepared correctly.
4. Mulch should be spread uniformly. The rate the mulch should be spread is 1.5 tons per acre; which is 60 bales per acre or 6 to 7 stems thick. A netting to secure mulch is always recommended.
5. Birdsfoot trefoil and crownvetch should be inoculated properly. Seed placement should be at a 1/4 to 1/2 inch deep and should be done immediately after seedbed preparation.
6. Maintain by controlling weeds and undesirable woody vegetation. Delay mowing until after July 15 to accommodate ground nesting wildlife. If pastured, always regulate grazing.

SEED RATES PER ACRE AND SEED NEEDED IN POUNDS					
MIX#	LOCATION	MIX#	LOCATION		
	0.2 ACRES				
SPECIES	RATE PER ACRE	#SEED NEEDED	SPECIES	RATE PER ACRE	#SEED NEEDED
SMOOTH BROME	25	5			
TIMOTHY	9	2			
RED CLOVER	4	1			

ADDITIONAL COMMENTS: AREA TO BE
VEGETATED IS THE EARTH FILL
AROUND THE PERIMETER OF THE
STRUCTURE. APPROXIMATELY 25'
WIDE FOR 310 LNFT = 7750 FT.²
OR 0.2 AC.

OWNER [REDACTED]

DESIGNED: YHQ

CHECKED: _____

SHEET 16

OF _____