Export To Excel

Project Number	Project Name	Type of Need	Reasons for Need	NRHE	C/F	Reg/Sec	Design Cap.	Diameter	Length	Number Needed	Cost Estimate	Date of Cost	Doc.
1000	Rehab Well #1	R1	A1	R	C	4A	1 MGD			1			6, 10
1001	Rehab Well #2	R1	A1	H	F	4A	1.21 MGD			1			6, 10
1002	Rehab Well #4	R1	A1	H	C	4A	1.08 MGD			1	$169,985.00	7/1/2009	6, 10
1003	Rehab Well #5	R1	A1	H	F	4A	0.72 MGD			1			6, 10
1004	Rehab Plant Aerators	T33	A6	H	F	1B	0.86 MGD			2			6, 10
1005	Groundwater Plant Rehab	T22	A6	H	C	1B	0.58 MGD			1	$271,975.00	7/1/2009	6, 10
1006	Rehab Ground Tank #1	S2	A1	H	F	4A	0.5 MG			1			6, 10
1007	Rehab Plant Hwy 25	S1	A1	H	F	4A	0.5 MG			1			6, 10
1008	Rehab Plant Elev. Tank	S1	A1	H	F	4A	0.15 MG			1			6, 10
1009	Midway/Pleasant Hill Tank	S1	A1	H	C	4A	0.05 MG			1	$87,032.00	7/1/2009	6, 10
1010	Plant Service Pumps	P1	A1	H	F	4A	1.08 MGD			2			6, 10
1011	Plant Service Pumps	P1	A1	H	F	4A	2.16 MGD			2			6, 10

1012	New Midway Tank	S1	A4	N	C	4A	0.1 MG			1	$475,957.00	7/1/2009	2
1013	Midway-Pleasant Hill Hill Ground Tank Rehab & Cont	S2	A1	H	C	4A	0.075 MG			1	$271,976.00	7/1/2009	2
1014	Harmony Area	S2	A1	H	C	4A	0.05 MG			1	$28,557.00	7/1/2009	2
1015	Rehab Plant Indust.Tanks	S1	A1	H	C	4A	0.5 MG			1	$218,941.00	7/1/2009	2
2000	Pipe Improvements	M1	A4	N	C	4A		3			$1,393,876.00	7/1/2009	2
3000	Water Meter Replacement	M8	A4	R	F	4A		0.75		267			6 , 10