Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S54 A1
Client Sample No. CC2-H8-1CT-100304
Description
Analysis Date 11/12/2004
Analyst TM

Volume (L) 5013.54
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000294
Dectection Limit. (struc/cc) 0.000880

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	46.0	0.00353	0.00183 - 0.00617	12
Total Asbestos Structures	46.0	0.00353	0.00183 - 0.00617	12
Asbestos Structures > 5um	26.8	0.00206	0.000829 - 0.00425	7
Asbestos Fibers and Bundles > 5um	15.3	0.00118	0.000321 - 0.00302	4
PCM Equivalent Fibers-US	15.3	0.00118	0.000321 - 0.00302	4
PCM Equivalent Structures-US	11.5	0.000883	0.00 - 0.00228	3
PROTOCOL ASB STRUCS 5-10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL ASB STRUCS >10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000880	0.00 - 0.000880	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000880	0.00 - 0.000880	0
AHERA-like Total Structures 3:1	46.0	0.00353	0.00183 - 0.00617	12
AHERA-like Asb Strucs >5 and 3:1	26.8	0.00206	0.000829 - 0.00425	7
AHERA-like Asb Strucs 5 - 10 and 3:1	7.7	0.000589	0.00 - 0.00185	2
AHERA-like Asb Strucs >10 and 3:1	19.2	0.00147	0.000478 - 0.00344	5
Total Other Amphibole Strucs 3:1	0.0	<0.000880	0.00 - 0.000880	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000880	0.00 - 0.000880	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000880	0.00 - 0.000880	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000880	0.00 - 0.000880	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4763 S10 A1	**Volume (L)**	5013.54
Client Sample No.	CC2-H8-1CT-100304	**No. of Grid Openings**	18
Description	Replicate Analysis of 041172-54 - Same Grid Openings	**Filter Area (mm2)**	385
Analysis Date	12/2/2004	**Area Analyzed (mm2)**	0.261
Analyst	TM	**Analytical Sens. (struc/cc)**	0.000294
		Dectection Limit. (struc/cc)	0.000880

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	61.3	0.00471	0.00269 - 0.00765	16

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No.	B4763 S11 A1	**Volume (L)**	5013.54
Client Sample No.	CC2-H8-1CT-100304	**No. of Grid Openings**	18
Description	Duplicate Analysis of 041172-54 - Same Grid Openings	**Filter Area (mm2)**	385
Analysis Date	11/19/2004	**Area Analyzed (mm2)**	0.261
Analyst	KM	**Analytical Sens. (struc/cc)**	0.000294
		Dectection Limit. (struc/cc)	0.000880

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	49.8	0.00383	0.00204 - 0.00655	13

Lab/Cor Sample No.	B4763 S12 A1	**Volume (L)**	5013.54
Client Sample No.	CC2-H8-1CT-100304	**No. of Grid Openings**	18
Description	Duplicate Analysis of 041172-54 - Reprep	**Filter Area (mm2)**	385
Analysis Date	12/6/2004	**Area Analyzed (mm2)**	0.261
Analyst	DW	**Analytical Sens. (struc/cc)**	0.000294
		Dectection Limit. (struc/cc)	0.000880

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	65.2	0.00501	0.00292 - 0.00801	17

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S55 A1
Client Sample No. CC2-H8-2CT-100304
Description
Analysis Date 12/2/2004
Analyst KM

Volume (L) 3647.28
No. of Grid Openings 25
Filter Area (mm2) 385
Area Analyzed (mm2) 0.362
Analytical Sens. (struc/cc) 0.000291
Dectection Limit. (struc/cc) 0.000871

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	30.4	0.00321	0.00160 - 0.00574	11
Total Asbestos Structures	30.4	0.00321	0.00160 - 0.00574	11
Asbestos Structures > 5um	16.6	0.00175	0.000642 - 0.00381	6
Asbestos Fibers and Bundles > 5um	8.3	0.000874	0.00 - 0.00226	3
PCM Equivalent Fibers-US	5.5	0.000583	0.00 - 0.00184	2
PCM Equivalent Structures-US	5.5	0.000583	0.00 - 0.00184	2
PROTOCOL ASB STRUCS 5-10	2.8	0.000291	0.00 - 0.00138	1
PROTOCOL ASB STRUCS >10	0.0	<0.000871	0.00 - 0.000871	0
PROTOCOL ASB STRUCS TOTAL	2.8	0.000291	0.00 - 0.00138	1
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000871	0.00 - 0.000871	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000871	0.00 - 0.000871	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000871	0.00 - 0.000871	0
PROTOCOL AMPH STRUCS 5-10	2.8	0.000291	0.00 - 0.00138	1
PROTOCOL AMPH STRUCS >10	0.0	<0.000871	0.00 - 0.000871	0
PROTOCOL AMPH STRUCS TOTAL	2.8	0.000291	0.00 - 0.00138	1
AHERA-like Total Structures 3:1	30.4	0.00321	0.00160 - 0.00574	11
AHERA-like Asb Strucs >5 and 3:1	16.6	0.00175	0.000642 - 0.00381	6
AHERA-like Asb Strucs 5 - 10 and 3:1	13.8	0.00146	0.000473 - 0.00340	5
AHERA-like Asb Strucs >10 and 3:1	2.8	0.000291	0.00 - 0.00138	1
Total Other Amphibole Strucs 3:1	0.0	<0.000871	0.00 - 0.000871	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000871	0.00 - 0.000871	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000871	0.00 - 0.000871	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000871	0.00 - 0.000871	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S56 A1
Client Sample No. CC2-H8-3CT-100304
Description
Analysis Date 12/12/2004
Analyst TM

Volume (L) 4690
No. of Grid Openings 19
Filter Area (mm2) 385
Area Analyzed (mm2) 0.275
Analytical Sens. (struc/cc) 0.000298
Dectection Limit. (struc/cc) 0.000892

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	40.0	0.00328	0.00164 - 0.00587	11
Total Asbestos Structures	40.0	0.00328	0.00164 - 0.00587	11
Asbestos Structures > 5um	7.3	0.000596	0.00 - 0.00188	2
Asbestos Fibers and Bundles > 5um	3.6	0.000298	0.00 - 0.00141	1
PCM Equivalent Fibers-US	3.6	0.000298	0.00 - 0.00141	1
PCM Equivalent Structures-US	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL ASB STRUCS >10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000892	0.00 - 0.000892	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000892	0.00 - 0.000892	0
AHERA-like Total Structures 3:1	40.0	0.00328	0.00164 - 0.00587	11
AHERA-like Asb Strucs >5 and 3:1	7.3	0.000596	0.00 - 0.00188	2
AHERA-like Asb Strucs 5 - 10 and 3:1	3.6	0.000298	0.00 - 0.00141	1
AHERA-like Asb Strucs >10 and 3:1	3.6	0.000298	0.00 - 0.00141	1
Total Other Amphibole Strucs 3:1	0.0	<0.000892	0.00 - 0.000892	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000892	0.00 - 0.000892	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000892	0.00 - 0.000892	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000892	0.00 - 0.000892	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S57 A1
Client Sample No. CC2-H8-4CT-100304
Description
Analysis Date 12/9/2004
Analyst DW

Volume (L) 4366.96
No. of Grid Openings 22
Filter Area (mm2) 385
Area Analyzed (mm2) 0.319
Analytical Sens. (struc/cc) 0.000277
Dectection Limit. (struc/cc) 0.000827

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	31.4	0.00277	0.00133 - 0.00509	10
Total Asbestos Structures	31.4	0.00277	0.00133 - 0.00509	10
Asbestos Structures > 5um	25.1	0.00221	0.000955 - 0.00436	8
Asbestos Fibers and Bundles > 5um	15.7	0.00138	0.000449 - 0.00323	5
PCM Equivalent Fibers-US	15.7	0.00138	0.000449 - 0.00323	5
PCM Equivalent Structures-US	9.4	0.000830	0.00 - 0.00214	3
PROTOCOL ASB STRUCS 5-10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL ASB STRUCS >10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000827	0.00 - 0.000827	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000827	0.00 - 0.000827	0
AHERA-like Total Structures 3:1	31.4	0.00277	0.00133 - 0.00509	10
AHERA-like Asb Strucs >5 and 3:1	25.1	0.00221	0.000955 - 0.00436	8
AHERA-like Asb Strucs 5 - 10 and 3:1	18.8	0.00166	0.000609 - 0.00361	6
AHERA-like Asb Strucs >10 and 3:1	6.3	0.000553	0.00 - 0.00174	2
Total Other Amphibole Strucs 3:1	0.0	<0.000827	0.00 - 0.000827	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000827	0.00 - 0.000827	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000827	0.00 - 0.000827	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000827	0.00 - 0.000827	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4760 S58 A1
Client Sample No. CC2-H8-5CT-100304
Description
Analysis Date 12/9/2004
Analyst KM

Volume (L) 3479.53
No. of Grid Openings 8
Filter Area (mm2) 385
Area Analyzed (mm2) 0.116
Analytical Sens. (struc/cc) 0.000955
Dectection Limit. (struc/cc) 0.00285

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	51.8	0.00573	0.00210 - 0.0125	6
Total Asbestos Structures	51.8	0.00573	0.00210 - 0.0125	6
Asbestos Structures > 5um	17.3	0.00191	0.00 - 0.00601	2
Asbestos Fibers and Bundles > 5um	8.6	0.000955	0.00 - 0.00452	1
PCM Equivalent Fibers-US	8.6	0.000955	0.00 - 0.00452	1
PCM Equivalent Structures-US	8.6	0.000955	0.00 - 0.00452	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL ASB STRUCS >10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL AMPH STRUCS >10	0.0	<0.00285	0.00 - 0.00285	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.00285	0.00 - 0.00285	0
AHERA-like Total Structures 3:1	51.8	0.00573	0.00210 - 0.0125	6
AHERA-like Asb Strucs >5 and 3:1	17.3	0.00191	0.00 - 0.00601	2
AHERA-like Asb Strucs 5 - 10 and 3:1	8.6	0.000955	0.00 - 0.00452	1
AHERA-like Asb Strucs >10 and 3:1	8.6	0.000955	0.00 - 0.00452	1
Total Other Amphibole Strucs 3:1	0.0	<0.00285	0.00 - 0.00285	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00285	0.00 - 0.00285	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00285	0.00 - 0.00285	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00285	0.00 - 0.00285	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-1CT-100304 *Lab/Cor Sample No.:* B4760 S54 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	AZQ	1		MD1-1	17	7.75	2.2			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	1	B44	AZQ		1	MB	15.5	3.75	4.1	5472	15350	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [1 0 1] - KM	
A	2	B24		NSD									
A	3	B4	CDQ	2	2	F	0.7	0.1	7.0	5473	15351	Mg Si, Fe Chrysotile Verified - KM	TAS_AHRA
A	3	B4	CMQ	3		MD1-0	6	4	1.5			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	B4	CMQ		3	MF	4.5	0.1	45			Mg, Si, Fe Chrysotile	
A	4	C14	AQ	4	4	F	13.3	1.75	7.6			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US; TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	5	C34	CMQ	5	5	F	0.7	0.05	14			Mg, Si Chrysotile	TAS_AHRA
A	5	C34	AQ	6	6	F	2	0.25	8.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	6	C43		NSD									
A	7	C23		NSD									
A	8	B13	AQ	7	7	F	11.5	0.8	14			Mg, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	9	B34		NSD									
B	10	B14	AQ	8		MD1-1	30.5	5.5	5.5			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	10	B14	AQ		8	MF	26	1.5	17			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	11	C4		NSD									
B	12	C24	AQ	9	9	F	4.25	1.1	3.9			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	13	C44		NSD									
C	14	B44	AQ	10	10	F	6	1.75	3.4			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	15	B24		NSD									
C	16	B4		NSD									
C	17	C14		NSD									
C	18	C44	AQ	11	11	F	3.45	0.3	12			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
C	18	C44	AQ	12		MD1-0	10.5	8	1.3			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	18	C44	AQ		12	MF	4	0.4	10			Mg, Al, Si, Ca, Fe Actinolite Alumino-actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-1CT-100304 *Lab/Cor Sample No.:* B4763 S10 A1

Descripiton: Replicate Analysis of 041172-54 - Same Grid Openings

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	AZQ	1		MD1-1	17.5	8	2.2			Actinolite	
A	1	B44	AZQ		1	MB	16	3.9	4.1			Mg, Si, Ca, Fe Actinolite	
A	2	B24		NSD									
A	3	B4	CMQ	2	2	F	0.6	0.1	6.0			Mg, Si, Fe Chrysotile	
A	3	B4	CMQ	3		MD1-0	6	4.25	1.4			Chrysotile	
A	3	B4	CMQ		3	MF	4	0.1	40			Mg, Si Chrysotile	
A	4	C34	AQ	4	4	F	2.1	0.25	8.4			Mg, Al, Si, Ca, Fe Actinolite	
A	5	C43	AQ	5	5	F	1.2	0.2	6.0			Mg, Al, Si, Ca, Fe Actinolite	
A	5	C43	AQ	6		MD1-1	9.5	3.3	2.9			Actinolite	
A	5	C43	AQ		6	MF	8.5	1.6	5.3			Mg, Si, Ca, Fe Actinolite	
A	6	C14	AQ	7	7	F	13.5	2	6.8			Mg, Al, Si, Ca, Fe Actinolite	
A	7	C23		NSD									
A	8	B13	AQ	8	8	F	10.2	1	10			Mg, Si, Ca, Fe Actinolite	
B	9	B34		NSD									
B	10	B14	AQ	9		MD1-1	31	14	2.2			Actinolite	
B	10	B14	AQ		9	MF	26	1.15	23			Mg, Si, Ca, Fe Actinolite	
B	11	C4		NSD									
B	12	C24	AZQ	10		MD1-1	13.8	9	1.5			Tremolite	
B	12	C24	AZQ		10	MF	13.8	3	4.6			Mg, Si, Ca, Fe Tremolite	
B	12	C24	AQ	11	11	F	4.25	1.2	3.5			Mg, Si, Ca, Fe Actinolite	
B	13	C44		NSD									
C	14	B44	AQ	12	12	F	6.2	1.75	3.5			Mg, Si, Ca, Fe Actinolite	
C	15	B24		NSD									
C	16	B4		NSD									
C	17	C14	AQ	13		MD1-1	22	18	1.2			Actinolite	
C	17	C14	AQ		13	MF	10.3	1.75	5.9			Mg, Al, Si, Ca, Fe Actinolite	
C	18	C44	AQ	14		MD1-1	45	8	5.6			Actinolite	
C	18	C44	AQ		14	MF	45	2.5	18			Mg, Si, Ca, Fe Actinolite	
C	18	C44	AQ	15	15	F	3.4	0.25	14			Mg, Al, Si, Ca, Fe Actinolite	
C	18	C44	AQ	16		MD1-0	10.25	8.5	1.2			Actinolite	
C	18	C44	AQ		16	MF	3.5	0.45	7.8			Mg, Al, Si, Ca, Fe Actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-1CT-100304 *Lab/Cor Sample No.:* B4763 S11 A1

Descripiton: Duplicate Analysis of 041172-54 - Same Grid Openings

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B13	AQ	1	1	F	10.5	0.8	13			Mg, Al, Si, Ca, Fe Actinolite	
A	2	B24		NSD									
A	3	B4	CD	2		MD1-0	6	4	1.5			Chrysotile	
A	3	B4	CD		2	MB	1.5	0.1	15			Chrysotile	
A	3	B4	CD	3	3	F	0.6	0.08	7.5			Chrysotile	
A	4	B44	AQ	4		MD1-1	17.5	7	2.5			Actinolite	
A	4	B44	AQ		4	MF	15	4.3	3.5			Mg, Al, Si, Ca, Fe Actinolite	
A	5	C14	AQ	5	5	F	14	1.5	9.3			Mg, Al, Si, Ca, Fe Actinolite	
A	6	C34	AQ	6	6	F	2	0.38	5.3			Mg, Al, Si, Ca, Fe Actinolite	
A	7	C23		NSD									
A	8	C43		NSD									
B	9	B34		NSD									
B	10	B14	AQ	7		MD1-1	27	5	5.4			Actinolite	
B	10	B14	AQ		7	MF	24	1.3	18			Mg, Al, Si, Ca, Fe Actinolite	
B	11	C4		NSD									
B	12	C24	AQ	8	8	F	14	3	4.7			Mg, Al, Si, Ca, Fe Actinolite	
B	13	C44	AQ	9		MD1-0	11	8	1.4			Actinolite	
B	13	C44	AQ		9	MF	4.5	1	4.5			Mg, Al, Si, Ca, Fe Actinolite	
C	14	B44	AQ	10	10	F	6.5	2	3.2			Mg, Al, Si, Ca, Fe Actinolite	
C	14	B44	AQ	11	11	F	10	3	3.3			Mg, Al, Si, Ca, Fe Actinolite	
C	15	B24		NSD									
C	16	B4		NSD									
C	17	C14		NSD									
C	18	C44	AQ	12	12	F	40	2.5	16			Mg, Al, Si, Ca, Fe Actinolite	
C	18	C44	AQ	13	13	F	3.8	0.3	13			Mg, Al, Si, Ca, Fe Actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-1CT-100304 *Lab/Cor Sample No.:* B4763 S12 A1

Descripiton: Duplicate Analysis of 041172-54 - Reprep

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24	AQ	1	1	F	4	1	4.0			Mg, Al, Si, Ca, Fe Actinolite	
A	3	B4		NSD									
A	4	C14	AQ	2	2	F	5	1	5.0			Mg, Al, Si, Ca, Fe Actinolite	
A	5	C42		NSD									
A	6	C12		NSD									
A	7	B2		NSD									
A	8	B22	AQ	3	3	F	11	1	11			Mg, Al, Si, Ca, Fe Actinolite	
A	9	B42	AQ	4		MD1-1	9	9	1.0			Actinolite	
A	9	B42	AQ		4	MF	9	3	3.0			Mg, Al, Si, Ca, Fe Actinolite	
A	10	B40	AQ	5		MD1-0	10	10	1.0			Actinolite	
A	10	B40	AQ		5	MB	5	1	5.0			Mg, Al, Si, Ca, Fe Actinolite	
A	10	B40	AQ	6	6	F	4.5	1	4.5			Mg, Al, Si, Ca, Fe Actinolite	
A	10	B40	AQ	7		MD1-1	20	15	1.3			Actinolite	
A	10	B40	AQ		7	MF	10	2.5	4.0			Mg, Al, Si, Ca, Fe Actinolite	
B	11	B43	AQ	8		MD1-1	20	20	1.0			Actinolite	
B	11	B43	AQ		8	MF	15	4.5	3.3			Mg, Al, Si, Ca, Fe Actinolite	
B	12	B23	AQ	9	9	F	11	1.5	7.3			Mg, Al, Si, Ca, Fe Actinolite	
B	12	B23	AQ	10		MD1-1	7.5	7.5	1.0			Actinolite	
B	12	B23	AQ		10	MF	7.5	2.5	3.0			Mg, Al, Si, Ca, Fe Actinolite	
B	12	B23	AQ	11		MD1-0	10	7.5	1.3			Actinolite	
B	12	B23	AQ		11	MF	5	0.85	5.9			Mg, Al, Si, Ca, Fe Actinolite	
B	13	B3	AQ	12		MD1-1	20	20	1.0			Actinolite	
B	13	B3	AQ		12	MF	20	5	4.0			Mg, Al, Si, Ca, Fe Actinolite	
B	13	B3	AQ	13		MD1-0	15	15	1.0			Actinolite	
B	13	B3	AQ		13	MF	4.5	1	4.5			Mg, Al, Si, Ca, Fe Actinolite	
B	14	C13	AQ	14		MD1-1	25	15	1.7			Actinolite	
B	14	C13	AQ		14	MF	12	2	6.0			Mg, Al, Si, Ca, Fe Actinolite	
B	15	C33	AQ	15		MD1-1	10	10	1.0			Actinolite	
B	15	C33	AQ		15	MF	10	1.5	6.7			Mg, Al, Si, Ca, Fe Actinolite	
B	16	C42		NSD									
B	17	C21	AQ	16		MD1-1	70	30	2.3			Actinolite	
B	17	C21	AQ		16	MF	10	2.5	4.0			Mg, Al, Si, Ca, Fe Actinolite	
B	18	C1	AQ	17		MD1-1	20	20	1.0			Actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041176R1

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001- FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-1CT-100304 *Lab/Cor Sample No.:* B4763 S12 A1

Descripiton: Duplicate Analysis of 041172-54 - Reprep

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	18	C1	AQ		17	MF	11	3	3.7			Mg, Al, Si, Ca, Fe Actinolite	

Sample No.: SRA-R01-100204 *Lab/Cor Sample No.:* B4763 S13 A1

Descripiton: Replicate Analysis of 041174-02 - Same Grid Openings

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A21	ADQ	1		MD1-1	30	15	2.0			Tremolite	
A	1	A21	ADQ		1	MF	7.8	1	7.8			Mg, Al, Si, Ca, Fe Tremolite	
A	2	A41	CDQ	2		MD1-0	1.7	0.35	4.9			Chrysotile	
A	2	A41	CDQ		2	MF	0.8	0.11	7.3			Mg, Si Chrysotile	
A	2	A41	AQ	3	3	F	2	0.18	11			Mg, Al, Si, Ca, Fe Actinolite	
A	3	B22		NSD									
A	4	C2	AQ	4	4	F	11.5	1.2	9.6			Na, Mg, Al, Si , Ca, Fe Actinolite	
A	5	C32	AQ	5	5	F	1.8	0.6	3.0			Mg, Al, Si, Ca, Fe Actinolite	
A	6	D11	AQ	6	6	F	2.6	0.45	5.8			Mg, Al, Si, Ca, Fe Actinolite	
A	7	D41	CD	7		MD1-0	7.5	3	2.5			Chrysotile	
A	7	D41	CD		7	MF	1.2	0.11	11			Chrysotile	
B	8	B34		NSD									
B	9	B14	CD	8		MD3-0	2	1	2.0			Chrysotile	
B	9	B14	CD		8	MF	1.2	0.11	11			Chrysotile	
B	9	B14	CD		9	MF	1.2	0.1	12			Chrysotile	
B	9	B14	CD		10	MF	1	0.1	10			Chrysotile	
B	10	C24		NSD									
B	11	D1	AQ	9	11	F	3	0.5	6.0			Mg, Al, Si, Ca, Fe Actinolite	
B	12	D21	AQ	10		MD1-0	4.5	3.8	1.2			Actinolite	
B	12	D21	AQ		12	MF	1.3	0.35	3.7			Mg, Al, Si, Ca, Fe Actinolite	
B	12	D21	AQ	11		MD1-0	12	6	2.0			Actinolite	
B	12	D21	AQ		13	MF	4	0.18	22			Mg, Al, Si, Ca, Fe Actinolite	
B	12	D21	AQ	12	14	F	3.8	0.38	10			Mg, Al, Si, Ca, Fe Actinolite	
B	13	D41	AQ	13	15	F	2	0.38	5.3			Mg, Al, Si, Ca, Fe Actinolite	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-2CT-100304 *Lab/Cor Sample No.:* B4760 S55 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B42	AQ	1		MD1-0	6	5	1.2			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B42	AQ		1	MF	3.3	0.3	11			Mg, Al, Si, Ca, Fe Actinolite	
A	1	B42	AZQ	2		MD1-0	6.5	4.5	1.4			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B42	AZQ		2	MF	1.5	0.2	7.5	5654	15494	Mg, Al, Si, Ca, Fe Actinolite Zone Axis - [1 3 4] KM	
A	2	B22		NSD									
A	3	B2		NSD									
A	4	C12	CMQ	3		MD1-0	2.5	1.2	2.1			Chrysotile	TAS_AHRA
A	4	C12	CMQ		3	MF	0.7	0.1	7.0			Mg, Si Chrysotile	
A	5	A31		NSD									
A	6	A11	ADQ	4		MD1-0	4.5	3.8	1.2			Actinolite	TAS_AHRA
A	6	A11	ADQ		4	MF	1.6	0.5	3.2			Mg, Al, Si, Ca, Fe Actinolite	
A	6	A11	ADQ	5		MD1-0	6.5	6.5	1.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	A11	ADQ		5	MF	4.5	0.8	5.6			Mg, Al, Si, Ca, Fe Actinolite	
A	7	D1		NSD									
A	8	D21	ADQ	6		MD1-1	20	20	1.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	8	D21	ADQ		6	MF	16.8	3.8	4.4			Mg, Al, Si, Ca, Fe Actinolite	AFB>5
A	9	D41		NSD									
A	10	C20		NSD									
A	11	C40		NSD									
A	12	A40		NSD									
A	13	A20		NSD									
B	14	B43		NSD									
B	15	B23		NSD									
B	16	B3		NSD									
B	17	C13		NSD									
B	18	C33		NSD									
B	19	B31		NSD									
B	20	B11	AQ	7	7	F	8	0.5	16			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-2CT-100304 *Lab/Cor Sample No.:* B4760 S55 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	20	B11	AQ	8	8	F	7	0.8	8.8			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	21	C1	CDQ	9	9	F	0.6	0.08	7.5	5655	15485	Mg, Si Chrysotile Verified - KM	TAS_AHRA
B	22	C21		NSD									
B	23	C41	AQ	10		MD1-0	5	4	1.2			Actinolite	TAS_AHRA
B	23	C41	AQ		10	MF	4.2	0.5	8.4			Mg, Al, Si, Ca, Fe Actinolite	
B	24	A10	AQ	11	11	F	2.7	0.5	5.4			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	25	D10		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-3CT-100304 *Lab/Cor Sample No.:* B4760 S56 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44	AQ	1		MD1-0	6.5	6.5	1.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B44	AQ		1	MF	2.75	0.4	6.9		15556	Mg, Al, Si, Ca, Fe Actinolite	
A	1	B44	AQ	2		MD1-1	16	11	1.5			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	1	B44	AQ		2	MF	11	2	5.5			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
A	1	B44	CDQ	3	3	F	1.1	0.05	22	5709	15557	Mg, Al, Si, Fe Chrysotile Verified - KM	TAS_AHRA
A	2	B24		NSD									
A	3	B4		NSD									
A	4	C14	AZQ	4	4	F	1.5	0.25	6.0	5710	15558	Mg, Al, Si, Ca, Fe Actinolite Zone Axis - [5 -1 -2] - KBM	TAS_AHRA
A	5	C34	AQ	5	5	F	1.3	0.3	4.3			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	6	C43		NSD									
A	7	C23	AQ	6	6	F	3.75	1.05	3.6			Mg, Si, Ca, Fe Actinolite	TAS_AHRA
A	8	C3	AQ	7	7	F	3.35	1.1	3.0			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	8	C3	AQ	8	8	F	4.5	1	4.5			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	9	B13		NSD									
A	10	B33		NSD									
B	11	B44	AQ	9		MD1-0	4.25	2.25	1.9			Actinolite	TAS_AHRA
B	11	B44	AQ		9	MF	2.5	0.5	5.0			Mg, Al, Si, Ca, Fe Actinolite	
B	12	B24		NSD									
B	13	B4		NSD									
B	14	C14	AQ	10	10	F	0.7	0.2	3.5			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	15	C34		NSD									
B	16	C43		NSD									
B	17	C23		NSD									
B	18	C3		NSD									
B	19	B13	CMQ	11	11	F	2.9	0.05	58			Mg, Si Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-4CT-100304 *Lab/Cor Sample No.:* B4760 S57 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B44		NSD									
A	2	B24		NSD									
A	3	B4	AQ	1	1	F	6	1	6.0			Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	4	C14		NSD									
A	5	C34	AZQ	2		MD1-0	7.5	6	1.2			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	5	C34	AZQ		2	MF	1.3	0.4	3.2	5681	15533	Mg, Al, Si, Ca, Fe Actinolite Zone Axis - [2 0 3] KBM	
A	6	C43	AQ	3	3	F	9	2.5	3.6			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	C43	AQ	4	4	F	9	1.2	7.5			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	7	C42		NSD									
A	8	C22	AQ	5		MD1-1	16	8	2.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	8	C22	AQ		5	MF	15	2.5	6.0			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
A	8	C22	CDQ	6	6	F	1.5	0.1	15	5682	15534	Mg, Si Chrysotile Verified - KM	TAS_AHRA
A	9	C2	AQ	7	7	F	1.3	0.3	4.3		15535	Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	10	B12	AQ	8		MD1-0	7	7	1.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	10	B12	AQ		8	MF	2.5	0.75	3.3			Mg, Al, Si, Ca, Fe Actinolite	
A	11	B30		NSD									
A	12	B10		NSD									
B	13	A31		NSD									
B	14	A11		NSD									
B	15	D1		NSD									
B	16	D21		NSD									
B	17	D41	AQ	9		MD1-0	70	18	3.9			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	17	D41	AQ		9	MF	4.5	0.6	7.5			Mg, Al, Si, Ca, Fe Actinolite	
B	18	C41	AQ	10		MD1-1	9	9	1.0			Actinolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	18	C41	AQ		10	MF	7.5	1.5	5.0			Mg, Al, Si, Ca, Fe Actinolite	AFB>5, PCMEF-US
B	19	C21		NSD									
B	20	C1		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041172R6

Client: Ecology and Environment, Inc.

Project Name: Site# 0440.01CP, 0440.01CP-0001-FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: CC2-H8-4CT-100304 *Lab/Cor Sample No.:* B4760 S57 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	21	B11		NSD									
B	22	B31		NSD									

Sample No.: CC2-H8-5CT-100304 *Lab/Cor Sample No.:* B4760 S58 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A31		NSD									
A	2	A1	ADQ	1		MD1-0	2	0.7	2.9			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
A	2	A1	ADQ		1	MF	2	0.35	5.7			Mg, Al, Si, Ca, Fe Actinolite	
A	3	B44		NSD									
A	4	B24	CDQ	2	2	F	2	0.1	20	1149	837	Mg, Si Chrysotile Verified - KM	TAS_AHRA
A	5	B4	ADQ	3	3	F	9	3	3.0			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	6	B13	AZQ	4	4	F	2.8	0.7	4.0	1150	836	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [7 1 6] - JH	TAS_AHRA
B	7	A10	ADQ	5	5	F	3	0.4	7.5			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	8	C11	CD	6		MD1-0	15	5	3.0			Chrysotile	AS>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	8	C11	CD		6	MB	1.5	0.2	7.5			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S95 A1
Client Sample No. TRA-H8-1TR-100904
Description
Analysis Date 11/22/2004
Analyst JH

Volume (L) 5023.98
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000294
Dectection Limit. (struc/cc) 0.000879

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	15.3	0.00118	0.000320 - 0.00301	4
Total Asbestos Structures	15.3	0.00118	0.000320 - 0.00301	4
Asbestos Structures > 5um	7.7	0.000588	0.00 - 0.00185	2
Asbestos Fibers and Bundles > 5um	7.7	0.000588	0.00 - 0.00185	2
PCM Equivalent Fibers-US	3.8	0.000294	0.00 - 0.00139	1
PCM Equivalent Structures-US	3.8	0.000294	0.00 - 0.00139	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL ASB STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Total Structures 3:1	15.3	0.00118	0.000320 - 0.00301	4
AHERA-like Asb Strucs >5 and 3:1	7.7	0.000588	0.00 - 0.00185	2
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Asb Strucs >10 and 3:1	7.7	0.000588	0.00 - 0.00185	2
Total Other Amphibole Strucs 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S94 A1
Client Sample No. TRA-H8-11TR-100904
Description
Analysis Date 11/22/2004
Analyst JH

Volume (L) 5088.2
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000290
Dectection Limit. (struc/cc) 0.000867

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.000867	0.00 - 0.000867	0
Total Asbestos Structures	0.0	<0.000867	0.00 - 0.000867	0
Asbestos Structures > 5um	0.0	<0.000867	0.00 - 0.000867	0
Asbestos Fibers and Bundles > 5um	0.0	<0.000867	0.00 - 0.000867	0
PCM Equivalent Fibers-US	0.0	<0.000867	0.00 - 0.000867	0
PCM Equivalent Structures-US	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL ASB STRUCS >10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000867	0.00 - 0.000867	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000867	0.00 - 0.000867	0
AHERA-like Total Structures 3:1	0.0	<0.000867	0.00 - 0.000867	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.000867	0.00 - 0.000867	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000867	0.00 - 0.000867	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.000867	0.00 - 0.000867	0
Total Other Amphibole Strucs 3:1	0.0	<0.000867	0.00 - 0.000867	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000867	0.00 - 0.000867	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000867	0.00 - 0.000867	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000867	0.00 - 0.000867	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S96 A1
Client Sample No. TRA-H8-2TR-100904
Description
Analysis Date 11/22/2004
Analyst JH

Volume (L) 4882.15
No. of Grid Openings 19
Filter Area (mm2) 385
Area Analyzed (mm2) 0.275
Analytical Sens. (struc/cc) 0.000286
Dectection Limit. (struc/cc) 0.000856

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	3.6	0.000286	0.00 - 0.00136	1
Total Asbestos Structures	3.6	0.000286	0.00 - 0.00136	1
Asbestos Structures > 5um	3.6	0.000286	0.00 - 0.00136	1
Asbestos Fibers and Bundles > 5um	3.6	0.000286	0.00 - 0.00136	1
PCM Equivalent Fibers-US	3.6	0.000286	0.00 - 0.00136	1
PCM Equivalent Structures-US	3.6	0.000286	0.00 - 0.00136	1
PROTOCOL ASB STRUCS 5-10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL ASB STRUCS >10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000856	0.00 - 0.000856	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000856	0.00 - 0.000856	0
AHERA-like Total Structures 3:1	3.6	0.000286	0.00 - 0.00136	1
AHERA-like Asb Strucs >5 and 3:1	3.6	0.000286	0.00 - 0.00136	1
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000856	0.00 - 0.000856	0
AHERA-like Asb Strucs >10 and 3:1	3.6	0.000286	0.00 - 0.00136	1
Total Other Amphibole Strucs 3:1	0.0	<0.000856	0.00 - 0.000856	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000856	0.00 - 0.000856	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000856	0.00 - 0.000856	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000856	0.00 - 0.000856	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S97 A1
Client Sample No. TRA-H8-3TR-100904
Description
Analysis Date 11/22/2004
Analyst JH

Volume (L) 5007.39
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000295
Dectection Limit. (struc/cc) 0.000881

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.000881	0.00 - 0.000881	0
Total Asbestos Structures	0.0	<0.000881	0.00 - 0.000881	0
Asbestos Structures > 5um	0.0	<0.000881	0.00 - 0.000881	0
Asbestos Fibers and Bundles > 5um	0.0	<0.000881	0.00 - 0.000881	0
PCM Equivalent Fibers-US	0.0	<0.000881	0.00 - 0.000881	0
PCM Equivalent Structures-US	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL ASB STRUCS >10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000881	0.00 - 0.000881	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000881	0.00 - 0.000881	0
AHERA-like Total Structures 3:1	0.0	<0.000881	0.00 - 0.000881	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.000881	0.00 - 0.000881	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000881	0.00 - 0.000881	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.000881	0.00 - 0.000881	0
Total Other Amphibole Strucs 3:1	0.0	<0.000881	0.00 - 0.000881	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000881	0.00 - 0.000881	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000881	0.00 - 0.000881	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000881	0.00 - 0.000881	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S98 A1
Client Sample No. TRA-H8-4TR-100904
Description
Analysis Date 11/22/2004
Analyst DW

Volume (L) 5022.34
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000294
Dectection Limit. (struc/cc) 0.000879

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.000879	0.00 - 0.000879	0
Total Asbestos Structures	0.0	<0.000879	0.00 - 0.000879	0
Asbestos Structures > 5um	0.0	<0.000879	0.00 - 0.000879	0
Asbestos Fibers and Bundles > 5um	0.0	<0.000879	0.00 - 0.000879	0
PCM Equivalent Fibers-US	0.0	<0.000879	0.00 - 0.000879	0
PCM Equivalent Structures-US	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL ASB STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000879	0.00 - 0.000879	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Total Structures 3:1	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
Total Other Amphibole Strucs 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000879	0.00 - 0.000879	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S99 A1
Client Sample No. TRA-H8-5TR-100904
Description
Analysis Date 11/23/2004
Analyst JH

Volume (L) 5045.1
No. of Grid Openings 18
Filter Area (mm2) 385
Area Analyzed (mm2) 0.261
Analytical Sens. (struc/cc) 0.000293
Dectection Limit. (struc/cc) 0.000875

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	0.0	<0.000875	0.00 - 0.000875	0
Total Asbestos Structures	0.0	<0.000875	0.00 - 0.000875	0
Asbestos Structures > 5um	0.0	<0.000875	0.00 - 0.000875	0
Asbestos Fibers and Bundles > 5um	0.0	<0.000875	0.00 - 0.000875	0
PCM Equivalent Fibers-US	0.0	<0.000875	0.00 - 0.000875	0
PCM Equivalent Structures-US	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL ASB STRUCS 5-10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL ASB STRUCS >10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL ASB STRUCS TOTAL	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL CHRYS STRUCS 5-10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL CHRYS STRUCS >10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL CHRYS STRUCS TOTAL	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL AMPH STRUCS 5-10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL AMPH STRUCS >10	0.0	<0.000875	0.00 - 0.000875	0
PROTOCOL AMPH STRUCS TOTAL	0.0	<0.000875	0.00 - 0.000875	0
AHERA-like Total Structures 3:1	0.0	<0.000875	0.00 - 0.000875	0
AHERA-like Asb Strucs >5 and 3:1	0.0	<0.000875	0.00 - 0.000875	0
AHERA-like Asb Strucs 5 - 10 and 3:1	0.0	<0.000875	0.00 - 0.000875	0
AHERA-like Asb Strucs >10 and 3:1	0.0	<0.000875	0.00 - 0.000875	0
Total Other Amphibole Strucs 3:1	0.0	<0.000875	0.00 - 0.000875	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.000875	0.00 - 0.000875	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.000875	0.00 - 0.000875	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.000875	0.00 - 0.000875	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S93 A1
Client Sample No. TRA-H2-1ZP-100904
Description
Analysis Date 11/21/2004
Analyst JH

Volume (L) 1200.09
No. of Grid Openings 7
Filter Area (mm2) 385
Area Analyzed (mm2) 0.101
Analytical Sens. (struc/cc) 0.00316
Dectection Limit. (struc/cc) 0.00946

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	976.0	0.313	0.254 - 0.381 (Poisson)	99
Total Asbestos Structures	1035.2	0.332	0.257 - 0.385 (Poisson)	105
Asbestos Structures > 5um	157.7	0.0506	0.0289 - 0.0822	16
Asbestos Fibers and Bundles > 5um	167.6	0.0538	0.0313 - 0.0861	17
PCM Equivalent Fibers-US	108.4	0.0348	0.0174 - 0.0623	11
PCM Equivalent Structures-US	118.3	0.0380	0.0196 - 0.0663	12
PROTOCOL ASB STRUCS 5-10	69.0	0.0221	0.00890 - 0.0456	7
PROTOCOL ASB STRUCS >10	19.7	0.00633	0.00 - 0.0199	2
PROTOCOL ASB STRUCS TOTAL	88.7	0.0285	0.0130 - 0.0540	9
PROTOCOL CHRYS STRUCS 5-10	49.3	0.0158	0.00514 - 0.0369	5
PROTOCOL CHRYS STRUCS >10	19.7	0.00633	0.00 - 0.0199	2
PROTOCOL CHRYS STRUCS TOTAL	69.0	0.0221	0.00890 - 0.0456	7
PROTOCOL AMPH STRUCS 5-10	19.7	0.00633	0.00 - 0.0199	2
PROTOCOL AMPH STRUCS >10	0.0	<0.00946	0.00 - 0.00946	0
PROTOCOL AMPH STRUCS TOTAL	19.7	0.00633	0.00 - 0.0199	2
AHERA-like Total Structures 3:1	976.0	0.313	0.254 - 0.381 (Poisson)	99
AHERA-like Asb Strucs >5 and 3:1	157.7	0.0506	0.0289 - 0.0822	16
AHERA-like Asb Strucs 5 - 10 and 3:1	118.3	0.0380	0.0196 - 0.0663	12
AHERA-like Asb Strucs >10 and 3:1	39.4	0.0127	0.00345 - 0.0324	4
Total Other Amphibole Strucs 3:1	0.0	<0.00946	0.00 - 0.00946	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.00946	0.00 - 0.00946	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.00946	0.00 - 0.00946	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.00946	0.00 - 0.00946	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

ANALYSIS DETAIL

Lab/Cor Sample No. B4773 S65 A1
Client Sample No. TRA-L2-1ZP-100904
Description
Analysis Date 11/2/2004
Analyst DW

Volume (L) 300.76
No. of Grid Openings 7
Filter Area (mm2) 385
Area Analyzed (mm2) 0.101
Analytical Sens. (struc/cc) 0.0126
Dectection Limit. (struc/cc) 0.0377

Structure Type	Filter Density (s/mm2)	Concen-tration (struc/cc)	95% Confidence Interval (struc/cc)	Struc. Count
Primary Asbestos Structures	995.8	1.27	1.03 - 1.54 (Poisson)	101
Total Asbestos Structures	995.8	1.27	1.03 - 1.54 (Poisson)	101
Asbestos Structures > 5um	216.9	0.278	0.174 - 0.420	22
Asbestos Fibers and Bundles > 5um	197.2	0.252	0.154 - 0.390	20
PCM Equivalent Fibers-US	187.3	0.240	0.144 - 0.374	19
PCM Equivalent Structures-US	197.2	0.252	0.154 - 0.390	20
PROTOCOL ASB STRUCS 5-10	59.2	0.0757	0.0278 - 0.165	6
PROTOCOL ASB STRUCS >10	9.9	0.0126	0.00 - 0.0598	1
PROTOCOL ASB STRUCS TOTAL	69.0	0.0883	0.0355 - 0.182	7
PROTOCOL CHRYS STRUCS 5-10	19.7	0.0252	0.00 - 0.0795	2
PROTOCOL CHRYS STRUCS >10	9.9	0.0126	0.00 - 0.0598	1
PROTOCOL CHRYS STRUCS TOTAL	29.6	0.0379	0.00 - 0.0978	3
PROTOCOL AMPH STRUCS 5-10	39.4	0.0505	0.0138 - 0.129	4
PROTOCOL AMPH STRUCS >10	0.0	<0.0377	0.00 - 0.0377	0
PROTOCOL AMPH STRUCS TOTAL	39.4	0.0505	0.0138 - 0.129	4
AHERA-like Total Structures 3:1	946.5	1.21	0.981 - 1.49 (Poisson)	96
AHERA-like Asb Strucs >5 and 3:1	197.2	0.252	0.154 - 0.390	20
AHERA-like Asb Strucs 5 - 10 and 3:1	138.0	0.177	0.0966 - 0.296	14
AHERA-like Asb Strucs >10 and 3:1	59.2	0.0757	0.0278 - 0.165	6
Total Other Amphibole Strucs 3:1	0.0	<0.0377	0.00 - 0.0377	0
Other Amphibole Strucs >5 and 3:1	0.0	<0.0377	0.00 - 0.0377	0
Other Amphibole Strucs 5 - 10 and 3:1	0.0	<0.0377	0.00 - 0.0377	0
Other Amphibole Strucs >10 and 3:1	0.0	<0.0377	0.00 - 0.0377	0

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-1TR-100904 *Lab/Cor Sample No.:* B4773 S95 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A13	AZQ	1	1	F	4.8	1	4.8	1061	789	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [9 1 10] - JH	TAS_AHRA
A	2	A32		NSD									
A	3	B40		NSD									
A	4	B12		NSD									
A	5	C11		NSD									
A	6	C33		NSD									
A	7	C41		NSD									
A	8	D30	AQ	2	2	F	15	4	3.8			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	9	D22	AQ	3	3	F	2.5	0.3	8.3			Mg, Al, Si, Ca, Fe Actinolite	TAS_AHRA
B	10	A12		NSD									
B	11	A32		NSD									
B	12	A40		NSD									
B	13	B32		NSD									
B	14	B11		NSD									
B	15	C33		NSD									
B	16	C20	AQ	4	4	F	14	0.6	23			Mg, Al, Si, Ca, Fe Actinolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	17	D32		NSD									
B	18	D10		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-11TR-100904 *Lab/Cor Sample No.:* B4773 S94 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A12		NSD									
A	2	A20		NSD									
A	3	B23		NSD									
A	4	B2		NSD									
A	5	C33		NSD									
A	6	C20		NSD									
A	7	C40		NSD									
A	8	D32		NSD									
A	9	D11		NSD									
B	10	A2		NSD									
B	11	A31		NSD									
B	12	B23		NSD									
B	13	B1		NSD									
B	14	C4		NSD									
B	15	C22		NSD									
B	16	C40		NSD									
B	17	D23		NSD									
B	18	D2		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-2TR-100904 *Lab/Cor Sample No.:* B4773 S96 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A11		NSD									
A	2	A32		NSD									
A	3	B10		NSD									
A	4	B3		NSD									
A	5	C12		NSD									
A	6	C31		NSD									
A	7	D40		NSD									
A	8	D42		NSD									
A	9	D2		NSD									
B	10	A13		NSD									
B	11	A32		NSD									
B	12	A20		NSD									
B	13	B32		NSD									
B	14	B13		NSD									
B	15	C12		NSD									
B	16	C31		NSD									
B	17	D40		NSD									
B	18	D22		NSD									
B	19	D1	AZQ	1	1	F	14	2.5	5.6	1062	790	Mg, Al, Si, Ca, Fe Actinolite Zone Axis [4 0 1] - JH	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-3TR-100904 *Lab/Cor Sample No.:* B4773 S97 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A20		NSD									
A	2	A33		NSD									
A	3	B40		NSD									
A	4	B10		NSD									
A	5	B23		NSD									
A	6	C4		NSD									
A	7	C21		NSD									
A	8	C40		NSD									
A	9	D12		NSD									
B	10	A1		NSD									
B	11	A23		NSD									
B	12	A41		NSD									
B	13	B20		NSD									
B	14	B3		NSD									
B	15	C11		NSD									
B	16	C40		NSD									
B	17	D20		NSD									
B	18	D2		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-4TR-100904 *Lab/Cor Sample No.:* B4773 S98 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B43		NSD									
A	2	B23		NSD									
A	3	B3		NSD									
A	4	C13		NSD									
A	5	C33		NSD									
A	6	C42		NSD									
A	7	C22		NSD									
A	8	C2		NSD									
A	9	B12		NSD									
A	10	B42		NSD									
B	11	B44		NSD									
B	12	B24		NSD									
B	13	B14		NSD									
B	14	C4		NSD									
B	15	C24		NSD									
B	16	C43		NSD									
B	17	C23		NSD									
B	18	C3		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H8-5TR-100904 *Lab/Cor Sample No.:* B4773 S99 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A11		NSD									
A	2	A42		NSD									
A	3	B30		NSD									
A	4	B13		NSD									
A	5	C1		NSD									
A	6	C23		NSD									
A	7	C42		NSD									
A	8	D30		NSD									
A	9	D12		NSD									
B	10	A20		NSD									
B	11	A32		NSD									
B	12	B21		NSD									
B	13	B13		NSD									
B	14	C11		NSD									
B	15	C33		NSD									
B	16	C41		NSD									
B	17	D20		NSD									
B	18	D2		NSD									

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S93 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	A31	CDQ	1	1	F	2.5	0.06	42	1059	787	Mg, Si Chrysotile Verified - JH	TAS_AHRA
A	1	A31	AZQ	2	2	F	1.5	0.5	3.0	1060	788	Mg, Si, Ca, Fe Tremolite Zone Axis [3 1 2] - JH	TAS_AHRA
A	1	A31	CD	3	3	F	1.7	0.05	34			Chrysotile	TAS_AHRA
A	1	A31	AQ	4	4	F	2.4	0.3	8.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	1	A31	CD	5	5	B	1.7	0.3	5.7			Chrysotile	TAS_AHRA
A	1	A31	CD	6	6	F	1.5	0.05	30			Chrysotile	TAS_AHRA
A	1	A31	CD	7	7	F	1.5	0.05	30			Chrysotile	TAS_AHRA
A	1	A31	CD	8	8	B	1	0.1	10			Chrysotile	TAS_AHRA
A	1	A31	AQ	9	9	F	1	0.3	3.3			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	1	A31	AQ	10	10	F	1.6	0.5	3.2			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	1	A31	CD	11	11	B	2.7	0.06	45			Chrysotile	TAS_AHRA
A	1	A31	CD	12	12	B	3	0.2	15			Chrysotile	TAS_AHRA
A	1	A31	AQ	13	13	F	4.5	0.3	15			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	1	A31	CD	14	14	F	1.5	0.03	50			Chrysotile	TAS_AHRA
A	1	A31	AQ	15	15	F	14	1.5	9.3			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
A	2	B22	AQ	16	16	F	9	1	9.0			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	B22	CD	17	17	B	4	0.1	40			Chrysotile	TAS_AHRA
A	2	B22	CD	18	18	F	2.3	0.07	33			Chrysotile	TAS_AHRA
A	2	B22	CD	19	19	F	1.6	0.05	32			Chrysotile	TAS_AHRA
A	2	B22	CD	20	20	B	4	0.3	13			Chrysotile	TAS_AHRA
A	2	B22	CD	21	21	B	1.5	0.25	6.0			Chrysotile	TAS_AHRA
A	2	B22	AQ	22	22	F	1.5	0.15	10			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	2	B22	AQ	23	23	B	1	0.3	3.3			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	2	B22	AQ	24	24	F	5.2	0.4	13			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	B22	AQ	25	25	F	3	0.9	3.3			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	2	B22	AQ	26	26	B	1.2	0.4	3.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	2	B22	AQ	27		MD2-1	6	5.5	1.1			Tremolite	AS>5, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	B22	AQ		27	MF	5.5	0.6	9.2			Mg, Si, Ca, Fe Tremolite	AFB>5, PCMEF-US

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S93 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	2	B22	AQ		28	MF	4.9	0.6	8.2			Mg, Si, Ca, Fe Tremolite	
A	2	B22	AQ	28	29	B	2.4	1	2.4			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	CD	29	30	F	1	0.04	25			Chrysotile	TAS_AHRA
A	3	B3	CD	30	31	B	1	0.2	5.0			Chrysotile	TAS_AHRA
A	3	B3	AQ	31	32	F	1.5	0.3	5.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	CD	32	33	B	8	0.15	53			Chrysotile	AS>5, AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	B3	AQ	33	34	F	2.4	0.4	6.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	34	35	B	8	1	8.0			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	B3	AQ	35	36	F	2.5	0.4	6.2			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	36	37	B	2.5	0.4	6.2			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	37	38	B	2.8	0.5	5.6			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	38	39	F	4	0.6	6.7			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	39	40	F	2.7	0.5	5.4			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	40	41	B	2.5	0.3	8.3			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	41	42	B	2.4	0.2	12			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	AQ	42	43	F	1	0.2	5.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	3	B3	CD	43	44	F	7.6	0.05	150			Chrysotile	AS>5, AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	3	B3	AQ	44	45	F	1	0.2	5.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	AQ	45	46	B	2.4	0.5	4.8			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	CD	46	47	B	3.5	0.2	18			Chrysotile	TAS_AHRA
A	4	D20	AQ	47	48	B	2.5	0.5	5.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	CD	48	49	F	2.3	0.05	46			Chrysotile	TAS_AHRA
A	4	D20	CD	49	50	F	1	0.04	25			Chrysotile	TAS_AHRA
A	4	D20	AQ	50	51	B	2.7	1	2.7			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	CD	51		CD2-1	7	1	7.0			Chrysotile	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	4	D20	CD		52	CF	7	0.05	140			Chrysotile	AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
A	4	D20	CD		53	CB	1	0.2	5.0			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S93 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	4	D20	AQ	52	54	F	5.2	0.7	7.4			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	4	D20	AQ	53	55	B	4	1	4.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	CD	54	56	F	2.3	0.05	46			Chrysotile	TAS_AHRA
A	4	D20	AQ	55	57	F	2.3	0.4	5.8			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
A	4	D20	CD	56	58	F	1.4	0.05	28			Chrysotile	TAS_AHRA
A	4	D20	CD	57	59	B	5	0.5	10			Chrysotile	TAS_AHRA
A	4	D20	CD	58	60	F	2.7	0.05	54			Chrysotile	TAS_AHRA
A	4	D20	CD	59	61	B	1.5	0.2	7.5			Chrysotile	TAS_AHRA
B	5	A21	CD	60	62	B	2.5	0.15	17			Chrysotile	TAS_AHRA
B	5	A21	AQ	61	63	F	1.5	0.5	3.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	5	A21	AQ	62	64	F	6	0.7	8.6			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	5	A21	CD	63	65	F	2.5	0.06	42			Chrysotile	TAS_AHRA
B	5	A21	CD	64	66	B	2.5	0.3	8.3			Chrysotile	TAS_AHRA
B	5	A21	CD	65	67	B	2.4	0.2	12			Chrysotile	TAS_AHRA
B	5	A21	CD	66	68	F	1.5	0.04	38			Chrysotile	TAS_AHRA
B	5	A21	CD	67	69	F	1	0.05	20			Chrysotile	TAS_AHRA
B	5	A21	CD	68	70	F	2.3	0.05	46			Chrysotile	TAS_AHRA
B	5	A21	CD	69	71	B	1.5	0.7	2.1			Chrysotile	TAS_AHRA
B	5	A21	AQ	70	72	F	1.2	0.3	4.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	5	A21	AQ	71	73	F	3.8	0.4	9.5			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	5	A21	AQ	72	74	F	1.5	0.5	3.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	6	B32	CD	73	75	B	4.8	0.25	19			Chrysotile	TAS_AHRA
B	6	B32	AQ	74	76	B	1.6	0.5	3.2			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	6	B32	CD	75	77	F	1.5	0.06	25			Chrysotile	TAS_AHRA
B	6	B32	CD	76	78	F	1.3	0.06	22			Chrysotile	TAS_AHRA
B	6	B32	CD	77	79	F	1.5	0.06	25			Chrysotile	TAS_AHRA
B	6	B32	AQ	78	80	F	2	0.5	4.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	6	B32	CD	79	81	F	2.4	0.04	60			Chrysotile	TAS_AHRA
B	6	B32	AQ	80	82	F	10	1.5	6.7			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	6	B32	AQ	81	83	F	3.8	0.2	19			Mg, Si, Ca, Fe Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-H2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S93 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	6	B32	CD	82	84	B	30	0.5	60			Chrysotile	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS >10, PSAS TOT, PCAS >10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	6	B32	CD	83	85	F	4	0.05	80			Chrysotile	TAS_AHRA
B	6	B32	CD	84	86	F	2.5	0.05	50			Chrysotile	TAS_AHRA
B	6	B32	AQ	85	87	F	7.5	0.4	19			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	6	B32	CD	86		CD3-1	23	2	12			Chrysotile	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	6	B32	CD		88	CB	23	0.6	38			Chrysotile	AFB>5, PCMEF-US
B	6	B32	CD		89	CB	2.3	0.2	12			Chrysotile	
B	6	B32	CD		90	CR6-0	1.5	0.3	5.0			Chrysotile	
B	6	B32	CD	87	91	F	1.2	0.07	17			Chrysotile	TAS_AHRA
B	6	B32	AQ	88	92	F	1	0.25	4.0			Tremolite	TAS_AHRA
B	6	B32	CD	89	93	F	1.2	0.05	24			Chrysotile	TAS_AHRA
B	7	C10	CD	90	94	F	12	0.05	240			Chrysotile	AS>5, AFB>5, PSAS >10, PSAS TOT, PCAS >10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	7	C10	CD	91		CD3-2	10	1	10			Chrysotile	AS>5, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	7	C10	CD		95	CF	8.5	0.08	110			Chrysotile	AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
B	7	C10	CD		96	CF	7.5	0.05	150			Chrysotile	AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
B	7	C10	CD		97	CF	1.5	0.05	30			Chrysotile	
B	7	C10	AQ	92	98	F	3.5	1	3.5			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	7	C10	CD	93	99	F	1	0.05	20			Chrysotile	TAS_AHRA
B	7	C10	CD	94	100	F	1	0.05	20			Chrysotile	TAS_AHRA
B	7	C10	AQ	95	101	F	3	0.3	10			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	7	C10	AQ	96	102	F	0.7	0.2	3.5			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	7	C10	AQ	97	103	F	2.8	0.25	11			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	7	C10	AQ	98	104	B	4	0.9	4.4			Mg, Si, Ca, Fe Tremolite	TAS_AHRA
B	7	C10	AQ	99	105	F	0.6	0.2	3.0			Mg, Si, Ca, Fe Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-L2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S65 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
A	1	B4	ADQ	1	1	F	10	0.4	25			Mg, Si, Ca, Fe Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B4	ADQ	2	2	F	1.5	0.35	4.3			Tremolite	TAS_AHRA
A	1	B4	ADQ	3	3	F	6	1.5	4.0			Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	1	B4	AZQ	4	4	F	3	0.35	8.6	5393	15288	Tremolite Zone Axis [2 1 1] - KM	TAS_AHRA
A	1	B4	AQ	5	5	F	4	1.2	3.3			Tremolite	TAS_AHRA
A	1	B4	AQ	6	6	F	2	0.4	5.0			Tremolite	TAS_AHRA
A	1	B4	AQ	7	7	F	3.8	1.1	3.5			Tremolite	TAS_AHRA
A	1	B4	CDQ	8	8	F	1.8	0.02	90	5394	15289	Mg, Si Chrysotile Verified - KM	TAS_AHRA
A	1	B4	CD	9	9	F	0.5	0.02	25			Chrysotile	TAS_AHRA
A	1	B4	AQ	10	10	F	1.2	0.2	6.0			Tremolite	TAS_AHRA
A	1	B4	CDQ	11	11	CC10-2	9	0.4	22			Chrysotile	AS>5, PCMES-US, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT
A	1	B4	CD	12	12	F	2.1	0.08	26			Chrysotile	TAS_AHRA
A	1	B4	CD	13	13	F	2.3	0.08	29			Chrysotile	TAS_AHRA
A	2	A41	CMQ	14	14	B	3	0.25	12			Mg, Si Chrysotile	TAS_AHRA
A	2	A41	CM	15	15	F	3.5	0.15	23			Chrysotile	TAS_AHRA
A	2	A41	CD	16	16	F	1	0.05	20			Chrysotile	TAS_AHRA
A	2	A41	CD	17	17	F	1	0.05	20			Chrysotile	TAS_AHRA
A	2	A41	CD	18	18	F	2	0.1	20			Chrysotile	TAS_AHRA
A	2	A41	CM	19	19	F	0.75	0.01	75			Chrysotile	TAS_AHRA
A	2	A41	AQ	20	20	F	2.5	0.2	12			Mg, Si, Ca Tremolite	TAS_AHRA
A	2	A41	AQ	21	21	F	7.5	1.2	6.2			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
A	2	A41	CMQ	22	22	CC20-1	6	6	1.0			Mg, Si Chrysotile	AS>5
A	2	A41	AQ	23	23	F	2	0.2	10			Mg, Si Tremolite	TAS_AHRA
A	2	A41	AQ	24	24	F	0.75	0.15	5.0			Mg, Si Tremolite	TAS_AHRA
A	2	A41	CMQ	25	25	CC10-0	4	4	1.0			Mg, Si Chrysotile	
A	2	A41	CM	26	26	F	0.75	0.05	15			Chrysotile	TAS_AHRA
A	2	A41	AQ	27	27	F	1	0.05	20			Mg, Si, Ca Tremolite	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-L2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S65 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
B	3	D41	AQ	28	28	F	4	1	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	29	29	F	2.5	0.75	3.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	30	30	F	45	2.75	16			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
B	3	D41	CM	31	31	F	2.5	0.05	50			Chrysotile	TAS_AHRA
B	3	D41	AQ	32	32	F	1.5	0.5	3.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	33	33	F	2.5	0.15	17			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	CMQ	34	34	F	2.5	0.05	50			Mg, Si Chrysotile	TAS_AHRA
B	3	D41	CMQ	35	35	F	0.5	0.05	10			Mg, Si Chrysotile	TAS_AHRA
B	3	D41	CM	36	36	F	4	0.1	40			Chrysotile	TAS_AHRA
B	3	D41	CM	37	37	F	1	0.05	20			Chrysotile	TAS_AHRA
B	3	D41	CMQ	38	38	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
B	3	D41	CMQ	39	39	F	1	0.05	20			Mg, Si Chrysotile	TAS_AHRA
B	3	D41	AZQ	40	40	F	5	0.7	7.1	5395	15291	Mg, Si, Ca, Fe Tremolite Zone Axis [1 0 1] - KM	TAS_AHRA
B	3	D41	AQ	41	41	F	2.5	0.6	4.2			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	42	42	F	4.5	0.25	18			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	43	43	F	2	0.4	5.0			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	44	44	F	5.5	0.75	7.3			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	3	D41	CM	45	45	F	3.5	0.1	35			Chrysotile	TAS_AHRA
B	3	D41	CM	46	46	F	2.5	0.05	50			Chrysotile	TAS_AHRA
B	3	D41	CD	47	47	F	2.5	0.1	25			Chrysotile	TAS_AHRA
B	3	D41	AQ	48	48	F	2.5	0.75	3.3			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	49	49	F	7.5	2	3.8			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
B	3	D41	CD	50	50	B	3	0.15	20			Chrysotile	TAS_AHRA
B	3	D41	AQ	51	51	F	4	0.3	13			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	AQ	52	52	F	2	0.15	13			Mg, Si, Ca Tremolite	TAS_AHRA
B	3	D41	CM	53	53	F	1	0.05	20			Chrysotile	TAS_AHRA
C	4	C21	CD	54	54	B	22.5	0.5	45			Chrysotile	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS >10, PSAS TOT, PCAS >10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	4	C21	CD	55	55	F	1.8	0.1	18			Chrysotile	TAS_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-L2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S65 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	4	C21	CD	56	56	F	1.1	0.08	14			Chrysotile	TAS_AHRA
C	4	C21	AQ	57	57	F	5.8	0.5	12			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	4	C21	AQ	58	58	F	6	1.3	4.6			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	4	C21	AQ	59	59	F	1.1	0.15	7.3			Mg, Si, Ca Tremolite	TAS_AHRA
C	4	C21	AQ	60	60	F	4	1.2	3.3			Mg, Si, Ca Tremolite	TAS_AHRA
C	4	C21	CD	61	61	B	3	0.2	15			Chrysotile	TAS_AHRA
C	4	C21	AQ	62	62	F	3.3	0.3	11			Mg, Si, Ca Tremolite	TAS_AHRA
C	4	C21	CD	63	63	B	2	0.12	17			Chrysotile	TAS_AHRA
C	4	C21	CM	64	64	F	0.6	0.02	30			Chrysotile	TAS_AHRA
C	4	C21	CD	65	65	F	2	0.1	20			Chrysotile	TAS_AHRA
C	4	C21	AQ	66	66	F	5.5	1	5.5			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	4	C21	AQ	67	67	F	2.8	0.7	4.0			Mg, Si, Ca Tremolite	TAS_AHRA
C	5	C44	AQ	68	68	F	20	0.7	29			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	5	C44	AQ	69	69	F	1.8	0.5	3.6			Mg, Si, Ca Tremolite	TAS_AHRA
C	5	C44	CD	70	70	B	1.5	0.15	10			Chrysotile	TAS_AHRA
C	5	C44	CD	71	71	F	1.5	0.08	19			Chrysotile	TAS_AHRA
C	5	C44	AQ	72	72	F	3.5	0.5	7.0			Tremolite	TAS_AHRA
C	5	C44	CD	73	73	CC8-0	3	1	3.0			Chrysotile	
C	5	C44	ADQ	74	74	F	3.3	0.45	7.3			Mg, Si, Ca Tremolite	TAS_AHRA
C	6	C34	CD	75	75	B	3.5	0.2	18			Chrysotile	TAS_AHRA
C	6	C34	AQ	76	76	F	9.5	1.2	7.9			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	6	C34	CD	77	77	B	1.3	0.15	8.7			Chrysotile	TAS_AHRA
C	6	C34	CD	78	78	F	1.8	0.05	36			Chrysotile	TAS_AHRA
C	6	C34	CD	79	79	F	4.9	0.08	61			Chrysotile	TAS_AHRA
C	6	C34	CD	80	80	CC5-0	4	0.8	5.0			Chrysotile	

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-L2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S65 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	6	C34	AQ	81	81	F	6	0.4	15			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	6	C34	CD	82	82	F	1.8	0.08	22			Chrysotile	TAS_AHRA
C	6	C34	CD	83	83	F	1.5	0.1	15			Chrysotile	TAS_AHRA
C	7	C14	CD	84	84	F	1.6	0.05	32			Chrysotile	TAS_AHRA
C	7	C14	CD	85	85	F	1	0.08	12			Chrysotile	TAS_AHRA
C	7	C14	AQ	86	86	F	11.5	1.3	8.8			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	C14	AQ	87	87	F	5.5	0.38	14			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, PSAS 5-10, PSAS TOT, PSAM 5-10, PSAM TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	7	C14	ADQ	88	88	F	3.8	0.4	9.5			Mg, Si, Ca Tremolite	TAS_AHRA
C	7	C14	AQ	89	89	F	11	1	11			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	C14	CD	90	90	F	2	0.08	25			Chrysotile	TAS_AHRA
C	7	C14	CD	91	91	F	5.2	0.08	65			Chrysotile	AS>5, AFB>5, PSAS 5-10, PSAS TOT, PCAS 5-10, PCAS TOT, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	7	C14	CD	92	92	F	1	0.05	20			Chrysotile	TAS_AHRA
C	7	C14	CD	93	93	F	4	0.1	40			Chrysotile	TAS_AHRA
C	7	C14	CD	94	94	F	2.8	0.08	35			Chrysotile	TAS_AHRA
C	7	C14	CD	95	95	F	1.5	0.05	30			Chrysotile	TAS_AHRA
C	7	C14	AQ	96	96	F	11.5	2	5.8			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS>10_AHRA
C	7	C14	CD	97		MD1-0	3	1.2	2.5			Chrysotile	TAS_AHRA
C	7	C14	CD		97	MF	1.8	0.05	36			Chrysotile	
C	7	C14	AQ	98	98	F	1.8	0.4	4.5			Mg, Si, Ca Tremolite	TAS_AHRA
C	7	C14	AQ	99	99	F	8	1	8.0			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA
C	7	C14	AQ	100	100	F	8.5	1	8.5			Mg, Si, Ca Tremolite	AS>5, AFB>5, PCMEF-US, PCMES-US, TAS_AHRA, AS>5_AHRA, AS5-10_AHRA

Lab/Cor, Inc.

A Professional Service Corporation in the Northwest

Report # 041191R6

Client: Ecology and Environment, Inc.

Project Name: Site #0440.01CP Sample Set #3 - FINAL RESULTS

TEM ASBESTOS STRUCTURE COUNT - RAW DATA

Sample No.: TRA-L2-1ZP-100904 *Lab/Cor Sample No.:* B4773 S65 A1

Descripiton:

Gr	No.	Loc.	ID	Prim	Tot	Class	Len	Wid	Asp	Neg#	EDS#	Comment	Count Categories
C	7	C14	AQ	101	101	F	4	0.8	5.0			Mg, Si, Ca Tremolite	TAS_AHRA