

CHAMPAIGN MGP PHASE 4 TENT MOVE

Preliminary Work:

- All ground surfaces that the tent will be moved on should be graded, compacted and leveled to the best that conditions allow.
- All hoses/ductwork should be disconnected and removed from the tent move area.
- All necessary electrical equipment should be disconnected and removed from the move area.
- All carbon vessels and blowers disconnected and moved to the far eastern side of the property
- Inspections of all dollies and other tent move equipment to ensure they are ready for use.
- Gable ends should be completely dismantled (gable supports, fabric, doors, purloins, etc.) and removed from the tent move area.
- All tension bars will be removed.
- All sand bags to be removed only after gable end fabric has been removed.
- Bay doors will be removed by a professional overhead door co. and will utilize the equipment operators to move the doors.
- Fabric should be tied up with rope on each tent bay from the outside of the tent.
- The fabric in the 6th bay from the south will be removed.
- New tent location should be surveyed and marked out.
- The trash dumpster and porti-john will be moved to east side.
- All snow/ice will be removed from tent base and tent move route.
- Silt fence and hay bails will be rerouted closer to the northern fence line.
- Any materials supplies within the tent move route must be moved to the eastern side of property.
- PPE trailer to be moved

