PRE-OPERATIONAL TESTING PROGRAM
40 CFR 146.87

Facility Information

Facility name:	Capio Sherburne Sequestration, LLC
Well name:	Capio Sherburne CCS Well No. 1
Facility contact:	Peter Hollis, Capio Sequestration - President Michael Neese, Capio Sequestration - Senior Vice President Capio Sherburne Sequestration, LLC 109 N. Post Oak Ln, Suite 140, Houston, Texas 77024 832-551-3300 / pete@fidelisinfra.com
Well location:	Sherburne Wildlife Management Area (WMA) Pointe Coupee Parish, Louisiana 30.521385, -91.718429

Introduction

The pre-operational testing program is limited to data collected during drilling and completion of the injection well for the purpose of ensuring conformance with the testing standards in 40 CFR 146.87 and the construction standards in 40 CFR 146.86. The testing program includes a combination of logs, surveys, cores, reservoir testing and integrity testing to provide site-specific subsurface data and to establish a baseline against which future measurements may be compared. Testing and monitoring activities, which will be conducted during the injection and post-injection phases are described in the Testing and Monitoring Plan of this application.

Notification of each step of the pre-operational testing plan will be provided to the UIC Program Director for witness opportunity. The schedule of activities will be provided a minimum of 30 days prior to the first test. Following all pre-operational testing, Capio will provide a descriptive report prepared by knowledgeable analysts and include interpretations of each test result.