



# *FTIR*

## Fourier Transform Infrared Spectrometer

Infraed signal to remotely monitor Shinkampo stack emissions

Only stack emissions regulated by Japanese Law

Barriers erected by Shinkampo  
block FTIR signal

Stated Shinkampo purpose is  
to “protect workers”

GOJ lacks authority to force removal


GOJ acknowledges FTIR safety  
2 1/2 months of negotiations








## NAF Atsugi FTIR Data







## *Monitoring -Shinkampo's Reaction*











**The RDF**  
(under construction)

**Construction  
Debris  
Handling Area**

**Waste Offload  
Area**

**Video Camera View**









**Standard Industry  
Truck Scale**





## *Truck Count Methodology*

- **Video surveillance camera aimed only at the incinerator loading area**
- **Count only trucks unloading combustible trash**
  - **separate by truck type/size**
  - **trucks handling construction debris not counted**
- **Subtract the noncombustibles removed from the burn pile**







## *Shinkampo Throughput Calculations*

**Height x Width x Length (of Truck Bed) = Truck Capacity**

**Number of Trucks x Truck Capacity = Volume**

**Volume x Density = Throughput**

**\*\*Density (tons/m<sup>3</sup>):**

Waste Plastic:	0.1 - 0.3
<b>Wood Scrap:</b>	<b>0.4 - 0.7</b>
Metal Scrap:	1.4 - 2.0
Sludge:	1.2 - 1.6
Glass/Ceramic	1.5
Construction Debris:	1.6 - 1.8

From: Ministry of Health & Welfare, New Paper on Waste Materials, page 20, Kuwahara Kazuo,





7 October 1998

Trucks Dumping into Incinerator Loading Area

2-ton Dump Trucks	2
4-ton Dump Trucks/Compactors	17
Box Vans	0
4-ton Stakebed Trucks	0
10-ton Short Dump Trucks	8
10-ton Medium Dump Trucks	3
10-ton Long Dump Trucks	0

Trucks Removing Noncombustibles from Incinerator Loading Area

4-ton Dump Trucks	0
10-ton Short Dump Trucks	0
10-ton Medium Dump Trucks	0





## *Typical Calculation - 7 October 1998*

### 4-ton Dump Trucks

Number of Trucks = 17

Volume

Height - 1.5 Meters

Width - 1.8 Meters

Length - 3.6 Meters

Volume = 9.7 Cubic Meters

Density = 415 Kilograms per Cubic Meter


Throughput from 4-ton Dump Trucks

17 trucks x 9.7 Cubic Meters/Truck x 415 Kilograms per Cubic Meter = 68,600  
Kilograms = **68.6 Metric Tons**





# Shinkampo Throughput







## *US vs. Shinkampo Throughput Estimates*

Date	US	Shin-kampo	2-ton dump	4-ton dump	Box van	4-ton stake-bed	10-ton dump short	10-ton dump medium	10-ton dump long
24 Sept. 98	275	30	3	27	0	1	11	3	1
25 Sept. 98	345	30	3	41	0	2	8	6	1
26 Sept. 98	139	30	3	28	1	0	2	0	0
28 Sept. 98	246	53	1	31	0	0	2	8	0
29 Sept. 98	216	89	1	29	0	2	4	4	0
30 Sept. 98	229	89	2	30	2	2	4	4	0





## *U.S. vs. Shinkampo's Crane Scale Estimates*

Date	USG Estimate (TPD)	Shinkampo Estimate (TPD)	Crane Loads (number of loads)
24 Sep 98	275	30	288
25 Sep 98	345	30	297
26 Sep 98	139	30	315
<b>90 TPD Permit Issued</b>			
28 Sep 98	246	53	296
29 Sep 98	216	89	304
30 Sep 98	229	89	308






## *Why would Shinkampo use 3 incinerators for only 30 tpd?*

- ✓ Increased power consumption for 3 induction fans
- ✓ Increased supplemental fuel, quench and caustic usage
- ✓ Increased wear and tear on incinerators, crane and hoist
- ✓ More plant staff
- ✓ Incinerators can only be maintained while off-line
- ✓ Less efficient operation of incinerators and APCs
- ✓ The Bottom Line: It Costs More Yen





## *Monitoring -Shinkampo's Reaction*







## *KPG's Regulatory "Do Loop"*



**Must obtain an Administrative Order to shut down the incinerators**






## Typical Baghouse Filter Facility







## Shinkampo's Design for Baghouse Filters



### Current Design is Lacking

- No carbon injection
- Small induction fan
- Uses existing (inadequate) quench
- Will do a satisfactory job removing dust





*27 December 1999 -27 January 2000*

- **GOJ/KPG commence 56 days of ambient air monitoring south of Shinkampo**
- **Shinkampo shuts down No. 1 & No. 2 incinerator**



- **Maintains burn volume of approx. 30 tons/day**
- **No baghouse filter construction apparent**
- **No incinerator “repair work” apparent**





## *27 Jan 2000--Baghouse Filter Construction*







## *The Perils of Relying Upon Baghouse Filters Alone to Protect NAF Atsugi*

- **Expensive**
  - Approximately \$1M/year cost to Shinkampo for electricity, bag replacement, additional lime, and carbon injection
- **Very Easily Bypassed**
  - Must bypass frequently throughout the day to blow down the dust collected on the bags
  - Must bypass during plant start up and shut down to prevent excessive back pressure build up
  - If only one bag is missing or burned through, unfiltered emissions follow path of least resistance through the gap
- **Shinkampo Routinely Bypasses Existing Pollution Controls**







## *Additional Joint Monitoring*

- **Set to commence as soon as the first set of baghouse filters are installed--Late March/Early April**
- **Same sites on NAF Atsugi, two sites off base south of the incinerator**
- **No value in starting prior to baghouse filter installation**
  - GOJ/KPG have stated an inability to take further action outside of "administrative recommendation" for baghouse filters
  - likely to obtain skewed data with Shinkampo operating only one incinerator
  - additional "bad" data will not compel KPG to order a higher stack (both KPG and Murata state incinerator not compatible with 100-meter stack---not supported by data)
  - winter J/M with wind blowing offbase and only one incinerator operating will dilute previous J/M data and not provide an accurate picture of the true situation




The 100 meter Solution






# Why a 100-meter stack?

**27-Meter Stack, 1-Hour  
Current Location,  $\mu\text{g}/\text{m}^3$**



**100-Meter Stack, 1-Hour  
New Location, 200 TPD,  $\mu\text{g}/\text{m}^3$**







## *Shinkampo History*

- **Sep 1998:** GOJ announces Shinkampo solution--Two Phase Plan
- **Sep 1998:** Shinkampo an issue at Clinton-Obuchi Summit
- **Oct 1998:** DFAA begins an active role with the USG on Shinkampo
- **Nov 1998:** SECDEF Cohen statement to GOJ that Shinkampo must be fixed
- **Dec 1998:** CNFJ Petition and Letter of Objection on Shinkampo burn volume
- **Dec 1998:** RDF installed and operational (Phase I of GOJ Two Phase Plan)
- **Jan 1999:** CNFJ intensifies Joint Committee push for tangible progress from GOJ
- **Feb 1999:** USG briefs GOJ on excess Shinkampo burn volume video surveillance
- **Feb 1999:** Shinkampo owner arrested for tax evasion
- **Mar 1999:** USG-GOJ discuss Joint Monitoring details
- **Apr 1999:** Winds shift, NAF Atsugi once again fumigated by Shinkampo for next 6 months
- **Apr 1999:** GOJ Joint Monitoring Plan to US/GOJ Joint Committee
- **Apr 1999:** DFAA begins 100 meter stack/baghouse filter design





## *Shinkampo History*

- **Apr 1999:** Construction plan signed by US side of Joint Committee, GOJ does not sign
- **May 1999:** Clinton-Obuchi Summit: PM Obuchi commits to solution by Mar 01
- **Jul 1999:** Commence Joint Monitoring
- **Jul 1999:** GOJ contract with Murata for construction does not occur
- **Jul 1999:** Construction plan still not signed by GOJ side of Joint Committee
- **Aug 1999:** DFAA fails to complete construction design
- **Aug 1999:** No Ayase Planning Commission approval for DFAA construction design
- **Aug 1999:** No funding for construction
- **Sep 1999:** Shinkampo fails to commence installation of baghouse filters
- **Oct 1999 :** DFAA delivers very preliminary construction design
- **Oct 1999:** Shinkampo notifies DFAA of its refusal to permit construction of 100 meter stack
- **Oct 1999:** Joint Monitoring data released; record setting levels of dioxin found at NAF Atsugi
- **Nov 1999:** KPG announces intent to conduct own monitoring, Shinkampo modifies operations
- **Nov 1999:** KPG issues "Administrative Recommendation" to Shinkampo





## *Shinkampo History*

- **Nov 1999:** GOJ expresses inability to close Shinkampo based on Joint Monitoring data
- **Nov 1999:** KPG expresses reluctance to revoke Shinkampo permit based on JM data
- **Nov 1999:** GOJ pressures US for additional Joint Monitoring
- **Nov 1999:** Shinkampo responds to KPG Admin Recommendation--offers to install dust collector
- **Nov 1999:** Shinkampo contracts with IHI for the installation of bag filters to remove dust
- **Dec 1999:** KPG accepts Shinkampo Improvement Plan
- **Dec 1999:** Shinkampo shuts down two incinerators & KPG/JEA begin a "joint" 56 day ambient air monitoring program
- **Jan 2000:** Preliminary site work at Shinkampo on baghouse filters