Proposed Riverside Basement Forensic Sampling

Building #7 Basement Opening-smaller opening on the Southeast side of the building. Located towards the middle of the building. Sludge is piled up close to floor surface.		**Date Taken:** 2/5/2012 **Security Level:** Public **Category:** Site Photo **Latitude:** **Longitude:**	**Sampling:** One (1) DP undisturbed core – assume 8'-10' length – analytes listed below 
Building #7 Basement Opening-smaller opening on the Southeast side of the building. Located towards the middle of the building. Sludge is piled up close to floor surface		**Date Taken:** 2/14/2012 **Security Level:** Public **Category:** Site Photo **Latitude:** 40.7707197222222 **Longitude:** -74.1689497222222	**Sampling:** One (1) DP undisturbed core – assume 8'-10' length – analytes listed below 

DPT cores and samples (6 to 10) obtained by subcontractor. Samples will be hand-delivered to Accutest Dayton, NJ lab (COC lab) – Accutest NJ will ship to Accutest MA lab who will analyze samples – analysis would be for:

1. Hydrocarbon Characterization by Qualitative GC/FID – Fingerprinting by EPA 8015 modified and/or ASTM D3328-06(suspect Stoddard Solvent, light naphtha, toluene, mineral spirits)
2. PAHs and Alkylated PAHs by GC/MS/SIM EPA 8270 modified and/or ASTM D 5739-06
3. TCL VOAs + 10 by SW-846 8260B
4. TCL SVOAs + 20 by SW-846 8270D
5. TAL Metals + Ti + Hg by SW-846 6020/7471
6. Cr(VI) by SW846 3060A/7196A

238159