PHASE I REPORT

ENGINEERING INVESTIGATIONS AND EVALUATIONS AT INACTIVE HAZARDOUS WASTE DISPOSAL SITES

Crouse Hinds
Onondaga County, NY

SUBMITTED TO

New York State Department of Environmental Conservation

SUBMITTED BY

ENGINEERING-SCIENCE, INC.
in association with
DAMES & MOORE

JUNE 1983

TABLE OF CONTENTS

SITE IDENTIFICATION

USEPA #NYD980641526

NYSDEC #734004

SECTION I

EXECUTIVE SUMMARY

Crouse-Hinds

Objective

The purpose of this two phase program is to conduct engineering investigations and evaluations at inactive hazardous waste disposal sites in New York State in order to calculate a Hazard Ranking System (HRS) score for each site and estimate the cost of any recommended remedial action. During the initial portion of this investigation (Phase I) all available data and records combined with information collected from a site inspection were reviewed and evaluated to determine the adequacy of existing information for calculating an HRS score. On the basis of this evaluation, a Phase II Work Plan was prepared for collecting additional HRS data (if necessary), evaluating remedial alternatives and preparing a cost estimate for recommended remedial action. The results of the Phase I study for this site are summarized below and detailed in the body of the report.

Site Background

The site consists of two adjacent landfills in the Town of Salina, Onondaga County, New York. The sites are located a short distance to the north west of Crouse-Hinds Wolf and Seventh North Street Manufacturing facility. The South landfill consists of 15 acres and has been inactive since 1969. It was used to dispose of both industrial and municipal wastes. The North landfill is still active and has been predominately used for industrial wastes. The surrounding area consists primarily of wet lands which have been extensively used as landfills. Extensive monitoring of the North landfill has determined that phenols, cyanides, benzene, toluene and xylene are leaching into the groundwater. Monitoring at the South landfill has detected low levels of cyanides.

Assessment

Insufficient information is available to complete a final HRS scoring. The preliminary HRS scoring for this site was:

S_M=10.51	S_A=0
S_{GW}=0	S_{FE}=0
S_{SW}=18.18	S_{DC}=0

The surface water route scored high on this site due to the large target scoring. Additional target information is required for the groundwater route. Sufficient ground and surface water data is available for scoring, however an air sample is required.

Recommendations

The following recommendations are made for the completion of Phase II:

- air monitoring survey to determine air quality

The estimated manhour requirements for Phase II are 193, while the estimated cost is $7,916.

SECTION II

SITE DESCRIPTION

Crouse-Hinds

This site consists of two adjacent landfills in the town of Salina, Onondaga County, New York. The sites are located a short distance to the northwest of Crouse-Hind's Wolf and Seventh North Street electrical products manufacturing facilities in Syracuse, and is separated from them by a Conrail right-of-way. The surrounding area is zoned for industrial use but consists primarily of wetlands which have been extensively utilized as landfills.

The South landfill covers approximately 15 acres of land and has been inactive since 1969. The North landfill consisting of 21 acres is currently active. Extensive groundwater monitoring of the landfills have determined the presence of organic (phenols, benzene, toluene) and inorganic (cadmium, cyanide, chromium) containments in the North landfill area.

SITE LOCATION MAP
CROUSE HINDS

REFERENCE: U.S.G.S. 7.5' TOPOGRAPHIC MAP.
SYRACUSE WEST, NY (1978) QUADRANGLE

SECTION III

HRS SCORING

HRS COVER SHEET

Facility name: Crouse-Hinds

Location: 7th North St., Syracuse, NY

EPA Region: II

Person(s) in charge of the facility: Mr. Patrick Vassallo

VP Manufacturing

Crouse-Hinds, Syracuse, NY

Name of Reviewer: ~~John Kubarewicz/Eileen Gillian~~ Date: May 19, 1983

General description of the facility:

(For example: landfill, surface impoundment, pile, container; types of hazardous substances; location of the facility; contamination route of major concern; types of information needed for rating; agency action, etc.)

Industrial landfill surrounded by municipal landfills. Preliminary finding indicate possible presence of phenols, benzene, toluene, and chloroform in groundwater.

Scores: $S_M = 10.51$ ($S_{gw} = 0$ $S_{sw} = 18.18$ $S_a = 0$)

$S_{FE} = 0$

$S_{DC} = 0$

GROUND WATER ROUTE WORK SHEET

Ground Water Route Work Sheet

Rating Factor	Assigned Value (Circle One)	Multiplier	Score	Max. Score	Ref. (Sectio
1 Observed Release	0 (45)	1	45	45	3.1
If observed release is given a score of 45, proceed to line 4. If observed release is given a score of 0, proceed to line 2.					
2 Route Characteristics					3.2
Depth to Aquifer of Concern	0 1 2 3	2		6 OR 9	
Net Precipitation	0 1 2 3	1		3	
Permeability of the Unsaturated Zone	0 1 2 3	1		3	
Physical State	0 1 2 3	1		3	
Total Route Characteristics Score				15	
3 Containment	0 1 2 3	1		3	3.3
4 Waste Characteristics					3.4
Toxicity/Persistence	0 3 6 9 12 15 (18)	1	18	18	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 (8)	1	8	8	
Total Waste Characteristics Score			26	26	
5 Targets					3.5
Ground Water Use	(0) 1 2 3	3	0	9	
Distance to Nearest Well/Population Served	(0) 4 6 8 10 12 16 18 20 24 30 32 35 40	1	0	40	
Total Targets Score			0	49	
6 If line 1 is 45, multiply 1 x 4 x 5. If line 1 is 0, multiply 2 x 3 x 4 x 5			0	57,330	
7 Divide line 6 by 57,330 and multiply by 100			S_{gw} = 0.00		

AIR ROUTE WORK SHEET

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)		Multiplier	Score	Max. Score	Ref. (Section)
1 Observed Release	(0)	45	1		45	5.1
Date and Location:						
Sampling Protocol:						5
If line 1 is 0, the S_a = 0. Enter on line 5. If line 1 is 45, then proceed to line 2.						6
2 Waste Characteristics						5.2
Reactivity and Incompatibility	0 1 2 3		1		3	
Toxicity	0 1 2 3		3		9	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8		1		8	
	Total Waste Characteristics Score				20	
3 Targets						5.3
Population Within 4-Mile Radius	0 9 12 15 18 21 24 27 30		1		30	
Distance to Sensitive Environment	0 1 2 3		2		6	
Land Use	0 1 2 3		1		3	
	Total Targets Score				39	
4 Multiply 1 x 2 x 3					35,100	5
5 Divide line 4 by 35,100 and multiply by 100				S_a =		

Fire and Explosion Work Sheet

	Rating Factor	Assigned Value (Circle One)	Multiplier	Score	Max. Score	Ref. (Section)
1	Containment	1 3	1		3	7.1
2	Waste Characteristics					7.2
	Direct Evidence	0 3	1		3	
	Ignitability	0 1 2 3	1		3	
	Reactivity	0 1 2 3	1		3	
	Incompatibility	0 1 2 3	1		3	
	Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1		8	
	Total Waste Characteristics Score				20	
3	Targets					7.3
	Distance to Nearest Population	0 1 2 3 4 5	1		5	
	Distance to Nearest Building	0 1 2 3	1		3	
	Distance to Sensitive Environment	0 1 2 3	1		3	
	Land Use	0 1 2 3	1		3	
	Population Within 2-Mile Radius	0 1 2 3 4 5	1		5	
	Buildings Within 2-Mile Radius	0 1 2 3 4 5	1		5	
	Total Targets Score				24	
4	Multiply 1 x 2 x 3				1,440	
5	Divide line 4 by 1,440 and multiply by 100			FE =		

June 23, 1982

DOCUMENTATION RECORDS
FOR
HAZARD RANKING SYSTEM

INSTRUCTIONS: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: CROUSE-HINDS

LOCATION: SYRACUSE, NY

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

40

Mean annual lake or seasonal evaporation (list months for seasonal):

27

Net precipitation (subtract the above figures):

13

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

Permeability associated with soil type:

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

SOLID + LIQUID + SLUDGE

* * *

5 TARGETS

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

UNKNOWN

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

N/A

Distance to above well or building:

N/A

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

0

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

0

Total population served by ground water within a 3-mile radius:

0

Is the facility completely surrounded by areas of higher elevation?

NO

1-Year 24-Hour Rainfall in Inches

2.2

Distance to Nearest Downslope Surface Water

0.11

Physical State of Waste

LIQUID

* * *

3 CONTAINMENT

Containment

Method(s) of waste or leachate containment evaluated:

UNCONTAINED

Method with highest score:

Is there tidal influence?

NO

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

N/A

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

0.1

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

UNKNOWN

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

NONE

AIR ROUTE

1 OBSERVED RELEASE

Contaminants detected:

NONE DETECTED

Date and location of detection of contaminants

N/A

Methods used to detect the contaminants:

N/A

Rationale for attributing the contaminants to the site:

N/A

* * *

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

N/A

Most incompatible pair of compounds:

N/A

Distance to critical habitat of an endangered species, if 1 mile or less:

UNKNOWN

Land Use

Distance to commercial/industrial area, if 1 mile or less:

0.

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

3.5

Distance to residential area, if 2 miles or less:

UNKNOWN

Distance to agricultural land in production within past 5 years, if 1 mile or less:

N/A

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

N/A

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

N/A

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION
01 STATE: NY | 02 SITE NUMBER: D980641526

II. SITE NAME AND LOCATION

01 SITE NAME	02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER
CROUSE HINDS	NORTH + SOUTH LANDFILL SITES

03 CITY	04 STATE	05 ZIP CODE	06 COUNTY	07 COUNTY CODE	08 CONG DIST
SYRACUSE	NY	13221	ONONDAGA	67	-

09 COORDINATES: LATITUDE 43° 04' 38.1" | LONGITUDE 76° 10' 13.0"

10 TYPE OF OWNERSHIP (Check one)
☑ A. PRIVATE ☐ B. FEDERAL _____ ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER _____ ☐ G. UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION	02 SITE STATUS	03 YEARS OF OPERATION
4 26 83 (MONTH DAY YEAR)	☑ ACTIVE ☐ INACTIVE	1950'S : PRESENT (BEGINNING YEAR : ENDING YEAR) ☐ UNKNOWN — NORTH 1950- SOUTH 1960-1969

04 AGENCY PERFORMING INSPECTION (Check all that apply)
☐ A. EPA ☐ B. EPA CONTRACTOR _____ (Name of firm) ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR _____ (Name of firm)
☐ E. STATE ☑ F. STATE CONTRACTOR ES (Name of firm) D+M (Subcontractor) ☐ G. OTHER _____ (Specify)

05 CHIEF INSPECTOR	06 TITLE	07 ORGANIZATION	08 TELEPHONE NO.
John Kubarewicz	PROJ ENGINEER	ES	(703) 591-7575
09 OTHER INSPECTORS	10 TITLE	11 ORGANIZATION	12 TELEPHONE NO.
ART SEANOR	GEOLOGIST	D+M	315 633-2572
			( )
			( )
			( )
			( )

13 SITE REPRESENTATIVES INTERVIEWED	14 TITLE	15 ADDRESS	16 TELEPHONE NO.
TIM STONE	FACILITY MANAGER	CROUSE-HINDS SYRACUSE	(315) 477-5573
DAVE RANKAINEN	FACILITY ENGINEER	" "	(315) 477-5573
			( )
			( )
			( )
			( )

17 ACCESS GAINED BY (Check one)	18 TIME OF INSPECTION	19 WEATHER CONDITIONS
☑ PERMISSION ☐ WARRANT	14:30	CLEAR SUNNY

IV. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)	03 TELEPHONE NO.
John Kubarewicz	ES	(703) 591-7575

04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM	05 AGENCY	06 ORGANIZATION	07 TELEPHONE NO.	08 DATE
SAME				5 6 83 (MONTH DAY YEAR)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE (02 SITE NUMBER) NY 0980641526

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
GROUND WATER SAMPLES TAKEN ON NORTH LAND FILL SITE SHOW LOW LEVELS OF PHENOLS (.013-.065 PPM), CYANIDES ALSO LOW .009-.021 PPM

01 ☑ B. SURFACE WATER CONTAMINATION
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
SAMPLES IN LEY CREEK ADJACENT TO NORTH LANDFILL HAVE LOW CONCENTRATIONS OF CYANIDES, ZINC, CHROMIUM

01 ☐ C. CONTAMINATION OF AIR
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
NONE APPARENT

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
N/A

01 ☐ E. DIRECT CONTACT
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
LANDFILL WORKERS

01 ☐ F. CONTAMINATION OF SOIL
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ Acres
04 NARRATIVE DESCRIPTION
NOT TESTED

01 ☐ G. DRINKING WATER CONTAMINATION
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
N/A

01 ☐ H. WORKER EXPOSURE/INJURY
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
N/A

01 ☐ I. POPULATION EXPOSURE/INJURY
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____
04 NARRATIVE DESCRIPTION
UNKNOWN

EPA FORM 2070-13 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION
01 STATE | 02 SITE NUMBER
NY 0980641526

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
☐ A. NPDES				
☐ B. UIC				
☐ C. AIR				
☐ D. RCRA				
☐ E. RCRA INTERIM STATUS				
☐ F. SPCC PLAN				
☐ G. STATE (Specify) 360	APPLIED	—	—	APPLIED FOR PERMIT 4/5/82 WITHDREW APPLICATION 3/10/82
☐ H. LOCAL (Specify)				
☐ I. OTHER (Specify)				
☐ J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE
☐ A. SURFACE IMPOUNDMENT		
☐ B. PILES		
☐ C. DRUMS, ABOVE GROUND		
☐ D. TANK, ABOVE GROUND		
☐ E. TANK, BELOW GROUND		
☒ F. LANDFILL	UNKNOWN	
☐ G. LANDFARM		
☐ H. OPEN DUMP		
☐ I. OTHER (Specify)		

04 TREATMENT (Check all that apply)
- ☐ A. INCINERATION
- ☐ B. UNDERGROUND INJECTION
- ☐ C. CHEMICAL/PHYSICAL
- ☐ D. BIOLOGICAL
- ☐ E. WASTE OIL PROCESSING
- ☐ F. SOLVENT RECOVERY
- ☐ G. OTHER RECYCLING/RECOVERY
- ☐ H. OTHER (Specify) NONE

05 OTHER
- ☐ A. BUILDINGS ON SITE

06 AREA OF SITE
15-5 (Acres)
22-N

07 COMMENTS
TWO SITES, NORTH SITE IS AN ACTIVE LANDFILL. SOUTH SITE IS CLOSED (USED FOR BOTH INDUSTRIAL AND MUNICIPAL)

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
☐ A. ADEQUATE, SECURE ☑ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.
LANDFILL

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☑ YES ☐ NO
02 COMMENTS FENCE GATE TO BLOCK VEHICLE ENTRY, OTHERWISE OPEN SECURITY CHECKS PERIODICALLY

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

SITE INSPECTION

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION
01 STATE (02 SITE NUMBER) NY D980641526

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-6} - 10^{-8}$ cm/sec ☐ B. $10^{-4} - 10^{-6}$ cm/sec ☑ C. $10^{-4} - 10^{-3}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than 10^{-6} cm/sec) ☐ B. RELATIVELY IMPERMEABLE ($10^{-4} - 10^{-6}$ cm/sec) ☑ C. RELATIVELY PERMEABLE ($10^{-2} - 10^{-4}$ cm/sec) ☐ D. VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK	04 DEPTH OF CONTAMINATED SOIL ZONE	05 SOIL pH	
780 (ft)	0 (ft)		

06 NET PRECIPITATION	07 ONE YEAR 24 HOUR RAINFALL	08 SLOPE: SITE SLOPE	DIRECTION OF SITE SLOPE	TERRAIN AVERAGE SLOPE
8 (in)	2.2 (in)	2.1 %	SE	2.5 %

09 FLOOD POTENTIAL
SITE IS IN 100 YEAR FLOODPLAIN

10
☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE	OTHER
A. _____ (mi)	B. 0.1 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)
0.1 (mi)
ENDANGERED SPECIES: ~~PEREGRINE~~ FALCON, GOLDEN EAGLE

13 LAND USE IN VICINITY

DISTANCE TO: COMMERCIAL/INDUSTRIAL	RESIDENTIAL AREAS; NATIONAL/STATE PARKS, FORESTS, OR WILDLIFE RESERVES	AGRICULTURAL LANDS: PRIME AG LAND	AG LAND
A. 0 (mi)	B. 3.5 (mi) (ONONDAGA PARK)	C. _____ (mi)	D. _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY
SITE IS ON GENERALLY FLAT AREA ADJACENT AND SOUTH OF LEY CREEK (ON FLOOD PLAIN)

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)
USGS

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

EPA

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
NY	D980941526

II. CURRENT OWNER(S) / PARENT COMPANY

01 NAME	02 D+B NUMBER	08 NAME	09 D+B NUMBER
CROUSE-HINDS		COOPER INDUSTRIES	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**10 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**11 SIC CODE**
WOLF ST		FIRST CITY TOWER	
05 CITY / 06 STATE / 07 ZIP CODE		**12 CITY / 13 STATE / 14 ZIP CODE**	
SYRACUSE / NY / 13221		HOUSTON / TX / 77210	
01 NAME	**02 D+B NUMBER**	**08 NAME**	**09 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**10 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**11 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**12 CITY / 13 STATE / 14 ZIP CODE**	
01 NAME	**02 D+B NUMBER**	**08 NAME**	**09 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**10 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**11 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**12 CITY / 13 STATE / 14 ZIP CODE**	
01 NAME	**02 D+B NUMBER**	**08 NAME**	**09 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**10 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**11 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**12 CITY / 13 STATE / 14 ZIP CODE**	

III. PREVIOUS OWNER(S) (List most recent first) / IV. REALTY OWNER(S) (If applicable; list most recent first)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**03 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**04 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**05 CITY / 06 STATE / 07 ZIP CODE**	
01 NAME	**02 D+B NUMBER**	**01 NAME**	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**03 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**04 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**05 CITY / 06 STATE / 07 ZIP CODE**	
01 NAME	**02 D+B NUMBER**	**01 NAME**	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**	**03 STREET ADDRESS (P.O. Box, RFD #, etc.)**	**04 SIC CODE**
05 CITY / 06 STATE / 07 ZIP CODE		**05 CITY / 06 STATE / 07 ZIP CODE**	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

NYS Tax Records

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
NY	[illegible]

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER
SAME	

03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE

05 CITY	06 STATE	07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
CITY SYRACUSE			
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY / 06 STATE / 07 ZIP CODE		05 CITY / 06 STATE / 07 ZIP CODE	
SYRACUSE / NY			
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY / 06 STATE / 07 ZIP CODE		05 CITY / 06 STATE / 07 ZIP CODE	

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY / 06 STATE / 07 ZIP CODE		05 CITY / 06 STATE / 07 ZIP CODE	
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY / 06 STATE / 07 ZIP CODE		05 CITY / 06 STATE / 07 ZIP CODE	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 0980641526

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ S. CAPPING/COVERING — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ T. BULK TANKAGE REPAIRED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ U. GROUT CURTAIN CONSTRUCTED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ V. BOTTOM SEALED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ W. GAS CONTROL — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ X. FIRE CONTROL — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ Y. LEACHATE TREATMENT — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ Z. AREA EVACUATED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☐ 1. ACCESS TO SITE RESTRICTED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
PRIVATE PROPERTY

01 ☐ 2. POPULATION RELOCATED — 02 DATE ____ — 03 AGENCY ____
04 DESCRIPTION
NO

01 ☒ 3. OTHER REMEDIAL ACTIVITIES — 02 DATE 1981 — 03 AGENCY ____
04 DESCRIPTION
1981 THREE GROUND WATER WELLS INSTALLED 6 SETS OF ANALYSIS OF WATER AND SOIL. (SOUTH LANDFILL)

1983 - NORTH LANDFILL - STUDIES UNDERWAY FOR LEACHATE EVALUATION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

SAME AS PART 3

EPA

POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION
01 STATE | 02 SITE NUMBER: NY 0980641526

II. SITE NAME AND LOCATION

01 SITE NAME	02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER
CROUSE-HINDS COMPANY	WOLF + 7 NORTH ST

03 CITY	04 STATE	05 ZIP CODE	06 COUNTY	07 COUNTY CODE	08 CONG DIST
SYRACUSE	NY	13221	ONONDAGA	67	—

09 COORDINATES LATITUDE	LONGITUDE
43°04'22.1"	76°10'13.0"

10 DIRECTIONS TO SITE (Starting from nearest public road)
SOUTH OF NEW YORK THRU WAY OFF 7TH NORTH STREET

III. RESPONSIBLE PARTIES

01 OWNER (If known)	02 STREET (Business, mailing, residential)
COOPER-INDUSTRIES	FIRST CITY TOWER, SUITE 4000

03 CITY	04 STATE	05 ZIP CODE	06 TELEPHONE NUMBER
HOUSTON	TX		(713) 739-3402

07 OPERATOR (If known and different from owner)	08 STREET (Business, mailing, residential)
CROUSE-HINDS COM	WOLF ST

09 CITY	10 STATE	11 ZIP CODE	12 TELEPHONE NUMBER
SYRACUSE	NY	13221	(315) 477-5393

13 TYPE OF OWNERSHIP (Check one)
☑ A. PRIVATE ☐ B. FEDERAL: _____ (Agency name) ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER: _____ (Specify) ☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)
☐ A. RCRA 3001 DATE RECEIVED: ___/___/___ (MONTH DAY YEAR) ☐ B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RECEIVED: ___/___/___ (MONTH DAY YEAR) ☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION
☑ YES DATE 4 26 83 (MONTH DAY YEAR)
☐ NO

BY (Check all that apply)
☐ A. EPA ☐ B. EPA CONTRACTOR ☒ C. STATE ☐ D. OTHER CONTRACTOR
☐ E. LOCAL HEALTH OFFICIAL ☐ F. OTHER: _____ (Specify)
CONTRACTOR NAME(S): Engineering-Science, Downes + Mundt

02 SITE STATUS (Check one)
☑ A. ACTIVE ☑ B. INACTIVE ☐ C. UNKNOWN

03 YEARS OF OPERATION
1950s (BEGINNING YEAR) | — (ENDING YEAR) ☐ UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED
PHENOLS CHROMIUM BENZENE
CYANIDES ZINC TOLUENE
CADMIUM CHLOROFORM

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION
POSSIBLE LEACHING OF MATERIALS INTO LEY CREEK GROUND WATER AND WATER SAMPLING INDICATE LOW LEVELS

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)
☐ A. HIGH (Inspection required promptly) ☐ B. MEDIUM (Inspection required) ☑ C. LOW (Inspect on time available basis) ☐ D. NONE (No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)	03 TELEPHONE NUMBER
John Kubarewicz	ES	(716) 691-7575

04 PERSON RESPONSIBLE FOR ASSESSMENT	05 AGENCY	06 ORGANIZATION	07 TELEPHONE NUMBER	08 DATE
			( )	5 18 83 (MONTH DAY YEAR)

EPA FORM 2070-12 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE | 02 SITE NUMBER
NY 0980641506

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

NONE APPARENT

01 ☐ K. DAMAGE TO FAUNA — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (Include common name(s) of species)

NONE APPARENT

01 ☒ L. CONTAMINATION OF FOOD CHAIN — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

IN SURFACE WATER BODIES

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES (Spills/Runoff/Standing liquids/Leaking drums) — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

NONE OBSERVED

01 ☐ N. DAMAGE TO OFFSITE PROPERTY — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

NONE OBSERVED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

N/A

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING — 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

N/A

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

CALOCERINOS + SPINA, 10/81, ENGINEERING REPORT AND PLAN OF OPERATION ACCOMPANYING APPLICATION FOR PERMIT

SECTION IV

SITE HISTORY

Crouse-Hinds

The company operated the South landfill from 1960 to 1969. It received a combination of municipal waste from the city of Syracuse (1961-1964) and industrial waste which consisted of foundry mold and core sand, scrap steel drums and shot, fly ash, paint scrapings, garbage and construction-demolition materials. The site was closed and covered in 1969. During 1981, consultants under contract to Crouse-Hinds installed three groundwater monitoring wells. Both groundwater quality analysis and soil analysis were determined (Calocerinos & Spina Consulting Engineers, 1981).

PCBs

The North landfill is still active. It was used from mid 1950 through 1972 for small quantities of solid wastes consisting primarily of foundry sand. In 1972, Crouse-Hinds decided to use the landfill for all non-putrescible solid wastes. These wastes consisted of foundry sand, floor sweepings, metal buffing and polishing residue, scrap lumber, plastics wastes, and paint scrapings. In addition zinc hydroxide sludge was deposited from 1972 to 1980. At the current time solid waste consists primarily of construction materials; the disposal of zinc hydroxide sludge and plastic wastes has been discontinued.

In April of 1981, Crouse-Hinds applied for a 360 permit to operate a non-hazardous landfill. Their application was withdrawn on March 10, 1982. As part of the 360 application, Crouse-Hinds initiated a groundwater monitoring program which included the installation of wells. A report (Calocerinos & Spina Consulting Engineers, 1981b) was prepared to provide additional information required by the State as part of the permitting process. This report included ground and surface water monitoring data which indicated that the groundwater had been contaminated by phenols. Subsequent studies (Thomsen Associates and Empire Soils Investigations, 1982 and 1983) have indicated the possible presence of toluene, benzene, and chloroform.

SECTION V

SUMMARY OF AVAILABLE DATA

Crouse-Hinds

Regional Geology and Hydrology

The site is located in the Erie-Ontario lowlands physiographic province. The bedrock of this region consists of sedimentary rocks of varying lithologies. Most of the rocks are deep aquifers with regional flow to the south.

In the recent past, most of New York State, including the site, has been repeatedly covered by a series of continental ice sheets. The activity of the glacier widened preexisting valleys and deposited widespread accumulations of till. In addition, distinct drumlin fields were formed in many parts of the region. The melting of ice, ending approximately 12,000 years ago, produced large volumes of meltwater; this water subsequently shaped channels and deposited locally thick accumulations of stratified, granular sediments.

As glacial ice retreated from the region, meltwater formed lakes in front of the ice margin. This region is covered by lake sediments, the most recent being from Lake Iroquois (a larger predecessor to Lake Ontario) and from Lake Tonawanda (an elongate lake which occupied an east-west valley and drained north into Lake Iroquois). The sediments consist of blanket silts, sand and beach ridges, which are occasionally underlain by lacustrine silts and clays (indicating quiet, deeper water deposition).

Granular deposits in this region frequently act as shallow aquifers, whereas lacustrine clays, as well as tills, often inhibit groundwater movement. However, fine-grained, water-lain sediments, such as silts and clays, frequently contain horizontal laminations and sand seams. These internal features facilitate lateral groundwater movement through otherwise low permeability materials.

Site Geology

The site geology is known from several hydrogeological investigations, which included on-site borings and well installations. Bedrock beneath the site is thought to occur at a depth of approximately 100 feet. It is probably Vernon Shale (Salina Group), weathered on the bedrock surface. Overlying the bedrock surface are sand and gravel layers, to a depth of approximately 50 feet. Above this depth, the soils become silty sands, silts, and clays. A peat layer is located at approximately 15 feet below the ground surface. Above the peat is a varying amount of fill.

Confining layer? need hydraulic conductivity test?

Site Hydrology

Site groundwater hydrology has been studied for the past several years. The following summary is based on a recent (1983) hydrogeological investigation. There appear to be two aquifers within the site soils. The shallow aquifer occurs within the fill material at a depth varying from 4 feet to 8 feet. Flow roughly follows the ground surface contours: south and northwest. A lower aquifer exists in the deep sands and gravels. This aquifer may be hydraulicly connected to the shale bedrock. Flow in the lower aquifer is toward the northwest. Two sets of potentiometric surface measurements have been recorded, showing approximately a 12-foot lowering of the surface between December 1982 and February 1983, and a significant increase in flow gradient during the same period. This change may be a normal seasonal occurrence.

Sampling and Analysis

Both surface and groundwater analytical data are available for the North Landfill. Figure V-1 shows sampling locations for a study conducted in 1981 as part of an application for a landfilling permit (Calocerinos and Spina, 1981a). Table V-1 summarizes analytical results of the sampling. As shown, both cyanide and phenols were detected in low concentrations in groundwater and Ley Creek. Additional monitoring wells were installed in 1983 (Rinaldo-Lee, 1983). The location of these wells is shown in Figure V-2, while the analytical results are shown in Table V-2. Benzene, toluene, and xylene were found in concentrations



FIGURE V-1 SAMPLING POINTS -- CROUSE-HINDS NORTH LANDFILL (Calcoerinos & Spina, 1981)

TABLE V-1

SUMMARY OF ANALYTICAL DATA CROUSE-HINDS NORTH LANDFILL
(Calocerinos & Spina, 1981)

Sample Date	Sampling Location		Phenol (ppm)	Cyanide (ppm)
2/11/82[1]	Well	1	BDL*	--
		2	0.039	--
		3	BDL	--
7/2/81	Well	1	0.040	0.010
		2	0.065	0.012
		3	BDL	0.009
7/21/81	Well	1	0.016	0.021
		2	0.030	0.015
		3	BDL	0.010
8/5/81	Well	1	BDL	0.009
		2	0.016	0.009
		3	BDL	0.005
7/8/81	Stream	1	BDL	BDL
		2	BDL	0.007
		3	BDL	0.010
		4	BDL	0.009
		5	BDL	0.013
	Stream	1	BDL	0.013
		2'	.013	0.010
		3	BDL	0.032
		4	BDL	0.015
		5	BDL	0.023

* Below Detectable Limit

[1] Crouse-Hinds DEC Meeting 2/23/82

FIGURE V-2 SAMPLING LOCATIONS CROUSE HINDS NORTH LANDFILL (Rinaldo-Lee, 1983)



TABLE V-2
SUMMARY OF CHEMICAL ANALYSIS NORTH LANDFILL

	Well	Date	pH	Conductance umhos	Phenol mg/l	Fe mg/l	Mn mg/l	Cyanide mg/l	Oil & Grease mg/l	Benzene ug/l	Toluene ug/l	Xylene ug/l	Total BTX ug/l	Other
SHALLOW WELLS	4A	12-27-82	7.8	5100	0.019	0.54	0.15	<0.004	-	4.0	1.0	36.0	41	*
		3-16-83	8.0	4900	0.025	3.7	0.1	-	3.4	12	6	136	154	-
	1	12-27-82	7.2	2650	<0.01	4.0	0.36	<0.004	-	4.0	4.0	20.0	24	*
		3-16-83	7.9	3000	0.04	27	0.2	-	21.9	9	5	92	106	-
	2	12-27-82	8.0	3750	<0.01	7.8	0.09	<0.004	-	210	33	<10	243	*
		3-16-83	7.7	3500	0.032	25.6	0.16	-	3.3	7	5	270	282	-
	3	12-27-82	7.1	4500	0.011	0.73	0.38	<0.004	-	220	<10	<10	220	*
		3-16-83	7.9	4000	<0.01	3.3	0.27	-	1.5	5	5	5	15	-
	6A	12-27-82	7.3	1550	0.213	0.15	0.15	<0.004	-	14	32	<10	46	*
		3-16-83	8.0	1380	0.262	7.0	0.19	-	4.3	15	28	50	93	-
	8A	12-27-82	8.5	2200	0.253	0.10	<0.01	<0.004	-	<1.0	<1.0	<1.0	<1.0	
		3-16-83	8.1	860	0.12	0.29	0.01	-	-	-	-	-	-	-
DEEP WELLS	4B	12-27-82	7.1	1500	<0.01	0.09	<0.01	<0.004	-	6.0	1.0	<1.0	7.0	
		3-16-83	8.1	1250	<0.01	0.07	0.01	-	3.3	5	5	5	15	-
	5	12-27-82	7.2	910	<0.01	0.02	<0.01	<0.004	-	<1.0	<1.0	<1.0	<1.0	
		3-16-83	8.0	1180	<0.01	<0.01	0.03	-	-	-	-	-	-	-
	6B	12-27-82	7.3	3500	<0.01	0.07	<0.01	<0.004	-	<1.0	<1.0	<1.0	<1.0	
		3-16-83	7.9	520	<0.01	0.13	0.02	-	2.0	5	5	5	15	-
	7	12-27-82	7.0	5400	<0.01	0.34	0.02	<0.004	-	<1.0	<1.0	<1.0	<1.0	
		3-16-83	8.0	4600	0.027	0.11	0.04	-	-	-	-	-	-	
	8B	12-27-82	7.1	8100	<0.01	0.32	0.07	<0.004	-	<1.0	<1.0	<1.0	<1.0	
		3-16-83	7.1	6500	0.167	0.04	0.06	-	-	-	-	-	-	

-not analyzed
*Chlorobenze suspected

ranging from 1 to 282 ppb. The highest concentrations of these parameters were found in the shallow wells. This study is still in progress and preliminary results have also indicated the presence of chloroform (Scott, 1983).

Soil and groundwater analyses are also available for the South Landfill (Calocerinos and Spina, 1981b). Well locations are shown on Figure V-3. Complete groundwater analyses for 1981 are included in Appendix A. Cyanides ranging in concentration from 0.007-0.015 ppm and total organic carbon ranging from 15-60 ppm were detected.

FIGURE V-3 SAMPLING LOCATIONS CROUSE-HINDS SOUTH LANDFILL



SECTION VI

ASSESSMENT OF ADEQUACY OF DATA

Site: Crouse Hinds

HRS Data Requirement	Comments on Data
Observed Release	
Ground Water	Data available, adequate for HRS evaluation.
Surface Water	Data available, adequate for HRS evaluation.
Air	No available data, field data collection recommended.
Route Characteristics	
Ground Water	Data available, adequate for HRS evaluation.
Surface Water	Data available, adequate for HRS evaluation.
Air	Data available, adequate for HRS evaluation.
Containment	Information available, adequate for HRS evaluation.
Waste Characteristics	Information available, adequate for HRS evaluation.
Targets	Insufficient information, more ground water target data collection recommended.
Observed Incident	Information available revealed no report of incident. No further investigation recommended.
Accessibility	Adequate information available.

SECTION VII

PHASE II WORK PLAN

Site: Crouse Hinds

Objectives

The objectives of the Phase II activities are:

- To collect additional field data necessary to complete the HRS scoring.
- To perform a conceptual evaluation of remedial alternatives and estimate budgetary costs for the most likely alternative.
- To prepare a site investigation report.

The additional field data required to complete the HRS are defined as follows:

Air - An air monitoring survey with an OVA meter is recommended to check the air quality above the surface of the site.

TASK DESCRIPTION

The proposed Phase II tasks are described in Table VII-1.

COST ESTIMATE

The estimated manhours required for the Phase II project are presented in Table VII-2 and the estimated project costs by tasks are presented in Table VII-3. The cost for performing the Phase II project is $7,916.

TABLE VII-1
PHASE II WORK PLAN - TASK DESCRIPTION
Site: Crouse Hinds

Tasks		Description of Task
TASK II-A	Update Work Plan	Review the information in the Phase I report, conduct a site visit, and revise the Phase II work plan.
II-B	Conduct Geophysical studies	No further studies necessary.
II-C	Conduct Boring/Install Install Monitoring Wells	No further installation of monitoring wells necessary
II-D	Construct Test Pits/ Auger Holes	No further construction of test pits/auger holes necessary.
II-E	Perform Sampling and Analysis	
	Soil samples from borings	No further sampling necessary.
	Soil samples from surface soils	No further sampling necessary.
	Soil samples from test pits and auger holes	No further sampling necessary.
	Sediment samples from surface water	No further sampling necessary.
	Ground-water samples	No further sampling necessary.
	Surface water samples	No further sampling necessary.
	Air samples	Using the OVA, determine the presence of organics.
	Waste samples	No further sampling necessary.
II-F	Calculate Final HRS	Based on the field data collected in Tasks IIB - IIE, complete the HRS form.
II-G	Conduct Site Assessment	Prepare final report containing Phase I report, additional field data, final HRS and HRS documentation records, and site assessments. The site assessment will consist of a conceptual evaluation of alternatives and a preliminary cost estimate of the most probable alternative.
II-H	Project Management	Project coordination, administration and reporting.

TABLE VII-2
PERSONNEL RESOURCES BY TASK
PHASE II HRS SITE INVESTIGATION (SITE: CROUSE HINDS)

TASK DESCRIPTION	TEAM MEMBERS, MANHOURS													
	PIC	IRB	PM	BPM	PCM	QAM	HSM	FTL	FT	RAAL	RAAT	SS	TOTAL HOURS	TOTAL $
II-A UPDATE WORK PLAN	1		4	1			1	2		6		8	23	376.0
II-B CONDUCT GEOPHYSICAL STUDIES													0	0
II-C CONDUCT BORING/INSTALL MONITORING WELLS													0	0
II-D CONSTRUCT TEST PITS/AUGER HOLES													0	0
II-E PERFORM SAMPLING AND ANALYSIS														
SOIL SAMPLES FROM BORINGS													0	0
SOIL SAMPLES FROM SURFACE SOILS													0	0
SOIL SAMPLES FROM TEST PITS AND AUGER HOLES													0	0
SEDIMENT SAMPLES FROM SURFCE WATER													0	0
GROUND-WATER SAMPLES													0	0
SURFACE WATER SAMPLES													0	0
AIR SAMPLES			1					1	8			2	12	133.66
WASTE SAMPLES													0	0
II-F CALCULATE FINAL HRS			3	3				3	24			16	49	563.23
II-G CONDUCT SITE ASSESSMENT	1	2	4	2				4	8	6	24	32	83	1029.44
II-H PROJECT MANAGEMENT	2		6	2		4	4					8	26	442.9
TOTALS	4	2	18	8	0	4	5	10	40	12	24	66	193	2546.03

TABLE VII-3
COST ESTIMATE BREAKDOWN BY TASK
PHASE II RAS SITE INVESTIGATION (SITE: CROUSE HINDS)

TASK DESCRIPTION	DIRECT LABOR HOURS	DIRECT LABOR COST	OTHER DIRECT COSTS (ODC), $ LAB ANALYSIS	TRAVEL AND SUBSISTANCE	SUPPLIES	EQUIP. CHARGES	SUBCONTRACTORS	MISC.	SUBTOTAL ODC	TOTAL ($)
II-A UPDATE WORK PLAN	23	376.8		100	50	50		25	225	601.8
II-B CONDUCT GEOPHYSICAL STUDIES									0	0
II-C CONDUCT BORING/INSTALL MONITORING WELLS									0	0
II-D CONSTRUCT TEST PITS/AUGER HOLES									0	0
II-E PERFORM SAMPLING AND ANALYSIS										
SOIL SAMPLES FROM BORINGS									0	0
SOIL SAMPLES FROM SURFACE SOILS									0	0
SOIL SAMPLES FROM TEST PITS AND AUGER HOLES									0	0
SEDIMENT SAMPLES FROM SURFACE WATER									0	0
GROUND-WATER SAMPLES									0	0
SURFACE WATER SAMPLES									0	0
AIR SAMPLES	12	133.66		85	25	15		5	130	263.66
WASTE SAMPLES									0	0
II-F CALCULATE FINAL RAS	49	563.23			50	50		25	125	688.23
II-G CONDUCT SITE ASSESSMENT	83	1029.44			100	200		75	375	1404.44
II-H PROJECT MANAGEMENT	26	442.9		150	150	50		50	400	842.9
TOTALS	193	2546.03	0	335	375	365	0	180	1255	3801.03

OVERHEAD =	3635.73
SUBTOTAL =	7436.76
FEE =	479.09
TOTAL PROJECT COST =	7915.85