


EPA Region 5 Records Ctr.



261544



Weston Way
West Chester, PA 19380
Phone 215-692-3030

26 July 1990

0316000067 -- Cook
Chicago / Paxton Ave Lagoons
Superfund / Tech Rept.

Illinois Environmental Protection Agency
Division of Land Pollution Control
Permit Section
2200 Churchill Road
Springfield, IL 62706

W.O. #1104-05-01

Attention: Mr. Steve Gobelman

Reference: Agency Contract No. BIE-9035
Paxton Avenue Lagoons Site
Chicago, Illinois - LPC #0316000067

Subject: Summary Report for Trial Burn Program for
a Transportable Incineration System (TIS)
at the Paxton Avenue Lagoons Site

Dear Steve:

Enclosed please find 5 copies of the subject report. Since the Appendices were larger than anticipated they will be sent to you tomorrow. Should you have any questions or comments, please do not hesitate to contact me at (215) 430-3117.

Very truly yours,

WESTON SERVICES, INC.

Andrea Hol for

Nancy P. Johnson, P.E.
Project Manager

NPJ:ma

Enclosures

cc: John Noland
Luis Velazquez
Jeff O'Neill
Mike Taylor
Mike Pantaloni

RECEIVED

JUL 27 1990

IEPA/DLPC



Date: 25 July 1990

**SUMMARY REPORT FOR TRIAL BURN PROGRAM
FOR A TRANSPORTABLE INCINERATION SYSTEM (TIS)
AT THE PAXTON AVENUE LAGOONS SITE**

Sections 1 through 6

Submitted to:

Illinois Environmental Protection Agency
Division of Land Pollution Control
Permit Section
2200 Churchill Road
P.O. Box 19276
Springfield, Illinois 62794-9276

Submitted by:

Weston Services, Inc.
Weston Way
West Chester, Pennsylvania 19380

25 July 1990



TABLE OF CONTENTS

<u>Section</u>	<u>Title</u>	<u>Page</u>
1	SUMMARY	1-1
	1.1 Introduction	1-1
	1.2 Background	1-2
	1.3 Objectives of the Trial Burn Program	1-2
	1.4 Executive Summary	1-2
	1.5 Document Organization	1-7
2	PROCESS OPERATION	2-1
	2.1 General Overview of Process	2-1
	2.2 Process Operation Data	2-3
	2.2.1 Process Measurement Methods	2-6
	2.3 Deviations from Test Plan	2-7
	2.3.1 Phased Approach for Conducting the Trial Burn Program	2-7
	2.3.2 Feeding Waste for 48 Hours Prior to Trial Burn Program	2-8
	2.3.3 Feed Shutdowns	2-8
	2.4 Requested Permit Conditions	2-10
	2.5 System Modifications	2-12
3	SAMPLING AND MONITORING PROCEDURES	3-1
	3.1 Description of Sampling Procedures	3-1
	3.2 Deviations from the Test Plan	3-12
	3.2.1 Sampling Frequency for Waste Feed -- Volatile Organics	3-12
	3.2.2 Sampling Frequency for Fly Ash from Heat Exchangers	3-12
4	ANALYTICAL PROCEDURES	4-1
	4.1 Analytical Methods	4-1
	4.2 Modifications to Analytical Procedures	4-1
	4.2.1 Metals in Sludge Feed	4-1



TABLE OF CONTENTS (continued)

<u>Section</u>	<u>Title</u>	<u>Page</u>
5	TEST RESULTS	5-1
5.1	Stack Emissions	5-1
5.1.1	Particulate and HCl	5-1
5.1.2	Sulfur Dioxide	5-1
5.1.3	Volatile Organics	5-1
5.1.3.1	PCE	5-9
5.1.4	Trace Metals	5-9
5.2	System Influent and Effluent Streams	5-9
5.2.1	System Influent Streams -- Waste Feed and Spike Solution	5-13
5.2.1.1	Waste Feed	5-13
5.2.1.2	Spike Solution	5-16
5.2.2	System Effluent Streams -- Bottom Ash, Fly Ash from the Heat Exchangers, Fly Ash from the Fabric Filter, and Scrubber Blowdown	5-16
5.2.2.1	Bottom Ash	5-16
5.2.2.2	Fly Ash from Heat Exchangers	5-20
5.2.2.3	Fly Ash from the Fabric Filter	5-20
5.2.2.4	Scrubber Blowdown	5-20
5.2.2.5	Comparison of Measured Concentrations of Metals Versus Maximum Allowable Concentrations	5-20
5.3	Process Streams	5-28
5.3.1	Discharge Gases from the Secondary Combustion Chamber	5-28
5.3.2	Discharge Gases from the Fabric Filter (Baghouse)	5-28
6	QUALITY ASSURANCE SUMMARY	6-1
6.1	Part A	6-1
6.1.1	Sample Holding Times	6-1
6.1.2	Surrogate Recoveries	6-2
6.1.3	Spike Recoveries	6-2
6.1.4	Replicate Analysis	6-2
6.1.5	Blank Samples	6-2
6.1.6	Calibration	6-4
6.1.7	Completeness	6-4
6.2	Part B	6-4



TABLE OF CONTENTS
(continued)

<u>Section</u>	<u>Title</u>	<u>Page</u>
	6.2.1 Sample Holding Times	6-5
	6.2.2 Surrogate Recoveries	6-5
	6.2.2.1 VOST	6-5
	6.2.2.2 Volatile Organics	6-5
	6.2.2.3 Semivolatile Organics	6-7
	6.2.3 Spike Recoveries	6-7
	6.2.4 Replicate Analysis	6-9
	6.2.5 Blank Samples	6-9
	6.2.6 Calibration	6-10
7	AUDIT SUMMARY	7-1
	7.1 Introduction	7-1
	7.2 Audit Results	7-1
	APPENDIX A HOURLY AVERAGE DATA	
	APPENDIX B WEIGH TICKET INFORMATION	
	APPENDIX C DAILY EVENT LOGS	
	APPENDIX D RAW ANALYTICAL DATA	
	APPENDIX E SAMPLING DATA	
	APPENDIX F SUMMARY OF VOLATILE ORGANICS TEST DATA	
	APPENDIX G SUMMARY OF PCE TEST DATA AND TEST RESULTS	
	APPENDIX H COMPARISON OF MAXIMUM ALLOWABLE CONCENTRATIONS OF METALS TO MEASURED CONCENTRATIONS	
	APPENDIX I RESULTS OF VOST AUDIT	



LIST OF TABLES

<u>Table</u>	<u>Title</u>	<u>Page</u>
1-1	Summary of Results of Trial Burn Program -- Part A	1-3
1-2	Summary of Results of Trial Burn Program -- Part B	1-5
2-1	Process Operation Data, Transportable Incineration System	2-4
2-2	Feed System Shutdown Summary	2-9
3-1	Sampling and Monitoring Plan for the Trial Burn -- Determining the DRE of the TIS	3-3
4-1	Summary of Extraction and Analytical Methods	4-2
5-1	Summary of Particulate and HCl Emissions Data Results	5-2
5-2	Summary of SO ₂ Emissions Data Results	5-5
5-3	Summary of Volatile Organics Emissions Data Results	5-6
5-4	Summary of PCE Emissions Data Results	5-10
5-5	Summary of Trace Metals Emissions Data Results	5-11
5-6	Summary of Analytical Results for Waste Feed (SF)	5-14
5-7	Summary of Analytical Results for Spike Solution (SS)	5-17
5-8	Summary of Analytical Results for Bottom Ash (BA)	5-18
5-9	Summary of Analytical Results for Fly Ash from Heat Exchangers (FAD)	5-21
5-10	Summary of Analytical Results for Fly Ash from Fabric Filter (FAH)	5-23
5-11	Summary of Analytical Results for Scrubber Blowdown (SB)	5-26
5-12	Summary of Analytical Results for Secondary Combustion Chamber Discharge Gases	5-29
5-13	Summary of Particulate Emissions Data Results for Fabric Filter Discharge Gases	5-30



LIST OF TABLES
(continued)

<u>Table</u>	<u>Title</u>	<u>Page</u>
6-1	Sample Surrogate Recovery Summary for VOST Analysis -- Part A	6-3
6-2	Sample Surrogate Recovery Summary for VOST Analysis -- Part B	6-6



LIST OF FIGURES

<u>Figure</u>	<u>Title</u>	<u>Page</u>
2-1	TIS Processing Flow Schematic	2-2
3-1	Location of Sampling Points	3-2



SECTION 1

SUMMARY

1.1 INTRODUCTION

Weston Services, Inc./Roy F. Weston, Inc. (WESTON) is submitting this summary test report for a transportable incineration system (TIS) to treat soils contaminated with polynuclear aromatic hydrocarbon (PAH) compounds and volatile organic compounds (VOCs). The TIS is designed to meet the Resource Conservation and Recovery Act (RCRA) incinerator performance standards specified in Chapter 40 of the Code of Federal Regulations (40 CFR), Part 264, Subpart O, and the Toxic Substances Control Act (TSCA) incinerator performance standards specified in 40 CFR 761.70(b).

The TIS technology was selected by the Illinois Environmental Protection Agency (IEPA) for remediation of two toxic and/or hazardous waste sites. The first site was the Lauder Salvage Yard located in Beardstown, Illinois. More than 8,500 tons of soil contaminated with polychlorinated biphenyls (PCBs) were successfully treated using the TIS. The second site currently being remediated is the Paxton Avenue Lagoons Site located in Chicago, Illinois (IEPA site number 0316000067).

The trial burn program for the Paxton Avenue Lagoons Site was conducted in two phases (or parts) on the following dates:

- Part A - 31 March 1990
- Part B - 5 and 6 April 1990

WESTON conducted the trial burn program and provided the analytical services.



1.2 BACKGROUND

WESTON has designed the TIS to treat soils contaminated with organic contaminants. The TIS employs a two-stage combustion process for incineration of solid wastes. The primary incineration chamber consists of a rotary kiln; the secondary combustion chamber consists of an afterburner. Flue gas exiting the afterburner is further treated by a pollution control system that removes particulate and neutralizes acidic gases. The controlled flue gas emissions are discharged to the atmosphere. The TIS is designed to accommodate over 20,000 pounds per hour (lb/hr) soil (on a wet basis).

1.3 OBJECTIVE OF THE TRIAL BURN PROGRAM

The objective of the trial burn program is to demonstrate that the TIS is capable of meeting the RCRA incinerator performance standards for soils contaminated with organic compounds.

Six tests were completed to meet the program objective, as follows:

- Part A - Three tests conducted to establish the maximum feed rate for the operating permit. The tests were completed using uncontaminated soil spiked with tetrachloroethylene (PCE).
- Part B - Three tests conducted to demonstrate the capability of the TIS to treat actual wastes spiked with PCE.

1.4 EXECUTIVE SUMMARY

A summary of the results of the six tests conducted during the trial burn program are presented in Table 1-1 (Part A) and Table 1-2 (Part B). The results indicate that the incinerator system achieved greater than 99.9947 percent destruction and removal efficiency (DRE) for the trial burn program.



Table 1-1

Summary of Results of Trial Burn Program
Part A'

Parameter	Units	Test A-1 3/31/90	Test A-2 3/31/90	Test A-3 3/31/90
Test time begin		10:15	11:45	13:35
Test time end		11:23	12:55	14:42
<u>Operating Parameters:</u>				
Average solid waste feed rate	lb/hr	20,310	20,310	20,310
PCE concentration in solid feed	ppm	1,620	1,620	1,620
Total chlorine in solid waste feed	ppm	1,390	1,390	1,390
Average auxiliary fuel feed rate	cfm			
- Rotary kiln		34	65	65
- Secondary combustion chamber		167	150	145
Auxiliary fuel heat release	10 ⁶ Btu/hr			
- Rotary kiln		1.99	3.80	3.80
- Secondary combustion chamber		9.76	8.77	8.47
Average gas residence time	sec	2.22	2.24	2.22
Combustion air flow rate	acfm	7,731	7,674	7,770
Average combustion gas				
- Oxygen	% dry volume	11.4	10.9	11.0
- Carbon dioxide	% wet weight	5.44	5.70	5.49
- Carbon monoxide	ppm	1.52	1.62	1.78
- Total hydrocarbons	ppm	3.22	2.01	3.01
Average combustion efficiency	%	99.99	99.99	99.99
Scrubber quench flow rate	gpm	396	395	395
Scrubber water pH	Not applicable	8.5	8.9	9.4



Table 1-1

**Summary of Results of Trial Burn Program
Part A^a
(continued)**

Parameter	Units	Test A-1 3/31/90	Test A-2 3/31/90	Test A-3 3/31/90
Destruction temperature	°F			
- Rotary kiln		1,592	1,524	1,518
- Secondary combustion chamber		1,852	1,850	1,852
Emissions:				
Total sample time	min.	60	60	60
Total sample volume	dscf	40.328	37.711	40.195
Average stack gas flow rate	dscfm	10,100	9,800	10,100
Average particulate concentration	gr/dscf			
- at 12% CO ₂		0.0015	0.0054	0.0218
- at 7% O ₂		0.0009	0.0033	0.0134
Average HCl mass rate	lb/hr	0.04	0.05	0.05
Average HCl removal	%	99.9	99.8	99.8
Average SO ₂ mass rate	lb/hr	NA ^b	NA	NA
POHC DRE	%	99.9983	99.9998	99.9967

^aSome values different than those included in summary submitted 9 April 1990 due to revised solid waste feed rate (downtime of 35 minutes was not previously subtracted from operational time).

^bNA = Not applicable.



Table 1-2
Summary of Results of Trial Burn Program
Part B'

Parameter	Units	Test B-1 4/5/90	Test B-2 4/6/90	Test B-3 4/6/90
Test time begin		13:54	08:22	13:41
Test time end		20:21	11:46	19:07
<u>Operating Parameters:</u>				
Average solid waste feed rate	lb/hr	5,320	4,750	4,750
PCE concentration in solid feed	ppm	6,550	7,320	8,430
Total chlorine in solid waste feed	ppm	5,610	6,800	7,220
Average auxiliary fuel feed rate	cfm			
- Rotary kiln		8.7	8.8	8.0
- Secondary combustion chamber		29.6	6.0	22.7
Auxiliary fuel heat release	10 ⁶ Btu/hr			
- Rotary kiln		0.51	0.51	0.47
- Secondary combustion chamber		1.73	0.35	1.33
Average gas residence time	sec	2.46	2.51	3.05
Combustion air flow rate	acfm	7,015	6,646	5,520
Average combustion gas				
- Oxygen	% dry volume	12.8	12.5	12.9
- Carbon dioxide	% wet weight	6.28	7.29	4.55
- Carbon monoxide	ppm	5.82	4.21	6.25
- Total hydrocarbons	ppm	1.67	0.64	6.26
Average combustion efficiency	%	99.98	99.99	99.96
Scrubber quench flow rate	gpm	398	399	399
Scrubber water pH	Not applicable	8.3	8.5	8.3



Table 1-2

Summary of Results of Trial Burn Program
Part B*
(continued)

Parameter	Units	Test B-1 4/5/90	Test B-2 4/6/90	Test B-3 4/6/90
Destruction temperature	°F			
- Rotary kiln		1,937	1,822	1,696
- Secondary combustion chamber		1,895	1,945	1,931
<u>Emissions:</u>				
Total sample time	min.	120	120	120
Total sample volume	dscf	65.316	70.610	75.395
Average stack gas flow rate	dscfm	7,700	7,900	8,800
Average particulate concentration	gr/dscf			
- at 12% CO ₂		0.0024	0.0070	0.0068
- at 7% O ₂		0.0018	0.0053	0.0048
Average HCl mass rate	lb/hr	0.07	0.15	0.12
Average HCl removal	%	99.8	99.6	99.7
Average SO ₂ mass rate	lb/hr	0.65	6.89	0.37
POHC DRE	%	99.9955	99.9947	99.9988

*Some values different than those included in summary submitted 9 April 1990 due to revised solid waste feed rate (downtime of 35 minutes was not previously subtracted from operational time).



The transportable incineration system met and exceeded RCRA guidelines for air emissions of particulate and hydrochloric acid (HCl) while processing a maximum rate of 20,310 lb/hr. Emissions of particulate ranged from 0.0015 grains/dry standard cubic foot (gr/dscf) to 0.0070 gr/dscf (corrected to 12 percent carbon dioxide). Particulate emissions were one order of magnitude below the regulatory criteria of 0.08 gr/dscf (corrected to 12 percent carbon dioxide). Emissions of HCl ranged from 0.04 lb/hr to 0.15 lb/hr, also at least one order of magnitude below the regulatory criteria of 4 lb/hr.

The demonstration test was conducted with minor deviations to the sampling and analysis procedures provided in the Trial Burn Plan. These deviations, which are fully described in Sections 3 and 4 of this report, had no effect on the demonstration of the unit or the accuracy of this summary report.

All data presented has passed WESTON's rigorous internal quality assurance program. The full quality assurance report is presented in Section 6 of this report.

1.5 DOCUMENT ORGANIZATION

This document has been organized into the following seven sections:

<u>Section</u>	<u>Title</u>
1	Summary
2	Process Operation
3	Sampling and Monitoring Procedures
4	Analytical Procedures
5	Test Results
6	Quality Assurance Summary
7	Audit Summary

The following appendices are also included:



- A Hourly Average Data
- B Weigh Ticket Information
- C Daily Event Logs
- D Raw Analytical Data
- E Sampling Data
- F Summary of Volatile Organics Test Data
- G Summary of PCE Test Data
- H Comparison of Maximum Allowable Concentrations
of Metals to Measured Concentrations
- I Results of VOST Audit