

King C. - 59 - Closure

P 131 911 291

file



Illinois Environmental Protection Agency · 2200 Churchill Road, Springfield, IL 62706

217/782-6762

Refer to: 0316500003 --- Cook County  
Chicago/Sherwin-Williams Company  
ILD005456439

EPA Region 5 Records Ctr.



355897

November 16, 1984

Mr. Stanley R. Fryzel  
Manager of Safety and Security  
Sherwin-Williams Company  
11541 S. Champlain Ave.  
Chicago, Illinois 60628

Dear Mr. Fryzel:

The closure plan submitted by Stanley R. Fryzel, dated September 10, 1984, and received by this Agency on September 13, 1984, to close the four treatment tanks in Building 515 used for the physical blending of waste solvent materials is hereby approved.


When closure is complete the owner or operator must submit to the Director certification both by the owner or operator and by an independent registered professional engineer that the facility has been closed in accordance with the specifications in the approved closure plan as required by 35 Ill. Adm. Code 725.215. These certifications must be received at this Agency within 30 days after closure, or within 30 days of the date of this letter, whichever is longer.

All certifications, logs, or reports which are required to be submitted to the Agency by the facility should be mailed to the following address:

Illinois Environmental Protection Agency  
Division of Land Pollution Control  
Permit Section  
2200 Churchill Road  
Springfield, Illinois 62706

Should you have any questions concerning this matter, please contact Linda Kissinger at (217)782-6762.

Very truly yours,

  
Lawrence W. Eastep, P.E., Manager  
Permit Section  
Division of Land Pollution Control

WKE  
LWE:LJK:mgg2366d, 25

cc: Northern Region  
Division File  
Financial Assurance Unit  
Compliance Monitoring Section

REQUEST FOR COMMENTS ON A PENDING PERMIT APPLICATION

Log No. C-39

To: Ken Beckely LPC ← Northern  
(Regional Manager or Compliance Monitoring) (Region)

From: LJK FPU, Permit Section  
(Reviewer) (Unit)

Facility No. ILD005456439 County Cook

City Chicago Facility Name Sherwin Williams Co.

The Permit Section received on 9-13-84 an application/additional  
(Date)

information to modify/develop/operate Closure Plan  
for the above site. A copy of this information is attached/available for your review.  
Your comments regarding the groundwater monitoring inadequacies, design, operation or  
any pending violations are requested. Please submit your comments by 10-3-84.  
If not received within the time specified, we would assume that you do not have  
any problems or concerns.

COMMENTS: No comments on plan. Closure was  
complete as of the 8/9/84 FSS inspection.  
CH 9/20/84

Pre-Issuance/Denial Meeting requested on \_\_\_\_\_  
(less than 60 days from receipt; OP < 40 days)

(Date) (Time -- a.m. or p.m.)

In Attendance Permit Section \_\_\_\_\_  
and/or Compliance \_\_\_\_\_  
Conference Call F.O.S. \_\_\_\_\_

Results of Meeting: \_\_\_\_\_

RECEIVED  
SEP 24 1984

IEPA-DLPC

Attachment

STATE OF ILLINOIS  
ENVIRONMENTAL PROTECTION AGENCY

IL 532-0357  
ADM 39  
054-002

Subject Partial Closure Plan - Chicago / Sherwin Williams  
Data 4 Tanks - Treatment  
Reviewed by WK Date 11/13/84

- Partial closure plan rec'd 9/13/84 for after the fact closure of 4 treatment tanks (Solvents). The building housing these tanks was removed & the site regraded week of 6/18/84. Wastes were previously removed for offsite treatment / disposal.
  - per FDS - ~~site~~ 4 tanks were closed and removed as of 8/9/84 inspection.
  - per Gene Dingledine - financial doc. OK
  - per Mrs. Michael - comment period ended 11/1/84 - none rec'd.
  - amended St. A rec'd 9/18/84 reflecting elimination of the 4 tanks mentioned above.
- ⇒ approved <sup>partial</sup> closure & require certification pursuant to 725.210 - 725.215



The Sherwin-Williams Company  
11541 S. Champlain Ave.  
Chicago, Illinois 60628  
Phone (312) 821-3000

September 10, 1984

Mr. Richard Carlson  
Illinois Environmental Protection Agency  
2200 Churchill Rd.  
Springfield, IL 62706

Dear Mr. Carlson:

Attached is an after-the-fact partial closure plan and schedule for a hazardous waste treatment facility at this Site. The particular operation utilized four tanks in a building that was part of a lacquer manufacturing facility. When plans were made for clearing the entire lacquer manufacturing site, the fact that a small hazardous waste treatment operation was included was overlooked. The waste treatment operation consisted of physical blending in the tanks of waste solvent materials to improve pumpability. The blended material was then pumped into tank wagons for removal. All of the materials so treated were generated on site.

This apparent violation of the provisions of 35 Illinois Administration Code 725.212 was called to our attention by Mr. Cliff Gould of the Maywood Office during this visit of August 9, 1984.

Closure was completed during the week of June 18, 1984, when the tanks and buildings involved were removed and the site graded.

A revised Part A is being prepared reflecting the elimination of the physical blending operation from our activities and will be submitted to your office.

Very truly, yours,

A handwritten signature in dark ink, appearing to read "Stanley R. Fryzel".

Stanley R. Fryzel  
Manager of Safety & Security

SRF:eb

Encl. Partial closure of hazardous waste treatment and storage facility.

RECEIVED

SEP 13 1984

IEPA-DLPC

PARTIAL CLOSURE OF HAZARDOUS WASTE STORAGE & TREATMENT FACILITY

Schedule for closure of facility used for physical blending of waste solvent materials to improve pumpability conducted in tanks located in Building 515.

C-Day denotes closure date.

C-180 Notify Illinois EPA of intent to close operation.

C-180 Obtain proposal for removal of tanks and demolition of building.

C-30 Schedule removal of any blended material.

C-25 Remove blended material. Wash tanks with clean solvent and pump out into tankwagon.

C-20 Complete arrangements for removal of tanks, razing of building, removal of debris and clearing of site.

C-5 Remove tanks and cut up for scrap steel. Demolish building 515 and remove debris.

C-Day Cover site with clean stone and grade.

Initial proposal for removal of building 515 and other structures was made December 6, 1983. Removal of remaining blended material and cleaning of tanks was carried out on May 21, 1984. Removal of tanks, cutting them up for scrap, destruction of the building, removal of debris was started on June 15, 1984, and completed the following week. The site was then covered and graded.

Estimated cost of closure is as follows:

(1) Cut-off of site facilities and utilities	\$2,500
(2) Removal of tanks, cutting into scrap & transfer from site. <i>20000 gal.</i>	2,000
(3) Razing of building and removal of debris	5,000
(4) Grading of site and covering with stone	500
Total estimated cost of closure	<u>\$10,000</u>

No surveillance necessary because of complete removal of building and tanks.

RECEIVED  
SEP 13 1984  
IEPA-DLPC