

**From:** [Don Edgington](#)  
**To:** [Angela Harbin](#); [oppie074@aol.com](mailto:oppie074@aol.com)  
**Cc:** [Moore, Gary](#); [Brescia, Nicolas](#); [Delgado, Paige](#)  
**Subject:** Plumbing SOW  
**Date:** Monday, February 11, 2019 8:22:10 AM

---

Angela:

For preparation of a RFQ for replacement of the sanitary sewer line in the backyards of both (b) (6) (b) (6)

- Removal of existing service from both residences to primary service line in each backyard, installed to gravity drain to main in the alley (north of residences);
- Installation of 4" Schedule 80 service, with (2) cleanouts and with sufficient couplings/fittings;
- Backfill construction with topsoil, lightly hand tamp and restore grade away from the house to the backyard;
- Reinstall/replace any Zoysia grass sod removed during removal/construction activities;
- Removal of any contractor generated debris/trash/remaining materials.

Oscar and Tom will provide measurements to you later this morning.

Thanks,

Don

**Confidentiality Warning:** This e-mail and any attachments contain information intended only for the use of the individual or entity named above. If the reader of this e-mail is not the intended recipient or the employee or agent responsible for delivering it to the intended recipient, any dissemination, publication or copying of this e-mail is strictly prohibited. Although this email has been scanned for malware, the sender does not accept any responsibility for any loss, disruption or damage to your data or computer system that may occur while using data contained in, or transmitted with, this e-mail. If you have received this e-mail in error, please immediately notify by return e-mail. Thank you.