

BP Waste Disposal Plan – MC 252 Incident

Wastes covered by this plan

1. Crude oil skimmed/collected from the water and spill source (E&P Waste)
2. Shore line waste collected that is contaminated with crude oil (E&P Waste)
3. Decontaminated fluids from cleaning response vessels with crude oil (E&P Waste)
4. Waste collected from response vessels responding to crude spill event (Municipal Waste)
5. Waste associated with Shore line operation. (Municipal Waste)

Wastes NOT covered by this plan

1. Transocean rig marine debris that is collected off the water and/or washed up on shore
Disposal of additional rig fluids (diesel etc.) that may cause a sheen separate from the crude release

Transocean will be responsible for the proper disposal of the above mentioned wastes.

Spill Response Objectives

1. Safe collection of waste at crude spill source and along the coastal clean up area from crude oil release
2. Proper segregation, labeling and containment of waste arriving at staging area
3. Short term (up to 2 weeks) storage of waste streams at staging area(s)

Staging area locations:

Fourchon, Louisiana (site for final vessel decon)
Venice, Louisiana
Biloxi, Mississippi
Pascagoula, Mississippi
Theodore/Mobile, Alabama
Pensacola, Florida

Staging area waste contacts:

Fourchon, Louisiana Decon Location Dan Hans 918 671 5572
Venice, Louisiana Jeron Schultz 314 574 1052
Biloxi, Mississippi Billy Farris 205 306 3507
Pascagoula, Mississippi Billy Farris 205 306 3507
Theodore/Mobile, Alabama Billy Farris 205 306 3507
Pensacola, Florida Ethan Clark 610 653 9062

Waste Management General

Five types of waste will be generated:

- Responder trash (food waste, wrappings, cardboard, paper, soda cans etc.)
- Crude oil contaminated spill equipment (PPE, absorbents, boom etc.)
- Crude oil contaminated natural debris (trees, seaweed, sand etc.) if shore is impacted
- Crude oil contaminated industrial type waste (buckets, batteries, tires, paint cans, washing machines, production equipment)
- Crude Oil/Water skimmed from water (only if not able to fit within the parameters of the Oil Recovery Destination Plan)

1. Segregate waste streams, as much as possible, into the 5 waste types.

Label containers appropriately with "BP", MC 252 Event, waste type and start date of accumulation.

Waste containers and transportation from the staging area will be provided by Heritage.

Industrial wastes/wastes for disposal in landfill will have to be profiled with the appropriate receiving disposal/recycling facility prior to shipment offsite.

All wastes will have to be manifested appropriately according to State and Federal requirements.

Each staging area will be manned with at least one each of the following people during operating periods:

- Security Personnel
- BP Personnel (or the equivalent)
- Heritage Environmental Services Personnel (or the equivalent)

Each staging area will be equipped with at least five active DOT-approved containers and five back-up DOT-approved containers. Each container will be clearly labeled with one of the 5 types of waste streams intended to be contained within (see above). Once waste begins to be accumulated within a container, the container shall be labeled with the accumulation start date. The label indicating what is within the container shall remain in place. Once accumulation begins within a container, the Heritage Environmental Services representative shall arrange to have the backup container in place. At no time shall we have less than two days worth of containers on site for each waste stream.

Upon receiving the waste at the waste segregation area, BP and Heritage personnel will place or supervise the placement of the waste into the appropriate containers. Once a container is considered full, the Heritage personnel shall ensure that the container is properly covered and labeled for transportation. Transportation shall be arranged by the Heritage personnel. If the waste is transported under a manifest rather than a Bill of Lading, the manifest shall be signed by BP personnel.

Only known BP clean-up contractors shall be allowed to bring waste to the staging areas. If others attempt to deposit non-spill related waste at the staging areas they shall be immediately turned away by security personnel.

Developed by: Tracy Dyer

Revised: 4/22/10 03:30

Revision 1

Updated by: Jerry Harrington

Revised: 4/23/10 15:45

Revision 2

Updated by: Kathy McCormick

Revised: 4/29/10 14:00

Revision 3

Updated by: Kathy McCormick

Revised: 4/30/10 14:00

Revision 4

Updated by: Maribeth Dobbins

Revised: 5/02/10 03:00

Revision 5