

**END OF YEAR 2001 THROUGH YEAR 2006
CLOSURE / CLOSEOUT PLAN**

CHINO MINES

Prepared For: Chino Mines Company
Hurley, New Mexico

VOLUME III

APPENDICES

A, B, C, D

March 2001

**M3 Engineering &
Technology Corp.**

**To be resubmitted to the State of New Mexico
within 5 years to update compliance
requirements**

M3



Tucson Office
2440 W. Rutliff Road, Suite 170
Tucson, AZ 85705
Phone: (520) 293-1488
Fax: (520) 293-8349
e-mail: m3@m3eng.com



Phoenix Office
6501 W. Frye Road, Suite 21
Chandler, AZ 85226
Phone: (480) 753-3607
Fax: (480) 753-3617
e-mail: m3phx@m3eng.com



Hermosillo Office
Veracruz y 12 de Octubre
Hermosillo, Sonora, México 83190
Phone: (52-62) 105400
Fax: (52-62) 105404
e-mail: m3mex@rtn.uson.mx

9680326

Equal Opportunity Employer



CHINO CLOSURE/CLOSEOUT TABLE OF CONTENTS

VOLUME I

Certification
Preface

SECTION	PAGE
1. Plan Summary	1-x
1.1 Purpose of Plan	1-x
1.2 Organization of this Report.....	1-x
1.3 Degree of Disturbance	1-x
1.4 Simplified Model of Reclamation Challenges.....	1-x
1.5 Proposed Plan and Comparison Case	1-x
1.6 Tailing Cover Study Parameters	1-x
1.7 Stockpile Cover Study Parameters.....	1-x
1.8 Post Mining Land Uses.....	1-x
1.9 Discussion of Cover and Seepage Models.....	1-x
1.10 Water Management System including Groundwater Model	1-x
1.11 Water Treatment Alternatives.....	1-x
1.12 Summary of Financial Assurances.....	1-x
1.13 Degree of Engineering and Scientific Development	1-x
2. Existing Facilities and Conditions	2-1
2.1 Regulatory Authority	2-1
2.2 History of Closure/Closeout Plan Submittal.....	2-1
2.3 History of Mining at Chino.....	2-2
2.4 Past and Current Land Uses.....	2-3
2.5 History of Land Ownership	2-3
2.6 Environmental Setting	2-4
2.6.1 Topography	2-4
2.6.2 Geology.....	2-6
2.6.3 Climate.....	2-9
2.6.4 Hydrology	2-11
2.6.5 Soils and Vegetation	2-17
2.6.6 Wildlife	2-19
2.6.7 Material Characteristics	2-19
2.7 Description of Mining Facilities	2-22
2.7.1 Santa Rita Pit	2-22
2.7.2 Waste and Leach Stockpiles	2-23
2.7.3 Maintenance Facilities Area	2-24
2.7.4 Solution Extraction – Electrowinning Plant	2-24
2.7.5 Ivanhoe Concentrator.....	2-25
2.7.6 Groundhog Mine.....	2-25
2.7.7 Hurley Power Plant.....	2-26

2.7.8	Tailing Impoundments	2-26
2.7.9	Water Use and Management	2-27
2.7.10	Other Ancillary Facilities, Structures and Systems	2-28
2.8	Permits and Discharge Plans	2-29
2.8.1	Existing Permits	2-29
2.8.2	Discharge Plans (DPs)	2-31
3.	Technical Considerations for Reclamation	3-1
3.1	Reclamation Plan	3-1
3.2	Units of Reclamation	3-1
3.2.1	Lampbright Stockpiles and Reservoir 8, DP-376 Area	3-1
3.2.2	SX/EW and Reservoirs 6 and 7, DP-591 Area	3-6
3.2.3	North Pit Stockpiles, Reservoir 5, and Santa Rita Pit, DP-459 Area	3-8
3.2.4	Reservoir 3A, DP-493 Area	3-12
3.2.5	Whitewater Stockpiles and Facilities, DP-526 Area	3-14
3.2.6	Ivanhoe Concentrator and Tailing Pipelines, DP-213 Area	3-19
3.2.7	Hurley Smelter, Lower Whitewater Creek and Older Tailing Ponds, DP-214 Area	3-22
3.2.8	Tailing Pond 7, DP-484 Area	3-27
4.	Proposed Post-Mining Land Use Designation	4-1
4.1	Wildlife Habitat Post-Mining Land Use	4-1
4.2	Industrial Post-Mining Land Use	4-3
4.3	Site-Specific Revegetation Success Guidelines	4-4
5.	Reclamation Designs and Post-Closure Monitoring	5-1
5.1	Facility Characteristics and Classification	5-2
5.1.1	Tailing Ponds General Description and Evaluation Criteria	5-2
5.1.2	Stockpiles General Description and Evaluation Criteria	5-3
5.1.3	Open Pit General Description and Evaluation Criteria	5-4
5.1.4	Reservoirs/Dams	5-4
5.1.5	Disturbed Areas	5-4
5.1.6	System Dynamics of Water Issues and Evaluation Criteria	5-4
5.2	Complying with Performance Objectives/Reclamation Design	5-5
5.2.1	Tailing Ponds	5-6
5.2.2	Stockpiles	5-10
5.2.3	Open Pit	5-13
5.2.4	Reservoirs/Dams	5-15
5.2.5	Disturbed Areas	5-16
5.2.6	Borrow Areas	5-16
5.3	Water Handling/Treatment	5-18
5.3.1	Performance Objectives	5-18
5.3.2	Closure/Closeout Plan Objectives	5-18
5.3.3	Water Treatment Plan	5-22
5.3.4	Beneficial Use of Effluents	5-27
5.4	Bioremediation	5-27
5.5	Post-Closure Monitoring and Contingency Plans	5-28
5.5.1	Erosion and Drainage Control Structures	5-28
5.5.2	Revegetation Success Monitoring	5-29

5.5.3	Surface Water Quality.....	5-29
5.5.4	Groundwater Quality	5-29
5.6	Cover Design	5-30
5.6.1	Introduction.....	5-30
5.6.2	South Mine Area.....	5-30
5.6.3	North Mine Area.....	5-31
6.	Summary of Closure/Closeout Activities	6-1
6.1	Discharge Plan Areas.....	6-1
6.1.1	Lampbright Stockpiles and Reservoir 8, DP-376 Area	6-1
6.1.2	SX/EW and Reservoirs 6 and 7, DP-591 Area	6-4
6.1.3	North Pit Stockpiles, Reservoir 5, and Santa Rita Pit, DP-459 Area....	6-5
6.1.4	Reservoir 3A, DP-493 Area.....	6-8
6.1.5	Whitewater Stockpiles and Facilities, DP-526 Area.....	6-9
6.1.6	Ivanhoe Concentrator and Tailing Pipelines, DP-213 Area.....	6-12
6.1.7	Lower Whitewater Creek and Older Tailing Ponds, DP-214 Area	6-14
6.1.8	Tailing Pond 7, DP-484 Area.....	6-16
6.2	Mining Facilities Not Within the Outlined Discharge Plan Areas	6-18
6.2.1	Mine Maintenance Facilities.....	6-18
6.2.2	Groundhog Mine Area	6-19
6.2.3	South Mine Area Topdressing Borrow Pit.....	6-20

VOLUME II

7.	Capital Cost Estimate.....	7-1
7.1	Introduction.....	7-1
7.2	Basis of Capital Cost Estimate.....	7-1
7.3	Cost Components by Mine Unit	7-13
7.4	Capital Cost Estimates	7-15
8.	Operating and Maintenance Cost Estimates	8-1
8.1	Basis of Operating Cost Estimate	8-1
8.1.1	Water Treatment Operating and Maintenance Cost.....	8-2
8.1.2	General Facilities Maintenance.....	8-4
9.	Financial Assurance Calculation.....	9-1
9.1	Project Schedule.....	9-1
9.1.1	Parameters Affecting Schedule.....	9-1
9.1.2	Project Schedule for Proposed Plan.....	9-2
9.1.3	Project Schedule for Comparison Case.....	9-2
9.2	Cash Flow	9-3
9.3	Possible Escalated Costs	9-3
9.4	Factors Impacting Financial Assurance	9-3
10.	Justification for Waiver.....	10-1
11.	End-of-Mine-Life Closure/Closeout.....	11-1

LIST OF TABLES

VOLUME I

- 2-1 Chino Resource Model Geological Code Descriptions
- 2-2 Reservoirs
- 2-3 Summary of Chino Closure/Closeout Related Permits
- 2-4 Summary of Chino Closure/Closeout Related Discharge Plan Areas

- 4-1 Proposed Interim Seed Mix and Rates for the North Mine Area, Chino Mine
- 4-2 Proposed Interim Seed Mix and Rates for the South Mine Area, Chino Mine
- 4-3 Functions and Attributes of the Primary Plant Species Proposed for the Chino Mine Reclamation Sites
- 4-4 Building Use Register

- 5-1 Summary of Tailing Pond Dimensions in 1998/2006
- 5-2 Summary of Stockpile Dimensions in 1998
- 5-3 Summary of Projected Stockpile Dimensions in 2006
- 5-4 Summary of Santa Rita Pit Dimensions in 1998
- 5-5 Summary of Projected Santa Rita Pit Dimensions in 2006
- 5-6 Summary of Reservoir Function and 1998 Dimensions
- 5-7 Summary of Disturbed Area Dimensions in 2001/2006
- 5-8 Tailing Pond Long-Term Slope Stability: Factor Of Safety
- 5-9 Stockpile Long-Term Slope Stability: Factor Of Safety
- 5-10 Borrow Areas
- 5-11 CCP Water Balance Methodology
- 5-12 Lime Treatment Influent Water Quality and Effluent Requirements

VOLUME II

- 8-1 Operating Cost – Water Treatment Plant and General Site Maintenance – Annual Cost Summary
- 8-2a Operating Cost – Water Treatment – 1,000 gpm Capacity with Chemical Treatment – Years 1-5
- 8-2b Operating Cost – Water Treatment – 800 gpm Capacity with Chemical Treatment – Years 6-10
- 8-2c Operating Cost – Water Treatment – 800 gpm Capacity with Chemical Treatment – Years 11-20
- 8-2d Operating Cost – Water Treatment – 600 gpm Capacity with Chemical Treatment – Years 21-30
- 8-3 Operating Cost – Water Treatment Electric Power – 1,000 gpm Capacity with Chemical Treatment
- 8-4a Operating Cost – Sampling, Sample Analysis, Reporting
- 8-4b Operating Cost Basis – Sampling, Sample Analysis, Reporting
- 8-5 Operating Cost – General Site Management
- 8-6 Operating Cost – Water Handling and General Site Electric Power

- 9-1 Project Cash Flow – Proposed Plan
- 9-2 Project Cash Flow – Comparison Case
- 9-3 Project Cash Flow – Proposed Plan Escalated @ 2.55%
- 9-4 Project Cash Flow – Comparison Case Escalated @ 2.55%

LIST OF FIGURES

VOLUME I

- 1-1 Base Case Perspective of the Projected Reclamation
- 1-2 Tailing Reclamation
- 1-3 Conceptual Waterflow Models

- 2-1 Site Location
- 2-2 Ore Processing Operations at Santa Rita and Hurley Sites of Chino Mine
- 2-3 Site Topography
- 2-4 Mine Maintenance Facilities Area
- 2-5 SX/EW Plant Area
- 2-6 Ivanhoe Concentrator/Precipitation Plant Area
- 2-7 Groundhog Mine Area
- 2-8 Hurley Smelter Area
- 2-9 Water Use and Supply Cycle at Chino Mine
- 2-10 Mine Layout and Closure/Closeout Areas

- 5-1 Conceptual Mine System Divisions

- 6-1 Lampbright Stockpile Area: Setting
- 6-2 Lampbright Stockpile Area: Characteristics
- 6-3 Santa Rita Pit Area: Setting
- 6-4 Santa Rita Pit Area: Facility Characteristics
- 6-5 West and South Stockpiles Area: Setting
- 6-6 West and South Stockpiles Area: Facility Characteristics
- 6-7 Middle Whitewater Creek Area: Setting
- 6-8 Middle Whitewater Creek Area: Facility Characteristics
- 6-9 Smelter Area: Setting
- 6-10 Smelter Area: Facility Characteristics
- 6-11 Older Tailing Ponds Area: Setting
- 6-12 Older Tailing Ponds Area: Facility Characteristics
- 6-13 Tailing Pond 7 Area: Setting
- 6-14 Tailing Pond 7 Area: Facility Characteristics
- 6-15 Mine Maintenance Facilities Area
- 6-16 Groundhog Mine Area

VOLUME II

None

LIST OF APPENDICES

- A List of Acronyms and Key Definitions
- B Drawings
- C Facility Characteristics Forms
- D Bibliography
- E Reports on Borrow Material and Cover Design
- F Reports on Structural Stability
- G Reports on Water Issues
- H Reports on Tailing Ponds
- I Reports on Stockpiles
- J Reports on Mine Pits
- K Reports on Impoundments and Miscellaneous Disturbed Areas

CHINO CLOSURE/CLOSEOUT APPENDIX A

I. ACRONYMS

ABA = Acid-Base Accounting
AGP = Acid Generating Potential
AMD = Acid Mine Drainage
ANFO = Ammonium Nitrate Fuel Oil
ANP = Acid Neutralizing Potential
AOC = Administrative Order of Consent
AST = Aboveground Storage Tanks
BLM = Bureau of Land Management
BMI = Borrow Materials Investigation
CCP = Closure/Closeout Plan
CCWP = Closure/Closeout Work Plan
CERCLA = Comprehensive Environmental Response, Compensation and Liability Act
CGWCS = Comprehensive Groundwater Characterization Study
COC's = Constituents of Concern
DBS&A = Daniel B. Stephens & Associates, Inc.
DP = Discharge Plan
EC = Electrical Conductivity
EIS = Environmental Impact Study
EPA = Environmental Protection Agency
GAI = Golder Associates, Inc.
GPS = Global Positioning System
HAP = Hazardous Air Pollutant
HDPE = High Density Polyethylene
HELP = Hydrologic Evaluation of Landfill Performance model
IARIBR = Investigation Area Remedial Investigative Background Report
IU = Investigation Unit
JS&A = John Shomaker and Associates
MA = Mineral Assemblage
MMD = Mining and Minerals Division
MSHA = Mine Safety and Health Administration (U.S. Department of Labor)
NA = Not Available
NMED = New Mexico Environment Department
NMMA = New Mexico Mining Act
NMWQCC = New Mexico Water Quality Control Commission
NOAA = National Oceanographic and Atmospheric Administration
NPDES = National Pollutant Discharge Elimination System
PLS = Pregnant Leach Solution; i.e., liquor carrying copper ore
PMC = Preliminary Materials Characterization
PMLU = Post Mining Land Use
POO = Mine Plan of Operations

RCRA = Resource Conservation and Recovery Act
 RUSLE = Revised Universal Soil Loss Equation
 SCS = Soil Conservation Service
 SMC = Supplemental Material Characterization
 SPCC = Spill Prevention, Control, and Countermeasure
 SPLP = Synthetic Precipitation Leaching Procedure
 SSE = Self-Sustaining Ecosystem
 SWPPP = Stormwater Pollution Prevention Plan
 SX/EW = Solution Extraction/Electrowinning; i.e., plant for extracting copper
 TBD = To Be Determined
 TDRW = Tailings Decant Return Water
 USBR = United States Bureau of Reclamation
 USDA = United States Department of Agriculture
 VOC = Volatile Organic Compound
 WCC = Woodward Clyde Consultants
 WEPP = Water Erosion Prediction Project
 XRD = X-Ray Diffusion

II. LEXICON AND TECHNICAL ABBREVIATIONS

- alluvial fan = a fan shaped alluvial deposit formed by a stream where its velocity is abruptly decreased such as at the foot of a ravine at a hill's base
- alluvium = unconsolidated sedimentary material (including clay, silt, sand, gravel and mud) deposited by flowing water
- aquifer = a zone, stratum, or group of strata acting as a hydraulic unit that stores or transmits water in sufficient quantities for beneficial use
- berm = an earthen structure, generally at least a few feet high, which acts as a barrier to redirect the flow of traffic or water
- bgs = below ground surface
- closeout plan = a plan that describes actions to be taken following the cessation of active mining activities that will allow for the establishment of self-sustaining ecosystem or post-mining land use, consistent with the requirements of New Mexico Mining Act Rule 5
- closure plan = a plan that describes actions to be taken following the cessation of active mining activities that will result in the long-term stabilization of the site and maintenance of environmental standards, as applicable
- detention ponds = structures constructed by excavation and/or building an embankment whose purpose is to retain water and allow for settlement of fines (silt and grit) and reduction in turbidity
- ephemeral stream = a stream or portion of a stream or wash that flows only in direct response to precipitation or snow melt. Such flow is of relatively short duration
- erosion = the wearing away of the land surface by running water, wind, ice, or other geological agents, including gravitational creep
- evapotranspiration = the process of transferring moisture from the earth to the atmosphere by evaporation of water transpired (given off) by plants

- financial assurance calculation = net present cost of scheduled and operating and maintenance cost estimates
- fluvial = of or relating to a river or stream
- gpd = gallons per day
- ground cover = soil layer placed over stockpiles and tailing dams
 - fine grain size is susceptible to movement by wind
 - coarse grain size is susceptible to movement by water
 - very coarse grain size is susceptible to movement by gravity (i.e., raveling)
- habitat = the natural environment of a plant or animal, including all biotic, climactic and soil conditions, or other environmental factors influencing living conditions
- hazardous waste = waste material exhibiting one or more of the following characteristics: ignitability, corrosivity, reactivity, and/or toxicity as defined by the Federal Resource Conservation and Recovery Act
- heavy metals = group of elements, usually required by organisms in trace amounts, but may be toxic in higher concentrations; includes lead, mercury, molybdenum, nickel, copper, cobalt, chromium, iron, silver, etc.
- inert = a substance that is considered chemically unreactive; not affecting any substance it comes in contact with
- interstitial = occupying the spaces between sediment particles
- leaching = a natural or artificial process through which one or more constituents of a solid are solubilized. The metal ions in an aqueous solution are called a "pregnant" solution
- mesic = characterized by requiring a moderate amount of moisture
- mil = 0.001"
- performance bond = financial guarantee to ensure that the activities described in the CCP can be adequately carried out in the event of forfeiture
- permeability = the property or capacity of a porous rock, sediment, or soil for transmitting a fluid; it is a measure of the relative ease of fluid flow under unequal pressure
- perennial stream = a stream continuing throughout the year
- pH = measure of hydrogen ion concentration; i.e., measure of acidity
- piezometric surface = an imaginary surface coinciding with the hydraulic pressure level of the water in a confined aquifer, or the surface representing the static head of ground water and defined by the level to which water will rise in a well or vertical pipe
- plant community = a vegetation complex unique in its combination of plants that occurs in particular locations under particular influences
- ppm = parts per million (by weight of constituent)
- raffinate = an acidic process water used to extract copper from ore and derived from recycled water from the SX/EW process
- rills = small channels or grooves made by erosional processes
- riprap = a layer of broken rock dumped or placed together irregularly to prevent erosion
- sediment = earth material transported, suspended or deposited by water
- sloped surfaces = those surfaces with a base/height ratio steeper than 7

- out slopes are those surfaces sloping away from the top surface of tailing ponds and stockpiles
- outslope crest is the junction of the top surface with the outslope surface
- outslope toe is the junction of the bottom of the outslope surface with natural terrain
- tailing = material left after extraction of metal or mineral
- TDS = total dissolved solids = fine material (with a diameter smaller than a few hundred micrometers) that is suspended in liquids such as water
- vadose = located above the water table
- water (domestic source) = surface or ground water that can be treated to potable quality
- water (ground) = the interstitial water that occurs in situated earth material and which is often capable of entering a well in sufficient amounts to be used as a supply
- water (impacted) = water which comes in contact with disturbed area and as a result does not meet the requirements for irrigation water, surface water or ground water
- water (irrigation) = water suitable for artificial application to assist in growth of vegetation
- water (non-impacted) = water which comes in contact with disturbed area but which does not change significantly
- water (potable) = suitable, safe or prepared for drinking
- water bars = erosion control measure for roads
- watershed = entire land area that contributes waters to a particular drainage system
- weathering = processes whereby larger particles of soils and rock are reduced to finer particles by wind, water, temperature changes, and plant and bacterial action
- wind fetch
 - upwind fetch = distance wind travels over open ground upwind of facility
 - downwind fetch = distance wind travels over open ground downwind of facility

III. KEY TERMS

The following definitions explain the terms and concepts used to characterize the facilities for conceptual design. The forms that follow summarize the information used in conceptual design.

Location Characteristics

Surface Water

Upstream: watershed with the potential for runoff

Downstream: drainages or channels that would accept runoff from the facility

Wind (assuming prevailing winds are from the west)

Upwind fetch: distance wind travels over open ground upwind of facility

- Blocked - facility is directly in wind shadow of prevailing winds
- Limited - facility is within ~ 500 ft. of hills or other upwind obstruction
- Med - facility is within ~ 2,000 ft. of hills or other upwind obstruction

Downwind fetch: distance wind travels over open ground downwind of facility

- Blocked - wind is immediately blocked downwind of facility
- Limited - hills or other downwind obstruction exist within ~ 500 ft. of facility
- Med - hills or other downwind obstruction exist within ~ 2,000 ft. of facility

Physical Characteristics

Grain size:

- Fine - susceptible to movement by wind
- Coarse - susceptible to movement by water
- Very coarse - susceptible to movement by gravity (e.g., raveling)

Leach Status

Stockpiles that have been or currently are being leached are considered leach stockpiles. All other stockpiles are considered non-leach, overburden or waste rock stockpiles.

Elevation Reference

ft msl = feet above mean sea level

Size and Dimension Definitions

The size and dimension definitions are presented according to the facility subgroups: outslopes, top surfaces, and perimeters. Note that open pit sideslopes are not termed outslopes, although the definitions for outslopes are equally applicable.

Outslopes (Tailing Ponds and Stockpiles) and Sideslopes (Open Pits)

Segment (no units): A portion of an outslope with uniform characteristics (i.e., uniform height, slope length, and slope angle). Segments are termed interior if they drain onto other facilities or exterior if they do not drain onto other facilities (indicated by (i) or (e), respectively, on the forms).

Crest elevation (feet above msl): Average elevation along the crest of an outslope segment.

Toe elevation (feet above msl): Average elevation along the toe of an outslope segment.

Height (feet): Vertical distance (i.e., difference) between crest and toe elevation

Base (feet): Length (i.e., horizontal map projection) between points of measurement for toe and crest elevations

Slope length (feet):

$$\text{Slope Length} = \sqrt{\text{Height}^2 + \text{Base}^2}$$

Slope (H:L): Base/height (e.g., 2.5 represents 2.5 ft horizontal to 1 ft vertical)

Slope angle (degrees): \tan^{-1} (height/base)

Surface area (acres): Area of an outslope segment, corrected for the horizontal map projection.

Top Surfaces (Stockpiles)

Surface slope angle (%): assumed to be flat or irregular

Surface area (acres): Area of a top surface. No correction from the horizontal map projection is used because such a correction is negligible for gently sloping surfaces.

Top Surfaces (Tailing Ponds)

Crest elevation (feet above msl): Elevation on top of tailing pond at tailing pond crest

Low point elevation (feet above msl): Elevation at low point on top of tailing pond

Vertical drop (feet): Vertical difference between toe of crest elevation and low point elevations

Horizontal length (feet): Length (i.e., horizontal map projection) between points of measurement for crest and low point elevations

Surface slope angle (H:1): Horizontal length/vertical drop (e.g., 2.5 represents 2.5 ft horizontal to 1 ft vertical)

Surface slope angle (%): (vertical drop/horizontal length) * 100

Surface area (acres): Area of a top surface. No correction from the horizontal map projection is used because such a correction is negligible for gently sloping surfaces.

Pit Bottoms (Open Pits)

Pit bottom area (acres): Area for the small, planar area at the bottom of an open pit. No correction from the horizontal map projection is used.

Top Surface Perimeters (Tailing Ponds and Stockpiles)

Runon perimeter (feet): Perimeter length along a top surface that may be subject to runon from adjacent hillslopes. Includes possibly blocked channels.

Runoff perimeter (feet): Perimeter length along the top edge of an outslope (i.e., the edge of the top surface) that may be subject to runoff from the top surface.

Neutral perimeter (feet): Perimeter length along the edge of a top surface that is subject to neither runon nor runoff.

Outslope Perimeters (Tailing Ponds and Stockpiles)

Interior toe perimeter (feet): Perimeter length along the toe of an outslope which drains onto another facility.

Exterior toe perimeter (feet): Perimeter length along the toe of an outslope which does not drain onto another facility.

Crest Perimeters (Open Pits)

Pit crest perimeter (feet): Perimeter length around the circumference of the crest of the open pit.

CHINO CLOSURE/CLOSEOUT



APPENDIX B

M3 DRAWINGS

<u>Drawing Number</u>	<u>Title</u>
Chino-00	Location Map
Chino-01	Property Plan with Discharge Permits Tailing, Piles, Pits, and Facilities
Chino-02	Site Plan Tailing Ponds Drainage
Chino-03	Plan Tailing Ponds 1 and 2
Chino-04	Plan Tailing Ponds B, C, and 4
Chino-05	Plan Tailing Ponds 6 East and 6 West
Chino-06	Plan Tailing Pond 7
Chino-07	Tailing Ponds Spillway Profiles
Chino-08	Tailing Ponds Spillway Construction Details
Chino-09	Tailing Ponds Outslope Surface Runoff Details
Chino-10	Tailing Ponds Connecting Channels
Chino-11	Site Plan – Proposed Plan Stockpile Area
Chino-12	Plan – Proposed Plan Lampbright Stockpiles

<u>Drawing Number</u>	<u>Title</u>
Chino-13	Plan – Proposed Plan South Stockpile
Chino-14	Plan – Proposed Plan West and Northeast Stockpiles
Chino-15	Stockpiles/Tailings Detention Ponds
Chino-16	Plan Water Treatment/Handling
Chino-17	Flowsheet Water Treatment/Handling
Chino-18	Earthen Channel Details Water Handling, Sheet 1
Chino-19	Earthen Channel Details Water Handling, Sheet 2
Chino-20	Site Plan Groundwater Flows
Chino-21	Site Plan Surface Water and Stockpile Seepage Flows
Chino-22	Site Plan – Comparison Case Stockpile Area
Chino-23	Plan – Comparison Case Lampbright and Northeast Stockpiles
Chino-24	Plan – Comparison Case South and West Stockpiles
Chino-25	Stockpiles – Comparison Case Outslope Details
Chino-26	Site Plan Discharge Permit Boundaries
Chino-27	Stockpile Top Surface Details

<u>Drawing Number</u>	<u>Title</u>
Chino-28	Miscellaneous Cover Details
Chino-29	Site Plan Water Treatment/Handling
Chino-30	Site Plan – Irrigation System Water Treatment/Handling
Chino-31	Property Plan with PMLU and Waiver Area Designations



90

180

SANTA CLARA

COBRE
MINING
COMPANY

CONTINENTAL
MINE

SANTA
RITA
OPEN PIT

CHINO MINE / CONCENTRATOR COMPLEX

BAYARD

HURLEY

CHINO SMELTER COMPLEX

CHINO TAILINGS PONDS

AIRPORT

TO DEMING


TYRONE
MINE



TO LORDSBURG

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO CLOSURE / CLOSEOUT
LOCATION MAP

CHINO-00






Note: Map coordinates are based on the New Mexico State Plane (NMSP) NAD 83, West Zone

0 2000 Feet
Scale 1" = 2000'


CHINO CLOSURE / CLOSEOUT
SITE PLAN
TAILING PONDS DRAINAGE

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO-02



Location Map



0 800 Feet
Scale 1" = 800'


Note: Map coordinates are based on the
New Mexico State Plane (NMSP)
NAD 83, West Zone

CHINO CLOSURE / CLOSEOUT
PLAN
TAILING POND 1 & 2


M3 Engineering & Technology Corp.
Tucson, Arizona

NAME: O:\2000\00315\Chino\Civil\CHINO-03.dwg LAST REV: LAST UPDATE: FEB 23, 2001 TIME: 5:32 AM BY: PR504 PLOT SCALE: 1:1

CHINO-03



Location Map





0 800 Feet
Scale 1" = 800'

Note: Map coordinates are based on the
New Mexico State Plane (NMSP)
NAD 83, West Zone

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO CLOSURE / CLOSEOUT
PLAN
TAILING POND B, C & 4

CHINO-04



Note: Map coordinates are based on the New Mexico State Plane (NMSP) NAD 83, West Zone


0 800 Feet
Scale 1" = 800'

M3 Engineering & Technology Corp.
Tucson, Arizona


CHINO CLOSURE / CLOSEOUT
PLAN
TAILING POND 6 EST & 6 WEST

CHINO-05


NAME: O:\2000\00315\Chino\Civil\CHINO-05.dwg LAST REV: LAST UPDATE: FEB 24, 2001 TIME: 3:23 PM BY: cr358 PLOT SCALE: 1:1



Ponds 7 & 8E/6W Spillways and Connecting Channels



Location Map



Explanation

- 6100 Land surface elevation contour (contour interval 5 ft and 25 ft)
- Facility outline
- Direction of slope
- Year 2004 projected contours
- Riprap at spillway entrance

Notes:

1. Topography is based on November 1998 data.


0 1000 Feet
Scale 1" = 1000'

M3 Engineering & Technology Corp.
Tucson, Arizona


CHINO CLOSURE / CLOSEOUT
PLAN
TAILING POND 7

CHINO-06


Profile of Tailing Ponds 4 & B/C Spillway



Profile of Tailing Pond 7 Spillway



Profile of Tailing Ponds 6E & 6W Spillway



Existing ground varies along profile

Bottom width varies
See table of outlet channel dimensions

Gila Conglomerate
(Typically slightly to strongly
indurated with cobbles)

Depth varies
See table of Outlet Channel Dimensions

Outlet Channel Cross Section



0 600 Feet
Scale 1" = 60'

Explanation

- Approximate existing ground surface
- Spillway/connecting channel centerline invert


Notes:

1. All profiles are at a x10 vertical exaggeration

Outlet Channel Dimensions

Tailing Pond	Bottom Width (Feet)	Minimum Depth (Feet)	Slope (ft/ft)
B & C	55	4	0.039
4 Upper	36	6.5	0.01
4 Lower	36	25	0.01
6E & 6W	125	5	0.036
7	125	4	0.041*



* Steepest portion of channel bed slope




Spillway Dimensions					
Tailing Pond	Bottom Width		Length		Slope (H:1)
	Feet	No. of Gabion Mattresses Wide	Feet	No. of Gabion Mattresses Long	
B & C	24	8	336	28-12'	2.9
4	36	12	343	28-12', 1-6'	3.0
6E & 6W	60	20	385	32-12'	3.2
7	60	20	243	20-12', 1-6'	3.8

Stilling Basin Dimensions									
Tailing Pond	Bottom Width		Length		Approximate Tooth Design				No. of Teeth
	Feet	No. of Gabion Mattresses Wide	Feet	No. of Gabion Mattresses Long	Height (ft)	Width (ft)	Length (ft)	Spacing (ft)	
B & C	24	8	30	2-12', 1-6'	1.50	0.75	1.50	2.00	~10
4	36	12	30	2-12', 1-6'	1.50	0.75	1.50	2.00	~15
6E & 6W	60	20	36	3-12'	1.75	0.75	1.75	2.00	~20
7	60	20	36	3-12'	1.75	0.75	1.75	2.00	~20


0 24 Feet
Scale 1" = 24'




DETAIL
N.T.S. RAVINE WATERWAY WITH STONE CENTER 2



DETAIL
N.T.S. TAILING SLOPE 4



SECTION
N.T.S. 3




SECTION

DETAIL

TAILING MESA BERM

3




SECTION

DETAIL - ROCK PROTECTED CHANNEL


RIVER BED WATERWAY WITH STONE CENTER


1



 FACILITY OUTLINE

0 2000 Feet
Scale 1" = 2000'





0 1200 Feet
Scale 1" = 1200'

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO CLOSURE / CLOSEOUT
PROPOSED PLAN
SOUTH STOCKPILE

CHINO-13



STATE HIGHWAY 356
RAILROAD

HIGHWAY 152

NORTHEAST
STOCKPILE

SEEPAGE COLLECTION


HANOVER CREEK


WEST
STOCKPILE

SEEPAGE COLLECTION

MAINTENANCE
FACILITIES
AREA

SANTA RITA PIT





- P SEEP / SPRING
- CGCS MONITOR WELL
- DP. SPECIFIC MONITOR WELL


0 2000 Feet
Scale 1" = 2000'


NAME: O:\2000\00315\Chino\Civil\CHINO-21.dwg LAST REV: LAST UPDATE: MAR 01, 2001 TIME: 10:26 AM BY: cr355 PLOT SCALE: 1:1

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO CLOSURE / CLOSEOUT
PLAN
WATER TREATMENT / HANDLING

CHINO-16







SECTION

DETAIL

N.T.S.

ON EXISTING BENCHES AND HAUL ROADS
BENCH SURFACE DITCH






0 2000 Feet
Scale 1" = 2000'

- p SEEP / SPRING
- APPROXIMATE REGIONAL GROUNDWATER FLOW DIRECTION
- FACILITY OUTLINE

M3 Engineering & Technology Corp.
Tucson, Arizona


CHINO CLOSURE / CLOSEOUT
SITE PLAN
GROUNDWATER FLOWS

CHINO-20



- SEEP / SPRING
- SURFACE WATER FLOW
- STOCKPILE SEEPAGE FLOW
- PIPELINE

0 2000 Feet
Scale 1" = 2000'



COLLECTION CHANNEL

0 2000 Feet
Scale 1" = 2000'

NAME: O:\2000\00315\Chino\Civil\CHINO-22.dwg LAST REV: LAST UPDATE: MAR 12, 2001 TIME: 5:00 PM BY: cr358 PLOT SCALE: 1:1

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO CLOSURE / CLOSOUT
COMPARISON CASE - SITE PLAN
STOCKPILE AREA

CHINO-22



NORTH LAMPBRIGHT
STOCKPILE LIMITS

RESERVOIR
No. 8

MAIN LAMPBRIGHT
STOCKPILE LIMITS

SOUTH LAMPBRIGHT
STOCKPILE

SLOPE
3%

SLOPE
3%

MAIN
LAMPBRIGHT
STOCKPILE

NORTH
LAMPBRIGHT
STOCKPILE

SOUTHWEST
LAMPBRIGHT

STATE HIGHWAY 152

SX-EW
PLANT

NORTH PIT
STOCKPILE LIMITS

NORTHEAST
STOCKPILE

SANTA RITA OPEN PIT

STOCKPILE
LIMIT

COLLECTION
CHANNEL

0 1200 Feet
Scale 1" = 1200'

PUSHDOWNS AT 4:1 AVG. SLOPE

CHINO CLOSURE / CLOSEOUT
COMPARISON CASE - PLAN
LAMPBRIGHT & NORTHEAST STOCKPILES

CHINO-23

M3 Engineering & Technology Corp.
Tucson, Arizona



STATE
HIGHWAY 152

SANTA RITA OPEN PIT

UPPER SOUTH
STOCKPILE

COLLECTION
CHANNEL

MAINTENANCE
FACILITIES
AREA

SOUTH
STOCKPILE

SLOPE 3%

WEST
STOCKPILE

SLOPE 3%

SOUTH
STOCKPILE
LIMIT

DRAINAGE

STATE HIGHWAY 356

COLLECTION
CHANNEL

RAILROAD

WEST
STOCKPILE
LIMIT

WATER
TREATMENT

COLLECTION
CHANNEL

STOCKPILE
LIMIT
COLLECTION
CHANNEL

1200 Feet

Scale 1" = 1200'


PUSHDOWNS AT 4:1 AVG. SLOPE


CHINO CLOSURE / CLOSEOUT
COMPARISON CASE - PLAN
SOUTH AND WEST STOCKPILE


CHINO-24

NAME: O:\2000\00315\Chino\Civil\CHINO-24.dwg LAST REV: LAST UPDATE: MAR 12, 2001 TIME: 5:04 PM BY: cr358 PLOT SCALE: 1:1


M3 Engineering & Technology Corp.
Tucson, Arizona










**DETAIL FOR STOCKPILES,
HAUL ROADS, BENCHES OR TOP SURFACES**
N.T.S.



DETAIL - TAILINGS LAUNDER COVER

10






NO WAIVER PROPOSED FOR:

3794 ACRES OF TAILING POND AREAS, REVEGETATED
1033 ACRES OF STOCKPILE TOP SURFACES
610 ACRES OF TAILING POND BORROW AREAS
5437 ACRES RECLAIMED TO SSE

**PROPOSED STOCKPILE
AND OPEN PIT WAIVER
AREAS
TOTALING 3173 ACRES**



**CLOSURE / CLOSEOUT PLAN
PROPERTY PLAN WITH PMLU AND
WAIVER AREA DESIGNATIONS**

M3 Engineering & Technology Corp.
Tucson, Arizona

CHINO-31

CHINO CLOSURE/CLOSEOUT APPENDIX C

FACILITY CHARACTERISTICS FORMS

Lake One

Tailing Pond 1

Tailing Pond 2

Axiflo Lake

Tailing Pond B

Tailing Pond C

Tailing Pond 4

Tailing Pond 6 West

Tailing Pond 6 East

Tailing Pond 7

South Stockpile

Northeast Stockpile

Upper South Stockpile

Northwest Stockpile

North Stockpile

East Pit Access

Main Lampbright Stockpile

South Lampbright Stockpile

North Lampbright Stockpile

Southwest Lampbright Stockpile

Groundhog No. 5 Stockpile

West Stockpile

Santa Rita Open Pit

**Chino Closure/Closeout
Facility Characteristics Form**

Lake One

Function	Inactive Historically used for water storage and flood retention
Location Characteristics	Major channel to east (i.e., Whitewater Creek) Regional depth to groundwater is less than 75 feet, direction of flow is south Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Earthen dam
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing and Planned Engineering Measures	Existing Whitewater Creek Diversion, smelter stormwater collection pond, planned upper Whitewater Creek diversion

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	220	220
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$976,690	\$1,831,722
Outslope Adjustment	\$0	\$0
Divots, Seed & Mulch	\$273,812	\$271,023
Channels, Conduits & Berms	\$128,469	\$127,160
Capital Cost Totals	\$1,378,971	\$2,229,906
Capital Cost/Acre	\$6,268	\$10,136

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 1

Function	Tailing deposition No active tailing deposition since 1953 Repository for tailing spill cleanup material through present
Location Characteristics	Major channel to east (i.e., Whitewater Creek) Runon from Tailing Pond 2 and possibly from west Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing and Planned Engineering Measures	Periodic grading of east outslope along Whitewater Creek Planned Upper Whitewater Creek diversion and dust cover capping

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	159	159
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$812,416	\$1,399,090
Outslope Adjustment	\$39,743	\$39,338
Divots, Seed & Mulch	\$197,891	\$195,876
Channels, Conduits & Berms	\$90,926	\$90,000
Capital Cost Totals	\$1,140,976	\$1,724,303
Capital Cost/Acre	\$7,176	\$10,845

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 2

Function	Tailing deposition Inactive since 1944
Location Characteristics	Major channel to east (i.e., Whitewater Creek) Runon from Tailing Pond B, runoff to Axiflo Lake Depth to regional groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing and Planned Engineering Measures	Planned Upper Whitewater Creek diversion, dust cover capping

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	150	150
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$793,648	\$1,339,207
Outslope Adjustment	\$47,691	\$47,205
Seepage Water Treatment	N/A	N/A
Interceptor Well & Pit Water Treatment	N/A	N/A
Runoff Water Treatment	N/A	N/A
Divots, Seed & Mulch	\$186,690	\$184,788
Channels, Conduits & Berms	\$85,286	\$84,417
Capital Cost Totals	\$1,113,314	\$1,655,618
Capital Cost/Acre	\$7,422	\$11,037

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Axiflo Lake

Function	Storage of TDRW, Tailing Pond 7 interceptor system discharge, and Bolton Wellfield production well water Active since 1919
Location Characteristics	Runon from Tailing Ponds 2, B, and 4 No downstream issues Depth to groundwater is greater than 75 feet, direction of flow is South Low upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Earthen dam
Physical Characteristics	Not applicable
Leach Status	Not applicable
Existing Engineering Measures	None

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	91	91
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$417,025	\$766,697
Outslope Adjustment	\$4,769	\$4,721
Divots, Seed & Mulch	\$113,259	\$112,105
Channels, Conduits & Berms	\$52,909	\$52,370
Capital Cost Totals	\$587,961	\$935,893
Capital Cost/Acre	\$6,461	\$10,285

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond B

Function	Tailing deposition Inactive since 1993
Location Characteristics	No upstream issues, runoff to Tailing Pond 2 and Axiflo Lake Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Dust cover capping

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	238	238
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$1,313,965	\$2,162,201
Outslope Adjustment	\$95,382	\$94,411
Divots, Seed & Mulch	\$296,215	\$293,198
Channels, Conduits & Berms	\$215,070	\$212,879
Capital Cost Totals	\$1,920,631	\$2,762,688
Capital Cost/Acre	\$8,070	\$11,608

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond C

Function	Tailing deposition Inactive since 1993
Location Characteristics	No upstream issues, no downstream issues Depth to regional groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Dust cover capping

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	158	158
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$959,914	\$1,496,120
Outslope Adjustment	\$95,382	\$94,411
Divots, Seed & Mulch	\$196,647	\$194,644
Channels, Conduits & Berms	\$332,939	\$329,547
Capital Cost Totals	\$1,584,881	\$2,114,722
Capital Cost/Acre	\$10,031	\$13,384

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 4

Function	Tailing deposition Inactive since 1988 Temporary disposal of excess water
Location Characteristics	No upstream issues, runoff to Axiflo Lake and Tailing Ponds 6 West and 6 East Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Dust cover capping

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	362	362
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$1,795,450	\$3,146,463
Outslope Adjustment	\$69,947	\$69,234
Divots, Seed & Mulch	\$450,545	\$445,956
Channels, Conduits & Berms	\$385,308	\$381,384
Capital Cost Totals	\$2,701,250	\$4,043,037
Capital Cost/Acre	\$7,462	\$11,169

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %		
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 6 West

Function	Tailing deposition Inactive since 1961
Location Characteristics	Runon from Tailing Pond 4, runoff to Tailing Pond 7 Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Outslope modification project, dust cap cover

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	425	425
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$2,256,831	\$3,797,429
Outslope Adjustment	\$136,714	\$135,322
Divots, Seed & Mulch	\$528,955	\$523,567
Channels, Conduits & Berms	\$241,566	\$239,106
Capital Cost Totals	\$3,164,067	\$4,695,424
Capital Cost/Acre	\$7,445	\$11,048

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 6 East

Function	Tailing deposition Inactive since 1988 Temporary disposal of excess water
Location Characteristics	Runon from Tailing Pond 4, runoff to Tailing Pond 7 Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Outslopes modification project, dust cap cover

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	428	428
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$2,210,721	\$3,780,265
Outslope Adjustment	\$114,458	\$113,293
Divots, Seed & Mulch	\$532,688	\$527,263
Channels, Conduits & Berms	\$360,802	\$357,128
Capital Cost Totals	\$3,218,670	\$4,777,948
Capital Cost/Acre	\$7,520	\$11,163

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

Tailing Pond 7

Function	Tailing deposition Active since 1988
Location Characteristics	Major channel to east (i.e., Whitewater Creek) Runon from Tailing Pond 6 East and 6 West, inflow from groundwater interceptor wells, no downstream issues, TDRW to Axiflo Lake Regional depth to groundwater is greater than 75 feet, direction of flow is South Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	Upstream, cyclone application
Physical Characteristics	Fine to coarse grained Low to medium saturated hydraulic conductivity
Leach Status	Not applicable
Existing Engineering Measures	Interceptor well system, seepage collection sump, 1988 and 1998 Whitewater Creek diversions, dust cover capping on outslope

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	1,563	1,563
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$8,501,995	\$14,112,266
Outslope Adjustment	\$580,241	\$574,331
Divots, Seed & Mulch	\$1,945,308	\$1,925,495
Channels, Conduits & Berms	\$2,027,206	\$2,006,559
Capital Cost Totals	\$13,054,750	\$18,618,651
Capital Cost/Acre	\$8,352	\$11,912

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Gila Cong.	Gila Cong.

**Chino Closure/Closeout
Facility Characteristics Form**

South Stockpile

Function	Rock stockpile
Location Characteristics	Southwest of Main Pit Possible runoff from South Stockpile A plus undisturbed hillslope to south No downstream issues Regional depth to groundwater is less than 75 feet, direction of flow is to Whitewater Creek and Main Pit Limited upwind fetch, limited to downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	No leach on extreme southern and northeast portions, Leach on remainder
Existing Engineering Measures	PLS and stormwater collection system, toe control systems All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	635	648
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$1,917,377	\$7,077,741
Outslope Adjustment	N/A	\$37,990,655
Divots, Seed & Mulch	\$253,916	\$904,629
Channels, Conduits & Berms	\$405,143	\$796,394
Capital Cost Totals	\$2,576,436	\$46,769,418
Capital Cost/Acre	\$4,057	\$72,175

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	32 / 68	100 / 0
Revegetation Area %	32	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

Northeast Stockpile

Function	Ore stockpile
Location Characteristics	
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Stormwater collection system, toe control systems Interceptor wells, all top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	77	111
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$232,256	\$1,521,898
Outslope Adjustment	N/A	\$2,763,880
Divots, Seed & Mulch	\$23,482	\$137,416
Channels, Conduits & Berms	\$51,830	\$12,137
Capital Cost Totals	\$307,568	\$4,435,331
Capital Cost/Acre	\$3,994	\$39,958

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	6 / 94	100 / 0
Revegetation Area %	6	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

**Upper South Stockpile
(Borrow Area ~ 50,000,000 cy)**

Function	Rock stockpile
Location Characteristics	South of Main Pit, southeast of South Stockpile A Runon from hillslopes Reservoir 3A to the south No downstream issues Regional depth to groundwater is greater than 75 feet, direction of flow is to the Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Toe control systems All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	152	152
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$25,829	\$25,565
Outslope Adjustment	N/A	N/A
Divots, Seed & Mulch	\$11,201	\$187,252
Channels, Conduits & Berms	\$55,042	\$14,768
Capital Cost Totals	\$92,072	\$227,586
Capital Cost/Acre	\$606	\$1,497

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	6 / 94	100 / 0
Revegetation Area %	6	100
Cover Material (Gila Cong. or Rhyolite)	N/A	N/A

**Chino Closure/Closeout
Facility Characteristics Form**

**Northwest Stockpile
(Borrow Area ~ 2,000,000 cy)**

Function	Rock stockpile
Location Characteristics	Northwest of Main Pit No upstream issues No downstream issues Regional depth to groundwater is greater than 75 feet, direction of flow is to Hanover Creek and Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Toe control systems All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	20	20
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$57,397	\$56,812
Outslope Adjustment	N/A	N/A
Divots, Seed & Mulch	\$24,892	\$24,638
Channels, Conduits & Berms	\$19,073	\$32,818
Capital Cost Totals	\$101,362	\$114,268
Capital Cost/Acre	\$5,068	\$5,713

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	N/A	N/A

**Chino Closure/Closeout
Facility Characteristics Form**

North Stockpile

Function	Rock/ore stockpile
Location Characteristics	North of Main Pit No upstream issues No downstream issues Regional depth to groundwater is less than 15 feet to greater than 200 feet, direction of flow is toward Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Stormwater collection system, toe control systems All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	20	27
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$67,140	\$315,184
Outslope Adjustment	N/A	0
Divots, Seed & Mulch	\$6,223	\$24,638
Channels, Conduits & Berms	\$9,642	\$8,204
Capital Cost Totals	\$83,005	\$348,026
Capital Cost/Acre	\$4,150	\$12,890

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	65 / 35	100 / 0
Revegetation Area %	65	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

East Pit Access

Function	Rock stockpile, serves as access to southeastern portion of the open pit
Location Characteristics	East of Upper South stockpile Runon from hillslopes Reservoir 9A to the southwest No downstream issues Regional depth to groundwater is greater than 75 feet, direction of flow is to the Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End-dump
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Runon controls, berming on top surface

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	45	45
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$67,140	\$691,409
Outslope Adjustment	N/A	\$0
Divots, Seed & Mulch	\$6,223	\$55,437
Channels, Conduits & Berms	\$17,764	\$8,204
Capital Cost Totals	\$91,127	\$755,050
Cost/Acre	\$2,025	\$16,779

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	11 / 89	100 / 0
Revegetation Area %	11	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

Main Lampbright Stockpile

Function	Ore stockpile
Location Characteristics	East of Main Pit North Diversion Channel to the north Pre-existing downstream drainage into Lampbright Draw Regional depth to groundwater is less than 5 feet to greater than 100 feet, direction of flow is to Lampbright Draw and Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped Top surface bermed for leaching
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Leach
Existing Engineering Measures	PLS and stormwater collection system, toe control systems, North Diversion Channel All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	352	452
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$2,300,581	\$7,052,695
Outslope Adjustment	N/A	\$18,490,385
Divot, Seed & Mulch	\$213,232	\$557,599
Channels, Conduits & Berms	\$282,861	\$525,379
Capital Cost Totals	\$421,855	\$26,626,058
Capital Cost/Acre	\$7,945	\$58,907

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	49 / 51	100 / 0
Revegetation Area %	49	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

South Lampbright Stockpile

Function	Ore stockpile
Location Characteristics	Southern extension of Main Lampbright stockpile No upstream issues Pre-existing downstream drainage into Lampbright Draw Regional depth to groundwater is less than 5 feet to greater than 100 feet, direction of flow is to Lampbright Draw and Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped Top surface bermed for leaching
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Leach
Existing Engineering Measures	PLS and stormwater collection system, toe control systems All top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	202	219
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$1,258,276	\$4,102,051
Outslope Adjustment	N/A	\$16,726,077
Divots, Seed & Mulch	\$116,625	\$328,967
Channels, Conduits & Berms	\$166,579	\$389,014
Capital Cost Totals	\$1,541,479	\$21,546,109
Capital Cost/Acre	\$7,631	\$98,384

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	46 / 54	100 / 0
Revegetation Area %	46	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

North Lampbright Stockpile

Function	Ore stockpile
Location Characteristics	Northern extension of Main Lampbright stockpile No upstream issues Downstream drainage into Lampbright Draw Regional depth to groundwater is less than 5 feet to greater than 100 feet, direction of flow is to Lampbright Draw and Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Leach
Existing Engineering Measures	PLS and stormwater collection system, toe control systems Interceptor wells, all top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	172	239
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$2,364,995	\$3,731,794
Outslope Adjustment	N/A	\$1,674,877
Divots, Seed & Mulch	\$219,202	\$268,808
Channels, Conduits & Berms	\$187,605	\$258,830
Capital Cost Totals	\$2,771,802	\$5,934,309
Capital Cost/Acre	\$16,115	\$24,830

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	87 / 13	100 / 0
Revegetation Area %	87	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

Southwest Lampbright Stockpile

Function	Rock stockpile
Location Characteristics	Southwest of Main Lampbright stockpile Runon from hillside to the west Pre-existing downstream drainage into Lampbright Draw (Tributary 1) Regional depth to groundwater is less than 5 feet to greater than 100 feet, direction of flow is to Lampbright Draw Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Non-leach
Existing Engineering Measures	Bermed, graded, and watered for dust control

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	99	112
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$347,615	\$1,154,198
Outslope Adjustment	N/A	\$4,385,942
Divots, Seed & Mulch	\$49,665	\$162,910
Channels, Conduits & Berms	\$74,938	\$30,709
Capital Cost Totals	\$472,218	\$5,733,759
Capital Cost/Acre	\$4,770	\$51,194

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	33 / 67	100 / 0
Revegetation Area %	33	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

Groundhog No. 5 Stockpile

Function	Rock stockpile
Location Characteristics	South facing slope in Lucky Bill Canyon No upstream issues No downstream issues In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Fine to coarse grained
Leach Status	Non-leach
Existing Engineering Measures	None

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	2	2
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$13,428	\$32,939
Outslope Adjustment	N/A	\$29,980
Divots, Seed & Mulch	\$1,245	\$2,464
Channels, Conduits & Berms	\$1,279	\$1,641
Capital Cost Totals	\$15,951	\$67,023
Capital Cost/Acre	\$7,976	\$33,512

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	100 / 0	100 / 0
Revegetation Area %	100	100
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

West Stockpile

Function	Ore stockpile
Location Characteristics	West of Main Pit No upstream issues Pre-existing downstream drainage into Hanover and former Santa Rita Creeks Regional depth to groundwater is less than 75 feet, direction of flow is to Hanover Creek and Main Pit Medium upwind fetch, medium downwind fetch In Mimbres Basin drainage
Construction Method	End dumped
Physical Characteristics	Range in size from very fine (silt and clay) to very large boulders High saturated hydraulic conductivity
Leach Status	Eastern portion leach, western portion non-leach
Existing Engineering Measures	PLS and stormwater collection system, toe control systems Interceptor wells, all top surfaces bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	531	621
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	\$1,732,866	\$7,211,266
Outslope Adjustment	N/A	\$22,700,395
Divots, Seed & Mulch	\$175,202	\$638,214
Channels, Conduits & Berms	\$275,047	\$700,786
Capital Cost Totals	\$2,183,114	\$31,250,661
Capital Cost/Acre	\$4,111	\$49,526

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	Yes	Yes
Topography (% sim. to surrounding/% modified)	27 / 73	87 / 13
Revegetation Area %	27	87
Cover Material (Gila Cong. or Rhyolite)	Rhyolite	Rhyolite

**Chino Closure/Closeout
Facility Characteristics Form**

Santa Rita Open Pit

Function	Mined pit
Location Characteristics	No upstream issues No downstream issues Main pit dewatering capture zone controls regional groundwater level and flow direction In Mimbres Basin drainage
Construction Method	Blasting, shoveling, and hauling rock in 50 foot benches
Physical Characteristics	Solid, intrusive, and skarn rocks with low primary permeability and medium fracture permeability
Leach Status	Not applicable
Existing Engineering Measures	Pit dewatering contains regional groundwater, toe control systems All perimeter runoff bermed

**Matrix of Costs
Capital Cost/Facility**

	<u>Proposed Plan</u>	<u>Comparison Case</u>
Acres	1,894	1,894
<u>Item</u>	<u>Capital Cost</u>	<u>Capital Cost</u>
Cover Material	N/A	N/A
Outslope Adjustment	N/A	N/A
Divots, Seed & Mulch	N/A	N/A
Channels, Conduits & Berms	\$421,855	\$417,544
Capital Cost Totals	\$421,855	\$417,559
Capital Cost/Acre	\$223	\$220

Matrix of Technical Parameters

	<u>Proposed Plan Compliance</u>	<u>Comparison Case Compliance</u>
Structurally Stable (Yes or No)	Yes	Yes
Erosion Cover Sufficient (Yes or No)	N/A	N/A
Topography (% sim. to surrounding/% modified)	0 / 100	0 / 100
Revegetation Area %	N/A	N/A
Cover Material (Gila Cong. or Rhyolite)	N/A	N/A

CHINO CLOSURE/CLOSEOUT

APPENDIX D

BIBLIOGRAPHY

1. State of New Mexico Letters

- MMD *Borrow Materials Investigation Work Plan for the Chino Mine Closeout Plan*. April 30, 1998.
- MMD Preliminary Open Pit and Stockpile Waiver Justification: Santa Rita Pit, Tasks 1 and 2, Chino Mine, Permit No. GR009RE, dated April 8, 1999
- MMD Comments on the Borrow Materials Investigation and Soil Suitability Assessment, Chino Mine, Permit No. GR009RE, dated May 18, 1999
- MMD Alternative Analysis Related to Closeout Plans for the Chino, Tyrone, and Continental Mines, Permit Nos. GR009RE, GR010RE, GR002RE, dated August 5, 1999
- MMD Stockpile Outslope Evaluation, Phelps Dodge Mining Company (Permit Nos. GR010RE, GR009RE, GR002RE), dated October 15, 1999
- MMD Cover Design Study Status Report, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated November 4, 1999
- NMED Letter to Mr. Dennis Bartlett, President, Chino Mines Company, regarding Discharge plan renewal and modification, DP-526, Chino Mines Company Whitewater Leach System. April 3, 1998.
- NMED Letter from Ms. Marcie Leavitt to Mr. Dennis Bartlett, President, Chino Mines Company, regarding Discharge plan amendment approval. July 9, 1998.
- NMED Chino Screening-Level Overtopping Study dated January 31, 1999; Chino Tailing Pond Surface Water Study Closure/Closeout Plan dated March 31, 1999, dated February 17, 2000
- NMED Incomplete Submittal: February 4, 2000 Stockpile Outslope Evaluation Submittal for the Chino, Tyrone, and Continental Mines, dated February 22, 2000
- MMD Request for Information, Conceptual Tailing Pond Surface Water Study, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated March 24, 2000
- MMD Request for Information, Slope Stability Analysis, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated April 10, 2000
- MMD Request for Information, Interim Technical Standards for Revegetation Success, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated May 8, 2000
- MMD Request for Information, Upper Whitewater Creek Diversion Project, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated August 28, 2000
- NMED Response to the Design Comparison Workplans, for Chino Mines Company, Phelps Dodge Tyrone, Inc., and Cobre Mining Company, dated September 20, 2000
- MMD Request for Information, Design Comparison Work Plans, Chino Mine, Tyrone Mine, and Continental Mine, Phelps Dodge Mining Company (Permit Nos. GR009RE, GR010RE, GR002RE), dated November 22, 2000
- MMD Site Investigation Report, Groundhog Mine Stockpile, Chino Mine, Chino Mines Company (Permit No. GR009RE), dated January 3, 2001

- NMED Northern Area Groundwater Flow Model and the Long-Term Post-Mining Pit Lake Water Quality for the Santa Rita Pit, Chino Mines, dated February 2, 2001
 - MMD Status Update on Chino Mine Documents, Chino Mines Company (Permit No. GR009RE), dated February 20, 2001
2. Bates, R.L. and J.A. Jackson, editors. 1987. *Glossary of Geology*. Third edition. American Geological Institute, Alexandria, Virginia. 571p.
 3. Chino. 1995. *Administrative Order on Consent, Investigation Area Remedial Investigation Background Report, Chino Mine Investigation Area*. Prepared for New Mexico Environmental Department. October 5, 1995.
 4. Chino. 1997a. *Chino Mines Company Plan of Operations (post 1998) and Proposal to Acquire Selected Federal Lands by Exchange*. Prepared for United States Department of the Interior, Bureau of Land Management, Las Cruces District Office, Mimbres Resource Area. May 1997.
 5. Chino. 1998a. *Revised Draft Emergency Response Plan, Lampbright Leach System (DP-376)*. April 1998.
 6. Chino. 1998b. *Comprehensive Groundwater Characterization Study, Phase 2 Report, Chino Mines Company, Hurley, New Mexico*. Prepared for the New Mexico Environment Department, Santa Fe, New Mexico. August 29, 1998. (Appendix G)
 7. Chino. 1998c. *Work Plan for Precipitation Plant Decommissioning, Discharge Plan DP-526*. Submitted to New Mexico Environment Department. October 1, 1998.
 8. Chino. 1998d. *Work Plan for Groundwater Flow Determination, South Stockpile*. Submitted to New Mexico Environment Department. June 1, 1998.
 9. Chino. 1998e. *Proposed Work Plan: Further Materials Characterization and Stockpile Seepage Study*. Prepared for New Mexico Energy, Minerals and Natural Resources Department Mining and Minerals Division and New Mexico Environment Department. October 23, 1998.
 10. Chino. *Borrow Materials Investigation – Chino Mine and Mill*. November 17, 1998.
 11. Chino. *Work Plan Cover Design Study*. August 3, 1998. (Appendix E)
 12. Chino. *Work Plan to Assess Slope Stability at Closure for Stockpiles and Tailing Impoundments*. August 3, 1998. (Appendix F)
 13. Chino. *Chino Mine Stockpile Outslope Evaluation, Final Work Plan*. February 12, 2001. (Appendix G)
 14. Chino. *Environmental Closure of Blackhawk Tailing Piles*. November 11, 1994. (Appendix H)

15. Chino. *Screening – Level Overtopping Study*. January 31, 1999. (Appendix H)
16. Chino. *Proposed Work Plan for Stockpile Outslope Evaluation*. April 16, 1999.
17. Chino. *Open Pit Study Work Plan*. September 28, 1998. (Appendix J)
18. Chino. *Work Plan for Pit Waiver Justification – Santa Rita Open Pit*. September 18, 1998. (Appendix J)
19. Chino. *Prior Reclamation at Groundhog Mine*. September 29, 1995. (Appendix K)
20. Chino. *Revised Work Plan – Lake One Closure Project*. October 23, 1998. (Appendix K)
21. Chino. *Upper Whitewater Creek Diversion Berm Design*. March 10, 1999. (Appendix K)
22. Dames & Moore. 1983. *Groundwater Monitoring Study, Chino Mill near Hurley, New Mexico*. Prepared for Kennecott Minerals Company. January 19, 1983.
23. Dames & Moore. 1997. *Monitor Well Installation and Groundwater Sampling, Reservoir 17 Design, Chino Mines Company*. September 5, 1997.
24. DBS&A. 1996a. *Existing Data Report, Chino Mine Tailing Ponds*. Prepared for Chino Mines Company, Hurley, New Mexico. February 9, 1996. (Appendix H)
25. DBS&A. 1996b. *Scoping Investigation Data Report, Chino Mines Company Tailing Source Areas*. Prepared for Chino Mines Company, Hurley, New Mexico. February 9, 1996.
26. DBS&A. 1998a. *Phase 2 CGCS Comparison of Groundwater Data Along Hanover Creek*. Prepared for Chino Mines Company, Hurley, New Mexico. October 16, 1998.
27. DBS&A. 1998c. *Preliminary Open Pit and Stockpile Waiver Justification: Santa Rita Pit, Task 1: Technical and Economic Feasibility and Environmental Unsoundness*. Submitted to Chino Mines Company, Hurley, New Mexico. November 25, 1998.
28. DBS&A. *Borrow Materials Investigation and Soil Suitability Assessment – Chino Mines Co.* November 12, 1998. (Appendix E)
29. DBS&A. *Borrow Materials Investigation Work Plan – Chino Mine Closure/Closeout*. March 31, 1998. (Appendix E)
30. DBS&A. *Closure/Closeout Plan – Chino Mine*. December 19, 1997.
31. DBS&A. *Cover Design Study Status Report – Chino Mine*. March 15, 1999. (Appendix E)
32. DBS&A. *Interim Technical Standards for Revegetation Success – Chino Mines Company*. November 30, 1999. (Appendix E)

33. DBS&A. *Preliminary Geochemical Transport Modeling of Selected Constituents in Tailing Pore Water – Chino Mines Co. – Older Tailing Source Areas*. January 31, 1997. (Appendix G)
34. DBS&A. *Preliminary Open Pit and Stockpile Waiver Justification: Santa Rita Pit*. November 30, 1998. (Appendix J)
35. DBS&A. *Preliminary Open Pit and Stockpile Waiver Justification: Santa Rita Pit – Task 2: Evaluation of Measure to Meet Applicable Regulations and Standards*. January 31, 1999. (Appendix J)
36. DBS&A. *Preliminary Stockpile Seepage Study – Chino Mine*. July 30, 1999. (Appendix G)
37. DBS&A. *Revised Closure/Closeout Plan – Chino Mine*. January 31, 1999.
38. DBS&A. *Stockpile Outslope Evaluation Work Plan – Mass Loading Model for the Chino Mine*. February 8, 2001. (Appendix G)
39. DBS&A. *Supplemental Treatment Information – Pit Waiver Justification*. March 24, 1999. (Appendix J)
40. DBS&A. *Phase I Investigation – Chino Mines Company – Older Tailing Source Areas*. June 12, 1997. (Appendix H)
41. DBS&A. *Stockpile Outslope Evaluation: Mass Loading Modeling Results for the Chino Mine*. March 2, 2001. (Appendix G)
42. Dick-Peddie, W.A. 1993. *New Mexico Vegetation, Past, Present, and Future*. University of New Mexico Press, Albuquerque, New Mexico. 244 pp.
43. Engineering-Environmental Management, Inc. (e²m). 1997. *Draft Ecological Baseline Survey Report at Chino Mines, Hurley, New Mexico*. Prepared for Chino Mines Company, Hurley, New Mexico. November 1997.
44. Finch, S.T., M.S., and J.W. Shomaker. 1998. *Performance Evaluation of Tailings Pond 7 Interceptor Wellfield (DP-484) and Recommendations for Improved Seepage Capture*. Prepared for Chino Mines Company Environmental Services Division, Hurley, New Mexico. John Shomaker & Associates, Inc., Albuquerque, New Mexico. June 1998.
45. GAI. 1994. *Report to Chino Mines Company on Mining Operation Site Assessment for the Chino Mine*. June 30, 1994.
46. GAI. 1995. *Interim Data Report to Chino Mines Company for Hydrogeologic Investigation of Lower Whitewater Creek*. Prepared for Chino Mines Company, Hurley, New Mexico. February 13, 1995.

47. GAI. 1996a. *Baseline EIS Monitor Well Data*. Letter report to Jodi Woods and Ned Hall of Chino Mines Company. December 12, 1996.
48. GAI. 1996b. *Environmental Assessment for the Chino Mines Company, South Mine Area Development Project, Grant County, New Mexico*.
49. GAI. 1996c. *Final Biological Assessment for the Chino Mines Company, South Mine Area Development Project, Grant County, New Mexico*.
50. GAI. 1997a. *Draft, An Assessment of Vegetation Communities in the Chino Mines Proposed Action Area*. Submitted to Chino Mines Company, Hurley, New Mexico.
51. GAI. 1997b. *Draft, An Assessment of Wildlife Communities in the Chino Mines Proposed Action Area*. Submitted to Chino Mines Company, Hurley, New Mexico.
52. GAI. 1997c. *DP-526 Remedial Hydrology Investigation, Volume I: Hydrogeology and Engineering Design*. Prepared for Chino Mines Company, Hurley, New Mexico.
53. GAI. 1997d. *Report to Chino Mines Company on DP-526 Remedial Hydrogeologic Investigations. Volume 1: Field Investigations and Remedial Design*. July 24, 1997.
54. GAI. 1997e. *Chino Mines Company, Santa Rita Mine Expansion, Groundwater and Surface Water Characterization, Phase II, Existing Groundwater Conditions in the EIS Expansion Area*. Prepared for Chino Mines Company, Hurley, New Mexico. September 17, 1997.
55. GAI. 1998a. *Waste Rock Characterization, Chino Mine*. Prepared for Chino Mines Company, Hurley, New Mexico. August 10, 1998. (Appendix I)
56. GAI. 1998b. *Draft Sampling and Analysis Plan for Collection of Waste Rock Samples in Support of the Lampbright Waste Rock Characterization Effort DP-376 Renewal*. October 1, 1998
57. GAI. *Comprehensive Groundwater Characterization Study – Phase 3 Report, Volumes 1 & 2 – Chino Mines Company*. January 1999. (Appendix G)
58. GAI. *Conceptual Tailing Pond Surface Water Study – Chino Mine*. July 2000. (Appendix H)
59. GAI. *Review of Coupled Hydrologic and Geochemical Processes in Mining Wastes and Other Highly Heterogeneous Media*. December 18, 2000. (Appendix G)
60. GAI. *Stockpile Characterization – Chino Mines Company*. May 25, 1999. (Appendix I)
61. GAI. *An Assessment of Soil in the Chino Mine Proposed Action Area*. 1998. (Appendix E)
62. GAI. *Slope Stability Analysis – Chino Mines Company*. January 29, 1999. (Appendix ?)

63. GAI. *Slope Stability Analysis for Tailings and Stockpiles*. March 2001. (Appendix F)
64. Hargis + Associates. 1986. Chino pit hydrogeology. In Call and Nichols, *Chino Slope Design Study, Phase 1: North Pit Final Recommendations, Lee Hill Preliminary Recommendations*. Prepared for Chino Mines Company, Hurley, New Mexico.
65. HCI. *Northern Area Groundwater Flow Model Report*. June 1, 2000.
66. HCI. *Questions and Initial Comments Related to Review of Report – Long-Term Post-Mining Pit Lake Water Quality – Santa Rita Pit*. April 26, 2000.
67. HCI. *Third Party Review of Hydrogeologic Characterization, Ground Water Flow Model and Predictions of Pit Lake Chemistry of Chino Mining Company's Santa Rita Pit*. November 2000.
68. Hernon, R.M., and W.R. Jones. 1968. Ore deposits of the Central Mining District, Grant County, New Mexico. pp. 1211-1238. In Ridge, J.D. (ed.), *Ore Deposits of the United States. 1933-1967*. The American Institute of Mining, Metallurgical, and Petroleum Engineers, Inc., New York.
69. John Shomaker & Associates, Inc. (JS&A). 1996. *Chino Mines Company Tailings Pond 7 (DP-484) Performance Assessment of Interceptor Wellfield*. Prepared for Chino Mines Company, Hurley, New Mexico. October 1996.
70. Lasky, Samuel G. 1936. *Geology and Ore Deposits of the Bayard Area, Central Mining District, New Mexico*. Bulletin 870, United States Department of the Interior, Geological Survey.
71. M3 Engineering & Technology Corporation. *RUSLE Erosion Calculations for Rhyolite and Gila Conglomerate Cover*. March 15, 2001. (Appendix E)
72. MMD. 1996a. *Closeout Plan Guidelines for Existing Mines*. Mining Act Reclamation Bureau, Santa Fe, New Mexico. April 30, 1996.
73. MMD. 1996b. *New Mexico Mining Act Rules*. Mining Act Reclamation Bureau, Santa Fe, New Mexico. February 15, 1996.
74. New Mexico (See Reference 1 for State of New Mexico letters)
75. New Mexico Water Quality Control Commission (NMWQCC). 1996. *New Mexico Water Quality Control Commission Regulations*. November 15, 1996.
76. O'Kane Consultants. *Final Report – Third Party Review of Cover Design Study Status Reports for Three Phelps Dodge Mines in New Mexico (Tyrone, Cobre/Continental, and Chino)*. January 2001.
77. O'Kane Consultants. *Third Party Review of Cover Design Status Report for Three Phelps Dodge Mines in New Mexico*. June 11, 2000.

78. O'Kane Consultants. *Third Party Review of Outslope Model Work Scope*. November 15, 2000.
79. Parham, T.L., R. Paetzold, and G.E. Souders. 1983. *Soil Survey of Grant County, New Mexico, Central and Southern Parts*. United States Department of Agriculture, Soil Conservation Service. 216p.
80. Rose, A.W., and W.W. Baltosser. 1966. The porphyry copper deposit at Santa Rita, New Mexico. pp. 205-220. In Titley, S.R., and G.L. Hidks (ed.), *Geology of the Porphyry Copper Deposits in Southwestern North America*. University of Arizona Press, Tucson, Arizona.
81. Skaggs, R.W. 1997. *Draft, Results of Raptor Surveys in the Vicinity of Santa Rita Pit, Spring and Summer 1997*.
82. SRK. *Conceptual Water Treatment Design, Closure/Closeout Plan, Chino Mines Company*. March 5, 2001. (Appendix G)
83. Trauger, F.D. 1972. *Water Resources and General Geology of Grant County New Mexico*. New Mexico State Bureau of Mines and Mineral Resources Hydrologic Report 2, 211p.
84. WCC. 1987. *Geotechnical and Hydrological Services, Tailing Pond No. 7, Chino Mines Company, Hurley, New Mexico*. Prepared for Chino Mines Company, Hurley, New Mexico. August 1987.
85. WCC. 1991. *Design Report, Tailing Pond No. 7, Groundwater Interceptor Well System, Hurley, New Mexico*. Prepared for Chino Mines Company, Hurley, New Mexico. December 1991.
86. WCC. 1992a. *Geophysical Study, Tailing Pond No. 7, Chino Mines, Hurley, New Mexico*. Prepared for Chino Mines Company, Hurley, New Mexico. September 1992.
87. WCC. 1992b. *Seismic Stability Evaluation and Piezometer Installation, Tailing Pond No. 7*. Prepared for Chino Mines Company, Hurley, New Mexico. March 1992.
88. WCC. 1996. *Phase III Hydrogeologic Evaluation of the Lampbright Leach Stockpile Area*. February 1996.
89. WCC. 1997a. *Closure Study for Chino Mine Stockpiles, Draft Report*. Prepared for Chino Mines Company, Hurley, New Mexico. August 1997.
90. WCC. 1997b. *Comprehensive Groundwater Characterization Study, Phase 1*. Prepared for Chino Mines Company, Hurley, New Mexico. April 1, 1997.
91. WCC. 1998a. *Hanover/Whitewater Creek Remedial Investigation, Data Quality Assessment Report for Groundhog Groundwater Samples*. Prepared for Chino Mines Company, Hurley, New Mexico. July 14, 1998.

92. WCC. *Long-Term Post-Mining Pit Lake Water Quality, Santa Rita Pit, Volumes 1 & 2 – Chino Mines Company*. May 7, 1999. (Appendix G)
93. WCC. *Northern Area Groundwater Flow Model – Chino Mines Company*. February 6, 1998. (Appendix G)

CHINO CLOSURE/CLOSEOUT APPENDIX E

REPORTS ON BORROW MATERIAL AND COVER DESIGN

Chino Mines Company. *Work Plan Cover Design Study*. August 3, 1998.

Daniel B. Stephens & Associates. *Borrow Materials Investigation Work Plan – Chino Mine Closure/Closeout*. March 31, 1998.

Daniel B. Stephens & Associates. *Borrow Materials Investigation and Soil Suitability Assessment – Chino Mines Company*. November 12, 1998.

Daniel B. Stephens & Associates. *Cover Design Study Status Report – Chino Mine*. March 15, 1999.

Daniel B. Stephens & Associates. *Interim Technical Standards for Revegetation Success – Chino Mines Company*. November 30, 1999.

Golder Associates, Inc. *An Assessment of Soil in the Chino Mine Proposed Action Area*. 1998.

M3 Engineering & Technology Corporation. *RUSLE Erosion Calculations for Rhyolite and Gila Conglomerate Cover*. March 15, 2001.

CHINO CLOSURE/CLOSEOUT APPENDIX F

REPORTS ON STRUCTURAL STABILITY

Chino Mines Company. *Work Plan to Assess Slope Stability at Closure for Stockpiles and Tailing Impoundments*. August 3, 1998.

Golder Associates, Inc. *Closure/Closeout Plan Addendum – Slope Stability Analysis – Chino Mines Company*. January 29, 1999.

Golder Associates, Inc. *Summary of Long-Term Stability Analyses for Stockpiles and Tailing Ponds at the Chino Mine*. March 8, 2001.

CHINO CLOSURE/CLOSEOUT APPENDIX G

REPORTS ON WATER ISSUES

Chino Mines Company. *Comprehensive Groundwater Characterization Study – Phase 2 Report – Chino Mines Company.* August 29, 1998.

Chino Mines Company. *Chino Mine Stockpile Outslope Evaluation, Final Work Plan.* February 12, 2001.

Daniel B. Stephens & Associates. *Preliminary Geochemical Transport Modeling of Selected Constituents in Tailing Pore Water – Chino Mines Company – Older Tailing Source Areas.* January 31, 1997.

Daniel B. Stephens & Associates. *Preliminary Stockpile Seepage Study – Chino Mine.* July 30, 1999.

Daniel B. Stephens & Associates. *Stockpile Outslope Evaluation Work Plan – Mass Loading Model for the Chino Mine.* February 9, 2001.

Daniel B. Stephens & Associates. *Stockpile Outslope Evaluation Mass Loading Modeling Results for the Chino Mine.* March 2, 2001.

Golder Associates, Inc. *Comprehensive Groundwater Characterization Study – Phase 3 Report, Volumes 1 & 2 – Chino Mines Company.* January 1999.

Golder Associates, Inc. *Review of Coupled Hydrologic and Geochemical Processes in Mining Wastes and Other Highly Heterogeneous Media.* December 18, 2000.

SRK. *Conceptual Water Treatment Design, Closure/Closeout Plan, Chino Mines Company.* March 5, 2001.

Woodward-Clyde Consultants. *Long-Term Post-Mining Pit Lake Water Quality, Santa Rita Pit, Volumes 1 & 2 – Chino Mines Company.* May 7, 1999.

Woodward-Clyde Consultants. *Northern Area Groundwater Flow Model – Chino Mines Company.* February 6, 1998.

CHINO CLOSURE/CLOSEOUT APPENDIX H

REPORTS ON TAILING PONDS

Chino Mines Company. *Environmental Closure of Blackhawk Tailing Piles*. November 11, 1994.

Chino Mines Company. *Screening – Level Overtopping Study*. January 31, 1999.

Daniel B. Stephens & Associates. *Existing Data Report – Chino Mine Tailing Ponds*. February 9, 1996.

Daniel B. Stephens & Associates. *Phase 1 Investigation – Chino Mines Company – Older Tailing Source Areas*. June 12, 1997.

Daniel B. Stephens & Associates. *Chino Mines Company Landfarm Closure Plan, DP-214*. January 31, 1999.

Golder Associates, Inc. *Conceptual Tailing Pond Surface Water Study – Chino Mine*. July 2000.

CHINO CLOSURE/CLOSEOUT APPENDIX I

REPORTS ON STOCKPILES

Golder Associates, Inc. *Waste Rock Characterization – Chino Mine.* August 10, 1998.

Golder Associates, Inc. *Stockpile Characterization – Chino Mines Company.* May 25, 1999.

CHINO CLOSURE/CLOSEOUT APPENDIX J

REPORTS ON MINE PITS

Chino Mines Company. *Work Plan for Pit Waiver Justification – Santa Rita Open Pit.* September 18, 1998.

Chino Mines Company. *Open Pit Study Work Plan.* September 28, 1998.

Daniel B. Stephens & Associates. *Preliminary Open Pit and Stockpile Waiver Justification: Santa Rita Pit.* November 30, 1998.

Daniel B. Stephens & Associates. *Preliminary Open Pit and Stockpile Waiver Justification, Santa Rita Pit – Task 2: Evaluation of Measures to Meet Applicable Regulations and Standards.* January 31, 1999.

Daniel B. Stephens & Associates. *Supplemental Treatment Information – Pit Waiver Justification.* March 24, 1999.

CHINO CLOSURE/CLOSEOUT APPENDIX K

REPORTS ON RESERVOIRS AND MISCELLANEOUS DISTURBED AREAS

Chino Mines Company. *Prior Reclamation at Groundhog Mine.* September 29, 1995.

Chino Mines Company. *Revised Work Plan – Lake One Closure Project.* October 23, 1998.

Chino Mines Company. *Upper Whitewater Creek Diversion Berm Design.* March 10, 1999.