

**From:** [Gray, David](#)  
**To:** [Curry, Ron](#); [Coleman, Sam](#); [Edlund, Carl](#); [Miller, Gary](#); [Banipal, Ben](#); [Peycke, Mark](#); [Meyer, John](#); [Phillips, Pam](#)  
**Subject:** San Jacinto Update 12/23  
**Date:** Wednesday, December 23, 2015 11:25:11 AM  
**Attachments:** [Draft Work Plan for Additional Rock Placement 12172015REV-2 NoP&C.PDF](#)  
[SJRWPs Cap Repair Approval with Mods 12-22-2015.pdf](#)

---

**Here is today's final update that has been shared publicly.**

**David**

I wanted to send you an update regarding San Jacinto River Waste Pits Superfund site in Harris County, Texas.

Today under the direction of EPA, the PRPs' will begin to delineate the repair area of the cap at San Jacinto River Waste Pits Superfund site in Harris County, Texas. Beginning measurements will be taken at approximately 5-foot intervals along the cap and as directed by EPA to determine locations needing repairs and then more exact measurements will be taken. The PRPs will collect sediment sampling from the repair area to assure EPA that no materials have been released from the site. EPA will also be conducting confirmation sampling of the area for analysis at an independent EPA approved laboratory. Quality assured sample results will be available to the public in about 60 days.

Last night, EPA approved with modifications the portion of the PRPs' work plan regarding the necessary repairs. A copy of the PRPs' work plan and EPA's modifications are attached. As reported earlier, equipment and materials to repair the cap are expected to arrive on December 29 and will take from 1 to 2 weeks to complete.

EPA will remain on-site during the assessment and repair activities to ensure compliance with the approved work plan.

David



9752344