

From: [Moore, Gary](#)
To: [Dorene Hancock](#)
Cc: [Steve Dicker](#); [Donald Richner](#)
Subject: CES: Drain Pipe Installation
Date: Thursday, April 30, 2015 6:53:00 AM

Dorene

EPA will be installing 2 - 4 inch drain pipes on the southwest side of the site to allow Stormwater to drain as it originally did. The pipes will have ball valves to shut off flow if necessary. Additionally, silt fencing, hay bales, absorbent boom, and perforated pipe with silt covering will also be incorporated.

This system will be used as the ponded area fills up due to rainfall.

If you have question, please call.

Thanks
Gary Moore
2147891627

Sent from my iPhone