FRIEDMAN & BRUYA, INC.

ENVIRONMENTAL CHEMISTS

Analysis For Total Metals By EPA Method 200.8

Client ID:	M119668	Client:	Alaskan Copper Works
Date Received:	05/29/08	Project:	Metro KC Composite, PO M119668
Date Extracted:	05/29/08	Lab ID:	805311-01 x10
Date Analyzed:	05/30/08	Data File:	805311-01 x10.016
Matrix:	Water	Instrument:	ICPMS1
Units:	ug/L (ppb)	Operator:	hr

Internal Standard:	% Recovery:	Lower Limit:	Upper Limit:
Germanium	92	60	125

Analyte:	Concentration ug/L (ppb)
Chromium	489
Nickel	649
Copper	514
Zinc	<10

Analysis For Total Metals By EPA Method 200.8

Client ID:	Method Blank	Client:	Alaskan Copper Works
Date Received:	Not Applicable	Project:	Metro KC Composite, PO M119668
Date Extracted:	05/29/08	Lab ID:	I8-198 mb
Date Analyzed:	05/30/08	Data File:	I8-198 mb.075
Matrix:	Water	Instrument:	ICPMS1
Units:	ug/L (ppb)	Operator:	hr

Internal Standard:	% Recovery:	Lower Limit:	Upper Limit:
Germanium	94	60	125

Analyte:	Concentration ug/L (ppb)
Chromium	<1
Nickel	<1
Copper	<1
Zinc	<1

Date of Report: 06/04/08
Date Received: 05/29/08
Project: Metro KC Composite, PO M119668, F&BI 805311

QUALITY ASSURANCE RESULTS FOR THE ANALYSIS OF WATER SAMPLES FOR TOTAL METALS USING EPA METHOD 200.8

Laboratory Code: 805306-01 (Duplicate)

Analyte	Reporting Units	Sample Result	Duplicate Result	Relative Percent Difference	Acceptance Criteria
Chromium	ug/L (ppb)	1.23	1.25	2	0-20
Nickel	ug/L (ppb)	4.62	4.78	3	0-20
Copper	ug/L (ppb)	11.6	12.3	6	0-20
Zinc	ug/L (ppb)	24.1	23.5	3	0-20

Laboratory Code: Laboratory Control Sample

Analyte	Reporting Units	Spike Level	Percent Recovery LCS	Percent Recovery LCSD	Acceptance Criteria	RPD (Limit 20)
Chromium	ug/L (ppb)	20	102	104	70-130	2
Nickel	ug/L (ppb)	20	102	108	70-130	6
Copper	ug/L (ppb)	20	106	109	70-130	3
Zinc	ug/L (ppb)	50	85	85	70-130	0

Data Qualifiers & Definitions

a - The analyte was detected at a level less than five times the reporting limit. The RPD results may not provide reliable information on the variability of the analysis.

A1 – More than one compound of similar molecule structure was identified with equal probablility.

b - The analyte was spiked at a level that was less than five times that present in the sample. Matrix spike recoveries may not be meaningful.

ca - The calibration results for this range fell outside of acceptance criteria. The value reported is an estimate.

c - The presence of the analyte indicated may be due to carryover from previous sample injections.

d - The sample was diluted. Detection limits may be raised due to dilution.

ds - The sample was diluted. Detection limits are raised due to dilution and surrogate recoveries may not be meaningful.

dv - Insufficient sample was available to achieve normal reporting limits and limits are raised accordingly.

fb - The analyte indicated was found in the method blank. The result should be considered an estimate.

fc – The compound is a common laboratory and field contaminant.

hr - The sample and duplicate were reextracted and reanalyzed. RPD results were still outside of control limits. The variability is attributed to sample inhomogeneity.

ht - The sample was extracted outside of holding time. Results should be considered estimates.

ip - Recovery fell outside of normal control limits. Compounds in the sample matrix interfered with the quantitation of the analyte.

j – The result is below normal reporting limits. The value reported is an estimate.

J - The internal standard associated with the analyte is out of control limits. The reported concentration is an estimate.

jl - The analyte result in the laboratory control sample is out of control limits. The reported concentration should be considered an estimate.

jr - The rpd result in laboratory control sample associated with the analyte is out of control limits. The reported concentration should be considered an estimate.

js - The surrogate associated with the analyte is out of control limits. The reported concentration should be considered an estimate.

lc - The presence of the compound indicated is likely due to laboratory contamination.

L - The reported concentration was generated from a library search.

nm - The analyte was not detected in one or more of the duplicate analyses. Therefore, calculation of the RPD is not applicable.

pc – The sample was received in a container not approved by the method. The value reported should be considered an estimate.

pr – The sample was received with incorrect preservation. The value reported should be considered an estimate.

ve - The value reported exceeded the calibration range established for the analyte. The reported concentration should be considered an estimate.

vo - The value reported fell outside the control limits established for this analyte.

x - The pattern of peaks present is not indicative of diesel.

y - The pattern of peaks present is not indicative of motor oil.

FRIEDMAN & BRUYA, INC.

ENVIRONMENTAL CHEMISTS

James E. Bruya, Ph.D.
Charlene Morrow, M.S.
Yelena Aravkina, M.S.
Bradley T. Benson, B.S.
Kurt Johnson, B.S.

3012 16th Avenue West
Seattle, WA 98119-2029
TEL: (206) 285-8282
FAX: (206) 283-5044
e-mail: fbi@isomedia.com

June 4, 2008

DUPLICATE

INVOICE #08ACU0604-2

Accounts Payable
Alaskan Copper Works
628 South Hanford
Seattle, WA 98134

RE: Project Metro KC, PO M02443, F&BI 805295 - Results of testing requested by Gerry Thompson for material submitted on May 28, 2008.

1 sample analyzed for Total Chromium, Copper, Nickel and Zinc by Method 200.8 @ $85 per sample	$ 85.00
Rush Charges (48 hr) 75% of $85.00	63.75
Amount Due	$ 148.75

FEDERAL TAX ID # (b) (6)

FRIEDMAN & BRUYA, INC.

ENVIRONMENTAL CHEMISTS

James E. Bruya, Ph.D.
Charlene Morrow, M.S.
Yelena Aravkina, M.S.
Bradley T. Benson, B.S.
Kurt Johnson, B.S.

3012 16th Avenue West
Seattle, WA 98119-2029
TEL: (206) 285-8282
FAX: (206) 283-5044
e-mail: fbi@isomedia.com

June 4, 2008

DUPLICATE

INVOICE #08ACU0604-1

Accounts Payable
Alaskan Copper Works
628 South Hanford
Seattle, WA 98134

RE: Project Metro KC Composite, PO M119668, F&BI 805311 - Results of testing requested by Gerry Thompson for material submitted on May 29, 2008.

1 sample analyzed for Total Chromium, Copper, Nickel and Zinc by Method 200.8 @ $85 per sample	$ 85.00
Rush Charges (24 hr) 100% of $85.00	85.00
Amount Due	$ 170.00

FEDERAL TAX ID # (b) (6)

805311

SAMPLE CHAIN OF CUSTODY

ME 05/29/08

AI4

Send Report To Gerald Thompson

Company Alaskan Copper Works

Address 628 S. Hanford St

City, State, ZIP Seattle WA 98134

Phone # 206-571-6033 Fax # 206-382-4305

SAMPLERS (signature)

PROJECT NAME/NO.	PO #
metro KC Composite	m 119668

REMARKS

Page # _____ of _____

TURNAROUND TIME

☐ Standard (2 Weeks)

☒ RUSH ASAP

Rush charges authorized by:

SAMPLE DISPOSAL

☐ Dispose after 30 days

☐ Return samples

☐ Will call with instructions

Sample ID	Lab ID	Date	Time	Sample Type	# of containers	TPH-Diesel	TPH-Gasoline	BTEX by 8021B	VOCs by 8260	SVOCs by 8270	HFS	4 Cr, Cu, Pb, Zn				Notes
m119668	01	5/29	12:00	H2O	1							X				

Friedman & Bruya, Inc.
3012 16th Avenue West
Seattle, WA 98119-2029
Ph. (206) 285-8282
Fax (206) 283-5044

FORMS\COC\COC.DOC

	SIGNATURE	PRINT NAME	COMPANY	DATE	TIME
Relinquished by:		Gerald Thompson	ACW	5/29/08	3:08pm
Received by:		Phan Phan	FEBI	5/29/08	V
Relinquished by:					
Received by:					

Page 22 of

AKC-00062822

FRIEDMAN & BRUYA, INC.

ENVIRONMENTAL CHEMISTS

James E. Bruya, Ph.D.
Charlene Morrow, M.S.
Yelena Aravkina, M.S.
Bradley T. Benson, B.S.
Kurt Johnson, B.S.

3012 16th Avenue West
Seattle, WA 98119-2029
TEL: (206) 285-8282
FAX: (206) 283-5044
e-mail: fbi@isomedia.com

June 4, 2008

Gerry Thompson, Project Manager
Alaskan Copper Works
628 South Hanford
Seattle, WA 98134

Dear Mr. Thompson:

Included are the results from the testing of material submitted on May 29, 2008 from the Metro KC Composite, PO M119668, F&BI 805311 project. There are 4 pages included in this report. Any samples that may remain are currently scheduled for disposal in 30 days. If you would like us to return your samples or arrange for long term storage at our offices, please contact us as soon as possible.

We appreciate this opportunity to be of service to you and hope you will call if you should have any questions.

Sincerely,

FRIEDMAN & BRUYA, INC.

Michael Erdahl
Project Manager

Enclosures
ACU0604R.DOC