



SoundEarth Strategies, Inc.
2811 Fairview Avenue East, Suite 2000
Seattle, Washington 98102

JORGENSEN FORGE OUTFALL SITE CORRUGATED METAL PIPE WORK PLAN

THIRD MODIFICATION FOR THE ADMINISTRATIVE ORDER ON CONSENT FOR REMOVAL ACTION,
CERCLA DOCKET NO. 10-2011-0017



Property:

Jorgensen Forge Property
Jorgensen Forge Outfall Site
8531 East Marginal Way South
Seattle, Washington

Report Date:

Month Day 2015

Prepared for:

U.S. Environmental Protection Agency
Region 10
1200 Sixth Avenue
Seattle, Washington

**PRELIMINARY DRAFT FOR
DISCUSSION PURPOSES ONLY**



PRELIMINARY DRAFT FOR DISCUSSION PURPOSES ONLY

TABLE OF CONTENTS

ACRONYMS AND ABBREVIATIONS	ii
1.0 INTRODUCTION	1
2.0 PROJECT BACKGROUND	2
3.0 WORK COMPLETED UNDER THE ORDER AND ITS MODIFICATIONS.....	3
4.0 NATURE AND EXTENT OF CONTAMINATION	3
4.1 PCBS.....	4
4.2 OTHER COMPOUNDS.....	5
5.0 REMOVAL ACTION OBJECTIVES.....	5
5.1 SITE SECURITY.....	6
5.2 SURVEY DATUMS AND CONSTRUCTION LAYOUT.....	7
5.3 SHORED EXCAVATION	7
5.3.1 SSP Installation	7
5.3.2 Management of Water Levels.....	8
5.3.3 Management of Settleable Solids	9
5.3.4 Confirmation Sampling	9
5.4 UNSHORED EXCAVATION	11
5.4.1 Sloping of Excavation Sidewalls	11
5.4.2 Off-Site Excavation	11
5.4.3 Confirmation Sampling	11
5.5 POST-EXCAVATION SITE RESTORATION	13
5.6 DECONTAMINATION PROCEDURES.....	13
5.7 MANAGEMENT AND DISPOSAL OF LIQUID WASTES	14
5.8 MANAGEMENT AND DISPOSAL OF SOLID WASTES.....	14
6.0 PERFORMANCE CRITERIA	14
7.0 ANTICIPATED TIMELINE AND KEY MILESTONES	14
8.0 PROJECT ORGANIZATION	15
9.0 REFERENCES	16

PRELIMINARY DRAFT FOR DISCUSSION PURPOSES ONLY

TABLE OF CONTENTS (CONTINUED)

TABLES

FIGURES

- Physiographic Setting
- Boundary, Topography, and Site Features Map
- Map of Adjacent Removal Action Projects
- Total PCB Concentrations in Soil
- Construction Staging Areas and Traffic Routes
- Sheetpile Layout
- Limits of Excavation
- Cross-Sections
- Confirmation Sample Location Map

APPENDICES

Decontamination Procedures (*Attach EPA-reviewed Decontamination Plan and EPA comment letter*)

Health and Safety Plan (*Assumes that the existing, EPA-approved HASP attached to the BODR for JFOS Phase4B will be updated to reflect current scope of work*)

Quality Assurance Project Plan/ Sampling and Analysis Plan/Quality Management Plan (*Assumes that the existing, EPA-approved QAP/SAP/QMP attached to the BODR for JFOS Phase4B will be updated to reflect current scope of work*)