

Resol.
File No. *16877*

Before the
Board of County Commissioners
of King County, Washington

SUBJECT:

*appropriating an
additional sum -
Boeing Field Trust
Contract -*

ACTION:

Passed

Dec. 10, 1956

Ent. Com'rs. Record, Vol. *58* Page *101*

Eng²
and (3)
File

R E S O L U T I O N

NO. 16877

WHEREAS, on Sept. 10, 1956, the Board of County Commissioners passed Resolution No. 16682 approving COH 46 for SOIL CEMENT STABILIZATION WORK FOR BOEING FIELD DUST CONTROL, and appropriated the sum of \$5,200.00 for the completion thereof, and




WHEREAS, during construction it was deemed necessary and advisable to increase the cement content of the soil cement stabilization, at the approximate sum of \$5,937.20 as shown on attached estimate of cost, and

WHEREAS, an additional sum of \$737.20 is necessary to complete the above project, now, therefore

BE IT RESOLVED by the Board of County Commissioners that the additional sum of \$737.20 or so much thereof as may be necessary to complete the above work, be hereby appropriated from funds accruing to the credit of the King County Road Fund under Chapter 187, Laws of 1937 as amended.

BE IT FURTHER RESOLVED that upon exact determination of all costs the County Road Fund shall be reimbursed from King County Airport Funds.


PASSED this 10th day of December 1956.




BOARD OF COUNTY COMMISSIONERS
King County, Wash.

ATTEST:
ROBERT A. MORRIS
Clerk of the Board

By 
Deputy

RCB:fd
12/4/56



Office of
King County Engineer
State of Washington

Dec. 4, 1956


County Road Engineer

905 County-City Building
Seattle 4, Washington

Honorable Board of
County Commissioners
Seattle, Wash.

Gentlemen:

COH 46



We submit herewith for your approval resolution and revised estimate of cost on BOEING FIELD- RUNWAY DUST CONTROL.

Very truly yours,

D. L. EVANS
COUNTY ROAD ENGINEER

RCB:fd
Encls.

REVISED

Date Dec. 3, 1956

ESTIMATE OF COST

Project No......COH 46

Location Boeing Field - Runway Dust Control
Sec. 33 T. 24 N.R. 4 EWM

District No. 2
KING COUNTY WASHINGTON

APPROXIMATE LENGTH 100' x 200'

ESTIMATE DATE OF COMMENCING WORK In progress ESTIMATED DATE OF COMPLETING WORK 1 Mo

QUANTITY	UNIT	ITEM	UNIT COST	AMOUNT	DISTRIBUTION	AMOUNT
	Acres	Clearing			Labor	
	"	Grubbing			Material	
480	Cu. Yds.	Excav. Unclassified common	1.00	480 00	Provisions and Supplies	
	" "	Structure Excav.			Use of Equipment—Repair	
	" "	Class "D" Excav.			" " " Rental	
	" "	Surfacing			Equipment Purchase	
	Only	Pipe End Protection			Ind. Ins. and Medical Aid	
	Lin. Ft.	Pipe 12"			Superintendence	
	" "	" 18"			Right-of-Way	
	" "	" 24"			Location Engineering	
	" "	Guard Rail			Construction Engineering	
	Sta. Yds.	Overhaul				
	Lin. Ft. Rdy.	Finish Shoulders and Ditches				
	Lin. Ft.	Slope Treatment				
2,222	Sq. Yds.	Prepare & mix soil cement	0.50	1,111 00		
1,350	Sacks	Portland Cement in Pl.	1.50	2,025 00		
2,222	Sq. Yds.	Welded wire mesh	0.70	1,555 40		
6	Only	Concrete hand holes in pl.	35.00	210 00		
		County Subtotal		5,381 40		
		Right-of-Way				
		Locating overhead		255 80		
		Construction Engineering		300 00		
		COUNTY TOTALS		5,937 20		

BOARD OF COUNTY COMMISSIONERS

By Alfredo

Chairman

County Road Engineer

KCSlip4 52977

SEA419337