



88022924

NR

8238

G.1

FINAL REPORT  
FOUNDATION INVESTIGATIONS  
EAST MARGINAL WAY PUMP STATION (B2)  
SEATTLE, WASHINGTON

**METROPOLITAN ENGINEERS**  
410 West Harrison Street  
Seattle 99, Washington

November 9, 1962

Mr. Frank J. Kersnar  
Metropolitan Engineers  
410 West Harrison Street  
Seattle 99, Washington

**METRO LIBRARY**  
MUNICIPALITY OF METROPOLITAN SEATTLE  
821 SECOND AVENUE  
SEATTLE, WA 98104

W210B-19

**FINAL REPORT**  
**FOUNDATION INVESTIGATION**  
**EAST MARGINAL WAY PUMP STATION (B2)**  
**SEATTLE, WASHINGTON**

**INTRODUCTION**

This report summarizes the foundation recommendations made to our design engineers during the final design of the proposed pump station. The 32-foot O.D. structure will be located on the west side of East Marginal Way as shown on the Plot Plan, sheet 1. The ground floor is planned at elevation 114\* with the pump room floor at elevation 91 and a tremie seal extending to elevation 78. In addition, this facility includes about 30 feet of 60-inch influent sewer entering the station at elevation 93, three 24-inch effluent force mains at about elevation 109, and an effluent junction structure at roughly elevation 106. The existing ground surface varies from elevation 107 to elevation 113 and will require filling to about elevation 114.

**FIELD EXPLORATIONS AND LABORATORY TESTING**

The subsurface conditions were explored by the drilling of two test borings with cable-tool drilling equipment to depths of 59 feet and 65 feet at the locations shown on the Plot Plan. The soils encountered were logged by our soils engineer and representative undisturbed samples were secured for visual examination and laboratory testing. The soils encountered are shown graphically on the boring logs on sheet 3. Following the drilling of these borings, two well points were installed at selected elevations and the borings backfilled. Because of the proximity to the Duwamish River, water level readings in the well points were taken during a tidal cycle to observe the effect of tidal fluctuation upon the ground water. During this same period, the tidal fluctuation of the river level was also observed in nearby slip no. 4. This data is presented on sheet 4. Natural in-place densities and moisture contents of the representative samples were determined and the test results are shown at the left of the respective boring logs. In addition, selected samples were subjected to a consolidation test, sieve analyses, and strain-controlled direct shear tests. The test results for the consolidation test and sieve analyses are shown on sheets 5 through 7. The direct shear test results, run at a strain rate of .01 inch per minute, were as follows:

\*Elevation 100 = Mean Sea Level

Sample	Axial Test Surcharge (psf)	Shear Strength (psf)		
		Yield	Peak	Ultimate
B1 @ elev. 92	1400	350	850	850
B1 @ elev. 78	2500	700	1800	1700
B1 @ elev. 73	600	300	550	440

#### SUBSURFACE CONDITIONS

Our borings disclosed that about 8 feet of loose fine to medium sand blanketed the site. Approximately 7 to 15 feet of soft compressible laminated silt and sandy silt underlay the surface layer and was in turn underlain by 7 to 17 feet of permeable loose to medium dense fine to medium sand. Between roughly elevation 80 and elevation 55, 20 to 25 feet of moderately soft to moderately firm interbedded or laminated silty fine sand and sandy silt was encountered and was underlain by generally fine sand to the depths explored.

As shown by the ground water data plot on sheet 4, the ground water level fluctuates with the river level and was observed to vary from elevation 99 to elevation 102. The ground water low and high varied from the low and high tide by 3 feet and 2 feet, respectively, with a time lag of approximately 2 hours. Therefore, the ground water conditions during construction should be predictable on the basis of river and tide stages.

#### CONCLUSIONS AND RECOMMENDATIONS

On the basis of the subsurface conditions disclosed during this investigation, it is concluded that construction of the pump station is feasible at this location. Since the foundation loading of the completed station is approximately equal to the weight of the soils removed, special foundations are not necessary and the structure can be supported directly on the undisturbed underlying soils.

The caisson method of construction is recommended since it eliminates the need for a deep open excavation close to the railroad as well as the need for sustained dewatering which could cause settlement of adjacent utilities and structures. Further, the silty soils below elevation 80 would be difficult to dewater and would be easily disturbed if inadequately dewatered.

Compressible soils underlie the surface and some settlement will occur due to site filling. The amounts of settlement will vary with the method and sequence of construction of the various units. In order to minimize total and differential settlement, it is recommended that the caisson be sunk to final elevation, the tremie seal poured and the caisson dewatered prior to beginning other work. The 60-inch influent sewer should then be installed and backfilled - preferably without dewatering. After the construction of the influent sewer, the area fill can be placed and the effluent pipes and junction structure constructed.

Since the pump station walls are rigid, the at-rest soil pressure should be used for wall design. Further, because of the quick inter-relation between ground water level and river stage, it is recommended that a flood stage ground water level of elevation 110 be used. Estimates of lateral wall pressures for various conditions were made and are shown on sheet 2.

November 9, 1962

Jetting may not be necessary during the sinking of the caisson, however, provisions should be made for its use if required. It is important that the jets be directed upward in order to destroy the skin friction and yet prevent the disturbance of the supporting soils below the final elevation. Further, the water level inside the caisson should be maintained higher than the exterior ground water (with due allowance for tidal effect) prior to pouring the tremie seal. This will prevent the formation of "quick" or "boil" conditions in the supporting soils caused by upward seepage into the interior of the caisson. River water could be pumped into the caisson for this purpose.

The area filling will cause some settlement of the underlying softer soils. The major portion will occur in the layers above the base of the station. It is estimated that settlement of the station itself due to filling will not exceed about 1/4 inch at the influent side and 3/4 to one inch at the effluent side. Additional amounts of settlement would occur if the area fill were in place before the area was dewatered during construction of the 60-inch influent sewer. Therefore, the area filling should be deferred until the influent sewer is installed and backfilled.

Approximately 3 to 4 inches of settlement is expected to occur at the level of the effluent units due to the area fill. Since 90 per cent of this settlement will take place within 30 to 45 days after filling, construction of the effluent force mains and junction structure at the end of this period would substantially reduce the settlement of these units. For this reason, it is recommended that construction of the effluent units be deferred until 45 days after fill placement. Work on the pump station equipment installation and superstructure can continue, of course, during this period.

## METROPOLITAN ENGINEERS



Eugene R. McMaster, P.E.  
Chief Foundation Engineer

ERM:ab




## Attachments:

- Sheet 1 - Plot Plan
- Sheet 2 - Lateral Wall Pressures
- Sheet 3 - Log of Borings
- Sheet 4 - Ground Water Data
- Sheet 5 - Consolidation Curve
- Sheet 6, 7 - Grain-Size Distribution

# CALCULATION SHEET

## METROPOLITAN ENGINEERS

### SEATTLE, WASHINGTON



KCSlip4 53004

SEA419364


# CALCULATION SHEET

## METROPOLITAN ENGINEERS


### SEATTLE, WASHINGTON

#### LATERAL WALL PRESSURE


(A) DURING CONSTRUCTION, CAISSON IN PLACE, BEFORE DEWATERING



(B) DURING CONSTRUCTION, TREMIE SEAL IN PLACE, AFTER DEWATERING




(C) AFTER CONSTRUCTION



DATE	BY	JOB NO.	TITLE	SHT. NO.
11-9-62	CHW	W210.B	LATERAL WALL PRESSURE	2


BORING No PS 1  
ELEVATION: 111.1  
DATE DRILLED: 10/3-5/60



• SAMPLED WITH 2 1/2" ID SPLIT-BARREL DRIVE SAMPLER

WATER LEVEL (SEE SHEET No 3)

BORING No PS 2  
ELEVATION: 107.6  
DATE DRILLED: 10/6-7/60



LOG OF BORINGS


SHEET NO. 3

KCS/JP4 53006

SEA419366


BORING NO. PS 2  
EL 107.6  
DRILLED 10/6-7/60

OW NO. 2




BORING NO. PS 1  
EL 111.1  
DRILLED 10/3-5/60

OW NO. 1



NOTES: 1 FROM EL 65 TO EL 66 HOLE WAS BACKFILLED WITH SAND  
2 AT EL 66, HOLE WAS SEALED WITH 2 SACKS OF CEMENT


1. AFTER COMPLETION, PULLED CASING BACK TO EL 65.2, BALLED AND JARRED AT EL 65.6  
2. DISPOSED 3 SACKS OF CEMENT AND CHURNED  
3. PULLED CASING BACK TO EL 78.6, BACKFILLED WITH 1 SACK OF CEMENT AND 0.5 CU YD OF SAND MIXED WITH OIL AND THEN PULLED THE REMAINDER OF CASING



GROUNDWATER DATA



R-2 SEMI-ANALYTICAL 300-713  
 KEUFFEL & ESSER CO. MADE IN U.S.A.  
 3 CYCLES X 70 DIVISIONS ALBANY, N.Y.




KCSlip4 53008

SEA419368

# METROPOLITAN ENGINEERS

JOB NO. W210B LOCATION \_\_\_\_\_ DATE SAMPLED \_\_\_\_\_ BY \_\_\_\_\_  
 BORING 2 DEPTH \_\_\_\_\_ ELEVATION \_\_\_\_\_ DATE TESTED \_\_\_\_\_ BY \_\_\_\_\_  
 SOIL CLASSIFICATION \_\_\_\_\_



## GRAIN-SIZE DISTRIBUTION

GRAVEL		SAND			FINES	
COARSE	FINE	COARSE	MEDIUM	FINE	SILT AND CLAY	

SHEET NO. 7

KCSlip4 53009

SEA419369

JOB NO. W210 B LOCATION \_\_\_\_\_  
 BORING 1 DEPTH \_\_\_\_\_ ELEVATION \_\_\_\_\_  
 SOIL CLASSIFICATION \_\_\_\_\_  
 DATE SAMPLED \_\_\_\_\_ BY \_\_\_\_\_  
 DATE TESTED \_\_\_\_\_ BY \_\_\_\_\_

METROPOLITAN ENGINEERS

