

B. ALL SLABS

Cover with Sisalkraft or approved as soon as possible and keep covered a minimum of 10 days.

C. HARDENER & SEALER

All interior slabs are to receive two coats of floor hardware and sealer; Chemi-Crete, Hillyard's Chem-Seal or approved. Clean surfaces and obtain Architect's approval before applying. Allow at least two weeks between coats.

3b-6 CONCRETE SLAB FINISHES

A. GENERAL

Screed slabs to true levels or slopes; finish monolithically, without topping.

B. INTERIOR SLABS

Trowel to hard, dense surfaces, free from trowel marks.

Do not dust surfaces with dry cement or mixture of cement and sand; wait until surfaces are dry enough for proper finishing.

C. EXTERIOR SLABS

Finish by screeding and floating only; leave slightly roughened surface. Mark off as shown on drawings, or as directed; round edges to 1/4" radius.

D. SLOPES TO DRAINS

True to line, evenly graded, 3/16" per foot, unless noted otherwise. Do not slope to drains unless specifically noted.

E. EXPANSION JOINTS

Asphalt expansion joint material, Carey "Elastite," or approved, 1/2" thick. Provide in the following locations:

1. Wherever exterior slabs abut vertical surfaces.
2. At intersection of new concrete pavement with existing.
3. Elsewhere noted on drawings.

F. CONSTRUCTION JOINTS

Provide keyed construction joints at each column line (25' o.c.).

End of Section 3b