

Wa 6906  
5:23:86  
5a

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION X  
1200 Sixth Avenue  
Seattle, Washington 98101

In the Matter of:

ENVIRONMENTAL PROTECTION AGENCY,

Complainant,

v.

PACIFIC WOOD TREATING CORPORATION,  
EPA ID No. WAD009036906,

Respondent.

No. 1085-09-26-3008P

AFFIDAVIT OF  
PATRICK H. WICKS



Patrick H. Wicks, having been duly sworn on oath, deposes and says:

1. I am currently a self-employed consulting environmental engineer, specializing in hazardous waste management, soil and ground water contamination. I have a Bachelor of Science degree in Chemical Engineering from the University of Idaho; and I am a licensed professional engineer in the State of Oregon. I have worked full time during the past 15 years in the hazardous waste and environmental area.

During the last 3 years alone, I have consulted on over 30 projects involving hazardous waste, soil and/or groundwater contamination due to hazardous materials or wastes, the cleanup of such

1 contamination, other evaluations involving hazardous materials/  
2 wastes in the environment or compliance with applicable statutes  
3 and regulations.

4 Previous to my current employment, I was involved in hazar-  
5 dous waste management with the Oregon Department of Environmental  
6 Quality. Subsequently, I managed the operations of hazardous  
7 waste treatment and disposal facilities and was involved in the  
8 development of similar new facilities for Chem-Security Systems,  
9 Inc. and Chem-Nuclear Systems, Inc. My resume and descriptions of  
10 recent consulting activities are attached.

11 2. In June, 1983, I was retained by Pacific Wood Treating  
12 Corporation ("PWT") to prepare a closure and post-closure plan for  
13 the Ridgefield Brick and Tile Facility ("the RBT site") near Ridge-  
14 field, Washington. I am personally familiar with the RBT site  
15 and the history of its operation and closure. In the preparation  
16 of these plans, I consulted with the firm of Sweet, Edwards & Asso-  
17 ciates, which had been retained by PWT to provide geotechnical  
18 services.

19 Preliminary Ground Water Investigation

20 3. In response to a notice of violation from EPA Region 10,  
21 PWT initiated an evaluation of groundwater at the RBT site in May,  
22 1983. This evaluation was prepared by Sweet, Edwards and complet-  
23 ed June 7, 1983. The report resulting from this evaluation was  
24 forwarded to the Washington Department of Ecology ("DOE") for com-  
25 ment on the same day.

1                                    Preparation of Draft Closure Plan

2            4.    The DOE June 20, 1983 Notice of Penalty and Order #83-  
3 284 required PWT to submit a closure plan. This order also re-  
4 quired that a post-closure plan be prepared. These plans were to  
5 be submitted by July 30, 1983. The DOE Order further requested  
6 submission of a groundwater monitoring plan by July 11, 1983. The  
7 Draft Closure Plan, Post-closure Plan and a Groundwater Monitoring  
8 Plan were completed July 15, 1983. These plans were submitted to  
9 the DOE on that same day; and copies were forwarded to Region 10.

10           5.    The Draft Closure Plan contained three options for clos-  
11 ure. Although there were some minor differences among the three  
12 options, all options included soil testing, drying the then-exist-  
13 ing pond, construction of a top seal over the waste, installation  
14 of vents, final grading, monitoring lysimeters, seeding the top  
15 seal and fencing as common features. The major differences among  
16 the options were as follows. Option I, in addition to the common  
17 features noted above, essentially provided for placing a low per-  
18 meability barrier constructed of onsite compacted soils along the  
19 southeast face of the refuse area, where it abutted the then-exist-  
20 ing pond. Option II was more rigorous than Option I, in that a  
21 compacted soil cutoff wall approximately 11 feet deep was to be  
22 added along the remaining perimeter of the refuse area, in conjunc-  
23 tion with the compacted soil barrier along the southeast face of  
24 the refuse area. Option III was more rigorous than Options I and  
25 II, since it provided for complete relocation of the waste onto a  
26 new bottom seal (to mitigate leachate migration), installation of

1 an underdrain system (to further protect groundwater) and installa-  
2 tion of a toe drain (as a leachate control feature and additional  
3 monitoring point).

4 6. DOE commented on the Draft Closure and Post-closure  
5 plans in a letter dated August 4, 1983. EPA's comments were in-  
6 corporated into a letter to Eric Egbers dated August 10, 1983.  
7 Subsequently, a meeting was held on August 18, 1983 at the Olympia  
8 offices of the DOE. This meeting was attended by representatives  
9 of DOE, EPA, PWT and PWT's consultants, Sweet, Edwards and the  
10 undersigned. During this meeting, the DOE and EPA comments on the  
11 Closure and Post-closure Plans were discussed. Revisions of the  
12 draft plan to achieve an acceptable closure were agreed upon. It  
13 was also agreed that changes to the plans would be provided in the  
14 form of an Addendum, covering agreed-upon modifications. The re-  
15 gulatory agencies were anxious that construction could begin as  
16 soon as DOE approval of the Draft Closure Plan and Addendum had  
17 been received, in order to complete closure in 1983, prior to the  
18 onset of fall rains.

19 DOE Approval

20 7. An Addendum to the Draft Closure Plan was completed on  
21 August 22, 1983. This Addendum was submitted to the DOE on August  
22 24, 1983. It addressed closure, post-closure and the groundwater  
23 monitoring provisions. On August 31, 1983, a meeting was held at  
24 PWT's Ridgefield facility. This meeting was attended by DOE and  
25 PWT representatives to review various items of the Addendum. The  
26 DOE representative, Eric Egbers, verbally authorized proceeding

1 with closure during this meeting, in accordance with the plans and  
2 discussions that day. He also indicated that approval of the  
3 plans would be confirmed by a DOE order. Of the three options  
4 proposed for closure, Option III, with modifications as reflected  
5 in the Addendum, was selected by DOE. Option III was carried out  
6 during the closure, as further described below.

7 8. On October 26, 1983, the DOE issued Order #83-468. This  
8 Order approved the Draft Closure Plan and Addendum with certain  
9 conditions which related principally to sampling, testing, mon-  
10 itoring and post-closure performance standards for the results of  
11 sampling and testing.

#### 12 Closure Construction

13 9. Closure construction was started September 8, 1983 and  
14 completed October 16, 1983. Major activities during closure are  
15 described below in approximate chronological order. A necessary  
16 prelude to closure was evacuation of water from the then-existing  
17 pond in the former clay pit at the site. This step is also de-  
18 scribed below.

19 The topography, location of waste disposed (refuse area) and  
20 other features of the site prior to closure are shown in Attach-  
21 ment A. Topography, location of the new waste encapsulation area  
22 (refuse area) and other features of the site following closure are  
23 shown in Attachments B and C.

#### 24 Pond Evacuation

25 10. Previous excavation of clay by RBT at the property had  
26 created a pit near the southeast corner of the site. A small part

1 of this pit had been filled with waste from PWT's plant. The lar-  
2 ger portion of this pit was a pond. During the preliminary ground-  
3 water investigation described above, water in this pond was sam-  
4 pled on May 31, 1983 and analyzed. Results of those analyses  
5 showed this water to be essentially uncontaminated. Fish, tad-  
6 poles and frogs were also observed in the pond during this sampl-  
7 ing.

8 11. Prior to closure construction, it was necessary to dry  
9 the pond due to certain provisions of all closure options under  
10 consideration, i.e., in Option III, the pond area was to be used  
11 as the new waste encapsulation area. No water would be allowed to  
12 accumulate in the pond for two weeks before closure construction  
13 commenced. On July 7, 1983, evaporation/evacuation of water in  
14 the pond was initiated, in accordance with procedures approved by  
15 DOE.

#### 16 Geotechnical Investigations and Chemical Analysis

17 12. Closure construction was initiated on September 8, 1983.  
18 Three bore holes, P-1, P-2 and P-3, were excavated in the former  
19 pond area to define the depth of the mica sand underlying this  
20 area and the depth to the cemented gravels. Test pits TP-1 and  
21 TP-2 were excavated to determine the quality of soil to be used  
22 for the compacted and clay-amended seal and in the various por-  
23 tions of closure construction.

24 13. In addition to proposals in the Draft Closure Plan and  
25 the Addendum, the DOE requested additional soil samples be col-  
26 lected adjacent to the preclosure waste area. The purpose of this

1 sampling was to obtain samples for chemical analysis to determine  
2 the chemical contamination levels of soil adjacent to, and as an  
3 indicator of migration of contaminants from, the refuse area.  
4 Accordingly, three additional borings, AH-1, AH-2 and AH-3, were  
5 advanced to obtain samples immediately adjacent to and below the  
6 then-existing refuse area. These samples were analyzed to confirm  
7 that migration of contaminants had not occurred from the old re-  
8 fuse area.

9 14. An additional auger hole, AH-4, was excavated near the  
10 southeast corner of the site. A lysimeter was installed in AH-4  
11 as the upgradient onsite monitoring point. During closure con-  
12 struction, this lysimeter was damaged and was later replaced with  
13 a new lysimeter at a slightly different location.

14 All borings, sampling and test pits were completed by Septem-  
15 ber 14, 1983.

16 15. A lysimeter is a monitoring device used for collecting  
17 ground water samples, usually in relatively shallow applications  
18 of less than 60 feet below the ground surface. The lysimeter body  
19 is a section of plastic pipe, commonly 1.5 to 2 inches in diame-  
20 ter. At the lower end of the body is a porous ceramic cup of the  
21 same diameter. At the upper end of the body is a seal or stopper  
22 through which two small diameter tubes run into the lysimeter  
23 body. One of these tubes extends to the porous ceramic cup at the  
24 lower end of the lysimeter. The other tube extends only slightly  
25 into the lysimeter body.  
26

1 Using lysimeters for collection of groundwater samples is  
2 accomplished by drawing a vacuum on the unit through the two small  
3 diameter tubes which extend above the ground surface and clamping  
4 these tubes to maintain the vacuum for a period of usually days or  
5 weeks. During this period, the vacuum causes any water present  
6 near the lysimeter to be drawn through the porous ceramic cup into  
7 the lysimeter. This water can then be brought to the surface by  
8 placing air pressure on one of the small diameter tubes and collect-  
9 ing the sample from the other tube.

10 Details of lysimeter installation at the RBT site are shown  
11 in Attachment D.

#### 12 Underdrain

13 16. An underdrain system was installed beneath the bottom  
14 seal for the new waste encapsulation area (refuse area in Attach-  
15 ment B) prior to its construction. The underdrain provides a mon-  
16 itoring system and addresses any concern over the potential up-  
17 welling of seasonally perched groundwater beneath the bottom seal.  
18 The underdrain option was discussed with Eric Egbers of the DOE  
19 and approval was given to Randy Sweet of Sweet, Edwards to install  
20 the system as described.

21 17. The underdrain system installed consisted of two 4-inch  
22 perforated pipes in 2 ft x 2 ft trenches with washed gravel back-  
23 fill. These pipes were aligned in a "V". At the apex of the V,  
24 the pipes were connected together. These were in turn connected  
25 to a new underground solid pipe (tight line) which terminated at a  
26 sump located at the southwest corner of the warehouse. This sys-



tem provides positive gravity drainage beneath the bottom seal. Any flow from the underdrain can be measured at the sump. Samples of water flowing from the underdrain can also be collected at the sump for analysis.

#### Bottom Seal

18. After completion of the underdrain system, the bottom seal was constructed in the former pond area. The area covered by this bottom seal is represented by the shaded refuse area in Attachment B. The Draft Closure Plan had provided for a compacted soil bottom seal. The Addendum added a requirement for the top portion of the seal to be a bentonite clay-amended compacted soil. The base of the bottom seal was constructed of compacted low permeability soils approximately 3 feet thick. On top of this soil base, a bentonite clay-amended compacted soil seal approximately 4 inches thick was constructed. This upper part of the bottom seal was constructed of low permeability onsite soils, amended with bentonite clay to achieve  $1 \times 10^{-7}$  centimeters per second coefficient of permeability. The upper part of the bottom seal was completed in three sections. As constructed, the bottom seal provides a barrier to the downward migration of leachate from the cell. Leachate collecting above the bottom seal will preferentially migrate or drain to the toe drain at the West end of the new waste encapsulation area. This further protects against leachate migrating through the bottom seal. As an additional protective feature, the underdrain provides a means to monitor any small proportion of leachate which might migrate through the bottom seal,

1 as well as monitoring shallow ground water below the bottom seal  
2 and protecting the bottom seal from the possibility of upwelling  
3 of shallow ground water.

4 Waste Relocation

5 19. Waste movement onto the first two of three sections of  
6 the upper bottom seal was initiated prior to completion of the  
7 third and final section of the upper bottom seal. Following com-  
8 pletion of the third section of the upper bottom seal, waste re-  
9 location from the former refuse area was completed. Excavation of  
10 the waste and movement onto the new bottom seal was accomplished  
11 using a large back hoe and crawler tractor.

12 Confirmation of Waste Removal

13 20. The addendum provided for chemical analyses on the soil  
14 underlying the former waste disposal area following waste reloca-  
15 tion to the new encapsulation area. However, as a result of a  
16 soil sampling and testing conducted at the site (as described  
17 above), there appeared to be no significant contamination immedi-  
18 ately below the waste in the former disposal area. DOE agreed,  
19 therefore, that further chemical testing of the soil immediately  
20 below the old disposal area was not necessary and that visual ob-  
21 servation could be used to determine when all wastes had been re-  
22 moved therefrom. Visual observations by PWT and its consultants  
23 during and near the end of the waste removal process revealed a  
24 dramatic difference in color between the wastes and the underlying  
25 soil. These visual observations proved to be a practical and ef-  
26

1     fective method of determining completion of waste removal and the  
2     limits of necessary excavation.

3     Toe Drain

4             21. Following movement of waste to the new encapsulation  
5     area, and placement of soil over the waste for surcharge, a toe  
6     drain was constructed at the western boundary of the waste cell.  
7     The purpose of this toe drain is to collect water from the waste  
8     cell which would occur principally due to precipitation infiltrat-  
9     ing through the top cover and into the waste cell. The toe drain  
10    consisted of perforated pipe installed in a gravel-filled trench,  
11    in contact with the waste. At the approximate center of the toe  
12    drain, a distribution box was provided with a vertical riser so  
13    that samples of water (leachate) could be collected at this point.  
14    The distribution box was also connected with an underground solid  
15    pipe (tight line) to a sump located at the southwest corner of the  
16    warehouse. This allowed for gravity drainage of leachate from the  
17    toe drain. Flow from the toe drain could be measured at the sump.  
18    The sump also provides an alternate sampling location.

19    Final Cap, Cover and Grading

20             22. During and following completion of the toe drain, low  
21    permeability soil from the site was placed over the waste cell and  
22    compacted in accordance with the plans. The depth of this com-  
23    pacted top cap was 18 inches. Following completion of this 18-  
24    inch top cap, a second 18-inch layer of top soil was added to the  
25    new waste cell area and to adjacent areas of the site. Final grad-  
26    ing of this site was then completed.

1     Vents, Seeding and Fencing

2           23. Vents were installed near the eastern boundary of the  
3 new waste cell. A shallow drainage ditch was excavated along the  
4 eastern, northern and southern boundary of the new encapsulation  
5 area. Seeding of the site was then completed. A three-strand,  
6 barbwire fence was constructed along the western and northern bound-  
7 ary of the new waste cell. The DOE had agreed to allow the exist-  
8 ing electrical fence along the southern and eastern property line  
9 and waste cell boundary to remain in place at that time.

10    Lysimeter Monitors

11           24. Lysimeters for monitoring groundwater were installed as  
12 follows: LS-1 was installed September 12, 1983. This is the up-  
13 gradient lysimeter located near the southeast corner of the prop-  
14 erty. LS-2 and LS-3 were completed September 28, 1983. These  
15 downgradient lysimeters are located west of the new waste cell.  
16 LS-1 was damaged during grading and other construction activities  
17 on the site in the latter half of September. This lysimeter was  
18 replaced slightly to the north of its original location.

19    Certification

20           25. Certification of closure of the RBT site is provided in  
21 a report. This certification report describes the consultants'  
22 inspections during closure construction, modifications to the clos-  
23 ure plans, provides formal certification of closure and provides  
24 various other materials relative to closure: site safety and op-  
25 erations plan, site exploration plans, boring logs, soil sampling  
26 data sheets, laboratory analysis results, access agreement for

1 drinking water well sampling, report on testing of bentonite-amended  
2 bottom seal, soil logs, site topography, color photograph re-  
3 productions and references.

4 Final inspection for purposes of certification was conducted  
5 at the site November 16, 1983. The formal report on certification  
6 was completed February 15, 1984. This report was submitted by PWT  
7 to DOE on May 31, 1984. PWT's certification was submitted on the  
8 same date.

#### 9 Post-Closure

##### 10 Monitoring

11 26. Following completion of closure construction, post-clo-  
12 sure environmental monitoring of the site was started as required  
13 by the approved plans. Other monitoring has also been performed  
14 by PWT on its own initiative.

15 Monitoring of potential groundwater contamination has con-  
16 sisted of sampling and testing of water from:

17 a. The three lysimeters installed at the site during clos-  
18 ure.

19 b. Three downgradient drinking water wells located near the  
20 site and one upgradient drinking water well.

21 c. Flow from the toe drain.

22 d. Flow from the underdrain.

23 Hazardous constituents that might be associated with the ash  
24 disposed at the RBT site were those potentially present in the  
25 wood treating sludge prior to its incineration. These include  
26 creosote, pentachlorophenol, arsenic, copper and chromium.

1 Parameters to be analyzed during post-closure monitoring were  
2 based on those listed in 40 CFR 265.92, plus three others not co-  
3 vered by Part 265 which are indicative of wood treating waste:  
4 copper, pentachlorophenol and naphthalene (a major constituent of  
5 creosote). Likewise, arsenic and chromium (which are included in  
6 the 40 CFR 265 list) would be indicative of wood treating waste  
7 constituents.

8 40 CFR 265.92 lists the following parameters for groundwater  
9 monitoring:

10 a. Drinking water parameters: arsenic, barium, cadmium,  
11 chromium, fluoride, lead, mercury, nitrate (as N), selenium, sil-  
12 ver, endrin, lindane, methoxychlor, toxaphene, 2,4-D, 2,4,5-TP  
13 silvex, radium, gross alpha, gross beta, turbidity, coliform bac-  
14 teria;

15 b. Groundwater quality parameters: chloride, iron, manga-  
16 nese, phenols, sodium, sulfate;

17 c. Groundwater contamination parameters: pH, specific con-  
18 ductance, total organic carbon, total organic halogen.

19 Using the 40 CFR 265 parameters as a starting point, para-  
20 meters appropriate to post-closure monitoring at the site after  
21 closure were discussed among DOE, EPA, PWT and its consultants on  
22 several occasions. As a result of these discussions, several para-  
23 meters were eliminated early on from the 40 CFR 265.92 list as not  
24 appropriate or necessary for monitoring at the RBT site. Others  
25 were eliminated later. Two slightly differing sets of groundwater  
26 monitoring parameters were proposed in the draft closure plan and

1 the Addendum. Both sets were based on the 40 CFR 265.92 list.  
2 Eventually, the parameters to be tested during post-closure were  
3 refined and established in the DOE October 1983 Order. The labor-  
4 atory analysis parameters for groundwater monitoring which were  
5 finally established in the DOE October 1983 Order are listed be-  
6 low.

7 The monitoring program required by the Addendum, as modified  
8 by the October 1983 Order, includes quarterly sampling and analy-  
9 sis of the toe drain, the three lysimeters and four drinking water  
10 wells in the first year after closure. After one year of quarter-  
11 ly monitoring, annual sampling and analysis was required. Labora-  
12 tory analysis parameters included: arsenic, barium, cadmium, chro-  
13 mium, lead, mercury, selenium, silver, copper, pentachlorophenol  
14 and naphthalene. Some samples have been tested for total phenols,  
15 pH and specific conductance, although these parameters are not  
16 required by the Order.

17 Performance standards for several parameters were established  
18 for all wells, lysimeters and the toe drain in the October 1983  
19 Order. These standards, expressed as parts per million (ppm), are  
20 as follows: 0.025 ppm arsenic, 0.5 ppm barium, 0.005 ppm cadmium,  
21 0.025 ppm chromium, 0.025 ppm lead, 0.001 ppm mercury, 0.005 ppm  
22 selenium, 0.025 ppm silver, 0.5 ppm copper, 0.025 ppm pentachloro-  
23 phenol and 1.15 ppm naphthalene. These were established at one-  
24 half the EPA primary or secondary drinking water standards or one-  
25 half the acute freshwater aquatic life toxicity criteria. The  
26 Order required that, if any of these standards were exceeded, du-



1 plicate samples must be tested. Performance standards for several  
2 parameters were established for the toe drain, as follows: 0.05  
3 ppm arsenic, 0.003 ppm pentachlorophenol and 0.62 ppm naphthalene.

4 27. Analytical results for the required post-closure monitor-  
5 ing of lysimeters (i.e. shallow groundwater), water wells (local  
6 drinking water supply) and the toe drain (leachate) have not ex-  
7 ceeded the performance standards for any of the samples. These  
8 results indicate no contamination of groundwater or surface water  
9 in excess of the performance standards is occurring. Additionally,  
10 although testing of the underdrain was not required, it was sam-  
11 pled and tested in December, 1985 for the same parameters. Analy-  
12 tical results from this sample did not exceed the performance stan-  
13 dards, further indicating that contamination in excess of the per-  
14 formance standards is not occurring.

15 28. In several respects, the groundwater monitoring system  
16 installed at the RBT site is superior to the 40 CFR 265 ground-  
17 water monitoring requirements. These include:

18 a. Monitoring of the toe drain provides a direct and rapid  
19 indication of the potential for contaminants in leachate from the  
20 new waste encapsulation area to migrate to groundwater or to sur-  
21 face water at the site.

22 b. Monitoring of the underdrain provides a rapid indication  
23 of whether shallow groundwater beneath the new waste encapsulation  
24 area is being contaminated. This underdrain monitoring provides a  
25 direct measure of any contaminant leakage through the bottom seal.

26



1 Monitoring of the three onsite lysimeters enhances shallow ground-  
2 water monitoring capability.


3 c. Monitoring of nearby drinking water supply wells pro-  
4 vides an indication of whether local drinking water is being con-  
5 taminated. Monitoring of drinking water supply wells is not re-  
6 quired in 40 CFR 265. Monitoring of these wells was included in  
7 the plans as an additional backup to assure no adverse impact on  
8 beneficial use of groundwater.

9 None of these factors would be addressed nearly as well by  
10 the 40 CFR 265 requirement of one upgradient and three downgradi-  
11 ent groundwater monitoring wells in the uppermost aquifer. A 40  
12 CFR 265 monitoring system will indicate contamination after ground-  
13 water has already become contaminated, but will not detect the  
14 potential for contamination prior to its occurrence. By contrast,  
15 the system installed at the RBT site will detect contamination  
16 potential prior to the occurrence of groundwater contamination.  
17 Further, the system at the RBT site monitors the quality of the  
18 local drinking water supply, which would not be accomplished by a  
19 40 CFR 265 monitoring system.

20 DOE and EPA Inspections


21 29. Inspection of the site following completion of closure  
22 was conducted by DOE on December 14, 1983. This inspection was to  
23 observe first quarterly sampling by Sweet, Edwards. Samples were  
24 also split with DOE. Present during this inspection were Eric  
25 Egbers of DOE, Sweet, Edwards representatives and PWT representa-  
26 tives.


1           30. On June 12, 1984, a groundwater monitoring compliance  
2 audit was conducted at the site by EPA Region 10 representatives,  
3 an EPA consultant and DOE personnel. Also present during this  
4 inspection were Sweet, Edwards and PWT representatives. This  
5 audit coincided with the collection of the third quarterly monitor-  
6 ing samples by PWT's consultants. PWT received no information  
7 from either DOE or EPA that either agency had any concern over the  
8 closure or post-closure care of the RBT site.  
9

10  
11 


Patrick H. Wicks

12  
13           SUBSCRIBED AND SWORN to before me this 23 day of  
14 May, 1986.

15   
16 Notary Public in and for the  
17 State of Washington, residing  
18 at 1000 1st Avenue, Seattle, WA  
19 MY COMMISSION Exp. 3/3/87  
20  
21  
22  
23  
24  
25  
26




- NOTES**
1. BASE MAP MODIFIED AFTER PACIFIC WOOD TREATING SURVEY.
  2. CONTOUR INTERVAL IS FIVE FEET.
  3. INDICATED CROSS-SECTIONS ARE DETAILED ON FIGURE 5 & 9.







**Sweet, Edwards & Associates, Inc.**  
 P.O. Box 380 • Kent, WA 98020 • (206) 423-3500

IN ASSOCIATION WITH:  
**PATRICK H. WOODS, P.E.**  
 CONSULTANT IN HAZARDOUS WASTE MANAGEMENT

**RBT SITE**  
 Existing  
 Topography  
**Figure 6**






DETAIL III-A

LINED AND CAPPED OFFSHORE WITH THE DRAIN -  
LONG-SECTION

NOTE: BOLD DASHED LINES INDICATE  
PROPOSED CUTS AND FILLS.



Sweet, Edwards & Associates, Inc.  
P.O. Box 300 • Falls Church, VA 22044 • 703-423-3000

IN ASSOCIATION WITH:  
PATRICK M. WICKS, P.E.  
REGISTERED IN HAZARDOUS WASTE MANAGEMENT

RBT SITE  
OPTION III  
Cross - Sections

Figure 11





PROJECT Pacific Wood Treating / RBT Site

Page 1 of 1

Location Ridgefield Brick &amp; Tile

Boring No. LS-1

Surface Elevation

Drilling Method Auger

Total Depth 54.5 ft.

Drilled By Sweet, Edwards &amp; Assoc.

Date Completed 9/12/83

Logged By J. Maul

WELL DETAILS	PENE- TRATION TIME/ RATE	DEPTH (FEET)	SAMPLE		PERME- ABILITY TESTING	SYMBOL	LITHOLOGIC DESCRIPTION	WATER QUALITY
			NO.	TYPE				
Bentonite Pellets		10						
Native Soil Backfill		20						
1.5 in. PVC riser		30						
40								
Bentonite Pellets		43.5	4-1A				43.5'-45.25' SILTY SAND- Tanish orange, lenses of feldspathic mica sand, medium fine, unsaturated.	
45			4-1B					
50			4-2A				52.0'-54.25' SAND- Orange and tan streaks, heavily oxidized, trace silt.	
52			4-2B					
Suction Lysimeter		60					Gravels at 54.5'. Auger refusal.	
Native Soil Slurry		70					Suction lysimeter installed at 52.0'.	