Analytical Laboratory

13339 Hagers Ferry Road
Huntersville, NC 28078-7929
McGuire Nuclear Complex - MG03A2
Phone: 980-875-5245 Fax: 980-875-4349

Order Summary Report

Order Number: **J12020345**

Customer Name(s): Bill Kennedy, Melonie Martin, Wayne Chapman, Tom Johnson

Customer Address: 3195 Pine Hall Rd
Mailcode: Belews Steam Station
Belews Creek, NC 28012

Lab Contact: Jason C Perkins Phone: 980-875-5348

Report Authorized By: (Signature) Digitally signed by jay perkins DN: cn=jay perkins, o=Analytical Lab, ou, email=jay.perkins@duke-energy.com, c=US Date: 2012.03.06 14:12:59 -05'00' **Date:** 3/5/2012

Program Comments:

Please contact the Program Manager (Jason C Perkins) with any questions regarding this report.

Data Flags & Calculations:

Any analytical tests or individual analytes within a test flagged with a Qualifier indicate a deviation from the method quality system or quality control requirement. The qualifier description is found at the end of the Certificate of Analysis (sample results) under the qualifiers heading. All results are reported on a dry weight basis unless otherwise noted.

Data Package:

This data package includes analytical results that are applicable only to the samples described in this narrative. An estimation of the uncertainty of measurement for the results in the report is available upon request. This report shall not be reproduced, except in full, without the written consent of the Analytical Laboratory. Please contact the Analytical laboratory with any questions. The order of individual sections within this report is as follows:

Job Summary Report, Sample Identification, Technical Validation of Data Package, Analytical Laboratory Certificate of Analysis, Analytical Laboratory QC Reports, Sub-contracted Laboratory Results, Customer Specific Data Sheets, Reports & Documentation, Customer Database Entries, Test Case Narratives, Chain of Custody (COC)

Certification:

The Analytical Laboratory holds the following State Certifications : North Carolina (DENR) Certificate #248, South Carolina (DHEC) Laboratory ID # 99005. Contact the Analytical Laboratory for definitive information about the certification status of specific methods.

Sample ID's & Descriptions:

Sample ID	Plant/Station	Collection Date and Time	Collected By	Sample Description
2012004159	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	FGD Purge Eff
2012004160	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	BIOREACTOR 1 INF.
2012004161	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	BIOREACTOR 1 INF. BLANK
2012004162	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	BIOREACTOR 2 EFF.
2012004163	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	BIOREACTOR 2 EFF. BLANK
2012004164	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	FILTER BLANK
2012004165	BELEWS	20-Feb-12 9:00 AM	P. GASSETT	Trip Blank

7 Total Samples

Technical Validation Review

Checklist:

COC and .pdf report are in agreement with sample totals and analyses (compliance programs and procedures).	☑ Yes	☐ No
All Results are less than the laboratory reporting limits.	☐ Yes	☑ No
All laboratory QA/QC requirements are acceptable.	☑ Yes	☐ No
The Vendor Laboratories have been qualified by the Analytical Laboratory	Yes	

Report Sections Included:

- ☑ Job Summary Report
- ☑ Sample Identification
- ☑ Technical Validation of Data Package
- ☑ Analytical Laboratory Certificate of Analysis
- ☐ Analytical Laboratory QC Report
- ☑ Sub-contracted Laboratory Results
- ☐ Customer Specific Data Sheets, Reports, & Documentation
- ☐ Customer Database Entries
- ☑ Chain of Custody
- ☑ Electronic Data Deliverable (EDD) Sent Separately

Reviewed By: Mary Ann Ogle Date: 3/5/2012

Certificate of Laboratory Analysis

Order # J12020345

Site: FGD Purge Eff
Sample #: 2012004159
Collection Date: 20-Feb-12 9:00 AM
Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
Carbonate, Bicarbonate, and Hydroxide Alkalinity								
Carbonate (CO3)	**Complete**				1	V_PRISM		
Bicarbonate (HCO3)	**Complete**				1	V_PRISM		
Hydroxide (OH)	**Complete**				1	V_PRISM		
NITRITE + NITRATE (COLORIMETRIC)								
Nitrite + Nitrate (Colorimetric)	**13**	mg-N/L		0.25	25	EPA 353.2	21-Feb-12 14:21	BGN9034
INORGANIC IONS BY IC								
Bromide	**110**	mg/L		5	50	EPA 300.0	24-Feb-12 20:47	JAHERMA
Chloride	**7400**	mg/L		100	1000	EPA 300.0	24-Feb-12 20:47	JAHERMA
Sulfate	**1300**	mg/L		100	1000	EPA 300.0	24-Feb-12 20:47	JAHERMA
MERCURY (COLD VAPOR) IN WATER								
Mercury (Hg)	**266**	ug/L		5	100	EPA 245.1	24-Feb-12 09:45	AGIBBS
Mercury Dissolved (cold vapor) in Water (Filtered)								
Mercury (Hg)	**< 2.50**	ug/L		2.5	50	EPA 245.1	02-Mar-12 10:07	AGIBBS
DISSOLVED METALS BY ICP								
Manganese (Mn)	**6.23**	mg/L		0.05	10	EPA 200.7	29-Feb-12 10:00	MHH7131
TOTAL RECOVERABLE METALS BY ICP								
Boron (B)	**243**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Calcium (Ca)	**4490**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Iron (Fe)	**111**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Lithium (Li)	**0.144**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Magnesium (Mg)	**755**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Manganese (Mn)	**7.28**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Potassium (K)	**60.4**	mg/L		1	10	EPA 200.7	27-Feb-12 11:12	MHH7131
Sodium (Na)	**43.7**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:12	MHH7131
DISSOLVED METALS BY ICP-MS								
Selenium (Se)	**286**	ug/L		10	10	EPA 200.8	22-Feb-12 14:53	MHH7131

Certificate of Laboratory Analysis

Order # J12020345

Site: FGD Purge Eff — **Sample #: 2012004159**
Collection Date: 20-Feb-12 9:00 AM — Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
TOTAL RECOVERABLE METALS BY ICP-MS								
Arsenic (As)	**165**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Cadmium (Cd)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Chromium (Cr)	**212**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Copper (Cu)	**93.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Nickel (Ni)	**159**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Selenium (Se)	**4980**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Silver (Ag)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
Zinc (Zn)	**186**	ug/L		10	10	EPA 200.8	29-Feb-12 09:51	DJSULL1
SELENIUM SPECIATION								
Vendor Parameter	**complete**				1	V_AS&C		
TOTAL DISSOLVED SOLIDS								
TDS	**20000**	mg/L		200	1	SM2540C	28-Feb-12 16:00	TJA7067
TOTAL SUSPENDED SOLIDS								
TSS	**3500**	mg/L		250	1	SM2540D		

Site: BIOREACTOR 1 INF. — **Sample #: 2012004160**
Collection Date: 20-Feb-12 9:00 AM — Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
Carbonate, Bicarbonate, and Hydroxide Alkalinity								
Carbonate (CO3)	**Complete**				1	V_PRISM		
Bicarbonate (HCO3)	**Complete**				1	V_PRISM		
Hydroxide (OH)	**Complete**				1	V_PRISM		
NITRITE + NITRATE (COLORIMETRIC)								
Nitrite + Nitrate (Colorimetric)	**15**	mg-N/L		0.25	25	EPA 353.2	21-Feb-12 14:24	BGN9034
INORGANIC IONS BY IC								
Bromide	**120**	mg/L		5	50	EPA 300.0	24-Feb-12 21:02	JAHERMA
Chloride	**7900**	mg/L		100	1000	EPA 300.0	24-Feb-12 21:02	JAHERMA
Sulfate	**1400**	mg/L		100	1000	EPA 300.0	24-Feb-12 21:02	JAHERMA
MERCURY 1631								
Vendor Parameter	**Complete**				1	V_BRAND		
MERCURY (COLD VAPOR) IN WATER								
Mercury (Hg)	**< 2.50**	ug/L		2.5	50	EPA 245.1	24-Feb-12 09:48	AGIBBS

Certificate of Laboratory Analysis

Order # J12020345

Site: BIOREACTOR 1 INF. **Sample #: 2012004160**

Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
Mercury Dissolved (cold vapor) in Water (Filtered)								
Mercury (Hg)	**< 2.50**	ug/L		2.5	50	EPA 245.1	02-Mar-12 10:09	AGIBBS
DISSOLVED METALS BY ICP								
Manganese (Mn)	**5.80**	mg/L		0.05	10	EPA 200.7	29-Feb-12 10:03	MHH7131
TOTAL RECOVERABLE METALS BY ICP								
Boron (B)	**257**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Calcium (Ca)	**3760**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Iron (Fe)	**< 0.100**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Lithium (Li)	**< 0.050**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Magnesium (Mg)	**807**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Manganese (Mn)	**6.47**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Potassium (K)	**24.8**	mg/L		1	10	EPA 200.7	27-Feb-12 11:16	MHH7131
Sodium (Na)	**46.5**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:16	MHH7131
DISSOLVED METALS BY ICP-MS								
Selenium (Se)	**112**	ug/L		10	10	EPA 200.8	22-Feb-12 14:57	MHH7131
TOTAL RECOVERABLE METALS BY ICP-MS								
Arsenic (As)	**21.1**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Cadmium (Cd)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Chromium (Cr)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Copper (Cu)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Nickel (Ni)	**58.7**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Selenium (Se)	**93.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Silver (Ag)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
Zinc (Zn)	**< 10.0**	ug/L		10	10	EPA 200.8	29-Feb-12 09:54	DJSULL1
SELENIUM SPECIATION								
Vendor Parameter	**complete**				1	V_AS&C		

Site: BIOREACTOR 1 INF. BLANK **Sample #: 2012004161**

Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
MERCURY 1631								
Vendor Parameter	**Complete**				1	V_BRAND		

Certificate of Laboratory Analysis

Order # J12020345

Site: BIOREACTOR 2 EFF. **Sample #: 2012004162**

Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
Carbonate, Bicarbonate, and Hydroxide Alkalinity								
Carbonate (CO3)	**Complete**				1	V_PRISM		
Bicarbonate (HCO3)	**Complete**				1	V_PRISM		
Hydroxide (OH)	**Complete**				1	V_PRISM		
NITRITE + NITRATE (COLORIMETRIC)								
Nitrite + Nitrate (Colorimetric)	**0.018**	mg-N/L		0.01	1	EPA 353.2	21-Feb-12 14:25	BGN9034
INORGANIC IONS BY IC								
Bromide	**110**	mg/L		5	50	EPA 300.0	24-Feb-12 21:18	JAHERMA
Chloride	**7500**	mg/L		100	1000	EPA 300.0	24-Feb-12 21:18	JAHERMA
Sulfate	**1500**	mg/L		100	1000	EPA 300.0	24-Feb-12 21:18	JAHERMA
MERCURY 1631								
Vendor Parameter	**Complete**				1	V_BRAND		
MERCURY (COLD VAPOR) IN WATER								
Mercury (Hg)	**< 1.00**	ug/L		1	20	EPA 245.1	24-Feb-12 09:50	AGIBBS
DISSOLVED METALS BY ICP								
Manganese (Mn)	**5.28**	mg/L		0.05	10	EPA 200.7	29-Feb-12 10:07	MHH7131
TOTAL RECOVERABLE METALS BY ICP								
Boron (B)	**246**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Calcium (Ca)	**3580**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Iron (Fe)	**< 0.100**	mg/L		0.1	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Lithium (Li)	**< 0.050**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Magnesium (Mg)	**785**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Manganese (Mn)	**6.07**	mg/L		0.05	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Potassium (K)	**28.9**	mg/L		1	10	EPA 200.7	27-Feb-12 11:20	MHH7131
Sodium (Na)	**44.2**	mg/L		0.5	10	EPA 200.7	27-Feb-12 11:20	MHH7131
TOTAL RECOVERABLE METALS BY ICP-MS								
Arsenic (As)	**24.0**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Cadmium (Cd)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Chromium (Cr)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Copper (Cu)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Nickel (Ni)	**8.02**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Selenium (Se)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Silver (Ag)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
Zinc (Zn)	**< 5.00**	ug/L		5	5	EPA 200.8	29-Feb-12 09:57	DJSULL1
SELENIUM SPECIATION								
Vendor Parameter	**complete**				1	V_AS&C		

Certificate of Laboratory Analysis

This report shall not be reproduced, except in full.

Order # J12020345

Site: BIOREACTOR 2 EFF. **Sample #: 2012004162**
Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst

Site: BIOREACTOR 2 EFF. BLANK **Sample #: 2012004163**
Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
MERCURY 1631								
Vendor Parameter	**Complete**				1	V_BRAND		

Site: FILTER BLANK **Sample #: 2012004164**
Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
Mercury Dissolved (cold vapor) in Water (Filtered)								
Mercury (Hg)	**< 0.05**	ug/L		0.05	1	EPA 245.1	02-Mar-12 10:14	AGIBBS
DISSOLVED METALS BY ICP								
Manganese (Mn)	**< 0.005**	mg/L		0.005	1	EPA 200.7	29-Feb-12 09:28	MHH7131
DISSOLVED METALS BY ICP-MS								
Selenium (Se)	**< 1.00**	ug/L		1	1	EPA 200.8	22-Feb-12 13:08	MHH7131

Site: Trip Blank **Sample #: 2012004165**
Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
TOTAL RECOVERABLE METALS BY ICP								
Boron (B)	**< 0.050**	mg/L		0.05	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Calcium (Ca)	**< 0.010**	mg/L		0.01	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Iron (Fe)	**< 0.010**	mg/L		0.01	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Lithium (Li)	**< 0.005**	mg/L		0.005	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Magnesium (Mg)	**< 0.005**	mg/L		0.005	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Manganese (Mn)	**< 0.005**	mg/L		0.005	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Potassium (K)	**< 0.100**	mg/L		0.1	1	EPA 200.7	27-Feb-12 11:00	MHH7131
Sodium (Na)	**< 0.050**	mg/L		0.05	1	EPA 200.7	27-Feb-12 11:00	MHH7131

Certificate of Laboratory Analysis

Order # J12020345

Site: Trip Blank **Sample #: 2012004165**

Collection Date: 20-Feb-12 9:00 AM Matrix: OTHER

Analyte	Result	Units	Qualifiers	RDL	DF	Method	Analysis Date/Time	Analyst
TOTAL RECOVERABLE METALS BY ICP-MS								
Arsenic (As)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Cadmium (Cd)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Chromium (Cr)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Copper (Cu)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Nickel (Ni)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Selenium (Se)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Silver (Ag)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
Zinc (Zn)	**< 1.00**	ug/L		1	1	EPA 200.8	29-Feb-12 09:45	DJSULL1
SELENIUM SPECIATION								
Vendor Parameter	**complete**				1	V_AS&C		

APPLIED SPECIATION AND CONSULTING, LLC

18804 Northcreek Parkway Bothell, WA, 98011
Tel: (425) 483-3300 Fax: (425) 483-9818
www.appliedspeciation.com

February 28, 2012

Jay Perkins
Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd.
Huntersville, NC 28078
(704) 875-5245

Project: HAPS/MACT Testing Belews Creek (LIMS # J12020345)

Dear Mr. Perkins,

Attached is the report associated with four (4) aqueous samples submitted for selenium speciation analysis on February 21, 2012. The samples were received in a sealed cooler at -0.3°C on February 22, 2012. Selenium speciation analysis was performed via ion chromatography inductively coupled plasma collision reaction cell mass spectrometry (IC-ICP-CRC-MS). Any issues associated with the analysis are addressed in the following report.

If you have any questions, please feel free to contact me at your convenience.

Sincerely,

Russell Gerads
Vice President
Applied Speciation and Consulting, LLC

Applied Speciation and Consulting, LLC

Report prepared for:

Jay Perkins
Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd.
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek (LIMS # J12020345)

February 28, 2012

1. Sample Reception

Four (4) aqueous samples in 125mL HDPE bottles (provided by Applied Speciation and Consulting) were submitted for selenium speciation analysis on February 21, 2012. The samples were received on February 22, 2012 in a sealed container at -0.3°C.

The samples were received in a laminar flow clean hood, void of trace metals contamination and ultra-violet radiation, and was designated a discrete sample identifier. An aliquot of each sample was filtered (0.45µm) and each filtrate was stored in a secure, monitored cryofreezer (maintained at a temperature of -80^{o}C) until selenium speciation analysis could be performed via ion chromatography inductively coupled plasma collision reaction cell mass spectrometry (IC-ICP-CRC-MS).

2. Sample Preparation

All sample preparation is performed in laminar flow clean hoods known to be free from trace metals contamination. All applied water for dilutions and sample preservatives are monitored for contamination to account for any biases associated with the sample results.

Selenium Speciation Analysis by IC-ICP-CRC-MS Prior to analysis, an aliquot of each sample was filtered with a syringe filter (0.45µm) and injected directly into a sealed autosampler vial. No further sample preparation was performed as any chemical alteration of a sample may shift the equilibrium of the system, resulting in changes in speciation ratios.

3. Sample Analysis

All sample analysis is preceded by a minimum of a five-point calibration curve spanning the entire concentration range of interest. Calibration curves are performed at the beginning of each analytical day. All calibration curves, associated with each species of interest, are

standardized by linear regression resulting in a response factor. All sample results are **instrument blank corrected** to account for any operational biases associated with the analytical platform.

Prior to sample analysis, all calibration curves are verified using second source standards which are identified as initial calibration verification standards (ICV).

Ongoing instrument performance is identified by the analysis of continuing calibration verification standards (CCV) and continuing calibration blanks (CCB) at a minimal interval of every ten analytical runs.

Selenium Speciation Analysis by IC-ICP-CRC-MS Each sample for selenium speciation analysis was analyzed by ion chromatography inductively coupled plasma collision reaction cell mass spectrometry (IC-ICP-CRC-MS) on February 23, 2012. An aliquot of each sample is injected onto an anion exchange column and mobilized by a basic (pH > 7) gradient. The eluting selenium species are then introduced into a radio frequency (RF) plasma where energy-transfer processes cause desolvation, atomization, and ionization. The ions are extracted from the plasma through a differentially-pumped vacuum interface and travel through a pressurized chamber (CRC) containing hydrogen gas which preferentially reacts with interfering ions of the same target mass to charge ratios (m/z). A solid-state detector detects ions transmitted through the mass analyzer and the resulting current is processed by a data handling system.

Retention times for each eluting species are compared to known standards for species identification.

4. Analytical Issues

The overall analyses went well and no significant analytical issues were encountered. All quality control parameters associated with this sample were within acceptance limits.

The estimated method detection limits (eMDLs) for selenite, selenate, and selenocyanate are generated from replicate analyses of the lowest standard in the calibration curve. Not all selenium species are present in preparation blanks; therefore, eMDL calculations based on preparation blanks are artificially biased low.

The eMDL for methylseleninic acid and selenomethionine is calculated from the average eMDL of selenite, selenate, and selenocyanate. The calibration does not contain methylseleninic acid or selenomethionine due to impurities in these standards which would bias the results for other selenium species.

If you have any questions or concerns regarding this report, please feel free to contact me.

Sincerely,

Russell Gerads
Vice President
Applied Speciation and Consulting, LLC

Selenium Speciation Results for Duke Energy
Project Name: HAPS/MACT Testing Belews Creek
Contact: Jay Perkins
LIMS #J12020342

Date: February 28, 2012
Report Generated by: Russell Gerads
Applied Speciation and Consulting, LLC

Sample Results

Sample ID	Se(IV)	Se(VI)	SeCN	MeSe(IV)	SeMe	Unknown Se Species (n)
FGd Purge Eff	234	53.3	ND (<1.6)	ND (<9.4)	ND (<9.4)	0 (0)
BioReactor 1 Inf	20.4	67.2	ND (<0.39)	4.0	ND (<2.4)	0 (0)
BioReactor 2 Eff	ND (<2.0)	ND (<4.7)	ND (<0.39)	ND (<2.4)	ND (<2.4)	0 (0)
Metals Trip Blk	ND (<0.079)	ND (<0.19)	ND (<0.016)	ND (<0.094)	ND (<0.094)	0 (0)

All results reflect the applied dilution and are reported in µg/L
ND = Not detected at the applied dilution
SeCN = Selenocyanate
MeSe(IV) = Methylseleninic acid
SeMe = Selenomethionine
Unknown Se Species = Total concentration of all unknown Se species observed by IC-ICP-MS
n = number of unknown Se species observed

Selenium Speciation Results for Duke Energy
Project Name: HAPS/MACT Testing Belews Creek
Contact: Jay Perkins
LIMS #J12020342

Date: February 28, 2012
Report Generated by: Russell Gerads
Applied Speciation and Consulting, LLC

Quality Control Summary - Preparation Blank Summary

Analyte (µg/L)	PBW1	PBW2	PBW3	PBW4	Mean	StdDev	eMDL*	eMDL 10x	eMDL 250x	eMDL 1000x
Se(IV)	0.000	0.000	0.000	0.000	0.000	0.000	0.008	0.079	2.0	7.9
Se(VI)	0.019	0.000	0.000	0.000	0.005	0.009	0.019	0.19	4.7	19
SeCN	0.000	0.000	0.000	0.000	0.000	0.000	0.002	0.016	0.39	1.6
MeSe(IV)	0.000	0.000	0.095	0.000	0.024	0.048	0.009	0.094	2.4	9.4
SeMe	0.000	0.000	0.000	0.000	0.000	0.000	0.009	0.094	2.4	9.4

eMDL = Estimated Method Detection Limit
*Please see narrative regarding eMDL calculations

Quality Control Summary - Certified Reference Materials

Analyte (µg/L)	CRM	True Value	Result	Recovery
Se(IV)	LCS	9.57	9.38	98.0
Se(VI)	LCS	9.48	9.09	95.9
SeCN	LCS	8.92	8.54	95.7
MeSe(IV)	LCS	6.47	5.79	89.4
SeMe	LCS	9.32	8.48	91.0

Selenium Speciation Results for Duke Energy
Project Name: HAPS/MACT Testing Belews Creek
Contact: Jay Perkins
LIMS #J12020342

Date: February 28, 2012
Report Generated by: Russell Gerads
Applied Speciation and Consulting, LLC

Quality Control Summary - Matrix Duplicates

Analyte (µg/L)	Sample ID	Rep 1	Rep 2	Mean	RPD
Se(IV)	BioReactor 2 Eff	ND (<2.0)	ND (<2.0)	NC	NC
Se(VI)	BioReactor 2 Eff	ND (<4.7)	ND (<4.7)	NC	NC
SeCN	BioReactor 2 Eff	ND (<0.39)	ND (<0.39)	NC	NC
MeSe(IV)	BioReactor 2 Eff	ND (<2.4)	ND (<2.4)	NC	NC
SeMe	BioReactor 2 Eff	ND (<2.4)	ND (<2.4)	NC	NC

ND = Not detected at the applied dilution
NC = Value was not calculated due to one or more concentrations below the eMDL

Quality Control Summary - Matrix Spike/ Matrix Spike Duplicate

Analyte (µg/L)	Sample ID	Spike Conc	MS Result	Recovery	Spike Conc	MSD Result	Recovery	RPD
Se(IV)	BioReactor 2 Eff	1390	1592	114.6	1390	1594	114.7	0.1
Se(VI)	BioReactor 2 Eff	1261	1279	101.4	1261	1284	101.8	0.4
SeCN	BioReactor 2 Eff	1144	812.1	71.0*	1144	821.9	71.9*	1.2

*Low recovery is attributed to matrix induced species conversion

CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST

Duke Energy

Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd
Huntersville, N. C. 28078
(704) 875-5245
Fax: (704) 875-4349

1)Project Name	HAPS/MACT Testing Belews Creek	2)Phone No:	
3) Client:	Bill Kennedy, Ron Laws, Allen Stowe, Wayne Chapman, Melonie Martin, Tom Johnson	4)Fax No:	
5)Business Unit: 20003	6)Process: 3500	Mail Code:	
8)Oper. Unit: BC00	9)Res. Type: 69400	10)Project ID: MACTCAR	

Analytical Laboratory Use Only

LIMS #: J12020345 | Matrix: OTHER | Samples Originating From: NC ✓ SC ___

Logged By: [signature] | Date & Time: 2-21-12 7:49

Cooler Temp (C): <1.0

SAMPLE PROGRAM: Ground Water ___ NPDES ___ UST ___ RCRA ___ Drinking Water ___ Waste ___

[redacted]
AS&C
PO#133241

Brooks Rand
PO#141391

[redacted]
PRISM
PO#144725

...plete all ...haded areas.

[19]Page 1 of 2
DISTRIBUTION
ORIGINAL to LAB,
COPY to CLIENT

[15]Preserv.: 1=HCL 2=H_2SO_4 3=HNO_3 4=Ice 5=None

[16]Analyses Required

LAB USE ONLY [11]Lab ID	Se Speciation Bottle ID	[13]Sample Description or ID	Date	Time	Signature	[17]Comp.	[18]Grab	TDS, TSS (4)	Hg - 245.1 (3)	Metals* (3)	Hg,IMS=Se, ICP=Mn (filtered by station) (3)	Se, Speciation, V_ASC (4)	Hg 1631, V_BRand (None)	Carbonate alkalinity, bicarbonate alkalinity, alkalinity, total (4.5), pH - V_Prism (4)	Chloride, Sulfate, Bromide - Dionex (4)	Nitrate-nitrite, C_NO3/NO2 (2,4)
J12004159		FGD Purge Eff	2-20	09:00	[signature]			1	1	1	1	1		1	1	1
60		BioReactor 1 Inf	2-20	09:00	[signature]				1	1	1	1	1	1	1	1
61		BioReactor 1 Inf Hg Blk	2-20	09:00	[signature]								1			
62		BioReactor 2 Eff	2-20	09:00	[signature]				1	1	1	1	1	1	1	1
63		BioReactor 2 Eff Hg Blk	2-20	09:00	[signature]								1			
64		Filter Blk									1					
65		Metals Trip Blk								1		1				

Customer to sign & date below ... from left to right.

1) Relinquished By: [signature]	Date/Time: 2-20-2012	2) Accepted By: [signature]	Date/Time: 2-20-12 13:35
3) Relinquished By: [signature]	Date/Time: 2-21-12 1300	4) Accepted By: [signature] -0.3°C	Date/Time: 2/22/12 11:30 am
5)Relinquished By	Date/Time	6)Accepted By:	Date/Time
7)Relinquished By	Date/Time	8)Accepted By:	Date/Time
9)Seal/Locked By: [signature]	Date/Time: 2-21-12	10) Seal/Lock Opened By	Date/Time
11)Seal/Locked By	Date/Time	12)Seal/Lock Opened By	Date/Time

A+B

[22]Requested Turnaround
14 Days ___
*7 Days ___
*48 Hr ___
*Other ___
* Add. Cost Will Apply

2-28-12

4 of 4

Comments
* Metals=TRM/IMS = As, Cd, Cr, Cu, Ni, Se, Ag, Zn TRM/ICP = B, Ca, FE, K, Li, Mg, Mn, Na,

February 29, 2012

Duke Energy
ATTN: Jay Perkins
Scientific Support-Laboratory
13339 Hagers Ferry Road
Huntersville NC 28078
jcperkins@duke-energy.com
labcustomer@duke-energy.com

RE: Project DUK-HV1201 Client Project: J12020345

Dear Mr. Perkins,

On February 22, 2012, Brooks Rand Labs (BRL) received two (2) wastewater samples and two (2) corresponding field blanks. Samples were logged-in for total mercury (Hg) analysis. All samples were received, prepared, analyzed, and stored according to BRL SOPs and EPA methodology.

The results were blank-corrected as described in the calculations section of the applicable SOP(s) and may be evaluated using adjusted reporting limits to account for sample aliquot size. Please refer to the *Sample Results* page for sample-specific detection limits and other details.

No qualification of the data was warranted, aside from concentration qualifiers, and all associated quality control sample results met the acceptance criteria.

BRL, an accredited laboratory, certifies the reported results of all analyses for which BRL is NELAP accredited meet all NELAP requirements. For more details, see the *Report Information* page of the report. Please feel free to contact me if you have any questions regarding this report.

Sincerely,

Tiffany Stilwater
Project Manager
tiffany@brooksrand.com

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Report Information

Laboratory Accreditation

BRL is accredited by the *National Environmental Laboratory Accreditation Program* (NELAP) through the State of Florida Department of Health, Bureau of Laboratories (E87982) and is certified to perform many environmental analyses. BRL is also certified by many other states to perform environmental analyses. For a current list of our accreditations /certifications, please visit our website at <http://www.brooksrand.com/default.asp?contentID=586>. Results reported relate only to the samples listed in the report.

Field Quality Control Samples

Please be notified that certain EPA methods require the collection of field quality control samples of an appropriate type and frequency; failure to do so is considered a deviation from some methods and for compliance purposes should only be done with the approval of regulatory authorities. Please see the specific EPA methods for details regarding required field quality control samples.

Common Abbreviations

BLK	method blank	**MS**	matrix spike
BRL	Brooks Rand Labs	**MSD**	matrix spike duplicate
BS	laboratory fortified blank	**ND**	non-detect
CAL	calibration standard	**NR**	non-reportable
CCV	continuing calibration verification	**PS**	post preparation spike
COC	chain of custody record	**REC**	percent recovery
CRM	certified reference material	**RPD**	relative percent difference
D	dissolved fraction	**RSD**	relative standard deviation
DUP	duplicate	**SCV**	secondary calibration verification
ICV	initial calibration verification	**SOP**	standard operating procedure
MDL	method detection limit	**SRM**	standard reference material
MRL	method reporting limit	**T**	total recoverable fraction

Definition of Data Qualifiers

(Effective 9/23/09)

B Detected by the instrument, the result is > the MDL but ≤ the MRL. Result is reported and considered an estimate.
E An estimated value due to the presence of interferences. A full explanation is presented in the narrative.
H Holding time and/or preservation requirements not met. Result is estimated.
J Estimated value. A full explanation is presented in the narrative.
J-M Duplicate precision (RPD) for associated QC sample was not within acceptance criteria. Result is estimated.
J-N Spike recovery for associated QC sample was not within acceptance criteria. Result is estimated.
M Duplicate precision (RPD) was not within acceptance criteria. Result is estimated.
N Spike recovery was not within acceptance criteria. Result is estimated.
R Rejected, unusable value. A full explanation is presented in the narrative.
U Result is ≤ the MDL or client requested reporting limit (CRRL). Result reported as the MDL or CRRL.
X Result is not BLK-corrected and is within 10x the absolute value of the highest detectable BLK in the batch. Result is estimated.

These qualifiers are based on those previously utilized by Brooks Rand, Ltd., those found in the EPA SOW ILM03.0, Exhibit B, Section III, pg. B-18, and the USEPA Laboratory Data Validation Functional Guidelines for Evaluating Inorganic Analyses; USEPA; July 2002. These supersede all previous qualifiers ever employed by BRL.

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Sample Information

Sample	Lab ID	Report Matrix	Type	Sampled	Received
BioReactor 1 Inf	1208015-01	Water	Sample	02/20/2012	02/22/2012
BioReactor 1 Inf Hg Blk	1208015-02	Water	Sample	02/20/2012	02/22/2012
BioReactor 2 Eff	1208015-03	Water	Sample	02/20/2012	02/22/2012
BioReactor 2 Inf Hg Blk	1208015-04	Water	Sample	02/20/2012	02/22/2012

Batch Summary

Analyte	Lab Matrix	Method	Prepared	Analyzed	Batch	Sequence
Hg	Water	EPA 1631	02/25/2012	02/27/2012	B120297	1200129

Sample Results

Sample	Analyte	Report Matrix	Fraction	Result	Qualifier	MDL	MRL	Unit	Batch	Sequence
BioReactor 1 Inf,										
1208015-01	Hg	Water	T	426		15.2	40.4	ng/L	B120297	1200129
BioReactor 1 Inf Hg Blk,										
1208015-02	Hg	Water	T	0.15	U	0.15	0.40	ng/L	B120297	1200129
BioReactor 2 Eff,										
1208015-03	Hg	Water	T	15.3		0.58	1.56	ng/L	B120297	1200129
BioReactor 2 Inf Hg Blk,										
1208015-04	Hg	Water	T	0.15	U	0.15	0.40	ng/L	B120297	1200129

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Accuracy & Precision Summary

Batch: B120297
Lab Matrix: Water
Method: EPA 1631

Sample	Analyte	Native	Spike	Result	Units	REC & Limits	RPD & Limits
B120297-SRM1	**Certified Reference Material (1209009, NIST 1641d 1000x dilution)**						
	Hg		15.68	14.73	ng/L	94% 85-115	
B120297-MS1	**Matrix Spike (1208004-01)**						
	Hg	758.5	3535	4800	ng/L	114% 71-125	
B120297-MSD1	**Matrix Spike Duplicate (1208004-01)**						
	Hg	758.5	3535	4565	ng/L	108% 71-125	5% 24
B120297-MS2	**Matrix Spike (1208004-03)**						
	Hg	29.10	139.0	168.1	ng/L	100% 71-125	
B120297-MSD2	**Matrix Spike Duplicate (1208004-03)**						
	Hg	29.10	140.2	177.0	ng/L	105% 71-125	5% 24

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Method Blanks & Reporting Limits

Batch: B120297
Matrix: Water
Method: EPA 1631
Analyte: Hg

Sample	Result	Units
B120297-BLK1	0.11	ng/L
B120297-BLK2	0.04	ng/L
B120297-BLK3	0.04	ng/L
B120297-BLK4	0.04	ng/L

Average: 0.06 **Standard Deviation:** 0.04 **MDL:** 0.15
Limit: 0.50 **Limit:** 0.10 **MRL:** 0.40

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Instrument Calibration

Sequence: 1200129
Instrument: THG-10
Date: 02/27/2012
Analyte: Hg

Total Mercury and Mercury Speciation by CVAFS
Method: EPA 1631

Lab ID	True Value	Result	Units	REC & Limits	
1200129-IBL1		4.20	pg of Hg		
1200129-IBL2		6.75	pg of Hg		
1200129-IBL3		4.72	pg of Hg		
1200129-IBL4		5.95	pg of Hg		
1200129-CAL1	25.00	24.83	pg of Hg	99%	
1200129-CAL2	100.0	90.79	pg of Hg	91%	
1200129-CAL3	500.0	481.7	pg of Hg	96%	
1200129-CAL4	2500	2727	pg of Hg	109%	
1200129-CAL5	10000	10670	pg of Hg	107%	
1200129-ICV1	1568	1473	pg of Hg	94%	85-115
1200129-CCB1		4.56	pg of Hg		
1200129-CCV1	500.0	512.9	pg of Hg	103%	77-123
1200129-CCV2	500.0	512.7	pg of Hg	103%	77-123
1200129-CCV3	500.0	444.8	pg of Hg	89%	77-123

Project ID: DUK-HV1201
PM: Tiffany Stilwater

Client PM: Jay Perkins
Client PO: 141391

Sample Containers

Lab ID: 1208015-01
Sample: BioReactor 1 Inf
Report Matrix: Water
Sample Type: Sample
Collected: 02/20/2012
Received: 02/22/2012

Des	Container	Size	Lot	Preservation	P-Lot	pH	Ship. Cont.
A	Bottle FLPE Hg-T	250mL	71470160 10	none	n/a		Cooler

Lab ID: 1208015-02
Sample: BioReactor 1 Inf Hg Blk
Report Matrix: Water
Sample Type: Sample
Collected: 02/20/2012
Received: 02/22/2012

Des	Container	Size	Lot	Preservation	P-Lot	pH	Ship. Cont.
A	Bottle FLPE Hg-T	250mL	71470160 10	none	n/a		Cooler

Lab ID: 1208015-03
Sample: BioReactor 2 Eff
Report Matrix: Water
Sample Type: Sample
Collected: 02/20/2012
Received: 02/22/2012

Des	Container	Size	Lot	Preservation	P-Lot	pH	Ship. Cont.
A	Bottle FLPE Hg-T	500mL	71490150 70	none	n/a		Cooler

Lab ID: 1208015-04
Sample: BioReactor 2 Inf Hg Blk
Report Matrix: Water
Sample Type: Sample
Collected: 02/20/2012
Received: 02/22/2012

Des	Container	Size	Lot	Preservation	P-Lot	pH	Ship. Cont.
A	Bottle FLPE Hg-T	250mL	71470160 10	none	n/a		Cooler

Shipping Containers

Cooler

Received: February 22, 2012 9:00
Tracking No: 472679668573 via FedEx
Coolant Type: Ice
Temperature: 0.4 °C

Description: Cooler
Damaged in transit? No
Returned to client? No

Custody seals present? No
Custody seals intact? No
COC present? Yes

DISTRIBUTION
ORIGINAL to LAB,
COPY to CLIENT

Duke Energy

Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd
Huntersville, N. C. 28078
(704) 875-5245
Fax: (704) 875-4349

Analytical Laboratory Use Only

LIMS # J12020345	Matrix: OTHER	Samples Originating From: NC ✓ SC ___
Logged By: AM	Date & Time: 2-21-12 7:49	SAMPLE PROGRAM: Ground Water ___ NPDES ___ Drinking Water ___ UST ___ RCRA ___ Waste ___
	Cooler Temp (C): <1.0	

[redacted]
AS&C
PO#133241

Brooks Rand
PO#141391

[redacted]
PRISM
PO#144725

Customer must Complete all shaded areas.

1)Project Name: HAPS/MACT Testing Belews Creek			2)Phone No:
2) Client: Bill Kennedy, Ron Laws, Allen Stowe, Wayne Chapman, Melonie Martin, Tom Johnson			4)Fax No:
5)Business Unit: 20003	6)Process: 3500		Mail Code:
8)Oper. Unit: BC00	9)Res. Type: 69400		10)Project ID: MACTCAR

[15]Preserv.: 1=HCL 2=H_2SO_4 3=HNO_3 4=Ice 5=None

[16]Analyses Required

LAB USE ONLY [11]Lab ID	Se Speciation Bottle ID	[13]Sample Description or ID	Date	Time	Signature	[17]Comp.	[18]Grab	TDS, TSS	Hg - 245.1	Metals*	Hg,IMS=Se, ICP=Mn (filtered by station)	Se, Speciation, V_ASC	Hg 1631, V_BRand	Carbonate alkalinity, bicarbonate alkalinity, alkalinity, total (4.5), pH - V_Prism	Chloride, Sulfate, Bromide - Dionex	Nittrate-nitrite, C_NO3/NO2			
Preserv.								4	3	3	3	4	None	4	4	2,4			
20120041 59		FGD Purge Eff	2-20	09:00	[signature]			1	1	1	1	1		1	1	1			
60		BioReactor 1 Inf	2-20	09:00	[signature]				1	1	1	1	1	1	1	1			
61		BioReactor 1 Inf Hg Blk	2-20	09:00	[signature]								1						
62		BioReactor 2 Eff	2-20	09:00	[signature]				1	1	1	1	1	1	1	1			
63		BioReactor 2 Eff Hg Blk	2-20	09:00	[signature]								1						
64		Filter Blk									1								
65		Metals Trip Blk								1		1							

Customer must complete appropriate columns.

Customer to sign & date below. Fill out from left to right.

1) Relinquished By: [signature]	Date/Time: 2-20-2012	2) Accepted By: [signature]	Date/Time: 2-20-12 13:35
3) Relinquished By: [signature]	Date/Time: 2-21-12 1300	4) Accepted By: [signature]	Date/Time: 2/22/12 0900
5) Relinquished By	Date/Time	6) Accepted By	Date/Time
7) Relinquished By	Date/Time	8) Accepted By	Date/Time
9) Seal/Locked By: [signature]	Date/Time: 2-21-12	10) Seal/Lock Opened By	Date/Time
11) Seal/Locked By	Date/Time	12) Seal/Lock Opened By	Date/Time

A+B

Customer, indicate Turnaround

[22]Requested Turnaround

14 Days ____________

*7 Days ____________

*48 Hr ____________

*Other ____________ *

Add. Cost Will Apply

2-28-12

Comments
* Metals=TRM/IMS = As, Cd, Cr, Cu, Ni, Se, Ag, Zn TRM/ICP = B, Ca, FE, K, Li, Mg, Mn, Na,

PRISM LABORATORIES, INC.
Full-Service Analytical & Environmental Solutions

NC Certification No. 402
SC Certification No. 99012
NC Drinking Water Cert No. 37735
VA Certification No. 1287

Case Narrative

02/27/2012

Duke Energy Corporation (04)
Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No.: J12020345
Lab Submittal Date: 02/21/2012
Prism Work Order: 2020468

This data package contains the analytical results for the project identified above and includes a Case Narrative, Sample Results and Chain of Custody. Unless otherwise noted, all samples were received in acceptable condition and processed according to the referenced methods.

Data qualifiers are flagged individually on each sample. A key reference for the data qualifiers appears at the end of this case narrative.

Please call if you have any questions relating to this analytical report.

Respectfully,

PRISM LABORATORIES, INC.

VP Laboratory Services

Reviewed By

Data Qualifiers Key Reference:

HT	Sample received and analyzed outside of the hold time.
BRL	Below Reporting Limit
MDL	Method Detection Limit
RPD	Relative Percent Difference
*	Results reported to the reporting limit. All other results are reported to the MDL with values between MDL and reporting limit indicated with a J.

Sample Receipt Summary

02/27/2012

Prism Work Order: 2020468

Client Sample ID	Lab Sample ID	Matrix	Date Sampled	Date Received
2012004159/FGD Purge Eff	2020468-01	Water	02/20/12	02/21/12
2012004160/BioReactor 1 Inf	2020468-02	Water	02/20/12	02/21/12
2012004162/BioReactor 2 Eff	2020468-03	Water	02/20/12	02/21/12

Samples received in good condition at 2.5 degrees C unless otherwise noted.

449 Springbrook Road - P.O. Box 240543 - Charlotte, NC 28224-0543
Phone: 704/529-6364 - Toll Free Number: 1-800/529-6364 - Fax: 704/525-0409

Duke Energy Corporation (04)
Attn: Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No.: J12020345
Sample Matrix: Water

Client Sample ID: 2012004159/FGD Purge Eff
Prism Sample ID: 2020468-01
Prism Work Order: 2020468
Time Collected: 02/20/12 09:00
Time Submitted: 02/21/12 15:05

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
General Chemistry Parameters									
pH	**6.9 HT**	**pH Units**			**1**	***SM4500-H B**	**2/22/12 14:00**	**JAB**	**P2B0426**
Total Alkalinity	**64**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0484**
Carbonate Alkalinity	BRL	mg/L	5.0	0.66	1	*SM2320 B	2/24/12 11:00	JAB	P2B0485
Bicarbonate Alkalinity	**64**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0487**

Duke Energy Corporation (04)
Attn: Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No.: J12020345
Sample Matrix: Water

Client Sample ID: 2012004160/BioReactor 1 Inf
Prism Sample ID: 2020468-02
Prism Work Order: 2020468
Time Collected: 02/20/12 09:00
Time Submitted: 02/21/12 15:05

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
General Chemistry Parameters									
pH	**7.0 HT**	**pH Units**			**1**	***SM4500-H B**	**2/22/12 14:00**	**JAB**	**P2B0426**
Total Alkalinity	**56**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0484**
Carbonate Alkalinity	BRL	mg/L	5.0	0.66	1	*SM2320 B	2/24/12 11:00	JAB	P2B0485
Bicarbonate Alkalinity	**56**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0487**

Duke Energy Corporation (04)
Attn: Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No.: J12020345
Sample Matrix: Water

Client Sample ID: 2012004162/BioReactor 2 Eff
Prism Sample ID: 2020468-03
Prism Work Order: 2020468
Time Collected: 02/20/12 09:00
Time Submitted: 02/21/12 15:05

Parameter	Result	Units	Report Limit	MDL	Dilution Factor	Method	Analysis Date/Time	Analyst	Batch ID
General Chemistry Parameters									
pH	**6.9 HT**	**pH Units**			**1**	***SM4500-H B**	**2/22/12 14:00**	**JAB**	**P2B0426**
Total Alkalinity	**130**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0484**
Carbonate Alkalinity	BRL	mg/L	5.0	0.66	1	*SM2320 B	2/24/12 11:00	JAB	P2B0485
Bicarbonate Alkalinity	**130**	**mg/L**	**5.0**	**0.66**	**1**	***SM2320 B**	**2/24/12 11:00**	**JAB**	**P2B0487**

Duke Energy Corporation (04)
Attn: Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No: J12020345

Prism Work Order: 2020468
Time Submitted: 2/21/2012 3:05:00PM

General Chemistry Parameters - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch P2B0426 - NO PREP										
LCS (P2B0426-BS1)				Prepared & Analyzed: 02/22/12						
pH	6.85		pH Units	6.860		100	99-101			
Batch P2B0484 - NO PREP										
Blank (P2B0484-BLK1)				Prepared & Analyzed: 02/24/12						
Total Alkalinity	BRL	5.0	mg/L							
LCS (P2B0484-BS1)				Prepared & Analyzed: 02/24/12						
Total Alkalinity	260	5.0	mg/L	250.0		104	90-110			
LCS Dup (P2B0484-BSD1)				Prepared & Analyzed: 02/24/12						
Total Alkalinity	259	5.0	mg/L	250.0		103	90-110	0.4	200	
Batch P2B0485 - NO PREP										
Blank (P2B0485-BLK1)				Prepared & Analyzed: 02/24/12						
Carbonate Alkalinity	BRL	5.0	mg/L							
LCS (P2B0485-BS1)				Prepared & Analyzed: 02/24/12						
Carbonate Alkalinity	260	5.0	mg/L				90-110			
LCS Dup (P2B0485-BSD1)				Prepared & Analyzed: 02/24/12						
Carbonate Alkalinity	259	5.0	mg/L				90-110	0.4	200	
Batch P2B0487 - NO PREP										
Blank (P2B0487-BLK1)				Prepared & Analyzed: 02/24/12						
Bicarbonate Alkalinity	BRL	5.0	mg/L							

Duke Energy Corporation (04)
Attn: Jay Perkins
13339 Hagers Ferry Road
Huntersville, NC 28078

Project: HAPS/MACT Testing Belews Creek
Project No: J12020345

Prism Work Order: 2020468
Time Submitted: 2/21/2012 3:05:00PM

General Chemistry Parameters - Quality Control

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch P2B0487 - NO PREP										
LCS (P2B0487-BS1)				Prepared & Analyzed: 02/24/12						
Bicarbonate Alkalinity	260	5.0	mg/L	250.0		104	90-110			
LCS Dup (P2B0487-BSD1)				Prepared & Analyzed: 02/24/12						
Bicarbonate Alkalinity	259	5.0	mg/L	250.0		103	90-110	0.4	200	

CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST FORM

Duke Energy

Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd
Huntersville, N. C. 28078
(704) 875-5245
Fax: (704) 875-4349

Analytical Laboratory Use Only

LIMS # JT202035 | Matrix: OTHER | Samples Originating From NC ✓ SC ___
Logged By AM | Date & Time 2-21-12 7:49
SAMPLE PROGRAM Ground Water ___ NPDES ___ Drinking Water ___ UST ___ RCRA ___ Waste ___
Cooler Temp (C) 2.1.0

[redacted] AS&C PO#133241
Brooks Rand PO#141391
[redacted] PRISM PO#144725

Customer must Complete

1)Project Name: HAPS/MACT Testing Belews Creek		2)Phone No:	
2) Client: Bill Kennedy, Ron Laws, Allen Stowe, Wayne Chapman, Melonie Martin, Tom Johnson		4)Fax No:	
5)Business Unit: 20003	6)Process: 3500	Mail Code:	
8)Oper. Unit: BC00	9)Res. Type: 69400	10)Project ID: MACTCAR	

[redacted] ...plete all ...haded areas.

[15]Preserv.: 1=HCl, 2=H_2SO_4, 3=HNO_3, 4=Ice, 5=None

LAB USE ONLY [11]Lab ID	Se Speciation Bottle ID	[13]Sample Description or ID	Date	Time	Signature	[17]Comp.	[19]Grab	TDS, TSS	Hg - 245.1	Metals*	Hg,IMS=Se, ICP=Mn (filtered by station)	Se, Speciation, V_ASC	Hg 1631, V_BRand	Carbonate alkalinity, bicarbonate alkalinity, total (4.5), pH - V_Prism	Chloride, Sulfate, Bromide - Dionex	Nitrate-nitrite, C_NO3/NO2	
								[16]Analyses Required									
								4	3	3	3	4	None	4	4	2,4	
20/200439		FGD Purge Eff	2-20	09:00	[redacted]			1	1	1	1	1		1	1	1	$1
60		BioReactor 1 Inf	2-20	09:00	[redacted]				1	1	1	1	1	1	1	1	$2
61		BioReactor 1 Inf Hg Blk	2-20	09:00	[redacted]								1				
62		BioReactor 2 Eff	2-20	09:00	[redacted]				1	1	1**	1	1	1	1	1	$3
63		BioReactor 2 Eff Hg Blk	2-20	09:00	[redacted]								1				
64		Filter Blk									1						
65		Metals Trip Blk								1		1					

Customer to complete appropriate columns to right

Customer to sign & date below - fill out from left to right.

1) Relinquished By [redacted]	Date/Time 2-20-2012	2) Accepted By [redacted]	Date/Time 2-20-12 13:35
3) Relinquished By [redacted]	Date/Time 2-21-12 1300	4) Accepted By	Date/Time
5) Relinquished By [redacted]	Date/Time 2-21-12 1415	6) Accepted By: [redacted]	Date/Time 2-21-12 1415
7) Relinquished By	Date/Time	8) Accepted By:	Date/Time
9) Seal/Locked By [redacted]	Date/Time 2-21-12	10) Seal/Lock Opened By	Date/Time
11) Seal/Locked By [redacted]	Date/Time 2-21-12 1505	12) Seal/Lock Opened By [redacted]	Date/Time 2.21.12 1505

Comments: Relinquished by [redacted] 2-21-12 1505

* Metals=TRM/IMS = As, Cd, Cr, Cu, Ni, Se, Ag, Zn TRM/ICP = B, Ca, FE, K, Li, Mg, Mn, Na, 1** Mn only

Customer, IMPORTANT! Please Indicate desired turnaround.

[22]Requested Turnaround
14 Days ___
*7 Days ___
*48 Hr ___
*Other ___ *
Add. Cost Will Apply
2-28-12

2.5°

2424[redacted]

CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST FORM

Duke Energy
Duke Energy Analytical Laboratory
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd
Huntersville, N. C. 28078
(704) 875-5245
Fax: (704) 875-4349

Analytical Laboratory Use Only

LIMS # J1202034S | Matrix: OTHER | Samples Originating From: NC ✓ SC ___
Logged By: AW | Date & Time: 2-21-12 7:49 | SAMPLE PROGRAM: Ground Water ___ NPDES ___ Drinking Water ___ UST ___ RCRA ___ Waste ___
Cooler Temp (C): <1.0

[19]Page 1 of 2
DISTRIBUTION
ORIGINAL to LAB,
COPY to CLIENT

Customer must Complete

[1]Project Name	HAPS/MACT Testing Belews Creek	[2]Phone No:	
[2] Client:	Bill Kennedy, Ron Laws, Allen Stowe, Wayne Chapman, Melonie Martin, Tom Johnson	[4]Fax No:	
[5]Business Unit:	20003	[6]Process: 3500	Mail Code:
[8]Oper. Unit:	BC00	[9]Res. Type: 69400	[10]Project ID: MACTCAR

AS&C PO#133241
Brooks Rand PO#141391
PRISM PO#144725

Complete all shaded areas.

[15]Preserv.: 1=HCL 2=H_2SO_4 3=HNO_3 4=Ice 5=None

LAB USE ONLY [11]Lab ID	Se Speciation Bottle ID	[13]Sample Description or ID	Date	Time	Signature	[17]Comp.	[18]Grab	[16]Analyses Required: TDS, TSS	Hg - 245.1	Metals*	Hg,IMS=Se, ICP=Mn (filtered by station)	Se, Speciation, V_ASC	Hg 1631, V_BRand	Carbonate alkalinity, bicarbonate alkalinity, total (4.5), pH - V_Prism	Chloride, Sulfate, Bromide - Dionex	Nitrate-nitrite, C_NO3/NO2
								4	3	3	3	4	None	4	4	2,4
12004139		FGD Purge Eff	2-20	09:00	PLJ			1	1	1	1	1		1	1	1
60		BioReactor 1 Inf	2-20	09:00	PLJ				1	1	1	1	1	1	1	1
61		BioReactor 1 Inf Hg Blk	2-20	09:00	PLJ								1			
62		BioReactor 2 Eff	2-20	09:00	PLJ				1	1	1**	1	1	1	1	1
63		BioReactor 2 Eff Hg Blk	2-20	09:00	PLJ								1			
64		Filter Blk									1					
65		Metals Trip Blk								1		1				

Customer to complete appropriate columns to right

Customer to sign & date below - fill out from left to right.

1) Relinquished By: PLJ	Date/Time: 2-20-2012	2) Accepted By: [signature]	Date/Time: 2-20-12 13:35
3) Relinquished By: [signature]	Date/Time: 2-21-12 1300	4) Accepted By:	Date/Time:
5) Relinquished By: Cindy Knox	Date/Time: 2-21-12 1415	6) Accepted By: [signature]	Date/Time: 2-21-12 1415
7) Relinquished By:	Date/Time:	8) Accepted By:	Date/Time:
9) Seal/Locked By: [signature]	Date/Time: 2-21-12	10) Seal/Lock Opened By	Date/Time:
11) Seal/Locked By	Date/Time:	12) Seal/Lock Opened By	Date/Time:

A+B

Customer, IMPORTANT! Please indicate desired turnaround.

[22]Requested Turnaround
14 Days ___
*7 Days ___
*48 Hr ___
*Other ___ *
Add. Cost Will Apply
2-28-12

Comments: * Metals=TRM/IMS = As, Cd, Cr, Cu, Ni, Se, Ag, Zn TRM/ICP = B, Ca, FE, K, Li, Mg, Mn, Na, 1** Mn only