September 18, 2013

Duke Energy
Miami Fort Generating Station
11021 Brower Road
North Bend, OH 45052

Attention: Mr. Michael Byrd
Environmental Coordinator

Re: Results – **September 2013**
Low-Level Mercury Sampling
Miami Fort Generating Station
North Bend, Ohio

In accordance with your request, URS prepared the following letter report transmitting low-level mercury test results for samples collected at the Miami Fort Generating Station located in North Bend, Ohio.

The scope of work involved the sampling of intake and discharge waters from the following sources and analysis of those samples for low-level mercury.

1. River Intake
2. Station 601 (WWT Influent)
   [Samples were collected at this station one detention time (approximately 14 hours as specified by Duke Energy) before samples collected at Outfall 608]
3. Outfall 608 (WWT Effluent)
   [Samples were collected at this outfall one detention time (approximately 14 hours as specified by Duke Energy) after samples collected at station 601]
4. Outfall 002 (Pond B Discharge)

Each sample was collected following the required Method 1669: *Sampling Ambient Water for Determination of Trace Metals at EPA Water Quality Criteria Levels* (Sampling Method) and analyzed by Method 1631E. At the request of Duke Energy, a dissolved low-level mercury sample was collected by Method 1669 from Outfall 608 and analyzed by Method 1631E. The collected dissolved sample was filtered at the laboratory utilizing 0.45 micron filtration.

Field staff from URS' Cincinnati office conducted the sampling and TestAmerica Laboratories Inc. located in North Canton, Ohio performed the analytical procedures. The analytical procedures included the analyses of a collected sample and duplicate sample (duplicates collected at Outfall 608 and Outfall 002), field blank (field blanks collected at the River Intake, Outfall 608, and Outfall 002), and trip blank.

URS Corporation
525 Vine Street, Suite 1800
Cincinnati, Ohio 45202
Tel: 513.651.3440
Fax: 1.877.660.7720 (toll free)

The results from the **September 3 and 4, 2013** sampling events are presented in the attached Table 1. A copy of the laboratory report is enclosed with this letter.

--ooOoo--

URS is pleased to provide continued assistance to Duke Energy in the execution of their environmental monitoring requirements. If there are any questions regarding the content of this report, please do not hesitate to contact the undersigned.

Sincerely,

URS Corporation

Michael A. Wagner
Project Manager

Dennis P. Connair, C.P.G.
Principal

MAW/DPC/Duke Energy-MFS LL Hg 2013
Job No. 14951061

TABLE 1

ANALYTICAL RESULTS
LOW-LEVEL MERCURY
RIVER INTAKE, STATION 601, OUTFALL 608, AND OUTFALL 002 (POND B)

DUKE ENERGY - MIAMI FORT STATION
NORTH BEND, OHIO

	Date Sampled / Results (ng/L, parts per trillion)					
Sample ID	**1/2-3/2013**	**2/4-5/2013**	**3/4-5/2013**	**4/1-2/2013**	**5/1-2/2013**	**6/3-4/2013**
River Intake	4.1	15	6.0	2.1	1.8	1.8
Station 601 (7)	730,000	320,000	82,000	94,000	Not in Service	180,000
Station 601 (7) [duplicate]	Not Collected	Not Collected	Not Collected	Not Collected		Not Collected
Station 601 (8)	330,000	370,000	140,000	130,000	280,000	130,000
Station 601 (8) [duplicate]	Not Collected	Not Collected	Not Collected	Not Collected	Not Collected	Not Collected
Outfall 608	50	54	110	49	91	2.3
Outfall 608 [duplicate]	46	55	110	50	92	2.4
Outfall 608 [dissolved, 0.45 micron]	0.63	<0.50	1.2	<0.50	<0.50	0.72
APB-002	5.1	9.1	4.8	1.9	3.5	3.5
APB-002 [duplicate]	5.3	9.3	4.8	1.8	3.7	3.6
Field Blank (RI-FB)	1.0	1.2	2.5	1.6	1.1	0.87
Field Blank (WWT-FB)	<0.50	<0.50	9.1	<0.50	<0.50	<0.50
Field Blank (AP-FB)	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50
Trip Blank	<0.50	<0.50	<0.50	<0.50	<0.50	<0.50

Samples collected by URS (Method 1669)
Sampling times are noted within the associated laboratory report for each collected sample
Samples analyzed by TestAmerica of North Canton, Ohio (Method 1631E).

TABLE 1 (continued)

Sample ID	Date Sampled / Results (ng/L, parts per trillion)					
	7/1-2/2013	8/1-2/2013	9/3-4/2013	10/xx/2013	11/xx/2013	12/xx/2013
River Intake	3.8	3.6	2.4			
Station 601 (7)	210,000	110,000	490,000			
Station 601 (7) [duplicate]	Not Collected	Not Collected	Not Collected			
Station 601 (8)	200,000	99,000	480,000			
Station 601 (8) [duplicate]	Not Collected	Not Collected	Not Collected			
Outfall 608	250	69	150			
Outfall 608 [duplicate]	240	63	150			
Outfall 608 [dissolved, 0.45 micron]	33	<0.50	14			
APB-002	4.0	6.6	2.2			
APB-002 [duplicate]	3.9	6.3	2.2			
Field Blank (RI-FB)	0.89	<0.50	<0.50			
Field Blank (WWT-FB)	<0.50	<0.50	<0.50			
Field Blank (AP-FB)	<0.50	<0.50	<0.50			
Trip Blank	<0.50	<0.50	<0.50			

Samples collected by URS (Method 1669) Samples analyzed by TestAmerica of North Canton, Ohio
Sampling times are noted within the associated laboratory report for each collected sample
Samples analyzed by TestAmerica of North Canton, Ohio (Method 1631E).

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.
TestAmerica Canton
4101 Shuffel Street NW
North Canton, OH 44720
Tel: (330)497-9396

TestAmerica Job ID: 240-28649-1
Client Project/Site: Miami Fort Station - J13090156

For:
Duke Energy Corporation
139 East Fourth Street
Cincinnati, Ohio 45202

Attn: Tara Thomas

Denise Pohl

Authorized for release by:
9/17/2013 8:47:09 AM

Denise Pohl, Project Manager II
denise.pohl@testamericainc.com

LINKS

Review your project results through TotalAccess

Have a Question? Ask The Expert

Visit us at: www.testamericainc.com

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

Table of Contents

Cover Page 1
Table of Contents 2
Definitions/Glossary 3
Case Narrative 4
Method Summary 6
Sample Summary 7
Detection Summary 8
Client Sample Results 10
QC Sample Results 22
QC Association Summary 23
Lab Chronicle 25
Certification Summary 28
Chain of Custody 29

Definitions/Glossary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Qualifiers

Metals

Qualifier	Qualifier Description
U	Indicates the analyte was analyzed for but not detected.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Job ID: 240-28649-1

Laboratory: TestAmerica Canton

Narrative

CASE NARRATIVE

Client: Duke Energy Corporation

Project: Miami Fort Station - J13090156

Report Number: 240-28649-1

With the exceptions noted as flags or footnotes, standard analytical protocols were followed in the analysis of the samples and no problems were encountered or anomalies observed. In addition all laboratory quality control samples were within established control limits, with any exceptions noted below. Each sample was analyzed to achieve the lowest possible reporting limit within the constraints of the method. In some cases, due to interference or analytes present at high concentrations, samples were diluted. For diluted samples, the reporting limits are adjusted relative to the dilution required.

TestAmerica Canton attests to the validity of the laboratory data generated by TestAmerica facilities reported herein. All analyses performed by TestAmerica facilities were done using established laboratory SOPs that incorporate QA/QC procedures described in the application methods. TestAmerica's operations groups have reviewed the data for compliance with the laboratory QA/QC plan, and data have been found to be compliant with laboratory protocols unless otherwise noted below.

The test results in this report meet all NELAP requirements for parameters for which accreditation is required or available. Any exceptions to NELAP requirements are noted in this report. Pursuant to NELAP, this report may not be reproduced, except in full, without the written approval of the laboratory.

Calculations are performed before rounding to avoid round-off errors in calculated results.

All holding times were met and proper preservation noted for the methods performed on these samples, unless otherwise detailed in the individual sections below.

All solid sample results are reported on an "as received" basis unless otherwise indicated by the presence of a % solids value in the method header.

This laboratory report is confidential and is intended for the sole use of TestAmerica and its client.

RECEIPT
The samples were received on 09/05/2013; the samples arrived in good condition. The temperature of the cooler at receipt was 19.8 C.

DISSOLVED LOW LEVEL MERCURY
Sample OUTFALL 608 DISS (240-28649-8) was analyzed for dissolved Low Level Mercury in accordance with EPA Method 1631E. The samples were prepared on 09/13/2013 and analyzed on 09/16/2013.

No difficulties were encountered during the Low Level Mercury analysis.

All quality control parameters were within the acceptance limits.

LOW LEVEL MERCURY
Samples STATION 601 (7) WWT (240-28649-1), STATION 601 (8) WWT (240-28649-2), RIVER INTAKE (RI) FB (240-28649-3), RIVER INTAKE (RI) (240-28649-4), OUTFALL 608 FB (240-28649-5), OUTFALL 608 (240-28649-6), OUTFALL 608 DUP (240-28649-7), OUTFALL 002 FB (240-28649-9), OUTFALL 002 (240-28649-10), OUTFALL 002 DUP (240-28649-11) and TRIP BLANK (240-28649-12) were analyzed for Low Level Mercury in accordance with EPA Method 1631E. The samples were prepared on 09/13/2013 and analyzed on 09/14/2013.

Job ID: 240-28649-1 (Continued)

Laboratory: TestAmerica Canton (Continued)

Samples STATION 601 (7) WWT (240-28649-1)[100X], STATION 601 (8) WWT (240-28649-2)[100X], OUTFALL 608 (240-28649-6)[10X] and OUTFALL 608 DUP (240-28649-7)[10X] required dilution prior to analysis. The reporting limits have been adjusted accordingly.

No difficulties were encountered during the Low Level Mercury analysis.

All quality control parameters were within the acceptance limits.

Method Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Method	Method Description	Protocol	Laboratory
1631E	Mercury, Low Level (CVAFS)	EPA	TAL CAN

Protocol References:

EPA = US Environmental Protection Agency

Laboratory References:

TAL CAN = TestAmerica Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

Sample Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
240-28649-1	STATION 601 (7) WWT	Water	09/03/13 17:15	09/05/13 09:15
240-28649-2	STATION 601 (8) WWT	Water	09/03/13 17:00	09/05/13 09:15
240-28649-3	RIVER INTAKE (RI) FB	Water	09/03/13 17:30	09/05/13 09:15
240-28649-4	RIVER INTAKE (RI)	Water	09/03/13 17:35	09/05/13 09:15
240-28649-5	OUTFALL 608 FB	Water	09/04/13 08:45	09/05/13 09:15
240-28649-6	OUTFALL 608	Water	09/04/13 08:50	09/05/13 09:15
240-28649-7	OUTFALL 608 DUP	Water	09/04/13 08:55	09/05/13 09:15
240-28649-8	OUTFALL 608 DISS	Water	09/04/13 09:00	09/05/13 09:15
240-28649-9	OUTFALL 002 FB	Water	09/04/13 09:15	09/05/13 09:15
240-28649-10	OUTFALL 002	Water	09/04/13 09:20	09/05/13 09:15
240-28649-11	OUTFALL 002 DUP	Water	09/04/13 09:25	09/05/13 09:15
240-28649-12	TRIP BLANK	Water	09/04/13 00:00	09/05/13 09:15

Detection Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: STATION 601 (7) WWT — Lab Sample ID: 240-28649-1

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	490000		20000		ng/L	100		1631E	Total/NA

Client Sample ID: STATION 601 (8) WWT — Lab Sample ID: 240-28649-2

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	480000		20000		ng/L	100		1631E	Total/NA

Client Sample ID: RIVER INTAKE (RI) FB — Lab Sample ID: 240-28649-3

No Detections.

Client Sample ID: RIVER INTAKE (RI) — Lab Sample ID: 240-28649-4

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	2.4		0.50		ng/L	1		1631E	Total/NA

Client Sample ID: OUTFALL 608 FB — Lab Sample ID: 240-28649-5

No Detections.

Client Sample ID: OUTFALL 608 — Lab Sample ID: 240-28649-6

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	150		5.0		ng/L	10		1631E	Total/NA

Client Sample ID: OUTFALL 608 DUP — Lab Sample ID: 240-28649-7

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	150		5.0		ng/L	10		1631E	Total/NA

Client Sample ID: OUTFALL 608 DISS — Lab Sample ID: 240-28649-8

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	14		1.0		ng/L	1		1631E	Dissolved

Client Sample ID: OUTFALL 002 FB — Lab Sample ID: 240-28649-9

No Detections.

Client Sample ID: OUTFALL 002 — Lab Sample ID: 240-28649-10

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	2.2		0.50		ng/L	1		1631E	Total/NA

Client Sample ID: OUTFALL 002 DUP — Lab Sample ID: 240-28649-11

Analyte	Result	Qualifier	RL		Unit	Dil Fac	D	Method	Prep Type
Mercury	2.2		0.50		ng/L	1		1631E	Total/NA

This Detection Summary does not include radiochemical test results.

Detection Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: TRIP BLANK **Lab Sample ID: 240-28649-12**

No Detections.

This Detection Summary does not include radiochemical test results.

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: STATION 601 (7) WWT

Lab Sample ID: 240-28649-1

Date Collected: 09/03/13 17:15

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	490000		20000		ng/L		09/13/13 13:35	09/14/13 09:51	100

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: STATION 601 (8) WWT

Lab Sample ID: 240-28649-2

Date Collected: 09/03/13 17:00

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	480000		20000		ng/L		09/13/13 13:35	09/14/13 09:55	100

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: RIVER INTAKE (RI) FB

Lab Sample ID: 240-28649-3

Date Collected: 09/03/13 17:30

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 09:59	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: RIVER INTAKE (RI)

Lab Sample ID: 240-28649-4

Date Collected: 09/03/13 17:35

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	2.4		0.50		ng/L		09/13/13 13:35	09/14/13 10:02	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 608 FB

Lab Sample ID: 240-28649-5

Date Collected: 09/04/13 08:45

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 10:07	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 608

Lab Sample ID: 240-28649-6

Date Collected: 09/04/13 08:50

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	150		5.0		ng/L		09/13/13 13:35	09/14/13 10:11	10

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 608 DUP

Lab Sample ID: 240-28649-7

Date Collected: 09/04/13 08:55

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	150		5.0		ng/L		09/13/13 13:35	09/14/13 10:15	10

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 608 DISS

Lab Sample ID: 240-28649-8

Date Collected: 09/04/13 09:00

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS) - Dissolved

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	14		1.0		ng/L		09/13/13 13:35	09/16/13 10:03	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 002 FB

Lab Sample ID: 240-28649-9

Date Collected: 09/04/13 09:15

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 10:19	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 002

Lab Sample ID: 240-28649-10

Date Collected: 09/04/13 09:20

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	2.2		0.50		ng/L		09/13/13 13:35	09/14/13 10:24	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 002 DUP

Lab Sample ID: 240-28649-11

Date Collected: 09/04/13 09:25

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	2.2		0.50		ng/L		09/13/13 13:35	09/14/13 10:28	1

Client Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: TRIP BLANK

Lab Sample ID: 240-28649-12

Date Collected: 09/04/13 00:00

Matrix: Water

Date Received: 09/05/13 09:15

Method: 1631E - Mercury, Low Level (CVAFS)

Analyte	Result	Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 10:39	1

QC Sample Results

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Method: 1631E - Mercury, Low Level (CVAFS)

Lab Sample ID: MB 240-101396/1-A — **Client Sample ID: Method Blank**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 101523 — **Prep Batch: 101396**

Analyte	MB Result	MB Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 09:26	1

Lab Sample ID: LCS 240-101396/2-A — **Client Sample ID: Lab Control Sample**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 101523 — **Prep Batch: 101396**

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Mercury			5.00	5.54		ng/L		111	77 - 123		

Lab Sample ID: MB 240-101402/1-A — **Client Sample ID: Method Blank**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 101523 — **Prep Batch: 101402**

Analyte	MB Result	MB Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 14:14	09/14/13 11:24	1

Lab Sample ID: LCS 240-101402/2-A — **Client Sample ID: Lab Control Sample**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 101523 — **Prep Batch: 101402**

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Mercury			5.00	5.34		ng/L		107	77 - 123		

Lab Sample ID: PB 240-101395/1-B PB — **Client Sample ID: Method Blank**
Matrix: Water — **Prep Type: Dissolved**
Analysis Batch: 101523 — **Prep Batch: 101396**

Analyte	PB Result	PB Qualifier	RL		Unit	D	Prepared	Analyzed	Dil Fac
Mercury	0.50	U	0.50		ng/L		09/13/13 13:35	09/14/13 10:43	1

Lab Sample ID: 240-28649-A-8-C MS — **Client Sample ID: Matrix Spike**
Matrix: Water — **Prep Type: Dissolved**
Analysis Batch: 101576 — **Prep Batch: 101396**

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits		
Mercury	5.3		30.0	26.8		ng/L		72	71 - 125		

Lab Sample ID: 240-28649-A-8-D MSD — **Client Sample ID: Matrix Spike Duplicate**
Matrix: Water — **Prep Type: Dissolved**
Analysis Batch: 101576 — **Prep Batch: 101396**

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Mercury	5.3		30.0	27.4		ng/L		74	71 - 125	2	24

QC Association Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Metals

Filtration Batch: 101395

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
240-28649-8	OUTFALL 608 DISS	Dissolved	Water	Filtration	
240-28649-A-8-C MS	Matrix Spike	Dissolved	Water	Filtration	
240-28649-A-8-D MSD	Matrix Spike Duplicate	Dissolved	Water	Filtration	
PB 240-101395/1-B PB	Method Blank	Dissolved	Water	Filtration	

Prep Batch: 101396

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
240-28649-1	STATION 601 (7) WWT	Total/NA	Water	1631E	
240-28649-2	STATION 601 (8) WWT	Total/NA	Water	1631E	
240-28649-3	RIVER INTAKE (RI) FB	Total/NA	Water	1631E	
240-28649-4	RIVER INTAKE (RI)	Total/NA	Water	1631E	
240-28649-5	OUTFALL 608 FB	Total/NA	Water	1631E	
240-28649-6	OUTFALL 608	Total/NA	Water	1631E	
240-28649-7	OUTFALL 608 DUP	Total/NA	Water	1631E	
240-28649-8	OUTFALL 608 DISS	Dissolved	Water	1631E	101395
240-28649-9	OUTFALL 002 FB	Total/NA	Water	1631E	
240-28649-10	OUTFALL 002	Total/NA	Water	1631E	
240-28649-11	OUTFALL 002 DUP	Total/NA	Water	1631E	
240-28649-12	TRIP BLANK	Total/NA	Water	1631E	
240-28649-A-8-C MS	Matrix Spike	Dissolved	Water	1631E	101395
240-28649-A-8-D MSD	Matrix Spike Duplicate	Dissolved	Water	1631E	101395
LCS 240-101396/2-A	Lab Control Sample	Total/NA	Water	1631E	
MB 240-101396/1-A	Method Blank	Total/NA	Water	1631E	
PB 240-101395/1-B PB	Method Blank	Dissolved	Water	1631E	101395

Prep Batch: 101402

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 240-101402/2-A	Lab Control Sample	Total/NA	Water	1631E	
MB 240-101402/1-A	Method Blank	Total/NA	Water	1631E	

Analysis Batch: 101523

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
240-28649-1	STATION 601 (7) WWT	Total/NA	Water	1631E	101396
240-28649-2	STATION 601 (8) WWT	Total/NA	Water	1631E	101396
240-28649-3	RIVER INTAKE (RI) FB	Total/NA	Water	1631E	101396
240-28649-4	RIVER INTAKE (RI)	Total/NA	Water	1631E	101396
240-28649-5	OUTFALL 608 FB	Total/NA	Water	1631E	101396
240-28649-6	OUTFALL 608	Total/NA	Water	1631E	101396
240-28649-7	OUTFALL 608 DUP	Total/NA	Water	1631E	101396
240-28649-9	OUTFALL 002 FB	Total/NA	Water	1631E	101396
240-28649-10	OUTFALL 002	Total/NA	Water	1631E	101396
240-28649-11	OUTFALL 002 DUP	Total/NA	Water	1631E	101396
240-28649-12	TRIP BLANK	Total/NA	Water	1631E	101396
LCS 240-101396/2-A	Lab Control Sample	Total/NA	Water	1631E	101396
LCS 240-101402/2-A	Lab Control Sample	Total/NA	Water	1631E	101402
MB 240-101396/1-A	Method Blank	Total/NA	Water	1631E	101396
MB 240-101402/1-A	Method Blank	Total/NA	Water	1631E	101402
PB 240-101395/1-B PB	Method Blank	Dissolved	Water	1631E	101396

Metals (Continued)

Analysis Batch: 101576

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
240-28649-8	OUTFALL 608 DISS	Dissolved	Water	1631E	101396
240-28649-A-8-C MS	Matrix Spike	Dissolved	Water	1631E	101396
240-28649-A-8-D MSD	Matrix Spike Duplicate	Dissolved	Water	1631E	101396

Lab Chronicle

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: STATION 601 (7) WWT — Lab Sample ID: 240-28649-1

Date Collected: 09/03/13 17:15 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		100	101523	09/14/13 09:51	DSH	TAL CAN

Client Sample ID: STATION 601 (8) WWT — Lab Sample ID: 240-28649-2

Date Collected: 09/03/13 17:00 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		100	101523	09/14/13 09:55	DSH	TAL CAN

Client Sample ID: RIVER INTAKE (RI) FB — Lab Sample ID: 240-28649-3

Date Collected: 09/03/13 17:30 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 09:59	DSH	TAL CAN

Client Sample ID: RIVER INTAKE (RI) — Lab Sample ID: 240-28649-4

Date Collected: 09/03/13 17:35 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:02	DSH	TAL CAN

Client Sample ID: OUTFALL 608 FB — Lab Sample ID: 240-28649-5

Date Collected: 09/04/13 08:45 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:07	DSH	TAL CAN

Client Sample ID: OUTFALL 608 — Lab Sample ID: 240-28649-6

Date Collected: 09/04/13 08:50 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		10	101523	09/14/13 10:11	DSH	TAL CAN

Lab Chronicle

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Client Sample ID: OUTFALL 608 DUP — Lab Sample ID: 240-28649-7

Date Collected: 09/04/13 08:55 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		10	101523	09/14/13 10:15	DSH	TAL CAN

Client Sample ID: OUTFALL 608 DISS — Lab Sample ID: 240-28649-8

Date Collected: 09/04/13 09:00 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Dissolved	Filtration	Filtration			101395	09/05/13 13:58	ADS	TAL CAN
Dissolved	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Dissolved	Analysis	1631E		1	101576	09/16/13 10:03	DSH	TAL CAN

Client Sample ID: OUTFALL 002 FB — Lab Sample ID: 240-28649-9

Date Collected: 09/04/13 09:15 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:19	DSH	TAL CAN

Client Sample ID: OUTFALL 002 — Lab Sample ID: 240-28649-10

Date Collected: 09/04/13 09:20 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:24	DSH	TAL CAN

Client Sample ID: OUTFALL 002 DUP — Lab Sample ID: 240-28649-11

Date Collected: 09/04/13 09:25 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:28	DSH	TAL CAN

Client Sample ID: TRIP BLANK — Lab Sample ID: 240-28649-12

Date Collected: 09/04/13 00:00 — **Matrix: Water**
Date Received: 09/05/13 09:15

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	1631E			101396	09/13/13 13:35	ADS	TAL CAN
Total/NA	Analysis	1631E		1	101523	09/14/13 10:39	DSH	TAL CAN

Lab Chronicle

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Laboratory References:

TAL CAN = TestAmerica Canton, 4101 Shuffel Street NW, North Canton, OH 44720, TEL (330)497-9396

Certification Summary

Client: Duke Energy Corporation
Project/Site: Miami Fort Station - J13090156

TestAmerica Job ID: 240-28649-1

Laboratory: TestAmerica Canton

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
California	NELAP	9	01144CA	06-30-14
Connecticut	State Program	1	PH-0590	12-31-13
Florida	NELAP	4	E87225	06-30-14
Georgia	State Program	4	N/A	06-30-14
Illinois	NELAP	5	200004	07-31-13 *
Kansas	NELAP	7	E-10336	01-31-14
Kentucky	State Program	4	58	06-30-14
L-A-B	DoD ELAP		L2315	07-18-16
Nevada	State Program	9	OH-000482008A	07-31-14
New Jersey	NELAP	2	OH001	06-30-14
New York	NELAP	2	10975	04-01-14
Ohio VAP	State Program	5	CL0024	01-19-14
Pennsylvania	NELAP	3	68-00340	08-31-14 *
Texas	NELAP	6		08-31-14 *
USDA	Federal		P330-11-00328	08-26-14
Washington	State Program	10	C971	01-12-14
Wisconsin	State Program	5	999518190	08-31-14

* Expired certification is currently pending renewal and is considered valid.

19.8

240-28649 Chain of Custody

CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST FORM

For detailed instructions, see: http://dewww/essenv/coc/

Analytical Laboratory Services
Mail Code MGO3A2 (Building 7405)
13339 Hagers Ferry Rd
Huntersville, N. C. 28078
(704) 875-5245
Fax: (704) 875-4349

Analytical Laboratory Use Only

LIMS #		Sample Class NPDES	Samples Originating From OH_X_
Logged By	Date & Time		
Vendor	URS (sample) Test America (v.lab)	Cooler Temp (C)	SAMPLE PROGRAM NPDES _x_
PO #			

[19]Page _1__ of __1_
DISTRIBUTION
ORIGINAL to LAB, COPY to CLIENT

Customer must Complete

1)Project NPDES - Monthly(Hg-1631)		2)Phone No: 513-467-4950
3)Client Miami Fort Station - Michael Byrd		4)Fax No:
5) Corp:	6) Center:	7)Mail Code:
8) Work Code:	9) LOB:	

Customer to complete all appropriate NON-SHADED areas.

[15]Preserv.:1=HCL 2=H_2SO_4 3=HNO_3 4=Ice 5=None

[16]Analyses Required

Customer to complete appropriate columns to right

LAB USE ONLY	12) Vendor ID#	[13]Sample Description or ID	[14]Collection Information Date	Time	Signature	[17]Comp.	[18]Grab	Hg - 1631 (5)	Diss. Hg* - 1631 (5)	[20]Total # of Containers
		Station 601 (7) WWT	9-3-13	1715	Kathi Ritchie		x	4		4
		Station 601 (8) WWT	9-3-13	1700	Kathi Ritchie		x	4		4
		River Intake (RI) FB	9-3-13	1730	Kathi Ritchie		x	2		2
		River Intake (RI)	9-3-13	1735	Kathi Ritchie		x	4		4
		Outfall 608 FB	9-4-13	0845	Kathi Ritchie		x	2		2
		Outfall 608	9-4-13	0850	Kathi Ritchie		x	4		4
		Outfall 608 Dup	9-4-13	0855	Kathi Ritchie		x	4		4
		Outfall 608 Diss	9-4-13	0900	Kathi Ritchie		x		4	4
		Outfall 002 FB	9-4-13	0915	[illegible]		x	2		2
		Outfall 002	9-4-13	0920	[illegible]		x	4		4
		Outfall 002 Dup	9-4-13	0925	[illegible]		x	4		4
		Trip Blank	—	—			x	1		1

Customer to sign & date below

21)Relinquished By [illegible]	Date/Time 09-04-13 / 1150	Accepted By: [illegible]	Date/Time 9-4-13 / 1150
Relinquished By [illegible]	Date/Time 9-4-13 / 15:00	Accepted By: [illegible]	Date/Time 9/5/13 915
Relinquished By	Date/Time	Accepted By:	Date/Time
23)Seal/Locked By	Date/Time	Sealed/Lock Opened By	Date/Time

24)Comments *(0.45micron, laboratory to filter)

Customer, important please indicate desired turnaround

[22]Requested Turnaround
14 Days _____
*10 Days ___X___
*48 Hr _____
*Other _____
* Add. Cost Will Apply

TestAmerica Canton Sample Receipt Form/Narrative **Login # :** 28649
Canton Facility

Client Duke Energy Site Name _____ Cooler unpacked by: [signature]

Cooler Received on 9/5/13 Opened on 9/5/13

FedEx: 1st (Grd) Exp UPS FAS Stetson Client Drop Off TestAmerica Courier Other _____

TestAmerica Cooler # _____ Foam Box ~~Client Cooler~~ Box Other _____

Packing material used: ~~Bubble Wrap~~ Foam Plastic Bag None Other _____

COOLANT: ~~Wet Ice~~ Blue Ice Dry Ice Water None

1. Cooler temperature upon receipt

IR GUN# A	(CF –1 °C) Observed Cooler Temp. _____ °C	Corrected Cooler Temp. _____ °C	
IR GUN# 4	(CF 0 °C) Observed Cooler Temp. _____ °C	Corrected Cooler Temp. _____ °C	☐ See Multiple Cooler Form
IR GUN# 5	(CF +1 °C) Observed Cooler Temp. _____ °C	Corrected Cooler Temp. _____ °C	
IR GUN# 8	(CF -0 °C) Observed Cooler Temp. 19.8 °C	Corrected Cooler Temp. 19.8 °C	

2. Were custody seals on the outside of the cooler(s)? If Yes Quantity 1 (Yes) No
   - -Were custody seals on the outside of the cooler(s) signed & dated? (Yes) No NA
   - -Were custody seals on the bottle(s)? Yes (No)
3. Shippers' packing slip attached to the cooler(s)? (Yes) No
4. Did custody papers accompany the sample(s)? (Yes) No
5. Were the custody papers relinquished & signed in the appropriate place? (Yes) No
6. Did all bottles arrive in good condition (Unbroken)? (Yes) No
7. Could all bottle labels be reconciled with the COC? (Yes) No
8. Were correct bottle(s) used for the test(s) indicated? (Yes) No
9. Sufficient quantity received to perform indicated analyses? (Yes) No
10. Were sample(s) at the correct pH upon receipt? Yes No (NA) pH Strip Lot# HC376062
11. Were VOAs on the COC? Yes (No)
12. Were air bubbles >6 mm in any VOA vials? Yes No (NA)
13. Was a trip blank present in the cooler(s)? (Yes) No

Contacted PM _____ Date _____ by _____ via Verbal Voice Mail Other
Concerning _____

14. CHAIN OF CUSTODY & SAMPLE DISCREPANCIES Samples processed by: [signature]

High temp ok UHG

15. SAMPLE CONDITION

Sample(s) _____ were received after the recommended holding time had expired.
Sample(s) _____ were received in a broken container.
Sample(s) _____ were received with bubble >6 mm in diameter. (Notify PM)

16. SAMPLE PRESERVATION

Sample(s) _____ were further preserved in the laboratory.
Time preserved: _____ Preservative(s) added/Lot number(s): _____.